

MILLENNIUM BULK TERMINALS—LONGVIEW NEPA ENVIRONMENTAL IMPACT STATEMENT

NEPA GEOLOGY AND SOILS TECHNICAL REPORT

PREPARED FOR:

U.S. Army Corps of Engineers, Seattle District
4735 East Marginal Way South
Seattle, WA 98134

PREPARED BY:

ICF International
710 Second Street, Suite 550
Seattle, WA 981041

September 2016



ICF International. 2016. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statements, NEPA Geology and Soils Technical Report*. September. (ICF 00264.13.) Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.

Contents

List of Tables	ii
List of Figures.....	ii
List of Acronyms and Abbreviations.....	iii
Chapter 1 Introduction	1-1
1.1 Project Description	1-1
1.1.1 On-Site Alternative	1-1
1.1.2 Off-Site Alternative	1-4
1.1.1 No-Action Alternative	1-6
1.2 Regulatory Setting.....	1-6
1.3 Study Area.....	1-7
Chapter 2 Affected Environment.....	2-1
2.1 Methods.....	2-1
2.1.1 Data Sources	2-1
2.1.2 Impact Analysis	2-2
2.2 Affected Environment.....	2-2
2.2.1 Project Area for the On-Site Alternative.....	2-2
2.2.2 Project Area for the Off-Site Alternative	2-15
Chapter 3 Impacts	3-1
3.1 On-Site Alternative	3-1
3.1.1 Construction: Direct Impacts	3-1
3.1.2 Construction—Indirect Impacts.....	3-2
3.1.3 Operations: Direct Impacts	3-2
3.1.4 Operations: Indirect Impacts	3-4
3.2 Off-Site Alternative	3-4
3.2.1 Construction: Direct Impacts	3-4
3.2.2 Construction: Indirect Impacts	3-5
3.2.3 Operations: Direct Impacts	3-5
3.2.4 Operations: Indirect Impacts	3-5
3.3 No-Action Alternative	3-6
Chapter 4 Required Permits.....	4-1
4.1 On-Site Alternative	4-1
4.2 Off-Site Alternative	4-1
Chapter 5 References	5-1

Tables

1	Regulations, Statutes, and Guidance for Geology and Soils	1-6
2	Soils and Soil Properties at the Project Area (On-Site Alternative)	2-15

Figures

1	Project Vicinity	1-2
2	On-Site Alternative.....	1-3
3	Off-Site Alternative	1-5
4	Geology and Soils Study Areas.....	1-8
5	Levees Adjacent to the On-Site Alternative and Off-Site Alternative.....	2-3
6	Local and Site Geology	2-5
7	Landslides in the Project Vicinity	2-8
8	Soil Types in the Project Vicinity for the On-Site Alternative and Off-Site Alternative	2-14

Acronyms and Abbreviations

Applicant	Millennium Bulk Terminals—Longview, LLC
BMP	best management practice
BNSF	BNSF Railway
CRD	Columbia River datum
CSZ	Cascadia Subduction Zone
Ecology	Washington State Department of Ecology
g	gravity
LVSW	Longview Switching Company
PGA	peak ground acceleration
Reynolds facility	Reynolds Metals Company facility
UP	Union Pacific
USGS	U.S. Geological Survey

This technical report assesses the potential geology and soil impacts of the proposed Millennium Bulk Terminals—Longview project (On-Site Alternative), Off-Site Alternative, and the No-Action Alternative. For the purposes of this assessment, geology and soils refers to items such as earthquakes and site constraints that may affect project engineering and design. This report describes the regulatory setting, establishes the method for assessing potential impacts, presents the existing geologic and soil conditions in the study area, and assesses potential impacts.

1.1 Project Description

Millennium Bulk Terminals—Longview, LLC (Applicant) proposes to construct and operate an export terminal in Cowlitz County, Washington, along the Columbia River (Figure 1). The export terminal would receive coal from the Powder River Basin in Montana and Wyoming and the Uinta Basin in Utah and Colorado via rail shipment, then load and transport the coal by ocean-going ships via the Columbia River and Pacific Ocean to overseas markets in Asia. The export terminal would be capable of receiving, stockpiling, blending, and loading coal by conveyor onto ships for export. Construction of the export terminal would begin in 2018. For the purpose of this analysis, it is assumed the export terminal would operate at full capacity by 2028. The following subsections present a summary of the On-Site Alternative, Off-Site Alternative, and No-Action Alternative.

1.1.1 On-Site Alternative

Under the On-Site Alternative, the Applicant would develop an export terminal on 190 acres (project area). The project area is located within an existing 540-acre area currently leased by the Applicant at the former Reynolds Metals Company facility (Reynolds facility), and land currently owned by Bonneville Power Administration. The project area is adjacent to the Columbia River in unincorporated Cowlitz County, Washington near Longview city limits (Figure 2).

The Applicant currently and separately operates at the Reynolds facility, and would continue to separately operate a bulk product terminal on land leased by the Applicant. Industrial Way (State Route 432) provides vehicular access to the Applicant's leased land. The Reynolds Lead and the BNSF Spur rail lines, both operated by Longview Switching Company (LVSW),¹ provide rail access to the Applicant's leased area from the BNSF Railway Company (BNSF) main line (Longview Junction) located to the east in Kelso, Washington. Ships access the Applicant's leased area including the bulk product terminal via the Columbia River and berth at an existing dock (Dock 1) operated by the Applicant in the Columbia River.

¹ LVSW is jointly owned by BNSF Railway Company (BNSF) and Union Pacific Railroad (UP).



Figure 1. Project Vicinity

Figure 2. On-Site Alternative

Under the On-Site Alternative, BNSF or Union Pacific Railroad (UP) trains would transport coal in rail cars from the BNSF main line at Longview Junction to the project area via the BNSF Spur and Reynolds Lead. Coal would be unloaded from rail cars, stockpiled and blended, and loaded by conveyor onto ocean-going ships at two new docks (Docks 2 and 3) on the Columbia River for export to Asia.

Once construction is complete, the export terminal would have an annual throughput capacity of up to 44 million metric tons of coal.² The export terminal would consist of one operating rail track, eight rail tracks for the storage of rail cars, rail car unloading facilities, stockpile areas for coal storage, conveyor and reclaiming facilities, two new docks in the Columbia River (Docks 2 and 3), and ship-loading facilities on the two docks. Dredging of the Columbia River would be required to provide access to and from the Columbia River navigation channel and for berthing at the two new docks.

Vehicles would access the project area from Industrial Way (State Route 432). Ships would access the project area via the Columbia River and berth at one of the two new docks. Trains would access the export terminal via the BNSF Spur and the Reynolds Lead. Terminal operations would occur 24 hours per day, 7 days per week. The export terminal would be designed for a minimum 30-year period of operation.


1.1.2 Off-Site Alternative

Under the Off-Site Alternative, the export terminal would be developed on an approximately 220-acre site adjacent to the Columbia River, located in both Longview, Washington, and unincorporated Cowlitz County, Washington, in an area commonly referred to as Barlow Point (Figure 3). The project area for the Off Site Alternative is west and downstream of the project area for the On-Site Alternative. Most of the project area for the Off-Site Alternative is located within Longview city limits and owned by the Port of Longview. The remainder of the project area is within unincorporated Cowlitz County and privately owned.

Under the Off-Site Alternative, BNSF or UP trains would transport coal from the BNSF main line at Longview Junction over the BNSF Spur and the Reynolds Lead, which would be extended approximately 2,500 feet to the west. Coal would be unloaded from rail cars, stockpiled and blended, and loaded by conveyor onto ocean-going ships at two new docks (Docks A and B) on the Columbia River. The Off-Site Alternative would serve the same purpose as the On-Site Alternative.

Once construction is complete, the Off-Site Alternative would have an annual throughput capacity of up to 44 million metric tons of coal. The export terminal would consist of the same elements as the On-Site Alternative: one operating rail track, eight rail tracks for the storage of rail cars, rail car unloading facilities, stockpile areas for coal storage, conveyor and reclaiming facilities, two new docks in the Columbia River (Docks A and B), and ship-loading facilities on the two docks. Dredging of the Columbia River would be required to provide access to and from the Columbia River navigation channel and for berthing at the two new docks.

² A metric ton is the U.S. equivalent to a tonne per the International System of Units, or 1,000 kilograms or approximately 2,204.6 pounds.

Figure 3. Off-Site Alternative

Vehicles would access the project area via a new access road extending from Mount Solo Road (State Route 432) to the project area. Trains would access the terminal via the BNSF Spur and the extended Reynolds Lead. Ships would access the project area via the Columbia River and berth at one of the two new docks. Terminal operations would occur 24 hours per day, 7 days per week. The export terminal would be designed for a minimum 30-year period of operation.

1.1.1 No-Action Alternative

Under the No-Action Alternative, the U.S. Army Corps of Engineers would not issue the requested Department of the Army permit under the Clean Water Act Section 404 and the Rivers and Harbors Act Section 10. This permit is necessary to allow the Applicant to construct and operate the proposed export terminal.

The Applicant plans to continue operating its existing bulk product terminal located adjacent to the On-Site Alternative project area, as well as expand this business whether or not a Department of the Army permit is issued. Ongoing operations would include storing and transporting alumina and small quantities of coal, and continued use of Dock 1. Maintenance of the existing bulk product terminal would continue, including maintenance dredging at the existing dock every 2 to 3 years. Under the terms of an existing lease, expanded operations could include increased storage and upland transfer of bulk products utilizing new and existing buildings. The Applicant would likely undertake demolition, construction, and other related activities to develop expanded bulk product terminal facilities.

In addition to the current and planned activities, if the requested permit is not issued, the Applicant would intend to expand its bulk product terminal business onto areas that would have been subject to construction and operation of the proposed export terminal. In 2014, the Applicant described a future expansion scenario under No-Action Alternative that would involve handling bulk materials already permitted for off-loading at Dock 1. Additional bulk product transfer activities could involve products such as a calcine pet coke, coal tar pitch, cement, fly ash, and sand or gravel. While future expansion of the Applicant's bulk product terminal business might not be limited to this scenario, it was analyzed to help provide context to a No-Action Alternative evaluation and because it is a reasonably foreseeable consequence of a Department of the Army denial.

1.2 Regulatory Setting

Different jurisdictions are responsible for the regulation of geology and soils. These jurisdictions and their regulations, statutes, and guidance that apply to geology and soils are summarized in Table 1.


Table 1. Regulations, Statutes, and Guidance for Geology and Soils

Regulation, Statute, Guideline	Description
Federal	
National Environmental Policy Act (42 USC 4321 <i>et seq.</i>)	Requires the consideration of potential environmental impacts. NEPA implementation procedures are set forth in the President's Council on Environmental Quality's Regulations for Implementing NEPA (49 CFR 1105).

Regulation, Statute, Guideline	Description
U.S. Army Corps of Engineers NEPA Environmental Regulations (33 CFR 320.4)	Requires the consideration of probable impacts, including cumulative impacts, of proposed activities and their intended use on public interest. Evaluations should reflect national concern for both protection and use of important resources including the cumulative effects on soil erosion and accretion.
Clean Water Act Section 402 General Permit for Stormwater Discharges Associated with Construction Activities	Primarily deals with water quality but includes eroded soil is potentially delivered offsite via water runoff. Mandates certain types of construction activity (and operations) comply with the EPA NPDES program. The EPA has delegated Ecology as the authority for the NPDES program in Washington State. Includes development of a stormwater pollution prevention plan.
State	
Washington State Environmental Policy Act (WAC 197-11, RCW 43.21C)	Requires state and local agencies in Washington to identify potential environmental impacts that could result from governmental decisions.
Local	
Cowlitz County SEPA Regulations (CCC Code 19.11)	Provide for the implementation of SEPA in Cowlitz County.
Cowlitz County Critical Areas Protection Ordinance (19.15)	Designates geologically hazardous areas (including seismic, volcanic, erosion, and landslide hazards) and defines performance standards and specific requirements for development within these areas.
Cowlitz County Grading (16.35)	Grading plan requirement and standards including the protection of water quality from adverse impacts of erosion and sedimentation.
Cowlitz County Building codes (16.05)	Cowlitz County and City of Longview adopt the 2012 International Building and Residential Codes.
City of Longview Comprehensive Plan (Off-Site Alternative only)	Chapter 5, Natural Environment Element, including Goals, Objectives, and Policy for Geological Hazards
City of Longview Critical Areas Ordinance (17.10.140) (Off-Site Alternative only)	Classifies geologic hazard areas (seismic, landslides, erosion, mines, volcanic) and contains procedures to address them.
Notes: NEPA = National Environmental Policy Act; CFR = Code of Federal Regulations; USC = United States Code; RCW = Revised Code of Washington; EPA = U.S. Environmental Protection Agency; NPDES = National Pollutant Discharge Elimination System; Ecology = Washington State Department of Ecology	

1.3 Study Area

The study area for geology and soils includes the project areas for the On-Site Alternative and Off-Site Alternative (Figure 4). Additionally, the study area includes the broader geologic environment influencing the project areas. These broader geologic influences include earthquakes (seismicity) and their associated impacts (e.g., ground shaking) as well as tsunamis (large earthquake-generated waves that can affect coastal zones and may extend some distance up large rivers) or off-site landslides that might reach the sites.

Figure 4. Geology and Soils Study Areas

Chapter 2

Affected Environment

This chapter describes the methods for assessing the affected environment and determining impacts, and the affected environment in the study area as it pertains to geology and soils.

2.1 Methods

This section describes the sources of information and methods used to characterize the affected environment and assess the potential impacts associated with the construction and operation of the proposed export terminal related to geology and soils.

2.1.1 Data Sources

Information with respect to geology and soils was collected through review of information and reports provided by the Applicant, Washington State Department of Natural Resources Division of Geology and Earth Resources materials, U.S. Geological Survey (USGS) maps and reports, U.S. Department of Agriculture Natural Resources Conservation Service soil information, and geological and soil literature. Additionally, a site visit conducted on January 29, 2014 provided an overview of affected environment at the project area.

The following sources of information were used to evaluate the characteristics of geology and soils in the study area.

- USGS National Seismic Hazard Maps and associated report.
- Cascadia Region Earthquake Workgroup report on the Cascadia Subduction Zone (CSZ) earthquakes.
- USGS reports on Washington State volcanic hazards.
- USGS reports on Columbia River liquefaction associated with CSZ earthquakes.
- Washington State Department of Natural Resources Division of Geology and Earth Resources geologic mapping and geologic hazards of the Longview area.
- Natural Resources Conservation Service soil mapping.
- Geotechnical engineering reports and geotechnical engineering data reports prepared for the project area for the On-Site Alternative.
- Professional workshop and refereed scientific journal materials on tsunamis in the Columbia River.
- Permit application and other materials prepared by the Applicant including:
 - Washington State Joint Aquatic Resources Permit Application
 - Cowlitz County Shoreline and Shoreline Conditional Use Application
 - Applicant's Purpose and Need

- Geology and soil reports prepared for the project areas.

2.1.2 Impact Analysis

The analysis of impacts related to geology and soils considered the following elements.

- Regional and site characteristics (bedrock, unconsolidated sediment, and soil characteristics) and how they influence site or structure stability through soil erosion, landslides, and settling.
- Potential ground shaking and ground settling due to earthquakes and the stability of the underlying materials.
- The potential for impacts related to volcanic hazards and tsunamis.

2.2 Affected Environment

The affected environment related to geology and soils in the study area are described below. Broader geologic context is provided as a foundation for the site-specific analysis.


2.2.1 Project Area for the On-Site Alternative

The following sections describe existing environmental conditions related to geology and soils in the project area and vicinity.

2.2.1.1 Local and Site Geology

The project area for the On-Site Alternative is located on the north shore of the Columbia River approximately 5 miles downstream of the confluence of the Cowlitz and Columbia Rivers at approximately river mile 63 on the Columbia River. The project area is approximately 16 feet Columbia River datum (CRD); the site is underlain by river and floodplain deposits and the surface is fairly level. Levees were constructed along the riverside of the project area (Figure 5) in approximately 1920, and the site has been industrialized since the 1940s (Anchor QEA 2011). The adjacent Columbia River navigation channel is approximately 43 feet deep at low tide (-43 feet CRD; National Oceanic and Atmospheric Administration Chart 18524) and from 28 to 42 feet deep at low tide at the location of the proposed docks (Dock 2 and Dock 3) (Millennium Bulk Terminals—Longview 2010). Although the project area is fairly level, steeper slopes descend into drainage ditches in the northern part of the project area and to the Columbia River on the south side of the project area and an on-site constructed pond. No unique geologic physical features occur at the project area.

While the physical attributes and location of the project area are dominated by their presence within the lower Columbia River valley, geologically they are within the broadly north to south-oriented physiographic-geologic province of the Puget Sound Lowland–Portland Basin–Willamette Valley lowland (Washington State Department of Natural Resources 2014a). In the Longview-Kelso area, this lowland area is quite narrow compared to the Puget Sound and Portland Basin–Willamette Valley portions to the north and south, respectively. The Longview-Kelso area is sometimes referred to locally as the Longview-Kelso basin (GRI 2012; URS Corporation 2014a).

Figure 5. Levees Adjacent to the On-Site Alternative and Off-Site Alternative


The regional geology is dominated by events related to the eastward movement of the Juan de Fuca tectonic plate against the North American plate (Evarts et al. 2009; Parsons et al. 2005). The Juan de Fuca plate plunges (or forms a subduction zone) progressively deeper as it moves east beneath the North American plate. This movement compresses the rocks above it thereby producing both uplift and down dropping (troughs or basins). This area is also referred to as the CSZ. Additionally, as the Juan de Fuca plate melts at depth, the associated magma (lava) rises to the surface forming the Cascade volcanic range. Consequently, the three major geologic zones from west to east are the Coast Range forearc, the Puget Sound–Portland Basin–Willamette Basin forearc trough (encompassing the project area) and the Cascade Range volcanic arc (Evarts et al. 2009).

The project area is underlain by late Pleistocene and Holocene alluvial (river) deposits to a depth of more than 300 feet below sea level. However, bedrock is exposed at several places near the project area, including Mount Solo to the immediate north of the project area (Figure 6); Mount Coffin approximately 0.5 mile upstream of the project area (Washington State Department of Natural Resources 2014b), and within the Columbia River where shallowly submerged bedrock has required excavation for channel maintenance at Longview just upstream of the Lewis and Clark Bridge (State Route 433) (Garmire 2012). Bedrock uplands also occur to the south across the Columbia River, to the northwest and north of the project area, and to the east of the project area across the Cowlitz River.

Three bedrock geologic units are exposed on Mount Solo (Figure 6). The bedrock at its central portion is mapped as Miocene age basalt (lava) flows of the Columbia River Basalt Group or Grande Ronde Basalt (Washington State Department of Natural Resources 2014b). This basalt is surrounded by Eocene age nearshore sedimentary rocks of sandstone and siltstone. The outermost bedrock is mapped as Eocene age volcanic rocks (basalt flows). At the study area scale landslides are also mapped along the slopes of Mount Solo (see *Landslides and Slope Stability*, below, for a more detailed discussion).

The low-lying area along the Columbia River is mapped as Quaternary alluvium, dune sand, loess (windblown silt), and artificial fill. Near the project area, the immediately underlying material is predominantly alluvium (i.e., river deposits of gravel, sand, and silt of Pleistocene to Holocene age) as well as artificial fill.

During Quaternary glaciations (between approximately 2 million to 10,000 years ago) sea level was more than 330 feet lower than present. During that time, the Columbia River incised to a similar depth of approximately 330 feet below current sea level at Longview (Baker et al. 2010; Peterson et al. 2013). Peterson et al. (2013) constructed cross-sections derived from boreholes in and near the project area. These cross-sections show, from the surface downward, about 20 feet of mud overlying sand or muddy sand/sandy mud from depths of approximately 20 feet to 160 feet, underlain in turn, by other sands, some muds, and Pleistocene gravel to a depth of approximately 330 feet (Peterson et al. 2013). The cross-section shows Mazama volcanic ash (derived from the explosion of Mount Mazama which created Crater Lake, Oregon) at approximately 45 to 60 feet below sea level. Mazama ash is approximately 7,700 years old (Peterson et al. 2013). Borings at the project area (GRI 2012:5) encountered volcanic ash between elevations -57.5 and -68 feet below mean sea level, ranging from 2 to 7 feet in thickness. Water wells at the project area reach almost 300 feet below ground depth, although there is a maximum reported depth of 410 feet (Anchor 2007; Anchor QEA 2013).

Figure 6. Local and Site Geology

In the late Pleistocene, a glacial dam forming massive Lake Missoula in Montana collapsed several times sending cataclysmic flows across the Columbia Plateau and down the Columbia River. In the Portland, Oregon, area these flows were more than 360 feet above present sea level and deposited sand banks at approximately 120 to 210 feet above present sea level (Peterson et al. 2013). These floods also deposited deep gravels and sands within the Columbia River valley. These deep gravels and sands underlie the project area at approximate depths of 120 feet and greater (Peterson et al. 2013). Regionally and locally, these deep floods also deposited fine-grained silts in the upper, slackwater parts of the flow. These floods extended up the Cowlitz River and deposited silts, which are now found on the flanks of the adjacent hills at Castle Rock and near the confluence of the Cowlitz and Toutle Rivers (Chan et al. 2007).

Based on the elevations of the silts at Castle Rock and in the Toutle River valley (Chan et al. 2007), the Lake Missoula flood levels would have reached at least 175 to 200 feet above sea level in the Mount Solo vicinity and would have scoured it at least to these elevations. No fine-grained silt deposits associated with these floods are reported on Mount Solo (Wegmann 2006).

Subsurface Conditions

General subsurface conditions are described above under *Local and Site Geology*. Because the materials beneath the project area are derived from river and floodplain sedimentation (including the contemporary development of wetlands on these surfaces), geotechnical boreholes show sediments consisting of upper silty fill overlying loose to dense sands with varying silt and clay content, silts with sand content, and interbedded organic silt and peat (Anchor 2007; Anchor QEA 2011; GRI 2012; URS Corporation 2014a). Based on geotechnical borings, groundwater begins at between 3 to 20 feet below the ground surface, so most sediments have varying amounts of water content (Anchor QEA 2011, 2013; GRI 2012; URS Corporation 2014a). Field index properties done on geotechnical borings indicate surface and near-surface sediments are soft or loose (URS Corporation 2014a). All of these properties indicate the potential for some amount of settlement under the loads (or weight) imposed by building and other structures. Consolidation tests indicate the potential for large settlement and the need for long periods for primary and secondary consolidation of these underlying materials (URS Corporation 2014a). This consolidation would minimize the potential for settlement under constructed structure loading.

Because of saturated sandy conditions at depth, liquefaction could occur during and after an earthquake. Geotechnical reports prepared for a previously proposed asphalt plant on the site identifies the potential for post-earthquake liquefaction settlement of 7 to 16 inches (GeoEngineers, Inc. 2007) and 12 to 16 inches (Shannon and Wilson, Inc. 2008).

A variety of geotechnical data has been collected at the project area (Anchor QEA 2011, 2013). Anchor QEA (2011) also summarizes earlier geotechnical borings and appends those data reports and geotechnical reports. The Anchor QEA (2011, 2013) data have been collected to assist with project design, but a geotechnical analysis and report using these recent data have not been prepared.

Landslides and Slope Stability

No landslides are identified for the project area in local slope instability reports or on-site investigations (Figure 7) (Fiksdal 1989; Wegmann 2006; Anchor 2007; GRI 2011, 2012). The project area is also flat and therefore has a low likelihood of landslides. The City of Longview (2006)

Comprehensive Plan identifies steep slopes lead from the flat, low-lying surfaces of the alluvium into the adjacent Columbia River; however, there is no indication of excessive erosion along these banks. Much of the shoreline has been armored with large riprap and angular rock along the length of the levee adjacent to the Off-Site Alternative along the Columbia River. The levee and shoreline armoring disconnect the river from its floodplain and protect the levee system from erosion.


Landslides have been identified on Mount Solo. Fiksdal (1989) identified two landslide areas on easternmost Mount Solo, one on the north side and one on the south side (Figure 7). More detailed mapping by Wegmann (2006) identified multiple landslides around Mount Solo (Figure 7). Wegmann (2006) also identified whether the features were inactive or active. One active landslide is relevant to the project area. The approximately 16-acre active landslide is located on the south slope of Mount Solo (Figure 7), about 200 feet from the northwest corner of the project area. This landslide is formed in sedimentary bedrock overlain by basalt flows (Wegmann 2006). It is oriented toward the southwest. The landslide toe (bottom) is just west of the intersection of Industrial Way and Memorial Park Drive on the north side of the road. Its active nature is identified by the presence of ground cracks, exposed and disrupted soil, and disrupted trees (Wegmann 2006). Landslides may also be caused, or existing landslides may be reactivated, by strong ground shaking from earthquakes.

2.2.1.2 Seismicity

As described by URS Corporation (2014) and by the Washington State Department of Natural Resources (2014b), Pacific Northwest earthquake origins are from one of four possible geologic events: interplate movement on the coastal CSZ, intraplate movement within the subducting Juan de Fuca tectonic plate that is sinking beneath the North American tectonic plate, shallow crustal movements within the North American tectonic plate, and movements beneath Cascade volcanoes (magma- or fault-related).

Although no great earthquakes (magnitude 8.0 to 9.0 or higher) have occurred on the CSZ during the historical record, reconstructions from the geologic record indicate more than 10 great earthquakes have occurred in Oregon and Washington over the last 5,000 years (Cascadia Region Earthquake Workgroup 2013; URS Corporation 2014a). Recurrence intervals for these earthquakes are approximately 250 to 900 years. These earthquakes result from fault rupture over most of the CSZ from northern California to southern British Columbia (Cascadia Region Earthquake Workgroup 2013) and cause substantial ground shaking and tsunamis. The last CSZ earthquake occurred in 1700 (Atwater et al. 1994; Jacoby et al. 1997).

Based on the historical record, intraplate movements are considered capable of generating earthquakes as large as magnitude 7.5 (URS Corporation 2014a). These earthquakes generally do not have faults that reach the ground surface and their recurrence interval is not known. Example intraplate earthquakes include the following: 1949 Olympia 7.1 magnitude, 1965 Seattle 6.5 magnitude and 2001 Nisqually 6.8 magnitude. These earthquakes did not cause substantial damage in the Longview area (Noson et al. 1988; Washington State Department of Natural Resources 2001; Washington State Seismic Safety Committee 2012; URS Corporation 2014a).

Figure 7. Landslides in the Project Vicinity

Shallow crustal earthquakes are widespread geographically and based on geologic data and historical records, these movements are capable of producing earthquakes greater than magnitude 6.0 and perhaps as high as magnitude 7.0 to 7.5 (URS Corporation 2014a). The 1872 North Cascade (Lake Chelan, Washington, area) magnitude 6.5 to 7.0 earthquake is considered the largest historical shallow crustal earthquake (Bakun et al. 2002; URS Corporation 2014a). Shallow crustal faults in southwestern Washington and northwestern Oregon have the potential to generate magnitude 6.0 and greater earthquakes (Wong et al. 2000; Lidke et al. 2003; Personius et al. 2003; URS Corporation 2014a).

Volcanic earthquakes occur beneath the Cascade volcanoes, which are approximately 30 miles or greater to the east of the project area. These earthquakes can be associated with the movement of magma or from faults such as that within the Mount St. Helens seismic zone (which may also be considered shallow crustal earthquakes). The largest recorded earthquake beneath Cascade volcanoes was a magnitude 5.1 earthquake in 1981 (U.S. Geological Survey 2013).

Surface Fault Rupture

No recognized crustal faults are active or potentially active in the immediate vicinity of the project area (Lidke et al. 2003; Personius et al. 2003; Barnett et al. 2009; Czajkowski and Bowman 2014.). The closest Holocene age (the last 10,000 years) faults are the Portland Hills and Frontal Fault–Lackamas Lake Faults approximately 40 miles to the southeast near Portland, Oregon (Wong et al. 2000; URS Corporation 2014a), and the Mount St. Helens Seismic Zone to the east and offshore faults to the west, both of which are approximately 60 miles away.

Strong Ground Shaking

URS Corporation (2014: Table 1) compiled a list of the largest known earthquakes felt in Washington derived from Noson et al. (1988) and from the Pacific Northwest Seismic Network (www.pnsn.org/ and www.pnsn.org/earthquakes/historic-catalog). Between 1872 and 2014, these earthquakes ranged in instrumental magnitude from 7.3 to 5.0 for all of Washington (URS Corporation 2014a: Table 1). Large earthquakes affecting the Longview area occur primarily in the Puget Sound area and Portland, Oregon, vicinity. They range in instrumental magnitude from 5.0 to 7.1 (URS Corporation 2014a: Table 1). Large or CSZ earthquakes would cause severe ground shaking in the Longview area including the project area.

Earthquake magnitude provides a specific measure with which to compare the energy released by different events. However, earthquake magnitude does not provide a direct measure of shaking at a given site because movement decreases with distance from the earthquake site. The distance from the earthquake also includes the depth within the Earth at which the earthquake actually occurred. For example, ground shaking from the 2001 Nisqually earthquake (magnitude 6.8) was not particularly violent since it occurred at 30 miles depth. The location directly above it was 30 miles away (Palmer et al. 2004).

The USGS National Seismic Hazard Maps determine earthquake ground motions for various probability levels, which are applied in seismic provisions of building codes. These values are derived by evaluating all the potential earthquakes (along with their locations, depths, and probabilities) that could affect an area. The maps show probabilistic peak ground motion as peak ground acceleration (PGA) expressed as a multiplier of the force of gravity (g). That is, the ground and overlying structures are accelerated from no motion at all to a peak motion value. This

acceleration causes shaking and stress on structures. The USGS (2014) map depicting 2% probability of PGA exceedance over 50 years shows the Longview area within the 0.4 to 0.5 g contour (Petersen et al. 2014). A PGA in the range of 0.34 to 0.65 g is perceived as severe shaking and could cause moderate to heavy damage, depending on the duration of the event, the types of underlying materials, and the structural integrity of affected buildings or structures (Petersen et al. 2014).

Ground shaking is also stronger in areas of soft soils or unconsolidated deposits such as sand and silt. The Site Class Map of Cowlitz County, Washington, characterizes the project area as site class E, which has the softest soil conditions and highest level of potential ground shaking (Palmer et al. 2004). As noted by the Cascadia Region Earthquake Workgroup (2013:11), one ground shaking–liquefaction hazard is underwater landslides that could disrupt Columbia River shipping channels.

One component of geotechnical analysis reports is to integrate the regional data with detailed, site-specific data to calculate ground shaking and other effects (such as liquefaction, see next section) for a particular location and type of construction. These reports use the regional earthquake and PGA data from the USGS National Seismic Hazard Maps and integrate it with bedrock, surficial sediment properties, and groundwater conditions derived from site-specific boreholes. Laboratory data on the characteristics of borehole samples and calculations are then used to derive the site-specific ground shaking, liquefaction and other parameters.

Secondary Seismic Hazards: Liquefaction and Subsidence

Liquefaction occurs when a saturated or partially saturated soil loses its strength and acts like a fluid due to applied stress such as earthquake shaking. The project area is subject to liquefaction and subsidence during ground shaking. The Liquefaction Susceptibility Map of Cowlitz County, Washington, characterizes the area as having high liquefaction susceptibility (Palmer et al. 2004). As noted above, the area is underlain by hundreds of feet of gravel, sand, silt, and organic layers. The sandy layers can liquefy during strong ground shaking. When liquefied these layers can flow like a liquid and/or lose consistency and no longer support the ground above them. The layers may flow laterally or be injected vertically depending on the strength and weakness of adjacent layers or whether the liquefying layer can exit the ground (e.g., by flowing out of an adjacent slope or into a river channel). If close to the surface, the flowing materials may be ejected at the surface (vent) forming one or more sand volcanoes.³ The loss of support for overlying layers may also result in them subsiding and moving laterally. These changes continue until the liquefied layer deliquesfies.

The geologic record provides evidence of liquefaction susceptibility along the Columbia River. One of the data sets providing information on the 1700 CSZ great earthquake was surface venting of liquefied layers. Several of these layers were dated by tree-ring analyses of trees affected by the sediment ejection or trees that began growing on the new ground (Atwater et al. 1994; Jacoby et al. 1997). Atwater et al. (1994) record such liquefaction events at Marsh, Brush, Price, Hunting, and Wallace Islands within the lower Columbia River. The Wallace Island site is between river miles 47.5 and 50 approximately 13 miles from the project area.

One geotechnical investigation at the project area indicated post-liquefaction settlement varies with location and earthquake magnitude but is estimated at 7 to 16 inches for a CSZ earthquake of

³ A sand volcano is a cone of sand formed by the ejection of sand onto the surface from a central point. The cone looks similar to a volcano. The process is often associated with earthquake liquefaction and the ejection of fluidized sand that can occur in water-saturated sediments during an earthquake.

magnitude 7.4 and a PGA of 0.24 g (GeoEngineers, Inc. 2007). Another geotechnical investigation estimated similar liquefaction-induced settlement of 12 to 16 inches for a magnitude 8.3 CSZ earthquake with a PGA of 0.26 g (Shannon and Wilson, Inc. 2008). These estimates were for a previously proposed asphalt plant at the site.

2.2.1.3 Volcanic Hazards

The primary volcanic hazard at Longview is from airborne fragments, ash fall, and lahars (volcanic mudflows) reaching, and continuing down, the Columbia River.

Volcanic Eruption and Ash Fall

Active volcanoes occur within the Cascade Range to the east of Longview. The active volcanoes nearest the area are Mount St. Helens (approximately 40 miles to the east), Mount Adams (approximately 70 miles to the east), and Mount Hood (approximately 80 miles to the southeast). The project area is not within the Cowlitz County–designated volcanic flowage hazard zone 1 (i.e., within a 5-mile radius of volcanic activity).

As noted by URS Corporation (2014), ash fall of more than 0.4 to 2 inches would disrupt transportation and operation of certain facilities. USGS estimates the annual probability of ash fall exceeding 4 inches at Longview to be between 0.01 and 0.02% or between 1 in 10,000 to 1 in 5,000 (Wolfe and Pierson 1995).

Lahars and Sedimentation

Lahars associated with the 1980 Mount St. Helens eruption flowed down the Toutle River to the Cowlitz River and reached the Columbia River at approximately the Lewis and Clark Bridge (SR 433) (Haini 1983). Lahars derived from the south flank of Mount Rainier in the upper Cowlitz River are unlikely to reach the lower Cowlitz River (Cakir and Walsh 2012). The Longview vicinity is not within the Cowlitz County–designated volcanic flowage hazard zone 3, which requires an evacuation and emergency management plan. That requirement only applies to areas upstream of the North Fork Toutle River sediment retention structure.

Upstream on the Columbia River, lahars have been documented along the Sandy River draining from Mount Hood in Oregon (Pierson et al. 2009). These sites are approximately 55 miles upstream of Longview. Lahars from Mount Adams could reach the Columbia River via the White Salmon River; its confluence with the Columbia River is more than 100 river miles upstream from Longview.

2.2.1.4 Mine Hazard Areas

Mine hazard areas in Cowlitz County are primarily associated with historical coal mining and areas underlain by or affected by the mine workings such as adits, tunnels, drifts, or airshafts. No bedrock with coal occurs along the Columbia River near Longview. The nearest historical coal mines are in the Coal Creek drainage approximately 7 miles northwest of Mount Solo and 5 miles northeast of Mount Solo on the east side of the Cowlitz River (Culver 1919; Vonheeder 1977). Based on a review of topographic maps and geologic reports (Culver 1919; Vonheeder 1977; Norman et al. 2001), no other mines have been documented near Mount Solo or the adjacent Columbia River deposits. Consequently, the issue is not discussed further.

2.2.1.5 Tsunamis

Washington and Oregon tsunamis could result from CSZ earthquakes along their coastline or similar major earthquakes in areas such as southern Alaska, Japan, or Indonesia. Tsunami hazard and evacuation maps for Washington and Oregon only extend up the Columbia River to a point just east of Astoria, Oregon (approximately 50 miles downstream of the project area at river mile 15) (Walsh et al. 2000; Washington State Department of Natural Resources 2010; Oregon Department of Geology and Mineral Industries 2012). Therefore, these maps are not applicable to the Longview area.

Based on previous work, Tolkova (2013) reviewed five documented historical tsunamis and their penetration up the Columbia River (August 23, 1872; November 4, 1952; May 23, 1960; March 28, 1964 [great Alaskan tsunami]; and March 11, 2011 [East Japan tsunami]). Instrumentally recorded tsunamis reach as far as Portland, Oregon, although with relatively small magnitude (i.e., wave height and energy). For example, the 1964 great Alaskan tsunami had a 0.3-meter (approximately 1-foot) height at Beaver (river mile 53). The 2011 East Japan tsunami registered a wave height between 0.001 to 0.004 meters (approximately 0.04 inches to 0.16 inches) at Longview (river mile 65.7). Tsunami wave height and penetration also vary with tide level with less height and penetration during a falling tide and greater wave height and penetration during rising tides (Tolkova 2013).

Evaluation of tsunami penetration up the Columbia River occurred at a Workshop on Tsunami Hydrodynamics in a Large River held at Oregon State University, Corvallis, in 2011 (http://isec.nacse.org/workshop/2011_orst/) and subsequently summarized by Yeh et al. (2012). These evaluations indicate that as a tsunami enters the river valley it is transformed into a long period (i.e., longer time between wave peaks), small amplitude (i.e., small height) wave (Yeh et al. 2012; Tolkova 2013). Modeling indicates that although the wave would advance to Portland at approximately river mile 107, its height would be quickly reduced upon entering the river because of energy dissipation (Yeh et al. 2012). For example, a numerical simulation indicated a tsunami height of 5.6 meters (18 feet) at the Columbia River mouth would decrease to 1.5 meters (approximately 4.9 feet) at river mile 18 (Astoria), to approximate 0.2 meter (0.65 foot or less than 8 inches) at Longview (river mile 65.7), and to 0.04 meter (0.13 foot or approximately 5 inches) at river mile 107 (Portland) (Yeh et al. 2012).

2.2.1.6 Sea Level Rise

Future sea level change in the vicinity of the Columbia River mouth is expected to be between -3 centimeters and +48 centimeters (approximately -1.2 inches and +18.9 inches) by 2050 and 10 to 143 centimeters (approximately 4 inches to 56 inches) by 2100 (National Research Council 2012). The range of values is based on consideration of several influences on sea level rise including tectonism (incorporation of tectonic uplift is the reason for the -3 centimeter value noted above) (National Research Council 2012). Considering the low gradient of the lower Columbia River, the maximum expected rise at Longview would be similar to the coastal sea level rise projections at the mouth of the Columbia River. The project area is behind Columbia River levees of approximately 36 feet CRD, as noted in the Surface Water and Floodplains Technical Report (ICF International 2016a), and since this is higher than the potential sea level rise, there would not be any impacts on soils on the project area or increased risk of erosion. Consequently, the issue is not discussed further.

2.2.1.7 Soils

Cowlitz County soils have been mapped by the Natural Resource Conservation Service⁴. Figure 8 shows the naturally occurring soils mapped at the project area. Excluding water, five soil units are mapped at the project area. These soil units and some of their relevant characteristics are presented in Table 2. All of these soil units reflect the alluvial (river deposit) origin of the soil parent material and are relatively fine-grained. The soil textures range from gravelly sandy loam (Arents, Map Unit Number 5), to loamy fine sand, to silt loam, to silty clay loam. These soils map units also reflect the low-gradient nature of these river deposits with map unit slopes from 0 to 8%. These map units reflect the soil characteristics throughout each soil's range in Washington (and Oregon) and the slopes along this landscape position, which are very flat (near zero), except adjacent to drainage ditches, ponds, and the Columbia River.

The project area is dominated by Caples silt loam (Map Unit Number 17) and the Maytown silt loam (Map Unit Number 127) (Figure 8; Table 2). A small area is mapped as Snohomish silty clay loam. The Pilchuck loamy fine sand (Map Unit Number 160) and the Arents (Map Unit Number 5) map units are narrow and parallel the Columbia River shoreline. With respect to the project area boundary, these soils are only encountered along the narrow trestle extension leading to the dock within the Columbia River.

The above discussion addresses the naturally occurring soils at the project area. The project area has been an industrial site since the 1940s and has had various amounts of surface disturbance (grading, digging for new foundations, asphalt road placement with underlying gravel base) and fill material placement. Consequently, site-specific surface soil materials may vary from the Natural Resource Conservation Service mapping. Geotechnical data reports for the project area indicate varying distributions of fill materials particularly under existing structures. This fill material includes sand, silt, mixed silt and sand, large gravel, and crushed rock (Anchor QEA 2011; GRI 2011, 2012).

The erosion hazard is characterized as slight for all soils reflecting the low landscape gradient. The K factor indicates a soils susceptibility to sheet and rill erosion. The higher the soil's K factor⁵ the higher its erosion potential. Based on the K factor, the Caples silty clay loam (Map Unit Number 17), the Maytown silt loam (Map Unit 127), and Snohomish silty clay loam (Map Unit Number 199) have a higher erosion hazard under bare soil conditions. These soils have a low susceptibility to wind erosion.

The site soils are all moderate with respect to their potential for corrosion of concrete. Their uncoated steel corrosion potential ranges from low (Pilchuck loam fine sand), to moderate (Arents), to high (Caples silty clay loam, Maytown silt loam, and Snohomish silty clay loam). Several standard engineering measures address concrete and steel corrosion such as improving drainage and replacing native soil with fill (Washington State Department of Transportation 2014).

⁴ <http://websoilsurvey.sc.egov.usda.gov/App/HomePage.htm>

⁵ K factor is a soil erodibility factor which represents both susceptibility of soil to erosion and the rate of runoff.


Figure 8. Soil Types in the Project Vicinity for the On-Site Alternative and Off-Site Alternative

Table 2. Soils and Soil Properties at the Project Area (On-Site Alternative)

Map Unit Number ^a	Soil Map Unit Name	Drainage Class	K Factor ^b	Erosion Hazard	Corrosion of Concrete ^c	Corrosion of Uncoated Steel ^d	Linear Extensibility/Class
5	Arents, 0 to 5% slopes	Moderately well drained	0.28	Slight	Moderate	Moderate	1.5%/Low
17	Caples silty clay loam, 0 to 3% slopes	Somewhat poorly drained	0.43	Slight	Moderate	High	7.0%/High
127	Maytown silt loam, 0 to 3% slopes	Moderately well drained	0.49	Slight	Moderate	High	3.6%/Moderate
160	Pilchuck loamy fine sand, 0 to 8% slope	Not defined	0.20	Slight	Moderate	Low	1.5%/Low
199	Snohomish silty clay loam, 0 to 1% slopes	Poorly drained	0.37	Slight	Moderate	High	4.5%/Moderate
263	Water	N/A	N/A	N/A	N/A	N/A	N/A

Notes:

- ^a Higher K factor values indicate greater potential for erosion: K factor values below 0.13 have low erosion potential; values 0.13 to 0.26 have medium erosion potential; values greater than 0.26 have high erosion potential.
- ^b The potential for concrete corrosion increases decreasing water and soil acidity and increases in sodium, magnesium sulfate, and sodium chloride.
- ^c The potential for corrosion of uncoated steel increases with soil water saturation, greater water acidity and conductivity.

Source: Natural Resource Conservation Service 2013

A soil's linear extensibility is a measure of its potential to expand during wetting and, conversely, to contract during drying. The more a soil expands the more potential it has to affect overlying materials such as structure foundations. The values in Table 2 are provided as a percent expansion and a descriptive classification (class). The soil expansion classes for the project area range from low (Arents, Pilchuck loamy fine sand), to moderate (Maytown silt loam, Snohomish silty clay loam), to high (Caples silty clay loam).

2.2.2 Project Area for the Off-Site Alternative

The following sections describe existing environmental conditions related to geology and soils in the project area and vicinity.

2.2.2.1 Local and Site Geology

The project area for the Off-Site Alternative is located approximately 0.3 mile west (downstream) of the project area for the On-Site Alternative. It is approximately 5 to 15 feet above CRD; it is underlain by river and floodplain deposits and the surface is level. The adjacent Columbia River

navigation channel is approximately 32 to 46 feet deep at low tide (-32 to -46 feet CRD) and from about 10 to 42 feet deep at low tide at the location of the proposed docks (Dock A and Dock B) per National Oceanic and Atmospheric Administration Chart 18524. Levees were constructed along the riverside of the project area (Figure 5) in approximately 1920 (Anchor QEA 2011). No unique physical geologic features are present at the project area.

The local geology of the project area is the same as described for the project area for the On-Site Alternative (URS Corporation 2014b; Section 2.1.1.1, *Local and Site Geology*).

Although no detailed drill hole information is available for the project area, overall conditions are expected to be very similar to the project area for the On-Site Alternative (Section 2.1.1.1, *Local and Site Geology*), because of the similar landscape position, proximity, and similarity of deposits along this portion of the Columbia River (Peterson et al. 2013).

Subsurface Conditions

Although geotechnical data are not available for the project area, Peterson et al. (2013) present cross-sections from the immediate vicinity that are directly relevant. The similarity in sedimentary deposits shows geotechnical characteristics at the project area for the On-Site Alternative (Section 2.1.1.1, *Local and Site Geology, Subsurface Conditions*) are generally applicable to this site.

Landslides and Slope Stability

No landslides are identified for the project area in local slope instability reports (Figure 7) (Fiksdal 1989; Wegmann 2006). The project area is also flat and therefore has a low likelihood of landslides. The City of Longview (2006) Comprehensive Plan identifies steep slopes from the flat, low-lying surfaces of the alluvium into the adjacent Columbia River; however, there is no indication of excessive erosion along these banks. Much of the shoreline has been armored with large riprap and angular rock along the length of the levee adjacent to the Off-Site Alternative along the Columbia River. The levee and shoreline armoring disconnect the river from its floodplain and protect the levee system from erosion.

The two active landslides on Mount Solo are relevant to the project area (Figure 7). The larger (approximately 16-acre) active landslide on the south slope of Mount Solo (Figure 7), described in Section 2.1.1.1, *Local and Site Geology, Landslides and Slope Stability*, is approximately 0.5 mile from the northeast corner of the project area. The smaller (approximately 0.56-acre) landslide at the westernmost portion of the Mount Solo area is more than 0.5 mile north of the project area, is oriented to the north, and has a low bedrock ridge to its south isolating it from the area to the south (Figure 7) (Wegmann 2006).

2.2.2.2 Seismicity

The seismicity discussion provided for the On-Site Alternative (Section 2.2.1.2, *Seismicity*) is applicable to the project area.

2.2.2.3 Volcanic Hazards

The discussion of volcanic hazards provided for the On-Site Alternative (Section 2.2.1.3, *Volcanic Hazards*) is applicable to the project area.

2.2.2.4 Tsunamis

The discussion of tsunamis provided for the On-Site Alternative (Section 2.2.1.4, *Tsunamis*) is applicable to the project area.

2.2.2.5 Sea Level Rise

The discussion of sea level rise provided for the On-Site Alternative (Section 2.2.1.5, *Sea Level Rise*) is applicable to the project area.

2.2.2.6 Soils

The discussion of soils for the On-Site Alternative (Section 2.2.1.6, *Soils*) is applicable to the Off-Site Alternative except Soil Number 127, Maytown silt loam (Figure 8, Table 2), does not occur at the project area. Moreover, the naturally occurring soils mapped are representative of the affected environment at the project area.

This chapter describes the impacts on geology and soils resulting from construction and operation of the proposed export terminal.

3.1 On-Site Alternative

The following sections describe the potential impacts related to geology and soils from the construction and operation of the On-Site Alternative.

Construction activities that could affect geology and soils include the following:

- Ground disturbance associated with construction of the export terminal
- Preloading of the coal stockpile areas

Operational activities that could affect geology and soils include the following:

- Exposure of people and structures to potential effects from catastrophic events

3.1.1 Construction: Direct Impacts

Construction of the On-Site Alternative would result in the following direct impacts.

Land, Physical Feature, or Soil Erosion

Construction at On-Site Alternative location would not result in the enlargement of land area by placing fill in the Columbia River or by causing sedimentation in the Columbia River. There are no unique physical features at the project area that would be affected by the On-Site Alternative. Although steep slopes locally occur along drainage ditches and the Columbia River banks, there are no indications of instability and project activities are not expected to cause instability at these locations.

Construction of the On-Site Alternative would affect approximately 190 acres of land and involve such ground-disturbing activities as grading, railroad construction, excavation for foundations, and road construction. Additionally, approximately 2.1 million cubic yards of material would be imported and used for preloading, or compressing soils onsite for the stockpile areas, as well as approximately 130,000 cubic yards of ballast rock for rail infrastructure and rail-related structures.

As discussed in Section 2.2.5, *Soils*, and shown in Table 2, although the soils in the project area have a moderate to high potential for erosion (i.e., moderate to high K factor), the on-site soils have a slight erosion hazard, primarily because of the site's flat gradient. However, since construction would occur over a period of several years, large areas of bare soil could be exposed for varying periods. Soil erosion could occur during periods of rainfall and would have the potential for off-site transport of eroded soil materials to waterways such as the Columbia River and adjacent ditches. Additionally, imported preload and rail ballast materials would be obtained commercially from an appropriate source. Wind erosion potential is limited because of

the precipitation levels that occur at the site, and proposed dust suppression during construction to control wind erosion of, but could occur during summer dry periods. Dust from coal stockpiles is addressed in the Air Quality Technical Report (ICF International 2016b). When build out is complete, the project area would be approximately 90% impervious surfaces, which would reduce soil erosion potential to near zero.

Dredging would occur at Docks 2 and 3. This in-water activity is discussed in the Water Quality Technical Report (ICF International 2016c) and the Surface Water and Floodplains Technical Report (ICF International 2016a).

Project Structures

As discussed in Section 2.2.5, *Soils*, and shown in Table 2, the on-site soils have moderate potential to corrode concrete, low to high potential to corrode steel, and have an expansion-contraction (wet-dry) class of low to high. A variety of standard engineering measures address concrete and steel corrosion such as improving drainage and replacing native soil with fill (Washington State Department of Transportation 2014).

The sediments underlying the project area are relatively fine-grained and water-saturated, and the water table is near the ground surface. These characteristics make the sediments susceptible to compaction from the weight of overlying materials and structures. This susceptibility is primarily of concern for the coal stockpile areas on the project area, because the coal's weight would cause compaction of the underlying sediment (estimated at approximately 8 to 10 feet), which would result in relatively substantial settlement of these underlying sediments. Compaction would be a lesser concern for other project components, because they involve much less weight.

Compaction and settlement of underlying sediments in the coal stockpile areas are addressed in the project design through preloading. Preloading involves import of material to compact the underlying soil to improve their load-bearing capacity. Approximately 2.1 million cubic yards of material would be imported into the coal stockpile areas (Millennium Bulk Terminals–Longview 2013) in stages over a period of up to 7 years.

3.1.2 Construction—Indirect Impacts

Construction of the On-Site Alternative would not result in indirect impacts on geology and soils because construction impacts would be immediate and would be limited to the project area. Therefore, no construction impacts would occur later in time or farther removed in distance from the direct impacts on the project area.

3.1.3 Operations: Direct Impacts

The On-Site Alternative would result in the following direct impacts. Operation of the proposed export terminal could expose people or structures to potential effects involving catastrophic events such as; rupture of a known earthquake fault, strong seismic ground shaking, seismic-related ground failure (i.e., liquefaction), landslides, and tsunamis. Thus, potential effects from these types of catastrophic events were evaluated.

Surface Faults

No earthquake faults at the project area reach the ground surface. Therefore, no ground surface ruptures could directly damage structures or buildings at the project area.

Ground Shaking

The Longview area, including the project area, could be subject to strong ground shaking from earthquakes. The USGS National Seismic Hazard Maps estimate a PGA of greater than 0.4 g for earthquakes with a 2% chance of being exceeded in 50 years (Petersen et al. 2014). This amount of shaking could directly damage proposed structures and buildings including those with human occupancy (one maintenance building and one administration building). Per the Cowlitz County Critical Areas Protection Ordinance (Cowlitz County Code 19.15), construction of the proposed export terminal would be required to comply with adopted International Building Code 16.05 and Cowlitz County Grading Ordinance 16.35, as applicable.

Seismic-Related Ground Failure, Including Liquefaction

The project area could be subject to liquefaction during strong ground shaking. Palmer et al. (2004) characterize the area as having high liquefaction susceptibility. Geotechnical investigation of the area for a previously proposed asphalt plant indicated that post-liquefaction settlement varies with earthquake location and earthquake magnitude but is estimated at 7 to 16 inches for a magnitude 7.4 CSZ earthquake with a PGA of 0.24 g (GeoEngineers, Inc. 2007). Shannon and Wilson, Inc. (2008) estimated similar liquefaction-induced settlement of 12 to 16 inches for a magnitude 8.3 CSZ earthquake with a PGA of 0.26 g for the previously proposed asphalt plant. Ground settling of this amount could damage proposed structures and buildings. These previous geotechnical studies used the earthquake magnitudes and PGAs recognized at the time of their preparation and did not address coal stockpiles. The On-Site Alternative would comply with the adopted International Building Code or International Residential Code (per Cowlitz County Code 19.15). Preloading of the stockpile area would expel groundwater and consolidate soils in the immediate vicinity of the coal stockpile areas, which would reduce the susceptibility of the soils to liquefaction. This would also be likely to reduce the potential for damage to proposed structures that occur in the immediate vicinity of the preloading area. Preparation of a geotechnical report would identify the specific soil conditions pre- and post-project construction, and would inform project design and construction techniques to further reduce potential impacts based on the risk of liquefaction.

Landslides

There are no existing landslides at the project area. Strong ground shaking associated with earthquakes would have minimal potential to cause new landslides at the project area, because the site is level and there is only about 40 feet of elevation difference between the site surface and the adjacent Columbia River bottom.

The project area is near the active deep-seated landslide on the south flank of Mount Solo, but it is located more than 50 feet from the its edge, which is the minimum distance required by the Cowlitz County Critical Areas Ordinance for landslide hazards. Additionally, because the project is at the toe (bottom) of the landslide, and is physically isolated from it, no actions taken at the project area would increase the risk that the landslide would be reactivated. However, as with all landslides, periods of prolonged and intense rainfall (including multiyear periods) or

earthquake-caused ground shaking could activate this landslide. The extent to which any such movement would be translated to the toe of the slide or the extent to which the toe might extend to the southwest towards the project area is uncertain.

Tsunamis

Large earthquakes in the Pacific Ocean or on the CSZ could cause a tsunami, which could affect the coastal zone of Washington and Oregon. Large tsunamis have been detected as far up the Columbia River as Portland, Oregon, as described in Section 2.2.5, *Tsunamis*. Modeling calculations found that an 18-foot-high tsunami at the Columbia River mouth decreased to less than 8 inches at Longview (Yeh et al. 2012). Tsunami levels at the project area would be similar and would not affect the project area structures or operation including ships at the docks.

3.1.4 Operations: Indirect Impacts

No indirect impacts on geology or soils have been identified.

3.2 Off-Site Alternative

The following sections describe the potential impacts related to geology and soils from the construction and operation of the Off-Site Alternative.

The site plan and design (size of project area, project elements, and construction activities) for the Off-Site Alternative are very similar to the On-Site Alternative. Moreover, the local geology, landscape position, subsurface conditions, and soils are virtually identical between the two sites (Section 2.2.2.6, *Soils*; Table 2; Peterson et al. 2013). Therefore, the construction-related direct impacts of the Off-Site Alternative would be the same or similar as those described above for the On-Site Alternative.

3.2.1 Construction: Direct Impacts

The construction related direct impacts of the proposed terminal at the Off-Site Alternative would be the same or similar as those described above for the proposed terminal at the On-Site Alternative. Construction of the proposed terminal at the Off-Site Alternative would result in the following direct impacts.

Soil Erosion

Construction of the Off-Site Alternative would not result in the enlargement of land area by placing fill in the Columbia River or by causing sedimentation in the Columbia River. There are no unique physical features at the project area that would be affected by the Off-Site Alternative. Although steep slopes locally occur along drainage ditches and the Columbia River banks, there are no indications of instability and project activities are not expected to cause instability at these locations.

Construction of the Off-Site Alternative would affect approximately 220 acres of land and involve such ground-disturbing activities as grading, railroad construction, excavation for foundations, and road construction. Additionally, approximately 2.1 million cubic yards of material would be imported and used for preloading, or compressing soils onsite for the

stockpile areas, as well as approximately 130,000 cubic yards of ballast rock for rail infrastructure and rail-related structures.

Erosion hazards would be the same as described for the On-Site Alternative (Section 3.1.1.1, *Construction: Direct Impacts*). When build-out is complete, the project area would be approximately 90% impervious surfaces, which would reduce soil erosion potential to near zero.

Dredging would occur at Docks A and B. This in-water activity is discussed in the Water Quality Technical Report (ICF International 2016c) and the Surface Water and Floodplains Technical Report (ICF International 2016a).

Project Structures

The potential impacts on project structures from underlying soil materials would be the same as described for the On-Site Alternative (Section 3.1.1.2, *Construction: Direct Impacts*).

3.2.2 Construction: Indirect Impacts

The Off-Site Alternative would not result in indirect impacts on geology and soils because construction impacts are immediate and no construction impacts would occur later in time or farther removed in distance than the direct impacts.

3.2.3 Operations: Direct Impacts

The Off-Site Alternative would result in the following direct impact.

Catastrophic Events

The direct impacts of operation of the proposed terminal at the Off-Site Alternative would be the same or similar as described for the proposed terminal at the On-Site Alternative. The project area has no surface faults that would affect the site or its structures. The project area would experience the same ground shaking seismic-related ground failure (including liquefaction potential), landslides, and tsunamis as the project area for the On-Site Alternative. Although no geotechnical borings and analysis have been conducted for the project area for the Off-Site Alternative, the site's general characteristics are expected to be similar to the project area for the On-Site Alternative, because the local geology, landscape position, subsurface conditions, and soils are virtually identical between the two sites (Section 2.2.2.6, *Soils*; Table 2; Peterson et al. 2013).

The Off-Site Alternative would comply with the adopted International Building Code or International Residential Code (per Cowlitz County Code 19.15).

3.2.4 Operations: Indirect Impacts

No indirect project related operational impacts have been identified for geology or soils.

3.3 No-Action Alternative

Under the No-Action Alternative, the Corps would not issue a Department of the Army permit authorizing construction and operation of the proposed export terminal. As a result, impacts resulting from constructing and operating the export terminal would not occur. In addition, not constructing the export terminal would likely lead to expansion of the adjacent bulk product business onto the export terminal project area.

The potential impacts on geology and soils could occur under the No-Action Alternative similar to what is described for the On-Site Alternative, but the magnitude of the impact would depend on the nature and extent of the future expansion.

The following permits would be required related to geology and soils.

4.1 On-Site Alternative

The On-Site Alternative would require the following permits related to geology and soils.

- **Fill and Grade Permits/Building Permits—Cowlitz County.** Fill and grade permits and building permits would be required from Cowlitz County to ensure that final design and construction follow the County and engineering requirements.
- **Critical Areas Permit—Cowlitz County.** The On-Site Alternative would require a Critical Areas Permit to address compliance with Cowlitz County's Critical Areas Ordinance related to the presence and protection of Critical Aquifer Recharge Areas located on site.
- **Construction Stormwater General Permit—Washington State Department of Ecology.** A Construction Stormwater General Permit would be required from the Washington State Department of Ecology to address erosion control and water quality during construction.
- **Industrial Stormwater General Permit—Washington State Department of Ecology.** An industrial Stormwater General Permit would be required from the Washington State Department of Ecology to address erosion control and water quality during operations. The permit and stormwater pollution prevention plan control adverse impacts through the application of best management practices. Best management practices are defined as schedules of activities, prohibitions of practices, maintenance procedures, and structural and managerial practices, that when used singly or in combination, prevent or reduce the release of pollutants and other adverse impacts on waters of Washington State. The types of best management practices are source control, treatment, and flow control.

4.2 Off-Site Alternative

The Off-Site Alternative would require the following permits related to geology and soils.

- **Building Permit—City of Longview.** A building permit would be required from the City of Longview to ensure that final design and construction follow the City and engineering requirements.
- **Critical Areas Permit—City of Longview and Cowlitz County.** A Critical Areas Permit may be required to address compliance with the City and County's critical areas ordinances should Critical Aquifer Recharge Areas be located on or adjacent to the off-site alternative.
- **Construction Stormwater General Permit and Industrial Stormwater General Permit—Washington State Department of Ecology.** Construction and Industrial Stormwater General Permits would be required, for reasons described above under On-Site Alternative.

The following measures were identified by the Applicant and would likely be permit requirements required for construction of the On-Site Alternative or Off-Site Alternative.

- A qualified geologist or engineer would monitor the fill placement during construction and conduct appropriate field tests to verify proper compaction of the fill soils.
- A site-specific preloading plan would be developed prior to initiating construction by the geotechnical engineer working with the civil and structural engineers. The plan would include measures to maintain proper site drainage, collection, and treatment of water generated, volumes, and sources of fill sources, and staging of fills, setbacks from existing structures. The plan would also consider the short- and long-term impacts on adjacent structures and features, including but not limited to, railroads, existing streets and utility connections, utilities, drainage features, landfills, existing hazardous materials, and buildings.
- Visual inspection would be conducted following abnormal seismic activity. These inspections would document whether the seismic activity resulted in changes to the surface conditions (i.e., soil settlement, structural damage).
- Best management practices would minimize the potential for erosion. A stormwater pollution prevention plan would be required and implemented. Clearing, excavation, and grading would be limited to the areas necessary for construction and would not be completed far in advance of facility construction.
 - **BMP C107: Construction Road/Parking Area Stabilization.** Roads, parking areas, and other on-site vehicle transportation routes would be stabilized to reduce erosion caused by construction traffic or runoff.

Chapter 5

References

- Anchor Environmental, LLC. 2007. *Remedial Investigation Report, Chinook Ventures, Inc. and Northwest Alloys, Inc.* June. Prepared for Washington State Department of Ecology.
- Anchor QEA. 2011. *Engineering Report for NPDES Application Millennium Bulk Terminals –Longview, LLC.* September.
- Anchor QEA. 2013. *Draft Remedial Investigation and Feasibility Study, Sections 1–5, Former Reynolds Metals Reduction Plant – Longview.* June.
- Atwater, B. F. (compiler). 1994. *Geology of Holocene Liquefaction Features along the Lower Columbia River at Marsh, Brush, Price, Hunting, and Wallace Islands, Oregon and Washington.* U.S. Geological Survey Open-File Report 94-209.
- Baker, D., C. Peterson, E. Hemphill-Haley, and D. Twitchell. 2010. Latest Pleistocene and Holocene (2-16 ka) sedimentation in the Columbia River estuary, Oregon, USA. *Marine Geology* 273:83–95.
- Bakun, W. H., R. A. Haugerud, M. G. Hopper, and R. S. Ludwin. 2002. The December 1872 Washington State earthquake. *Bulletin of the Seismological Society of America* 92(8):3239–3258.
- Barnett, E. A., C. S. Weaver, K. L. Meagher, R. A. Haugerud, Z. Wang, I. P. Madin, Y. Wang, R. E. Wells, R. J. Blakely, D. B. Ballantyne, and M. Darienzo. 2009. *Earthquake Hazards and Lifelines in the Interstate 5 Urban Corridor: Woodburn, Oregon, to Centralia, Washington.* U.S. Geological Survey Scientific Investigations Map 3027.
- Cakir, R. and T.J. Walsh. 2012. *Loss Estimation Pilot Project for Lahar Hazards from Mount Rainier, Washington.* Washington Division of Geology and Earth Resources, Information Circular 113, May.
- Cascadia Region Earthquake Workgroup. 2013. *Cascadia Subduction Zone Earthquakes. A Magnitude 9.0 Earthquake Scenario. Update 2013.* Also available as Washington Division of Geology and Earth Resources Information Circular 116, Oregon Department of Geology and Mineral Industries Open-File Report 0-13-22, and British Columbia Geological Survey Information Circular 2013-3.
- Chan, K. J., D. R. Gaylord, J. E. O'Connor, and F. F. Foit. 2007. History of Pleistocene and Holocene volcanoclastic sedimentation in the Cowlitz River valley, southwestern Washington State. Geological Society of America 103rd Annual Meeting, Cordilleran Section, 4-6 May 2007. Abstract. Available: https://gsa.confex.com/gsa/2007CD/finalprogram/abstract_121047.htm.
- City of Longview. 2006. *Comprehensive Plan.* Chapter 5 Natural Environment. Prepared by Jones & Stokes, Cowlitz Wahkiakum Council of Governments, and E.D. Howe and Company. December.
- Culver, H. E. 1919. *The Coal Fields of Southwestern Washington.* Washington Geological Survey Bulletin No. 19. Available: www.dnr.wa.gov/publications/ger_b19_coal_fields_sw_wa.pdf. Accessed: April 2, 2014.

- Czajkowski, J. L., and J. D. Bowman. 2014. Faults and Earthquakes in Washington State. Washington Division of Geology and Earth Resources Open File Report 2014-05, 1 sheet, scale 1:750,000.
- Evarts, R.C., J.E. O'Connor, R.E. Wells and I.P. Madin. 2009. The Portland Basin: A (big) river runs through it. *Geological Society of America Today* 19(9):4–10.
- Fiksdal, A. J. 1989. *Slope Stability of the Longview-Kelso Urban Area Cowlitz County*. Washington State Department of Natural Resources, Division of Geology and Earth Resources, Open-File Report 73-2. October.
- Garmire, K. 2012. Rock blasting and removal Columbia River channel deepening. Dredging 2012 Conference, Presentation, San Diego, California October 22–25, 2012. Available: http://dredging12.pianc.us/docs/Tuesday/Room%202/garmire_10_15_12_Dredging_2012_Garmire.pdf. Accessed: April 1, 2014.
- GeoEngineers, Inc. 2007. *Report of Geotechnical Engineering Services, Longview Asphalt Plant, Longview, Washington, May 11, 2007*. Appended to Anchor QEA, LLC. 2011.
- GRI. 2011. *Geotechnical Data Report, Millennium Bulk Terminals – Longview, LLC*. July.
- GRI. 2012. *Geotechnical Data Report, Upland Bulk Handling Facility and Shiploader Dock, Millennium Bulk Logistics, Inc., Longview, Washington*. October 23.
- Haini, F. P. 1983. Sediment deposition in the Columbia and lower Cowlitz rivers, Washington-Oregon, caused by the May 18, 1980, eruption of Mount St. Helens. U.S. *Geological Survey Circular* 850-K. Available: <http://pubs.er.usgs.gov/publication/cir850K>. Accessed: April 1, 2014.
- ICF International. 2016a. *Millennium Bulk Terminals— Longview, NEPA Environmental Impact Statement, NEPA Surface Water and Floodplains Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016b. *Millennium Bulk Terminals— Longview, NEPA Environmental Impact Statement, NEPA Air Quality Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016c. *Millennium Bulk Terminals— Longview, NEPA Environmental Impact Statement, NEPA Water Quality Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- Jacoby, G. C., D. E. Bunker, and B. E. Benson. 1997. Tree-ring evidence of an A.D. 1700 Cascadia earthquake in Washington and northern Oregon. *Geology* 11:999–1002.
- Lidke, D. J., S. Y. Johnson, P. A. McCrory, S. F. Petronius, A. R. Nelson, R. L. Dart, L-A. Bradley, K. M. Haller, and M. N. Machette. 2003. *Map and Data for Quaternary Faults and Folds in Washington State*. U.S. Geological Survey Open-File Report 03-428. Available: <http://pubs.usgs.gov/of/2003/428/>; Accessed April 2, 2014.
- Millennium Bulk Terminals—Longview, LLC. 2010. *Washington State Joint Aquatic Resources Permit Application*. March 30. Available: www.ecy.wa.gov/geographic/millennium. Accessed: April 10, 2014.

- Millennium Bulk Terminals—Longview, LLC. 2013. *Applicant's Purpose and Need, Expanded Project Description, Alternatives Considered – Millennium Coal Export Terminal, Longview, Washington*. December.
- National Research Council. 2012. *Sea-Level Rise for the Coasts of California, Oregon, and Washington: Past, Present, and Future*. Committee on Sea Level Rise in California, Oregon, and Washington.
- Natural Resource Conservation Service. 2013. Web Soil Survey. Available: <http://websoilsurvey.sc.egov.usda.gov/App/HomePage.htm>. Accessed: January 2, 2015.
- Norman, D.K., A.B. Dunn, and C.M. Kenner. 2001. Reconnaissance investigation of sand, gravel, and quarried bedrock resources in the Mount St. Helens 1:100,000 quadrangle, Washington. Washington Division of Geology and Earth Resources Information Circular 95, 52pp.
- Noson, L. L., A. Qamar, and G. W. Thorsen. 1988. Washington State earthquake hazards. *Washington Division of Geology and Earth Resources Information Circular 85*.
- Oregon Department of Geology and Mineral Industries. 2012. Tsunami inundation and evacuation maps for Oregon. *Oregon Geology Fact Sheet*.
- Palmer, S. P., S. L. Magsino, E. L. Bilderback, J. L. Poelstra, D. S. Folger, and R. A. Niggemann. 2004. Liquefaction susceptibility and site class maps of Washington State, by County. Washington. Washington State Department of Natural Resources, Washington Division of Geology and Earth Resources Open File Report 2004-20. Available: <ftp://ww4.dnr.wa.gov/geology/pubs/ofr04-20>. Accessed: April 2, 2014.
- Parsons, T., R. J. Blakely, T. M. Brocher, N. I. Christensen, M. A. Fisher, E. Flueh, F. Kilbride, J. H. Luetgert, K. Miller, U. S. ten Brink, A. M. Trehu, and R. E. Wells. 2005. *Earthquake Hazards of the Cascadia Fore Arc of Washington*. U.S. Geological Survey Professional Paper 1661-D. Available: <http://pubs.usgs.gov/pp/pp1661d/>. Accessed: April 2, 2014.
- Personius, S. F., R. L. Dart, L-A. Bradley, and K. M. Haller. 2003. Map and data for Quaternary faults and fold in Oregon. U.S. Geological Survey Open-File Report 03-095. Available: <http://pubs.usgs.gov/of/2003/ofr-03-095/>. Accessed: April 2, 2014.
- Peterson, C. D., E. B. Gates, R. Minor, and D. L. Baker. 2013. Accommodation space controls the latest Pleistocene and Holocene (16-0 ka) sediment size and bypassing in the lower Columbia River Valley: a large fluvial-tidal system in Oregon and Washington, USA. *Journal of Coastal Research* 29(5):1191–1211.
- Petersen, M. D., M. P. Moschetti, P. M. Powers, C. S. Mueller, K. M. Haller, A. D. Frankel, Y. Zeng, S. Rezaeian, S. C. Harmsen, O. S. Boyd, N. Field, R. Chen, K. S. Rukstales, N. Luco, R. L. Wheeler, R. A. Williams, and A. H. Olsen. 2014. Documentation for the update of the United States national seismic hazard maps. U.S. Geological Survey Open-File Report 2014-1091, 243p.
- Pierson, T. C., W. E. Scott, J. W. Vallance, and P. T. Pringle. 2009. Eruption-related lahars and sedimentation response downstream of Mount Hood: field guide to volcanoclastic deposits along the Sandy River, Oregon. Pages 221–236 in J. E. O'Conner, R. J. Dorsey, and I. P. Madin (eds.), *Volcanoes to Vineyards: Geologic Fieldtrips through the Dynamic Landscape of the Pacific Northwest: Geological Society of America Field Guide 15*.

- Shannon and Wilson, Inc. 2008. *Draft Geotechnical Report, Longview Asphalt Plant, Longview, Washington*. May. Appended to Anchor QEA, LLC. 2011.
- Tolkova, E. 2013. Tide-tsunami interaction in the Columbia River, as implied by historical data and numerical simulations. *Pure and Applied Geophysics* 170(6-8):1115–1126.
- U.S. Geological Survey. 2013. Earthquake Monitoring at Mount St. Helens. August 15. Available: http://volcanoes.usgs.gov/volcanoes/st_helens/st_helens_monitoring_102.html. Accessed: April 2, 2014.
- URS Corporation. 2014a. *Millennium Coal Export Terminal, Longview, Washington – Earth Resource Report*. September.
- URS Corporation. 2014b. *Millennium Coal Export Terminal, Longview, Washington – Off-Site Alternative – Barlow Point Appendix C Earth Resource Report*. November 2014. 17pp.
- Vonheeder, E. R. 1977. Cowlitz County, Washington, coal resources, Washington. Washington Division of Geology and Earth Resources Open File Report 77-5, 1 p., 2 plates. Available: www.dnr.wa.gov/publications/ger_ofr77-5_coal_cowlitz_co_130k.pdf; Accessed April 2, 2014.
- Walsh, T. J., C. G. Curuthers, A. C. Heinitz, E. P. Meyers, A. M. Baptista, G. B. Erdakos, and R. A. Kamphaus. 2000. Tsunami hazard map of the southern Washington coast – modeled tsunami inundation from a Cascadia subduction zone earthquake. Washington Division of Geology and Earth Resources Geologic Map GM-49, 1 sheet, scale 1:100,000, with 12p. text.
- Washington State Department of Ecology. 2014. *2012 Stormwater Management Manual for Western Washington*. Amended December 2014. Publication No. 14-10-055.
- Washington State Department of Natural Resources. 2001. Nisqually earthquake issue. *Washington Geology* 8(3).
- Washington State Department of Natural Resources. 2010. Tsunami inundation maps (in alphabetical order by name). Division of Geology and Earth Resources. Available: http://www.dnr.wa.gov/Publications/ger_tsunami_inundation_maps.pdf. Accessed: April 2, 2014).
- Washington State Department of Natural Resources. 2014a. *Geology of Washington – Portland Basin*. Available: <http://www.dnr.wa.gov/ResearchScience/Topics/GeologyofWashington/Pages/portland.aspx>. Accessed: April 2, 2014.
- Washington State Department of Natural Resources. 2014b. *Washington Interactive Geologic Map*. Division of Geology and Earth Resources. Available: www.dnr.wa.gov/ResearchScience/Topics/GeosciencesData/Pages/geology_portal.aspx and <https://fortress.wa.gov/dnr/geology/?Theme=wigm>). Accessed: April 2, 2014.
- Washington State Department of Transportation. 2014. *Geotechnical Design Manual*. August. Revision Package M 46-03.10.
- Washington State Seismic Safety Committee. 2012. *Resilient Washington State – A Framework for Minimizing Loss and Improving Statewide Recovery after an Earthquake*. Final report and recommendations. November.

- Wegmann, K. W. 2006. Digital landslide inventory for the Cowlitz County urban corridor, Washington. Washington Division of Geology and Earth Resources Report of Investigations 35, version 1.0. May.
- Wolfe, E. W., and T. C. Pierson. 1995. Volcanic-Hazard Zonation for Mount St. Helens, Washington. U.S. Geological Survey Open-File Report 95-497. Available: <http://pubs.usgs.gov/of/1995/0497/>. Accessed: April 2, 2014.
- Wong, I., W. Silva, J. Bott, D. Wright, P. Thomas, N. Gregor, L. Li, M. Mabey, A. Sojourner, and Y. Wang. 2000. Earthquake scenario and probabilistic ground shaking maps for the Portland, Oregon, metropolitan area. Oregon Department of Geology and Mineral Resources, Interpretive Map Series IMS-16.
- Yeh, H., E. Tolkova, D. Jay, S. Talke, and H. Fritz. 2012. Tsunami hydrodynamics in the Columbia River. *Journal of Disaster Research* 7(5):604–608.

MILLENNIUM BULK TERMINALS—LONGVIEW NEPA ENVIRONMENTAL IMPACT STATEMENT

NEPA SURFACE WATER AND FLOODPLAINS TECHNICAL REPORT

PREPARED FOR:

U.S. Army Corps of Engineers, Seattle District
4735 East Marginal Way South
Seattle, WA 98134

PREPARED BY:

ICF International
710 Second Ave, Suite 550
Seattle, WA 98104

September 2016



ICF International. 2016. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Surface Water and Floodplains Technical Report*. September. (ICF 000264.13) Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.

Contents

List of Tables	ii
List of Figures.....	ii
List of Acronyms and Abbreviations.....	iii
Chapter 1 Introduction	1-1
1.1 Project Description	1-1
1.1.1 On-Site Alternative	1-1
1.1.2 Off-Site Alternative	1-4
1.1.3 No-Action Alternative	1-6
1.2 Regulatory Setting.....	1-6
1.3 Study Areas	1-9
1.3.1 On-Site Alternative	1-9
1.3.2 Off-Site Alternative	1-9
Chapter 2 Affected Environment.....	2-1
2.1 Methods.....	2-1
2.1.1 Data Sources	2-1
2.1.2 Impact Analysis	2-2
2.2 Affected Environment.....	2-3
Chapter 3 Impacts	3-1
3.1 On-Site Alternative	3-1
3.1.1 Construction: Direct Impacts	3-1
3.1.2 Construction: Indirect Impacts	3-3
3.1.3 Operations: Direct Impacts	3-3
3.1.4 Operations: Indirect Impacts	3-10
3.2 Off-Site Alternative	3-11
3.2.1 Construction: Direct Impacts	3-11
3.2.2 Construction: Indirect Impacts	3-12
3.2.3 Operations: Direct Impacts	3-12
3.2.4 Operations: Indirect Impacts	3-12
3.3 No-Action Alternative	3-13
Chapter 4 Required Permits.....	4-1
4.1 On-Site Alternative	4-1
4.2 Off-Site Alternative	4-2
Chapter 5 References	5-1

Tables

1	Regulations, Statutes, and Guidelines for Floodplains	1-6
2	Tidal Station 9440422—Longview	2-4
3	Tidal Heights at Tidal Station 9440422—Longview	2-5
4	Summary of Proposed Changes to Stormwater Collection and Discharge by Basin	3-6
5	Proposed Changes to Water Collection and Discharge in Volume and Rate of Discharge.....	3-9

Figures

1	Project Vicinity	1-2
2	On-Site Alternative.....	1-3
3	Off-Site Alternative	1-5
4	Surface Water Study Area for the On-Site Alternative	1-10
5	Floodplain Study Area On-Site Alternative	1-11
6	Surface Water Study Area for the Off-Site Alternative.....	1-12
7	Floodplain Study Area for the Off-Site Alternative	1-13
8	Existing Site Drainage System for the On-Site Alternative	2-9
9	Proposed Drainage Plan for the On-Site Alternative	3-5

Acronyms and Abbreviations

Applicant	Millennium Bulk Terminals—Longview, LLC
BMP	best management practice
BNSF	BNSF Railway Company
CCC	Cowlitz County Code
CDID	Consolidated Diking Improvement District
CEQ	Council on Environmental Quality
CFR	Code of Federal Regulations
cfs	cubic feet per second
Corps	U.S. Army Corps of Engineers
CRD	Columbia River Datum
Ecology	Washington State Department of Ecology
EPA	U.S. Environmental Protection Agency
FEMA	Federal Emergency Management Agency
FIRM	Flood Insurance Rate Map
MSL	Mean Sea Level
NAVD88	North American Vertical Datum of 1988
NEPA	National Environmental Policy Act
NFIP	National Flood Insurance Program
NGVD29	National Geodetic Vertical Datum of 1929
NPDES	National Pollutant Discharge Elimination System
RCW	Revised Code of Washington
Reynolds facility	Reynolds Metals Company facility
SEPA	State Environmental Policy Act
SWMP	stormwater management plan
UP	Union Pacific Railroad
USC	United States Code
USGS	U.S. Geological Survey
WAC	Washington Administrative Code
WRIAs	Water Resource Inventory Areas

This technical report assesses the potential surface water and floodplains impacts of the proposed Millennium Bulk Terminals—Longview project (On-Site Alternative), Off-Site Alternative and No-Action Alternative. For the purposes of this assessment, surface water and floodplains refers to on-site drainage, the Consolidated Diking Improvement District (CDID) #1, the Columbia River, and the Columbia River and Cowlitz River floodplain. This report describes the regulatory setting, establishes the method for assessing potential surface water and floodplains impacts, presents the historical and current surface water and floodplain conditions in the study areas, and assesses the potential for impacts on surface water and floodplains.

1.1 Project Description

Millennium Bulk Terminals—Longview, LLC (Applicant) proposes to construct and operate an export terminal in Cowlitz County, Washington, along the Columbia River (Figure 1). The export terminal would receive coal from the Powder River Basin in Montana and Wyoming and the Uinta Basin in Utah and Colorado via rail shipment, then load and transport the coal by ocean-going ships via the Columbia River and Pacific Ocean to overseas markets in Asia. The export terminal would be capable of receiving, stockpiling, blending, and loading coal by conveyor onto ships for export. Construction of the export terminal would begin in 2018. For the purpose of this analysis, it is assumed the export terminal would operate at full capacity by 2028. The following subsections present a summary of the On-Site Alternative, Off-Site Alternative, and No-Action Alternative.

1.1.1 On-Site Alternative

Under the On-Site Alternative, the Applicant would develop an export terminal on 190 acres (project area). The project area is located within an existing 540-acre area currently leased by the Applicant at the former Reynolds Metals Company facility (Reynolds facility), and land currently owned by Bonneville Power Administration. The project area is adjacent to the Columbia River in unincorporated Cowlitz County, Washington near Longview city limits (Figure 2).

The Applicant currently and separately operates at the Reynolds facility, and would continue to separately operate a bulk product terminal on land leased by the Applicant. Industrial Way (State Route 432) provides vehicular access to the Applicant's leased land. The Reynolds Lead and the BNSF Spur rail lines, both operated by Longview Switching Company (LVSW),¹ provide rail access to the Applicant's leased area from the BNSF Railway Company (BNSF) main line (Longview Junction) located to the east in Kelso, Washington. Ships access the Applicant's leased area including the bulk product terminal via the Columbia River and berth at an existing dock (Dock 1) operated by the Applicant in the Columbia River.

¹ LVSW is jointly owned by BNSF Railway Company (BNSF) and Union Pacific Railroad (UP).



Figure 1. Project Vicinity

Figure 2. On-Site Alternative

Under the On-Site Alternative, BNSF or Union Pacific Railroad (UP) trains would transport coal in rail cars from the BNSF main line at Longview Junction to the project area via the BNSF Spur and Reynolds Lead. Coal would be unloaded from rail cars, stockpiled and blended, and loaded by conveyor onto ocean-going ships at two new docks (Docks 2 and 3) on the Columbia River for export to Asia.

Once construction is complete, the export terminal would have an annual throughput capacity of up to 44 million metric tons of coal. The export terminal would consist of one operating rail track, eight rail tracks for the storage of rail cars, rail car unloading facilities, stockpile areas for coal storage, conveyor and reclaiming facilities, two new docks in the Columbia River (Docks 2 and 3), and ship-loading facilities on the two docks. Dredging of the Columbia River would be required to provide access to and from the Columbia River navigation channel and for berthing at the two new docks.

Vehicles would access the project area from Industrial Way (State Route 432). Ships would access the project area via the Columbia River and berth at one of the two new docks. Trains would access the export terminal via the BNSF Spur and the Reynolds Lead. Terminal operations would occur 24 hours per day, 7 days per week. The export terminal would be designed for a minimum 30-year period of operation.

1.1.2 Off-Site Alternative

Under the Off-Site Alternative, the export terminal would be developed on an approximately 220-acre site adjacent to the Columbia River, located in both Longview, Washington, and unincorporated Cowlitz County, Washington, in an area commonly referred to as Barlow Point (Figure 3). The project area for the Off Site Alternative is west and downstream of the project area for the On-Site Alternative. Most of the project area for the Off-Site Alternative is located within Longview city limits and owned by the Port of Longview. The remainder of the project area is within unincorporated Cowlitz County and privately owned.

Under the Off-Site Alternative, BNSF or UP trains would transport coal from the BNSF main line at Longview Junction over the BNSF Spur and the Reynolds Lead, which would be extended approximately 2,500 feet to the west. Coal would be unloaded from rail cars, stockpiled and blended, and loaded by conveyor onto ocean-going ships at two new docks (Docks A and B) on the Columbia River. The Off-Site Alternative would serve the same purpose as the On-Site Alternative.

Once construction is complete, the Off-Site Alternative would have an annual throughput capacity of up to 44 million metric tons of coal. The export terminal would consist of the same elements as the On-Site Alternative: one operating rail track, eight rail tracks for the storage of rail cars, rail car unloading facilities, stockpile areas for coal storage, conveyor and reclaiming facilities, two new docks in the Columbia River (Docks A and B), and ship-loading facilities on the two docks. Dredging of the Columbia River would be required to provide access to and from the Columbia River navigation channel and for berthing at the two new docks.

Vehicles would access the project area via a new access road extending from Mount Solo Road (State Route 432) to the project area. Trains would access the terminal via the BNSF Spur and the extended Reynolds Lead. Ships would access the project area via the Columbia River and berth at one of the two new docks. Terminal operations would occur 24 hours per day, 7 days per week. The export terminal would be designed for a minimum 30-year period of operation.

[illegible]

1.1.3 No-Action Alternative

Under the No-Action Alternative, the U.S. Army Corps of Engineers would not issue the requested Department of the Army permit under the Clean Water Act Section 404 and the Rivers and Harbors Act Section 10. This permit is necessary to allow the Applicant to construct and operate the proposed export terminal.

The Applicant plans to continue operating its existing bulk product terminal located adjacent to the On-Site Alternative project area, as well as expand this business whether or not a Department of the Army permit is issued. Ongoing operations would include storing and transporting alumina and small quantities of coal, and continued use of Dock 1. Maintenance of the existing bulk product terminal would continue, including maintenance dredging at the existing dock every 2 to 3 years. Under the terms of an existing lease, expanded operations could include increased storage and upland transfer of bulk products utilizing new and existing buildings. The Applicant would likely undertake demolition, construction, and other related activities to develop expanded bulk product terminal facilities.

In addition to the current and planned activities, if the requested permit is not issued, the Applicant would intend to expand its bulk product terminal business onto areas that would have been subject to construction and operation of the proposed export terminal. In 2014, the Applicant described a future expansion scenario under No-Action Alternative that would involve handling bulk materials already permitted for off-loading at Dock 1. Additional bulk product transfer activities could involve products such as a calcine pet coke, coal tar pitch, cement, fly ash, and sand or gravel. While future expansion of the Applicant's bulk product terminal business might not be limited to this scenario, it was analyzed to help provide context to a No-Action Alternative evaluation and because it is a reasonably foreseeable consequence of a Department of the Army denial.

1.2 Regulatory Setting

Federal, state, and local regulations, statutes, and guidelines require the review of the possible environmental impacts of the proposed export terminal at the On-Site Alternative or Off-Site Alternative location, including potential impacts on surface water and floodplains. The jurisdictional authorities and corresponding regulations, statutes, and guidance for determining potential aesthetic impacts are summarized in Table 1.

Table 1. Regulations, Statutes, and Guidelines for Floodplains

Regulation, Statute, Guideline	Description
Federal	
National Environmental Policy Act (42 USC 4321 <i>et seq.</i>)	Requires the consideration of potential environmental effects. NEPA implementation procedures are set forth in the President's Council on Environmental Quality's Regulations for Implementing NEPA (49 CFR 1105).
U.S. Army Corps of Engineers NEPA Environmental Regulations (33 CFR 230)	Provides guidance for implementing the procedural provisions of NEPA for the Corps. It supplements CEQ regulations 40 CFR 1500–1508.

Regulation, Statute, Guideline	Description
Rivers and Harbors Act of 1899	Authorizes the Corps to protect commerce in navigable streams and waterways of the United States by regulating various activities in such waters. Section 10 (33 USC 403) specifically regulates construction, excavation, or deposition of materials into, over, or under navigable waters, or any work that would affect the course, location, condition, or capacity of those waters.
Clean Water Act (33 USC 1251 <i>et seq.</i>)	Establishes the basic structure for EPA to regulate discharges of pollutants into the waters of the United States and regulating quality standards for surface water.
Section 404 of the Clean Water Act	Regulates the placement of dredged or fill material into waters of the United States, including special aquatic sites such as sanctuaries and refuges, wetlands, mudflats, vegetated shallows, coral reefs, and riffle and pool complexes. EPA is the agency responsible for enforcing this act.
Section 401 of the Clean Water Act	Requires that a water quality certification be obtained from Ecology for any activity that requires a federal permit or license to discharge any pollutant into a water of the United States. This certification attests that the state has reasonable assurance that the proposed activity would meet state water quality standards.
Sections 301 and 402 of the Clean Water Act	Prohibits the discharge of any pollutant to a water of the United States without a permit. Section 402 (33 USC 1342) establishes the NPDES permitting program, under which such discharges are regulated.
National Flood Insurance Act of 1968	Established the NFIP, a federal floodplain management program designed to reduce future flood losses nationwide through the implementation of community-enforced building and zoning ordinances in return for the provision of affordable, federally backed flood insurance to property owners. FEMA is the agency responsible for enforcing the National Flood Insurance Act.
Executive Order 11990, Protection of Wetlands	Applies to all agencies managing federal lands, sponsoring federal projects, or providing federal funds to state or local projects. EPA is the agency responsible for enforcing this Executive Order.
Executive Order 11988, Floodplain Management	Requires federal agencies to avoid, to the extent possible, the long- and short-term adverse impacts associated with the occupancy and modification of floodplains and to avoid direct and indirect support of floodplain development wherever there is a practicable alternative (42 FR 26951). FEMA is the agency responsible for enforcing this Executive Order.
State	
Washington State Environmental Policy Act (WAC 197-11, RCW 43.21C)	Requires state and local agencies in Washington to identify potential environmental impacts that could result from governmental decisions.

Regulation, Statute, Guideline	Description
Water Resources Act of 1971 (RCW 90.54)	Sets forth fundamental policies for the state to ensure that waters of the state are protected and fully utilized for the greatest benefit. Ecology is the agency responsible for enforcing the Water Resources Act.
Water Pollution Control (RCW 90.48)	Policy to maintain the purity of waters of the state consistent with public health and public enjoyment, as well as propagation and protection of wildlife and industrial development of the state, and to that end require the use of all known available and reasonable methods by industries and others to prevent and control the pollution of the waters of the state.
Water Quality Standard for Surface Waters of the State of Washington (173-201A WAC)	Establishes water quality standards for surface waters of the state of Washington.
Shoreline Management Act	Regulates and manages the use, environmental protection, and public access of the state's shorelines. The Shoreline Management Act (RCW 90.58) was passed by the Washington State Legislature in 1971 and adopted in 1972. Ecology is the agency responsible for enforcing the Shoreline Management Act.
Local	
Cowlitz County SEPA Regulations (CCC Code 19.11)	Provide for the implementation of SEPA in Cowlitz County.
Cowlitz County Stormwater Drainage Ordinance	The Cowlitz County Stormwater Drainage Ordinance is a requirement of the NPDES Phase II Municipal Stormwater Permit issued to Cowlitz County by Ecology. The permit requires Cowlitz County to reduce stormwater runoff and pollution in unincorporated areas of Cowlitz County adjacent to the City of Longview and City of Kelso. The On-Site Alternative or Off-Site Alternative would not be within the area affected by the NPDES Phase II Municipal Stormwater Permit.
Cowlitz County Phase II Municipal Stormwater Management Plan	Requires Cowlitz County to develop a SWMP. The SWMP must incorporate best management practices to reduce the discharge of pollutants from the regulated area to the maximum extent practicable to protect water quality. Cowlitz County is responsible for enforcing the SWMP.
Cowlitz County Critical Areas Ordinance	Requires Cowlitz County, in compliance with the Growth Management Act, to adopt development regulations based upon the best available science that assure the protection of critical areas such as wetlands, aquifer recharge areas, geologically hazardous areas, fish and wildlife habitat, and frequently flooded areas. Cowlitz County is responsible for enforcing this ordinance.
Cowlitz County Shoreline Master Program	Requires Cowlitz County to provide for the enhancement of shorelines and protection against adverse effects to vegetation, wildlife, and waters of the state and their aquatic life.

Regulation, Statute, Guideline	Description
Notes: USC = United States Code; NEPA = National Environmental Policy Act; CFR = Code of Federal Regulations; CEQ = Council on Environmental Quality; EPA = U.S. Environmental Protection Agency; Corps = U.S. Army Corps of Engineers; Ecology = Washington State Department of Ecology; NPDES = National Pollutant Discharge Elimination System; NFIP = National Flood Insurance Program; FEMA = Federal Emergency Management Agency; WAC = Washington Administrative Code; RCW = Revised Code of Washington; CCC = Cowlitz County Code; City = City of Longview; SWMP = stormwater management plan	

1.3 Study Areas

The study areas for the On-Site Alternative and Off-Site Alternative are described below.

1.3.1 On-Site Alternative

The study area for direct impacts on surface water is the portion of the Columbia River and stormwater drainage ditches within and adjacent to the project area for the On-Site Alternative. The study area for indirect impacts on surface water encompasses the CDID #1 stormwater system drainage ditches adjacent to the project area for the On-Site Alternative and the Columbia River downstream 1 mile from the project area. Figure 4 shows the study areas for surface water for the On-Site Alternative.

The study area for direct impacts on floodplains is the project area for the On-Site Alternative. The study area for indirect impacts on floodplains is the project area and surrounding 500-year floodplain on the north side of the Columbia River around the project area. The indirect impact study area extends 1 mile from the direct impact study area unless there is no mapped floodplain, or if a levee or ditch is present that could affect flooding. Figure 5 shows the study area for floodplains.

1.3.2 Off-Site Alternative

Similar to the On-Site Alternative, the study area for direct impacts on surface water is the portion of the Columbia River and stormwater drainage ditches within and adjacent to the project area for the Off-Site Alternative. The study area for indirect impacts on surface water encompasses the CDID #1 stormwater system drainage ditches adjacent to the project area for the Off-Site Alternative and the Columbia River downstream 1 mile from the project area. Figure 6 shows the study areas for surface water for the Off-Site Alternative.

The study area for direct impacts on floodplains is the project area for the Off-Site Alternative. The study area for indirect impacts is the project area and surrounding 500-year floodplain on the north side of the Columbia River around the project area. The indirect impact study area extends 1 mile from the direct impact study area unless there is no mapped floodplain, or if a levee or ditch is present that could affect flooding. Figure 7 shows the study area for floodplains for the Off-Site Alternative.

Figure 4. Surface Water Study Area for the On-Site Alternative


Figure 5. Floodplain Study Area On-Site Alternative



Figure 6. Surface Water Study Area for the Off-Site Alternative

Figure 7. Floodplain Study Area for the Off-Site Alternative

Chapter 2

Affected Environment

This chapter describes the methods and sources of information used to evaluate the potential impacts on surface waters and floodplains associated with the construction and operation of the proposed export terminal.

2.1 Methods

This section describes the methods used to characterize the affected environment and assess the potential impacts of the proposed export terminal on surface water and floodplains.

The affected environment related to surface waters and floodplains in the study areas and the evaluation of the potential effects of the On-Site Alternative or Off-Site Alternative are based on various reports and other pertinent literature (Section 2.1.1, *Data Sources*). No field surveys were conducted to prepare this report. The *Engineering Report for NPDES Application Millennium Bulk Terminals—Longview, LLC* (Anchor QEA 2011) was used to establish baseline conditions for on-site surface water conditions. Designations from the Washington State Department of Ecology (Ecology) and the Oregon Department of Environmental Quality were reviewed to establish environmental baseline conditions for the Columbia River. The impact analysis involved evaluating the potential changes the proposed project could have on surface waters and floodplains.

2.1.1 Data Sources

The following sources of information were used to characterize the study areas.

- *Engineering Report for NPDES Application Millennium Bulk Terminals—Longview, LLC* (Anchor QEA 2011)
- *Engineering Report Update for NPDES Application Millennium Bulk Terminals—Longview, LLC* (Anchor QEA 2014)
- CDID #1 website
- *Columbia River Basin: State of the River Report for Toxics* (U.S. Environmental Protection Agency 2009)
- *Diminishing Returns: Salmon Declines and Pesticides* (Ewing 1999)
- *Millennium Coal Export Terminal Longview, Washington: Permanent Impacts to Aquatic Habitat* (Grette Associates, LLC 2014a)
- *Millennium Coal Export Terminal Longview, Washington: Off-Site Alternative—Barlow Point Permanent Impacts to Aquatic Habitat* (Grette Associates, LLC 2014b)
- *Columbia River Estuary ESA Recovery Module for Salmon and Steelhead* (National Marine Fisheries Service 2011)
- Columbia River Estuary Operational Forecast System website

- *Designated Beneficial Uses Mainstem Columbia River 340-41-0101* (Oregon Department of Environmental Quality 2003)
- *303(d)/305(b) Integrated Water Quality Assessment Report* (Oregon Department of Environmental Quality 2012)
- *Millennium Coal Export Terminal Longview, Washington: Water Resource Report Supplemental* (URS Corporation 2014a)
- *Millennium Coal Export Terminal Longview, Washington. Affected Environment Analysis – Water Resources* (URS Corporation 2014b)
- *Millennium Coal Export Terminal Longview, Washington: Water Collection and Drainage Package.* (URS Corporation 2014c)
- *Millennium Coal Export Terminal Longview, Washington: Water Management Plan* (URS Corporation 2014d)
- *Millennium Coal Export Terminal Longview, Washington: Water Balance Calculation* (URS Corporation 2014e)
- U.S. Geological Survey (USGS) water-quality data, Columbia River Estuary, 2004–2005 (U.S. Geological Survey 2005)
- USGS water-quality data, Columbia River at Dalles, Oregon, 2012 (USGS 14105700)
- *Stormwater Management Manual for Western Washington* (Washington State Department of Ecology 2012)
- Columbia River facts and maps website (Washington State Department of Ecology 2014a)
- Grays-Elochoman, Cowlitz River Basins Water Resource Management Programs (Washington State Department of Ecology 2014b)
- Other literature, as cited in the text

2.1.2 Impact Analysis

The following methods were used to evaluate the potential impacts of the On-Site Alternative, Off-Site Alternative, and No-Action Alternative on surface waters and floodplains. This impact analysis evaluates how surface water conditions could affect the project area.

Potential surface water and floodplain impacts have been evaluated with respect to how the On-Site Alternative, Off-Site Alternative, and No-Action Alternative could affect certain parameters such as changes to surface water drainage, surface water discharge, and floodplain connectivity. The assessment of impacts is also based on regulatory controls and the assumption that the On-Site Alternative, Off-Site Alternative would include the following elements.

On-Site Alternative:

- An individual and general construction National Pollutant Discharge Elimination System (NPDES) permit for stormwater discharges and for stormwater improvements.

Off-Site Alternative:

- An individual and general construction NPDES permit for stormwater discharges and for the stormwater improvements.

For the purpose of this analysis, construction impacts are based on peak construction period and operations impacts are based on maximum throughput capacity (up to 44 million metric tons per year).

2.2 Affected Environment

The affected environment related to floodplains in the study areas is described below.

2.2.1 On-Site Alternative

In general, the project area is protected by a robust levee system operated and maintained by CDID #1. CDID #1 also operates and maintains a series of ditches and pump stations that receive surface water and shallow groundwater inflow that originates on the project area, as well as other adjacent areas and Longview. In addition, the Applicant now operates and maintains independent stormwater and facility process water treatment and conveyance facilities for the project area. Ultimately, all of these waters are discharged to the Columbia River as groundwater, surface water, or treated stormwater discharge.

The project area is located on the right-bank floodplain of the Columbia River near river mile 63 near Longview (Figure 4). The project area is generally protected from Columbia River flooding by a levee that was originally constructed in the 1920s and then improved in 1949. Project area topography is relatively flat.

2.2.1.1 Columbia River

The Columbia River basin comprises 260,000 square miles from its headwaters in British Columbia, Canada, to its mouth in Astoria, Oregon, bordering Washington and Oregon. The basin includes parts of seven states, 13 federally recognized Native American reservations, and one Canadian province; 19% of the watershed is in Washington. The average annual flow for the Columbia River at Beaver Army Terminal near Quincy, Oregon,² is approximately 236,600 cubic feet per second (cfs) (1 cfs = 448.8 gallons per minute). The river's annual discharge rate fluctuates with precipitation and ranges from 63,600 cfs in a low water year to 864,000 cfs in a high water year (U.S. Geological Survey 2014).

The Columbia River, downstream from the U.S.-Canadian border has been identified by the US Fish and Wildlife Service (USFWS) and the National Marine Fisheries Service (NMFS) as a flow-exempt water body, which is to say that it is exempt from flow control requirements associated with the detention/retention and discharge of stormwater. However, water quality criteria must still be met for all stormwater discharges.

Dam construction began in the early 20th century for flood control and power production. Today, a major dam is located on average every 72 miles in the Columbia River watershed (Bonneville Power Administration 2001). After dams were constructed along the river, the flow regime of the river changed substantially. Records kept since 1878 show that flows were much higher in the spring and lower in winter before dam construction. In addition, the velocity of the water moving down the river was significantly greater before dam construction began in the 1930s. In 1917, Washington

² Approximately 12 river miles downstream of the project area.

adopted a water code to help manage water allocations from surface water bodies in the state, including the Columbia River.

Since the water code was adopted, the state has allocated 768 surface water and 1,379 groundwater rights on the mainstem Columbia River. These Columbia River water users have the right to take approximately 13,000 cfs in instantaneous withdrawals from April through October, when most crops are grown in the basin. The total annual withdrawal from the mainstem Columbia River during the growing season is about 4.7 million acre-feet of water (1 acre-foot = 325,851 gallons, enough water to cover 1 square acre of land to a depth of 12 inches).

The Bureau of Land Management is the single largest water user on the mainstem Columbia River and is allocated about two-thirds of the water from the river. Ecology has allocated 768 surface water and 1,379 groundwater rights on the mainstem Columbia River (Washington State Department of Ecology 2014a).

The lower Columbia River is tidally influenced by the Pacific Ocean from the estuary near Astoria, to Bonneville Dam, located upstream of Portland (Bonneville Power Administration 2001). Tidal fluctuations are diurnal, meaning there are two high tides and two low tides in each 24-hour tidal cycle. Tidal ranges vary along the lower Columbia River and are reported to have a mean range of 3.78 feet at Longview (Table 2).

Table 2. Tidal Station 9440422—Longview

Established	March 23, 1985
Present Installation	March 22, 2002
Mean Tidal Range	3.78 feet
Source: National Oceanic and Atmospheric Administration 2014.	

The Columbia River experiences seasonal variation in flow from year to year depending on snow mass in the upper watershed. To account for this variability and provide a basis for navigation, in 1911 the U.S. Army Corps of Engineers (Corps) established a unique low-water datum on the Columbia River. The datum references the lowest recorded water level at that time and was recorded in Portland, Oregon, on October 6, 1886. This recorded water level became the “zero” of the gage operating there at that time and it has never been changed. This datum is called the Columbia River Datum (CRD).

CRD is primarily maintained by the Corps’ Portland District and is tied to National Geodetic Vertical Datum of 1929 (NGVD29). Elevations of CRD are held at benchmarks along the river basin, and tide gages can be set to these elevations during survey operations. Shortly after the establishment of NGVD29, geodetic ties were made at all possible benchmarks where a tie to CRD existed. The presence of a geodetic tie at a CRD benchmark allows a reference point to which tidal datums can be leveled. For recent hydrographic and photogrammetric surveys, the relationships between CRD, NGVD29, North American Vertical Datum of 1988 (NAVD88), and tidal datums were reconciled at all installed subordinate tide gages and provided to the Office of Coast Survey and National Geodetic Survey (National Oceanic and Atmospheric Administration 2014).

All tidal datums are above CRD for the entire river, in keeping with the original premise of the low water reference datum. Trends of Mean Sea Level (MSL) reveal a slight downward slope from the entrance to upstream. There is a notable drop in MSL near Longview, between the sections of the system under basin influence and those under river influence. The differences between high water

tidal datums and low water tidal datums also change drastically near Longview, with a much larger difference occurring in the estuary entrance than the upper reaches of the river basin (National Oceanic and Atmospheric Administration 2014). This is important to consider when reviewing tidal data upstream and downstream of Longview. Table 3 includes the current reported tidal heights at Longview. Data is presented in CRD, but the comparison to NAVD88 can also be determined.

Table 3. Tidal Heights at Tidal Station 9440422—Longview

Description	Acronym	Height (feet CRD)
Mean Higher High Water	MHHW	6.991
Mean High Water	MHW	6.512
Mean Tide Level	MTL	4.623
Mean Sea Level	MSL	4.475
Mean Low Water	MLW	2.736
Mean Lower Low Water	MLLW	2.382
Columbia River Datum	CRD	0.000
North American Vertical Datum 1988	NAVD88	-2.487

Source: National Oceanic and Atmospheric Administration 2014

CRD is a Corps nontidal datum defined at distinct river miles relative to NAVD88, and is used as chart datum above river mile 23 on the Columbia River. Datums are computed using observations from the low river stages of the year, generally August through October, due to the masking of the tidal signal from strong seasonal river runoff during other times of the year. Depending on river flow, water levels can be significantly higher than Columbia River datums.

NAVD88 and NGVD29 are fixed geodetic datums whose elevation relationships to local MSL and other tidal datums may not be consistent from one location to another. It is not uncommon for datums to become confused and elevations in waterways, especially tidal elevations, to be misrepresented or misreported with errors of several feet. For clarity, the definitions of the most common datums that could be encountered over the course of this analysis are provided below.

- **Mean Sea Level.** MSL is a tidal datum determined over a 19-year National Tidal Datum Epoch. The tidal epoch is based on the lunar cycle and requires an adjustment to all tidal gages each 19-year period. MSL pertains to local MSL and should not be confused with the fixed datum of NGVD29, often casually referred to as “Sea Level Datum” or NAVD88.
- **NGVD29.** NGVD29 is a fixed datum adopted as a national standard geodetic reference for heights but is now considered superseded. NGVD29 is sometimes referred to as Sea Level Datum of 1929 or as MSL on some early issues of Geological Survey Topographic Quads. NGVD29 was originally derived from surveys based on 26 tidal stations (21 in the coastal United States and 5 in coastal Canada), hence the confusion with the name.
- **NAVD88.** NAVD88 is a fixed datum and replaces NGVD29 as the national standard geodetic reference for heights. It is derived from a simultaneous, least squares,³ and minimum constraint adjustment of Canadian/Mexican/United States leveling observations. Local MSL observed at Father Point/Rimouski, Canada, was held fixed as the single initial constraint. While the conversion between NAVD88 and NGVD29 varies at all locations except for Father

³ A mathematical procedure for finding the best-fitting curve to a given set of points by minimizing the sum of the squares of the offsets (the residuals) of the points from the curve.

Point/Rimouski, Canada, that at all other locations NAVD88 is lower than NGVD 29 and should, therefore, be reported with a larger elevation.

2.2.1.2 Water Resource Inventory Area 25

A watershed generally has a topographic boundary that defines an area draining to a single point of interest. Precipitation falling on a ridgeline of a mountain would drain into one watershed or the other depending on which side of the ridge the rain falls. Ecology and other state natural resources agencies have divided Washington State into 62 Water Resource Inventory Areas (WRIAs) to delineate and manage the state's major watersheds. The project area is located in WRIA 25, the Grays/Elochoman Basin.

2.2.1.3 Consolidated Diking Improvement District No. 1

The study area for the On-Site Alternative is surrounded and protected by the levees, ditches, and pump stations of CDID #1, which consists of 19 miles of levees, including the Columbia River levee; over 35 miles of sloughs, ditches, and drains for flood protection; a stormwater collection and routing system; and seven pump stations for removing and discharging stormwater to receiving waters outside of the levee system, such as the Columbia River. The combined capacity of the seven pump stations (19 pumps across these stations) is 700,000 gallons per minute. These pump stations are instrumental for removing stormwater and preventing local and area-wide flooding. The need for this pumping capacity is apparent when considering 1 inch of rain falling on the 16,000-acre watershed is equivalent to 434-million gallons of water. Removal of 4.8 inches of rain deposited from a 1986 storm required 54 hours of continuous pumping. These components work together to keep the local community dry. Information presented below is available on the CDID #1 website (Consolidated Diking Improvement District No. 1 2014).

In 1923, six separate diking districts were merged to form CDID #1. CDID #1 worked with the Corps to raise the levees in 1949. The facilities described below are in the project area and are currently operated and maintained by CDID #1.

Columbia River Levee

The CDID#1 levee system can be divided into three major segments, but the project area is primarily protected by the Columbia River levee segment. This levee protects the project area from flooding along the Columbia River and from related backwater elevations in Coal Creek Slough. It extends from the main pump station and office complex around the western edge of Longview and unincorporated portions of Cowlitz County, up the Columbia River to its confluence with the Cowlitz River. The levee is a mixture of well-defined rural levees and overbuilt sections associated with urbanized levees through industrial areas.

Vegetation on the levees is controlled through system-wide mowing, typically occurring at the beginning and middle of the growing season. The tops of all levees are maintained with a drivable surface for vehicle access. Regular patrols identify issues that could affect access for maintenance or emergency purposes such as unwanted vegetation, illegal dumping, abandoned vehicles, and unauthorized structures.

In addition to ongoing inspections conducted by CDID #1 personnel, CDID #1 participates in two inspection programs overseen by the Corps. These programs, identified below, ensure that the

operations and maintenance work undertaken by CDID #1 is in conformance with applicable federal standards.

- **Rehabilitation and Inspection Program, ER 500-1-1.** Conducted annually, this routine inspection takes approximately 1 day, which involves driving the levee system to assess whether the flood control works would continue to provide the intended degree of flood protection and determine if the maintenance program is adequate.
- **Periodic Inspection, National Levee Safety Program Act of 2007.** Conducted every 5 years, this is a more thorough review of all levee and stormwater removal systems. The inspection is conducted entirely on foot, takes approximately 4 days to complete, and consists of a large multidisciplinary team of engineers.

Pump Stations

CDID #1 operates seven pumping stations with 19 pumps. The combined water capacity of these pumps is 700,000 gallons per minute. These pump stations are located throughout the greater Longview area and are instrumental for removing stormwater and preventing local and area-wide flooding. The two pumps of primary interest in the project vicinity are the Reynolds Pump Station and the Industrial Way Pump Station.

- **Reynolds Pump Station.** The Reynolds Pump Station is located at the terminus of Ditch 14, adjacent to the Columbia River. This pump station draws water from Ditch 10 and pumps directly to the Columbia River. Total pumping capacity is 80,000 gallons per minute.
- **Industrial Way Pump Station.** The Industrial Way Pump Station is located adjacent to Ditch 5 and Industrial Way. It has a pumping capacity of 90,000 gallons per minute and pumps water a distance of nearly 0.5 mile, where it discharges to the Columbia River through the levee at the east end of the project area.

To provide additional safeguards against system failure and oversight of individual pump stations, CDID #1 maintains a radio-operated Supervisory Control and Data Acquisition system. This system performs real-time tracking of water-surface elevations, operational status, and alarm conditions for each facility and provides a visual readout to staff at the CDID #1 office, maintenance office, and main pump station. This system enables CDID #1 staff to respond quickly to issues that need attention and logs data that could be useful for troubleshooting system failures if they occur.

Sloughs, Ditches, and Drains

CDID #1 maintains approximately 35 miles of sloughs, ditches, and drains that collect and convey stormwater to the CDID #1 pump stations. There are 15 numbered ditches and 31 numbered drains, together with cutoff sloughs and one bypass ditch. The drainage ditch system is composed of a combination of human-made ditches and altered natural channels. Longview is built on a natural floodplain and the levees—which prevent the river flood waters from inundating the city—also prevents stormwater, which falls behind the levees from escaping.

The ditches have a dual function, acting as a conveyance system to transport stormwater to the pumping stations and as a storage reservoir for intense rainfalls exceeding the capacity of the pumps. The Columbia River is the ultimate destination of the drainage water.

The sloughs, ditches, and drains are maintained on a regular rotational basis. Maintenance work involves cleaning ditches of mud and debris, clearing and removing vegetation and mowing on the

banks and areas above water level, and repairing ditch banks that have eroded or slumped. The majority of ditches and drains are accessible by vehicle along at least one bank, and maintenance is performed using excavation equipment (backhoe, track hoe, etc.) with the removed material being applied to the drainage way bank or placed in a dump truck and hauled to an approved disposal site. Some submerged vegetation is treated chemically. These treatments are contracted to a State of Washington-certified contractor for performing this type of work and are performed in compliance with local, state, and federal laws governing such operations.

Below is a description of the CDID #1 ditches located on or adjacent to the project area.

- **Ditch 5.** Ditch 5 borders the eastern edge of Parcel 10213 and extends south from 38th Avenue to the Industrial Way Pump Station along Industrial Way, which pumps water to the Columbia River via an underground pipe. A second branch of Ditch 5 extends from the pump station southeast along the north side of Industrial Way to Washington Way. It connects with other drainage ditches (Ditch 1 and Ditch 3) and conveys flow to the pump station.
- **Ditch 10.** North of Industrial Way, Ditch 10 extends west from 38th Avenue, crosses under Industrial Way through a culvert, then turns northwest, eventually connecting to other segments of the drainage system including Ditch 14 and Ditch 16. Ditch 14 conveys flow south to the Reynolds Pump Station, which discharges to the Columbia River through an underground pipe. South of Industrial Way, Ditch 10 is north of the former cable plant and remnant forested area. Ditch 10 intersects with Ditch 14 (see below) just north of the closed Black Mud Pond facility.
- **Ditch 14.** Ditch 14 is located along the western boundary of the project area and consists of a trapezoidal-shaped drainage ditch that receives flow from Ditch 10, Ditch 16, and other privately owned ditches located both onsite (e.g., Cable Plant Ditch) and off site. It conveys flow toward the south to Reynolds Pump Station, which pumps water under the Columbia River levee.

2.2.1.4 On-Site Drainage

Stormwater and shallow groundwater drainage for the project area is controlled by a system of ditches, pump stations, treatment facilities, and outfalls. All of these facilities operate under a single NPDES permit. As shown in Figure 8, all of the project area drainage is either held onsite to evaporate, discharged to CDID #1 ditches and eventually to the Columbia River, or treated on site and then discharged through Outfall 002A to the Columbia River.

Figure 8. Existing Site Drainage System for the On-Site Alternative

The following is a brief description of the on-site drainage components of the project area.

- **Sheetflow and infiltration.** Subbasin 4A, 5, 5A, 5B, 6A, and 7 receive sheet flow from storm events where it subsequently infiltrates or evaporates.
- **Columbia River discharge.** Subbasins 1, 2, 3A, 4, and 6 are conveyed via pumped systems or gravity to Facility 73 where they are treated and then discharged to the Columbia River via #1 Outfall 002A.
- **CDID discharge.** Subbasin 3 flows through a vegetated ditch that discharges to Ditch 10 through Outfall 003C. During larger storm events, a portion of the flows from Subbasin 2 and Subbasin 5 (both described above) can discharge to the CDID #1 ditch system. Subbasin 2 will overflow the rerouted 006 pump station and discharge to Ditch 14 through Outfall 006. This is a designed overflow system and it is equipped with a high-flow alarm to alert staff when it is activated. Subbasin 5 flows can enter a vegetated ditch that discharges to Ditch 10 through Outfall 005. Ultimately, all CDID #1 ditch flows discharge to the Columbia River.
- **Drainage features on Parcel 10213.** These features include three vegetated ditches, two unvegetated ditches, and a shallow stormwater pond. Two of the vegetated ditches run north-south across the two larger portions of Parcel 10213. They are narrow and linear and convey stormwater to a culvert approximately 16 inches in diameter located on the north end of these ditches, which then empties into CDID Ditch 10. The third vegetated ditch consists of three segments of linear vegetated ditches adjacent to Industrial Way. These three ditch segments are connected by two culverts that are beneath the site's access roads. This feature likely collects stormwater from Industrial Way and adjacent areas and conveys it to CDID Ditch 10.

One unvegetated ditch runs parallel to Ditch 10 and consists of two sections of a narrow ditch that was likely constructed to intercept shallow groundwater affecting agricultural use of the site. This unvegetated ditch is several feet deep, near vertical along its sides, and is bisected by one of the vegetated ditches that runs parallel across the site; however, there is no surface hydrology connection between these two ditches. The other unvegetated ditch serves as the outlet channel for the stormwater pond. This ditch is located at the northeast end of the stormwater pond and conveys excess stormwater from the pond to CDID Ditch 10 through a 16-inch culvert. All six features are privately owned and are not managed by CDID #1.

- **Off-site privately owned ditch.** This ditch is located near the northwest corner of the former Reynolds Metals Plant. It conveys flow into Ditch 14 at a point just north of the closed Black Mud Pond facility.

Outfall 002A

Outfall 002A is a 30-inch outfall to the Columbia River that discharges the water it receives from Facility 73 (the site's stormwater treatment system). Typical flow rates through the outfall are currently less than 2,000 gallons per minute and there is a maximum flow rate of 14,000 gallons per minute.

2.2.1.5 Columbia River and Cowlitz River Floodplain

The project area is located on the right bank floodplain of the Columbia River approximately 5 miles downstream of the confluence of the Cowlitz River and the Columbia River (Figure 1). The Columbia River, from the U.S.-Canadian border downstream, has been identified as a flow-exempt water body,

which is to say that it is exempt from flow control requirements associated with the detention/retention and discharge of stormwater. However, water quality criteria must still be met for all stormwater discharges.

Longview and Kelso were developed on the floodplain of the Columbia River and Cowlitz River. The majority of the project area is behind the Columbia River levee that is operated and maintained by CDID #1. The average elevation of the project area is 13.9 feet NAVD88 (16.4 feet CRD), and the levee averages 33.9 feet NAVD (36.4 feet CRD) (Anchor QEA 2014). The portion of the project area waterward of the Columbia River levee is in the floodway of the Columbia River. Construction and operation of the proposed new docks and trestle would occur on the riverward side of the existing levee. Construction and operations landward of the levee system would be located beyond the 100-year floodplain, but within the 500-year floodplain (Federal Emergency Management Agency 2015a). The City of Longview and the adjacent industrial areas along the Columbia River in unincorporated Cowlitz County are all located within the 500-year floodplain (Figure 5). The 500-year floodplains are those areas that have a 0.2% chance of flooding annually.

CDID #1 operates the slough, ditch, and drain system several feet lower than the low-flow elevation of the Columbia River throughout the year. This strategy provides necessary stormwater storage capacity and allows the pump system to maximize the flood control potential of the levee's interior drainage. The combined capacity of the seven CDID #1 pump stations (19 pumps across these stations) is 700,000 gallons per minute. These pump stations are instrumental for removing stormwater and preventing local and area-wide flooding. The need for this pumping capacity is apparent when considering 1 inch of rain falling on the 16,000-acre watershed is equivalent to 434-million gallons of water. Removal of 4.8 inches of rain deposited from a 1986 storm required 54 hours of continuous pumping.

The Federal Emergency Management Agency (FEMA) Flood Insurance Rate Map (FIRM) maps the project area landward of the CDID #1 Columbia River levee as Zone X (Federal Emergency Management Agency 2015b). Zone X is described by FEMA as follows.

Areas between limits of the 100-year flood and 500-year flood; or certain areas subject to 100-year flooding with average depths less than one (1) foot or where the contributing drainage area is less than one square mile; or areas protected by levees from the base flood (Medium shading).

The current FIRM delineates the project area in “medium shading” and maps the current levee that protects the site.

Flooding at the project area is expected to be minimal under current conditions. The following events could cause flooding.

- Pump station failures
- Precipitation events that exceed pumping capacity
- Levee failure
- Levee overtopping

The portions of the project area (i.e., trestle and dock) located waterward of the levee are within the FEMA-mapped floodway. FEMA defines the floodway as the channel of a river and adjacent land areas that must be reserved in order to discharge the base flood without cumulatively increasing the water surface elevation more than a designated height. Under NFIP regulations, development in floodways must ensure there would be no increase in upstream flood elevations..

2.2.2 Off-Site Alternative

Similar to the On-Site Alternative, the Off-Site Alternative project area is also located on the right bank of the Columbia River and is protected by a robust levee system; however, the Off-Site Alternative project area is undeveloped, other than unpaved access roads, irrigation ditches, and agricultural activity. Similar to the On-Site Alternative, the FEMA FIRM delineates the project area in “medium shading” and maps the current levee that protects the project area; the project area landward of the levee is Zone X – Other Flooded Areas, with a reduced risk due to the levee. This area has a 0.2% chance of flooding annually; also known as the 500-year floodplain. There is a linear band of Zone AE along the waterward side of the levee. Zone AE areas are inundated by the 100-year flood event for which base flood elevations have been determined. Flooding at the project area is expected to be minimal under current conditions. Like the On-Site Alternative, the portions of the project area (i.e., trestle and dock) located waterward of the levee are within the FEMA-mapped floodway.

The project area for the Off-Site Alternative is located approximately 6 miles downstream of the confluence of the Cowlitz River and the Columbia River, and is downstream of the On-Site Alternative project area. Surface water flow and floodplain interactions at the project area for the Off-Site Alternative are anticipated to be the same or similar to those of the project area for the On-Site Alternative, in terms of drainage and infiltration, interaction with the Columbia River, and site-specific hydrology. No developed stormwater system is present on the project area for the Off-Site Alternative, other than irrigation ditches. No direct outfall to the Columbia River is associated with the Off-Site Alternative. All stormwater is either infiltrated or conveyed to CDID #1 ditches and then discharged to the Columbia River at existing CDID #1 pump stations. The project area for the Off-Site Alternative is disconnected from the Columbia River and would not provide floodplain functions such as water storage or fish and wildlife habitat.

Surface water features on or adjacent to the project area for the Off-Site Alternative include the Mount Solo Slough, and Ditch 10, Ditch 14, and Ditch 16. The project area is also crossed by a network of smaller excavated ditches that drain into Mount Solo Slough. Each of these is briefly described below.

Mount Solo Slough. Mount Solo Slough is a privately owned drainage ditch located between the project area for the Off-Site Alternative and the closed Mount Solo landfill that forms the northern boundary of the project area. It is a highly meandering natural drainage that has been historically managed as a drainage ditch. It connects to Ditch 14 to the east and Ditch 16 to the north, both of which both connect to Ditch 10.

Ditch 10. Ditch 10 runs along the south side of Mount Solo Road to the north of the project area. Although it is located entirely offsite, Ditch 10 does connect with Ditch 14, which crosses the eastern portion of the project area, and to Ditch 16, which connects to the north end of Mount Solo Slough.

Ditch 14. Ditch 14 crosses a short section of the eastern portion of the project area, just south of its confluence with Ditch 10.

Ditch 16. Ditch 16 extends between the northern end of Mount Solo Slough and Ditch 10, which runs along Mount Solo Road.

This chapter describes the impacts on surface water and floodplains that would result from construction and operation of the proposed export terminal.

3.1 On-Site Alternative

Potential impacts on surface water and floodplains from the construction and operation of the On-Site Alternative are described below.

The following sections describe the potential impacts related to surface water and floodplains from the constructions and operation of the On-Site Alternative.

The following constructions activities could affect surface water and floodplains.

- Disturbance of surface soils during construction of the export terminal.
- Redirection of drainage and sheet flow during construction.
- Removal of vegetation from leveed floodplain.

The following operations activities could affect surface water and floodplains.

- Use of water from rainfall runoff and on-site wells for dust suppression, washdown water, and fire-protection systems.
- Redirection of stormwater via a new pump station.

3.1.1 Construction: Direct Impacts

Construction of the On-Site Alternative would take place in areas of the Columbia River and landward in a Zone B flood zone, an area within the floodplain that is protected from the base flood by a system of levees.

The following constructions activities at the project area could affect surface water and floodplains.

- Preparing the project area and preloading the coal stockpile areas.
- Regrading the project area to drain toward specific collection areas.
- Constructing the rail loop.
- Installing coal processing equipment (unloading facilities, transfer towers, conveyors).
- Constructing offices, maintenance buildings, and other structures.
- Constructing water-management and storage facilities.
- Construction of Docks 2 and 3 and Removal of Existing Pile Dikes.

The following direct impacts on surface water and floodplains could occur because of construction activities associated with the On-Site Alternative.

Alter Drainage from Heavy Equipment and Staging Areas

Placement of heavy equipment, including but not limited to excavators, pile-driving equipment, forklifts, and rail-track-laying equipment, and establishment of on-site staging areas could redirect sheet flow and potentially lead to localized flooding on- or offsite. Redirection of sheet flow has the potential to create rivulet and/or gully flow across bare soil, which could result in erosion and introduce sediment to the surrounding drainage channels and basins. Introduction of increased sediment loads to the drainage system could change the sediment deposition and transport characteristics of that system, resulting in potential changes in storage, increased channel gradient, and reduced pool depth. In compliance with the required SWPPP that would be prepared and implemented during construction, a majority of the stormwater runoff would be collected and treated prior to discharge to the Columbia River. The potential for localized flooding and increased erosion from redirected sheet flow increases with higher density of heavy equipment placement onsite. This could result in the need for additional channel maintenance. However, this is unlikely because erosion and sediment control BMPs and requirements of the NPDES construction general permit that would be obtained for the proposed project, as described in the NEPA Water Quality Technical Report (ICF International 2016a). Compliance with erosion and sediment control BMPs and NPDES Construction Stormwater General Permit requirements would minimize potential impacts during construction and all measures would be monitored to ensure effectiveness. Weekly inspection and inspection within 24 hours of a rain event would likely be required under the NPDES permit. Inspections must be performed by a Certified Erosion and Sediment Control Lead.

Decrease Floodplain Floodwater Retention

Because the project area is protected by levees, it does not function as a floodplain during events up to the 500-year flood event. Vegetation that would be removed from the project area does not currently contribute to the Columbia River floodplain's ability to retain or absorb floodwaters below the 500-year flood event. Activities that occur landward of the levee would not modify conditions in the Columbia River. Construction and operation of the proposed project would be unlikely to have any measurable impact on floodplain function at the 500-year flood event due to the extent of floodplain inundation and level of development within this area. Thus, the proposed export terminal would not decrease the ability of the Columbia River to retain floodwaters within the 500-year floodplain. A 500-year flood event would however have substantial impacts on the proposed project and would likely require substantial repair and replacement of facilities, equipment, and infrastructure.

Construction of Docks 2 and 3 and Removal of Existing Pile Dikes

The Columbia River would be permanently altered and benthic (i.e., river bottom) habitat removed by the placement of piles. A total of 610 of the 630 36-inch-diameter steel piles required for the trestle and docks would be placed below the ordinary high water mark, permanently removing approximately 0.10 acre (4,312 square feet) of benthic habitat. The majority of this habitat is located in the Delivered Water Zone (Grette 2014a). The placement of piles would displace benthic habitat, and the areas within each pile footprint would cease to contribute toward primary or secondary productivity. Individual pile footprints are relatively small (7.07 square feet) and are spaced throughout the dock and trestle footprint.

Creosote-treated piles would be removed from the deepest portions of two existing timber pile dikes located in the Columbia River. In total, approximately 225 linear feet of the dikes would be removed. Removal of creosote-treated piles would result in a temporary increase in turbidity and would temporarily affect benthic habitat. Turbidity would be localized and short-term and the benthic habitat affected would recover relatively quickly. Benthic invertebrates typically recolonize disturbed areas within 30–45 days following disturbance. Overall, however, the removal of creosote-treated woodpiles from the Columbia River would be a beneficial impact, as any remaining creosote in those piles would be removed from the aquatic environment. Refer to the NEPA Fish Technical Report (ICF International 2016b) for further information.

Use Water for Construction

Construction would use water from rainfall runoff and on-site groundwater wells for dust suppression, washdown water, and fire-protection systems. This use would be regulated under the NPDES Construction Stormwater General Permit. Rainfall would be collected and treated and either stored in a detention pond, or discharged to the Columbia River through the existing Outfall 002A. The On-Site Alternative would not withdraw water from the Columbia River or other surface waters in the study area to meet construction water needs and, therefore, would not impact surface water and floodplains.

3.1.2 Construction: Indirect Impacts

Construction of the proposed terminal would not result in indirect impacts on surface waters or floodplains because construction would be limited to the project area.

3.1.3 Operations: Direct Impacts

The following direct impacts on surface water and floodplains could occur as a result of operations of the proposed export terminal.

Water Use for Operations

The proposed terminal would use water from rainfall runoff and on-site groundwater wells for dust suppression, washdown water, and fire-protection systems. Rainfall would be collected and treated and either stored in a detention pond or discharged to the Columbia River through the existing Outfall 002A. Water would not be drawn from the Columbia River or other surface waters in the study area for operations. Thus, no impacts on surface water and floodplains are anticipated during operations.

Alter Water Collection and Discharge

Currently, stormwater runoff at the project area is managed by infiltration or evaporation and by a complex stormwater collection and treatment system (Facilities 77 and 73); in conformance with the Applicant's existing NPDES permit (WA-000008-6). The NPDES system includes 12 stormwater basins and five outfalls that the Applicant manages under its NPDES permit, which discharge to the Columbia River. The existing stormwater collection and treatment system configuration would not adequately serve the needs of the future terminal and would need to be expanded. Information on stormwater is included in the NEPA Water Quality Technical Report (ICF International 2016a).

The project water management system would collect all stormwater and surface water (washdown water) from the stockpile areas, rail loop, office areas, the dock, and other paved/impervious surface areas at the project area and direct these waters to a series of vegetated ditches and ponds, then to a collection basin or sump (Figure 9). Similar to current conditions, collected water would be pumped to an existing on-site treatment facility consisting of settling pond(s) with flocculent addition to promote settling as needed. Chemical treatments must be identified as part of the NPDES permit process. Treated water would be pumped to a surface storage pond for reuse in support of operations, or, if storage is not necessary the excess treated water would be discharged to the Columbia River via outfall 002A in accordance with the NPDES permit limits. The surface storage pond would have an approximate capacity of 3.6 million gallons and would be used to store water for reuse. The capacity of the pond would include a reserve of 0.36 million gallon maintained at all times for fire suppression. The stored water would be available for reuse for dust suppression, washdown and cleanup, and fire suppression. Water for dust suppression would be applied on the main stockpiles, within unloading and conveyance systems, and at the dock. Excess water from dust suppression and washdown would be collected, treated, and stored for reuse.

The proposed changes in water management for each basin are summarized in Table 4.


Figure 9. Proposed Drainage Plan for the On-Site Alternative

Table 4. Summary of Proposed Changes to Stormwater Collection and Discharge by Basin

Basin	Existing Collection and Discharge	Proposed Collection and Discharge
1	<p>Collection: Collected from facility collection piping, pumps and ditches, directed to Sump/Pump Station (Facility 77), routed through Facility 73 treatment facility, then discharged to Columbia River through Outfall 002A.</p> <p>Discharge: Basin 1 gravity flows to Facility 77 and is then routed through Facility 73 for treatment and eventual discharge to the Columbia River via Outfall 002A.</p>	<p>Approximately 48% of this area (32 acres) would be absorbed into the project area. Stormwater generated in Basin 1 contained within the project area would be collected, treated, and reused; excess would be directed to the On-Site Alternative treatment system for discharge to the Columbia River under the NPDES permit.</p> <p>Excess from the project area would be collected and treated within the project area, then routed to a new internal outfall (monitored under a separate NPDES permit). The outfall would tie in to the existing Facility 77 sump, and all waters from the Applicant would go through Facility 73. The Applicant's existing discharge line from Facility 73 would continue to discharge to the Columbia River through the existing Outfall 002A.</p> <p>The remaining areas of Basin 1 outside of the project area would continue to gravity flow to Facility 77 and be routed through Facility 73 for treatment and eventual discharge to the Columbia River via Outfall 002A.</p>
2	<p>Collection: Collected from the top of the cap of the closed Black Mud Pond facility into a sump where it is routed through a pump station to drainage ditches that gravity flow into Facility 77, routed through Facility 73 for treatment and then discharged to Columbia River through Outfall 002A. During heavy storm events, stormwater from the cap may overflow Outfall 006 Sump/Pump Station and flow to Ditch 14.</p> <p>Discharge: From the sump, it is routed through a pump station to drainage ditches that gravity flow into Facility 77, routed through Facility 73 for treatment and then discharged to Columbia River through Outfall 002A. During heavy storm events, stormwater from the cap may overflow Outfall 006 Sump/Pump Station and flow to Ditch #14.</p>	<p>The On-Site Alternative would not modify Basin 2.</p> <p>The drainage routing for Basin 2 would remain the same as its current condition.</p>

Basin	Existing Collection and Discharge	Proposed Collection and Discharge
3	<p>Collection: Stormwater generated in Basin 3 ponds locally and/or drains to a vegetated ditch located along the northeastern boundary of the site, adjacent to Industrial Way. The vegetated ditch discharges by gravity drainage to Ditch 10.</p> <p>Discharge: Stormwater discharges by gravity to Ditch 10, located at the north edge of the basin and south of Industrial Way.</p>	<p>The On-Site Alternative would occupy approximately 85% of Basin 3 (21.8 acres). Runoff in Basin 3 in the project area would be collected, treated, and reused.</p> <p>Excess would be directed to the On-Site Alternative's treatment system for discharge under NPDES permit through Facility 77 to Facility 73, and then to Outfall 002A. Runoff in Basin 3 outside of the On-Site Alternative would continue to gravity flow and discharge to Ditch 10.</p>
3A	<p>Collection: Collected from facility pumps, directed to Sump/Pump Station (Facility 77) routed through Facility 73 treatment facility and then discharged to Columbia River through Outfall 002A.</p> <p>Discharge: Directed to Sump/Pump Station (Facility 77) routed through Facility 73 treatment facility and then discharged to Columbia River through Outfall 002A.</p>	<p>The On-Site Alternative would occupy 100% of Basin 3A. Runoff in Basin 3A in the project area would be collected, treated, and reused.</p> <p>Excess would be directed to the On-Site Alternative treatment system for discharge under the NPDES permit through Facility 77 to Facility 73, and then through Outfall 002A.</p>
4	<p>Collection: Collected and routed to Facility 77.</p> <p>Discharge: From Facility 77, pumped through Facility 73 treatment facility and then discharged to Columbia River through Outfall 002A.</p>	<p>The On-Site Alternative would not occupy areas of Basin 4.</p> <p>The drainage routing for Basin 4 would remain the same as its current condition.</p>
4A	<p>Collection: Allowed to pond and evaporate or infiltrate into the soil.</p> <p>Discharge: Allowed to pond and evaporate or infiltrate into the soil.</p>	<p>The On-Site Alternative would not occupy areas of Basin 4A.</p> <p>The drainage routing for Basin 4A would remain the same as its current condition.</p>
5	<p>Collection: Collected by gravity to Ditch 14.</p> <p>Discharge: Stormwater discharges by gravity to the Ditch 14, located at the north edge of the basin and south of Industrial Way.</p>	<p>The On-Site Alternative would occupy 93% of Basin 5.</p> <p>Runoff in Basin 5 within the On-Site Alternative would be collected, treated, and reused. Excess would be directed to the On-Site Alternative's treatment system for discharge under CET NPDES permit through Facility 77 to Facility 73, and then to Outfall 002A. Runoff in Basin 5 outside of the On-Site Alternative would continue to discharge by gravity to CDID Ditch #14.</p>

Basin	Existing Collection and Discharge	Proposed Collection and Discharge
5A	<p>Collection: Allowed to pond and evaporate or infiltrate into the soil.</p> <p>Discharge: Allowed to pond and evaporate or infiltrate into the soil.</p>	<p>The On-Site Alternative would occupy 91% of Basin 5A.</p> <p>Runoff in Basin 5A within the On-Site Alternative would be collected, treated, and reused. Excess would be directed to the On-Site Alternative treatment system for discharge under the NPDES permit through Facility 77 to Facility 73, and then to Outfall 00 On-Site Alternative 2A. Runoff in Basin 5A outside of the On-Site Alternative would continue to be allowed to pond and evaporate or infiltrate into the soil.</p>
5B	<p>Collection: Allowed to pond and evaporate or infiltrate into the soil.</p> <p>Discharge: Allowed to pond and evaporate or infiltrate into the soil.</p>	<p>The On-Site Alternative would occupy 100% of Basin 5B.</p> <p>Runoff in Basin 5B within the project area would be collected, treated, and reused. Excess would be directed to the On-Site Alternative treatment system for discharge under the NPDES permit through Facility 77 to Facility 73, and then to Outfall 002A.</p>
6	<p>Collection: Allowed to pond and evaporate or infiltrate into the soil. Stormwater sheet flows from this area and is collected in the U-Ditch located to the south of the former plant's water treatment system and is conveyed to the collection sump at Facility 77, then pumped through Facility 73 treatment facility and then discharged to Columbia River through Outfall 002A.</p> <p>Discharge: From Facility 77, stormwater is then pumped through Facility 73 treatment facility and then discharged to Columbia River through Outfall 002A.</p>	<p>The On-Site Alternative would occupy approximately 25% of Basin 6. Runoff in Basin 6 within the project area would be collected, treated, and reused.</p> <p>Excess would be directed to the On-Site Alternative treatment system for discharge under the NPDES permit through Facility 77 to Facility 73, and then to Outfall 002A. Runoff in Basin 6 outside of the project area would continue to gravity flow and discharge to Facility 77 would be routed through Facility 73 for treatment, and discharge to the Columbia River via Outfall 002A.</p>
6A	<p>Collection: Allowed to pond and evaporate or infiltrate into the soil.</p> <p>Discharge: Allowed to pond and evaporate or infiltrate into the soil.</p>	<p>The project area would occupy approximately 3% of Basin 6A. The settling pond of Facility 73 would eventually be relocated from Basin 6 into Basin 6A as an indirect impact of the On-Site Alternative.</p> <p>Runoff in Basin 6A outside of the project area would continue to be allowed to pond and evaporate or infiltrate into the soil.</p>
7	<p>Collection: Allowed to pond and evaporate or infiltrate into the soil.</p> <p>Discharge: Allowed to pond and evaporate or infiltrate into the soil.</p>	<p>The project area would not occupy areas of Basin 7.</p> <p>The drainage routing for Basin 7 would remain the same as its current condition.</p>

The proposed reuse of stormwater and surface water would alter the rate and volume of discharge from the project area. Table 5 summarizes the proposed changes in runoff volume and velocity for each basin. The proposed water collection and drainage system would reduce the annual runoff volume and 50-year peak discharge from each basin affected by operations of the On-Site Alternative.

This reduction would decrease the potential for on-site flooding during heavy rain and result in a potentially beneficial impact on the existing water treatment infrastructure by increasing available treatment capacity.

Table 5. Proposed Changes to Water Collection and Discharge in Volume and Rate of Discharge

Basin	Area (acres)	% Reduced by On-Site Alternative	Existing Avg. Annual Runoff Ac-ft (MGY)	Proposed Avg. Annual Runoff Ac-ft (MGY)	Existing Peak Runoff Discharge ^a (cfs)	Proposed Peak Runoff Discharge ^a (cfs)
1	88.7	48	284 (92.5)	147 (48.0)	44.7	23.2
2	33.1	0	52 (16.9)	52 (16.9)	5.5	5.5
3	64.2	85	165 (53.8)	24 (8.0)	24.5	3.6
3A	9.4	100	18 (5.9)	0	2.7	0.0
4	52.3	0	92 (30.0)	92 (30.0)	10.4	10.4
4A	5.6	0	13 (4.2)	13 (4.2)	2.0	2.0
5	25.1	93	55 (18.0)	4 (1.2)	8.1	0.6
5A	21.4	91	32 (10.4)	3 (1.0)	3.3	0.3
5B	17.3	100	28 (9.1)	0	3.0	0.0
6	40.5	25	64 (20.9)	48 (15.6)	6.9	5.2
6A	12.9	3	20 (6.5)	19.5 (6.4)	2.2	2.1
7	14.1	0	22 (7.2)	22 (7.2)	2.3	2.3

^a Volume provided for 50-year storm.

Avg = average; Ac-ft = acre-feet; MGY = million gallons per year; cfs = cubic feet per second

Discharge Less Water to CDID #1 Ditches

Basins 2, 3, and 5 of the existing water management system at the project area currently discharge to CDID #1 drainage ditches. Once constructed, most of the project area would no longer drain to the CDID ditches. The exception being a portion of the access overpass and frontage improvements. All stormwater and excess dust suppression water within the footprint of the project area would be collected, conveyed, treated, and either stored onsite for reuse or discharged to the Columbia River. Therefore, no negative impacts on the CDID #1 ditches would occur and less water would be discharged to the ditches. As discussed below, this could have a beneficial indirect impact on the CDID ditches.

Instigate Flooding from Interior Drainage System Failure

A new pump station and 18-inch outfall line is proposed to convey stormwater from the project area to the existing Facility 77 sump, and then all waters from the project area would go through Facility 73 (Figure 9).

Failure of the interior drainage pumps could result in flooding onsite for Basin 3A. However, backup systems would be built into the system to avoid flooding associated with pump failure.

3.1.4 Operations: Indirect Impacts

The project water management system would be unlikely to have any measurable impact on the Columbia River. Discharges to the river from the terminal are expected to decrease from 276 million to 138.5 million gallons per year. The Columbia River has a mean annual discharge of 55.85 trillion gallons per year.⁴ The proposed changes to the volume and velocity of surface water discharged to the Columbia River associated with the On-Site Alternative would be negligible within the Columbia River. Annual discharge to the river is estimated to decrease from 276 to 138.5 million gallons per year, which would equate to a decrease in average annual flow in the Columbia River of 0.0000025 ($2.5 \times 10^{-6} \%$). A decrease in flow of this magnitude would essentially be undetectable in the lower Columbia River.

The CDID #1 ditches are much smaller than the Columbia River; therefore, changes to the volume of surface water discharged from the project area could potentially have a measurable effect on the capacity of the ditches. Operating the proposed terminal would reduce flow to the ditches from 88 to 26.3 million gallons per year. This could be beneficial to the ditches because there would be additional capacity for drainage. With a combined capacity of 700,000 gallons per minute, CDID #1 pump stations are instrumental for removing stormwater and preventing local and area-wide flooding. The need for this pumping capacity is apparent when considering 1 inch of rain falling on the 16,000-acre watershed is equivalent to 434 million gallons of water. Removal of 4.8 inches of rain deposited from a 1986 storm required 54 hours of continuous pumping. Thus, any reduction in discharge to the CDID ditch system could provide a flood control benefit during significant rain events.

The On-Site Alternative would be located behind the Columbia River Levee. The levee protects the City of Longview, as well as those adjacent areas of industrial waterfront in unincorporated Cowlitz County, from flooding associated with the Columbia and Cowlitz Rivers. The Columbia River Levee provides protection from the 100-year flood event, but not the 500-year flood event (Federal Emergency Management Agency 2015a).

The Columbia River is a heavily managed river system. Facilities such as flood control dams and reservoirs on the Columbia River and its tributaries provide flood control storage of 37 million acre-feet. The total active storage in the Columbia River Basin is 55.8 million acre-feet (Harrison 2008). This active storage provides some protection against flood events but does not preclude a 500-year flood. Were a 500-year flood to occur, the proposed terminal as the City of Longview and adjacent industrial waterfront in unincorporated Cowlitz County would flood.

⁴ USGS Station 14246900 Columbia River at Beaver Army Terminal, near Quincy, Oregon: Average Discharge for Period of Record, 23 years (water years 1969, 1992–2013).

A 500-year flood event would overtop the Columbia River levee and inundate the indirect impact study area (Figure 5), and beyond. The proposed project would not be expected to have a measurable effect on floodplain function (i.e., water storage) during a 500-year event, based on the extent of the 500-year floodplain and the level of development that currently exists within this area. However, a 500-year flood event would have a substantial impact on the proposed terminal; it would likely cause considerable damage to the proposed export terminal and redeposit stockpiled coal in the Columbia River. Any coal or other debris that remained on the floodplain once flood waters receded would likely be cleaned up and either retained for storage/shipment or disposed of at an approved facility.

3.2 Off-Site Alternative

Potential impacts on surface water and floodplains under the Off-Site Alternative are described below.

3.2.1 Construction: Direct Impacts

Constructing the terminal at the Off-Site Alternative location would have impacts similar to the On-Site Alternative, although the Off-Site Alternative would also require the construction of a new access road, and an extension of the rail spur line. The following direct impacts on surface water and floodplains could occur as a result of construction activities at the Off-Site Alternative location.

Alter Drainage from Heavy Equipment and Staging Areas

Construction of the Off-Site Alternative would involve ground-disturbing activities (excavation, grading, filling, trenching, backfilling, and compaction) that would permanently alter the existing site drainage. In compliance with the required SWPPP that would be prepared and implemented during construction, a majority of the stormwater runoff would be collected and treated prior to discharge to the Columbia River. Under current conditions, stormwater that does not infiltrate or evaporate on site is assumed to flow into the CDID ditches. However, it is unknown how much water is currently discharged to the CDID ditches; thus, the potential impacts of altering drainage patterns on the Off-Site Alternative location are unknown.

Decrease Floodplain Floodwater Retention

Similar to the project area for the On-Site Alternative, the project area for the Off-Site Alternative is within the Columbia River 500-year floodplain, but protected from the 100-year flood event by a levee. Because the land is undeveloped, no demolition would be required; however, existing vegetation would need to be removed. This vegetation does not currently provide any sort of function that would contribute to the floodplain's ability to retain or absorb floodwater or reduce flow or velocity. Construction and operation of the proposed export terminal would be unlikely to have any measurable impact on floodplain function during a 500-year flood event due to the extent of floodplain inundation and level of development within the 500-year floodplain. Thus, no measurable decrease in the ability of the Columbia River to retain floodwaters within the 500-year floodplain would be expected to result from constructing or operating the Off-Site Alternative. A 500-year flood event would however have substantial impacts on the proposed project and would likely require substantial repairs and replacement of facilities, equipment, and infrastructure.

3.2.2 Construction: Indirect Impacts

Construction of the Off-Site Alternative would not result in indirect impacts on surface waters or floodplains because construction of the export terminal would be limited to the project area.

3.2.3 Operations: Direct Impacts

The following direct impacts on surface water and floodplains could occur as a result of operations of the proposed export terminal at the Off-Site Alternative location.

Use Water for Operations

The volume of stormwater and water pumped for operations and the volume of water stored for reuse would be similar to the On-Site Alternative. Thus, the potential impacts related to stormwater volume and velocity would be similar to those described for the On-Site Alternative. The Off-Site Alternative would also require an NPDES permit, which would dictate that stormwater be collected and treated before being discharged to surface waters.

Alter Water Collection and Discharge

Under the Off-Site Alternative, stormwater currently infiltrates or evaporates with overflow conveyed and discharged to the CDID ditch system. If the Off-Site Alternative were implemented, stormwater would be collected, conveyed and discharged to a project treatment system and then stored within a storage pond for reuse under a new NPDES permit. Because the acreage of the stockpiles, rail system, and other impervious areas would be similar to the On-Site Alternative, the amount of stormwater and water collected for reuse and/or discharged to the Columbia River would also be similar. Thus, it is expected that the Off-Site Alternative would result in an increase in discharge to the Columbia River and a decrease in discharge to the CDID ditches. How much of a change in discharge volumes is unknown.

Cause Effects on Floodplains

The Off-Site Alternative project area is in an area of the floodplain that is protected from the base flood by a system of levees. The existing CDID levee system is designed to protect the property from the 100-year and 500-year flood event. The Off-Site Alternative project area would not require a City or County floodplain management permit since the entire site is located in an area designated as between a 100-year and 500-year floodplain per the FEMA Map 53003201D dated September 2, 1993.

3.2.4 Operations: Indirect Impacts

Similar to indirect operations impacts of the On-Site Alternative, changes to the water management system for the Off-Site Alternative have the potential to affect receiving waters offsite and downstream, such as the CDID ditches. Changes in flow to the Columbia River would have a negligible impact because the anticipated change in flow would be minor in comparison to the overall flow in the Columbia River. The Off-Site Alternative could slightly increase CDID#1 ditch system drainage capacity by operating a water management system that would collect, convey, treat, and either store stormwater for on-site reuse or discharge excess stormwater to the Columbia River.

Similar to the On-Site Alternative, the proposed project would not be expected to have a measurable effect on floodplain storage during a 500-year event, based on the extent of the 500-year floodplain and level of development that already currently exists within the floodplain. A 500-year flood event would however have a substantial impact on the proposed project at the Off-Site Alternative, and would likely cause considerable damage to the proposed export facility and would likely transport stockpiled coal from the stockpile areas and deposit the coal within the floodplain and active channel of the Columbia River, along with a significant amount of other industrial, commercial and residential related debris from other existing development within the 500-year floodplain. Any coal or other debris that remained on the floodplain once flood waters receded would likely be cleaned up and either retained for storage/shipment or disposed of at an approved facility.

3.3 No-Action Alternative

Under the No-Action Alternative, the Corps would not issue a Department of the Army permit authorizing construction and operation of the proposed export terminal. As a result, impacts resulting from constructing and operating the terminal would not occur. In addition, not constructing the terminal would likely lead to expansion of the adjacent bulk product business onto the export terminal project area. The following discussion assesses the likely consequences of the No-Action Alternative related to surface water and floodplains.

The extent of impervious surface could increase but drainage patterns would be similar to current conditions. Any new or expanded industrial uses that could substantially alter drainage patterns would trigger a new NPDES Construction Stormwater General permit, NPDES Industrial Stormwater Permit or modification to the permitting process. Thus, potential impacts related to surface water and floodplains under the No-Action Alternative would be similar to what is described for the On-Site Alternative, but the magnitude of impact would depend on the nature and extent of the expansion.

The following permits would be required in relation to surface water and floodplains.

4.1 On-Site Alternative

The On-Site Alternative would require the following Cowlitz County permits related to surface water and floodplains.

- **Shoreline Substantial Development Permit and Conditional Use Permit—Cowlitz County Department of Building and Planning and Washington State Department of Ecology.** The On-Site Alternative would result in new development in the shoreline area regulated by the Washington State Shoreline Management Act and *Cowlitz County Shoreline Master Program* (Cowlitz County 2012). The On-Site Alternative would require a Shoreline Substantial Development Permit. This permit is administered by the Cowlitz County Department of Building and Planning. The On-Site Alternative would also require a Conditional Use Permit from Cowlitz County and Ecology.
- **Critical Areas Permit—Cowlitz County Department of Building and Planning.** The On-Site Alternative would result in development in designated critical areas because the project area contains a frequently flooded area, an erosion hazard area, and a critical aquifer recharge area. Therefore, it would require a Critical Areas Permit from the Cowlitz County Department of Building and Planning.
- **Floodplain Permit – Cowlitz County Building and Planning.** A floodplain permit would be required from Cowlitz County to address development in any areas designated as Frequently Flooded Areas.
- **NPDES Construction Stormwater General Permit—Washington State Department of Ecology.** A Construction Stormwater General Permit would be required from Ecology to address erosion control and water quality during construction.
- **NPDES Industrial Stormwater Permit—Washington State Department of Ecology.** An Industrial Stormwater Permit would be required from Ecology for discharge of industrial use water during operations.
- **Hydraulic Project Approval—Washington Department of Fish and Wildlife.** The On-Site Alternative would require a hydraulic project approval from WDFW because project elements would affect the Columbia River.
- **Clean Water Act Authorization, Section 404—U.S. Army Corps of Engineers.** Construction and operation of the On-Site Alternative would affect waters of the United States, including wetlands. Because impacts would exceed 0.5 acre, Individual Authorization from the Corps under Section 404 of the Clean Water Act and appropriate compensatory mitigation for the acres and functions of the affected wetlands would be required.
- **Rivers and Harbors Act—U.S. Army Corps of Engineers.** Construction and implementation of the On-Site Alternative would affect navigable waters of the United States (i.e., the Columbia

River). The Rivers and Harbors Act authorizes the Corps to protect commerce in navigable streams and waterways of the United States by regulating various activities in such waters. Section 10 of the RHA (33 USC 403) specifically regulates construction, excavation, or deposition of materials into, over, or under navigable waters, or any work that would affect the course, location, condition, or capacity of those waters.

4.2 Off-Site Alternative

The Off-Site Alternative would require the same permits from the same entities for surface water and floodplains impacts as the On-Site Alternative, with the addition of the following.

- **Shoreline Substantial Development Permit—City of Longview.** The Off-Site Alternative would result in new development in the shoreline area regulated by the *Draft City of Longview Shoreline Master Program* (City of Longview 2015). Therefore, this alternative would require a Shoreline Substantial Development Permit from the City of Longview.
- **Critical Areas Permit—City of Longview and Cowlitz County.** The Off-Site Alternative would result in development in designated critical areas in the City of Longview and Cowlitz County. Therefore, this alternative would require Critical Areas Permits from the City of Longview Community Development Department and the Cowlitz County Department of Building and Planning.

Chapter 5

References

- Anchor QEA. 2011. *National Pollutant Discharge Elimination System Engineering Report Millennium Bulk Terminals*. Longview, WA. Prepared for Millennium Bulk Terminals—Longview, LLC. Portland, OR. September 2011.
- Anchor QEA. 2014. *Engineering Report Update for NPDES Application Millennium Bulk Terminals*. Longview, WA. Prepared for Millennium Bulk Terminals—Longview, LLC. Portland, OR. September 2011. July 2014.
- Bonneville Power Administration. 2001. *The Columbia River System Inside Story*. Available: https://www.bpa.gov/power/pg/columbia_river_inside_story.pdf. Accessed: March 16, 2015.
- City of Longview. 2013. *Draft City of Longview Stormwater Management Master Plan*. May 2013. Revised October 2013 and September 2014. Available: <http://www.mylongview.com/modules/showdocument.aspx?documentid=1544>. Accessed: March 16, 2015.
- Consolidated Diking Improvement District No. 1. 2014. *Consolidated Diking Improvement District No. 1 Website*. Available: <http://www.cd1d1.org/default.html>.
- Cowlitz County. 2012. *Cowlitz County Phase II Stormwater Management Program*. Available: <http://www.co.cowlitz.wa.us/DocumentCenter/View/802>. Accessed: March 16, 2015.
- Ewing, Richard. 1999. *Diminishing Returns: Salmon Declines and Pesticides*. Available: <http://www.pcffa.org/salpest.pdf>. Accessed: October 20, 2014.
- Federal Emergency Management Agency. 2015a. Flood Insurance Rate Map, Cowlitz County, Washington and Incorporated Areas. Map Number 53015C0494G. December 16, 2015. Available: <https://msc.fema.gov/portal>.
- Federal Emergency Management Agency. 2015b. *Definitions of FEMA Flood Zone Designations*. Last updated: March 19, 2010. Available: <http://snmapmod.snco.us/fmm/document/fema-flood-zone-definitions.pdf>. Accessed: March 16, 2015.
- Grette Associates, LLC. 2014a. *Millennium Coal Export Terminal Longview, Washington: Permanent Impacts to Aquatic Habitat*. September.
- Grette Associates, LLC. 2014b. *Millennium Coal Export Terminal Longview, Washington: Off-Site Alternative – Barlow Point Permanent Impacts to Aquatic Habitat*. September 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals—Longview, LLC. Longview, WA.
- Harrison, J. 2008. *Floods and Flood Control*. Columbia River History Project. Northwest Power and Conservation Council. Available: <https://www.nwcouncil.org/history/Floods>
- ICF International. 2016a. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Water Quality Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.

- ICF International. 2016b. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Fish Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- National Marine Fisheries Service. 2011. *Columbia River Estuary ESA Recovery Module for Salmon and Steelhead*. Portland, OR. January 2011.
- National Oceanic and Atmospheric Administration. 2014. *Columbia River Estuary Operational Forecast System*. Available: http://tidesandcurrents.noaa.gov/ofs/creofs/creofs_info.html.
- Oregon Department of Environmental Quality. 2003. *Designated Beneficial Uses Mainstem Columbia River* (340-41-0101).
- Oregon Department of Environmental Quality. 2012. *Integrated Water Quality Assessment Report*. 303(d)/305(b).
- URS Corporation. 2014a. *Millennium Coal Export Terminal Longview, Washington: Water Resource Report Supplemental*. Seattle, WA. September 2014.
- URS Corporation. 2014b. *Millennium Coal Export Terminal Longview, Washington. Affected Environment Analysis – Water Resources*. January 2014.
- URS Corporation. 2014c. *Millennium Coal Export Terminal Longview, Washington: Water Collection and Drainage Package*. Seattle, WA. November 2014.
- URS Corporation. 2014d. *Millennium Coal Export Terminal Longview, Washington: Water Management Plan*. Seattle, WA. November 2014.
- URS Corporation. 2014e. *Millennium Coal Export Terminal Longview, Washington: Water Balance Calculation*. Seattle, WA. December 2014.
- U.S. Environmental Protection Agency. 2009. *Columbia River Basin: State of the River Report for Toxics*. EPA 910-R-08-004.
- U.S. Geological Survey. 2005. *Water-Quality Data, Columbia River Estuary, 2004–2005*.
- U.S. Geological Survey. 2014. USGS 14246900. *Columbia River at Beaver Army Terminal near Quincy, OR*. Available: <http://wdr.water.usgs.gov/wy2013/pdfs/14246900.2013.pdf?1423677243767>.
- Washington State Department of Ecology. 2012. *Stormwater Management Manual for Western Washington*. Publication No. 12-10-030. Olympia, WA.
- Washington State Department of Ecology. 2014a. *Columbia River Facts and Maps*. Available: <http://www.ecy.wa.gov/programs/wr/cwp/cwpfactmap.html>.
- Washington State Department of Ecology. 2014b. *Grays-Elochoman, Cowlitz River Basins Water Resource Management Programs*. Available: http://www.ecy.wa.gov/programs/wr/instream-flows/ge_cowlitz.html.

MILLENNIUM BULK TERMINALS—LONGVIEW NEPA ENVIRONMENTAL IMPACT STATEMENT NEPA GROUNDWATER TECHNICAL REPORT

PREPARED FOR:

U.S. Army Corps of Engineers, Seattle District
4735 East Marginal Way South
Seattle, WA 98134

PREPARED BY:

ICF International
710 Second Avenue, Suite 550
Seattle, WA 98104

September 2016



ICF International. 2016. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Groundwater Technical Report*. September. (ICF 00264.13.) Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.

Contents

List of Tables	iii
List of Figures.....	iii
List of Acronyms and Abbreviations.....	iii
Chapter 1 Introduction	1-1
1.1 Project Description	1-1
1.1.1 On-Site Alternative	1-1
1.1.2 Off-Site Alternative	1-4
1.1.3 No-Action Alternative	1-6
1.2 Regulatory Setting.....	1-6
1.3 Study Area.....	1-8
1.3.1 On-Site Alternative	1-8
1.3.2 Off-Site Alternative	1-8
Chapter 2 Affected Environment.....	2-1
2.1 Methods.....	2-1
2.1.1 Data Sources	2-1
2.1.2 Impact Analysis	2-1
2.2 Affected Environment.....	2-2
2.2.1 Regional Setting	2-3
2.2.2 Local Setting.....	2-1
2.2.3 Groundwater Quality	2-10
2.2.4 Water Supply	2-27
Chapter 3 Impacts	3-1
3.1 On-Site Alternative	3-1
3.1.1 Construction: Direct Impacts	3-1
3.1.2 Construction: Indirect Impacts	3-4
3.1.3 Operations: Direct Impacts	3-4
3.1.4 Operations: Indirect Impacts	3-7
3.2 Off-Site Alternative	3-8
3.2.1 Construction: Direct Impacts	3-8
3.2.2 Construction: Indirect Impacts	3-9
3.2.3 Operations: Direct Impacts	3-10
3.2.4 Operations: Indirect Impacts	3-11
3.3 No-Action Alternative	3-11

Chapter 4 Required Permits	4-1
4.1 On-Site Alternative	4-1
4.2 Off-Site Alternative	4-1
Chapter 5 References	5-1
5.1 Written References.....	5-1
5.2 Personal Communications	5-2

Tables

1	Regulations, Statutes, and Guidelines for Groundwater	1-6
2	Screening Levels for Groundwater	2-21
3	Groundwater Cleanup Standards	2-27
4	Water Rights Claims and Certificates	2-29

Figures

1	Project Vicinity.....	1-2
2	On-Site Alternative	1-3
3	Off-Site Alternative.....	1-5
4	Groundwater Study Areas for the On-Site Alternative and Off-Site Alternative	1-9
5	Watershed Map.....	2-4
6	Groundwater Gradients and Flow Direction for the On-Site Alternative	2-4
7	Water Management System in the Project Area for the On-Site Alternative.....	2-5
8	Schematic of Stormwater Flow in the Project Area for the On-Site Alternative	2-6
9	Mint Farm Shallow Aquifer Monitoring Wells and Groundwater Gradients	2-12
10	Mint Farm Deep Aquifer Monitoring Wells and Groundwater Gradients	2-13
11	Former and Existing Facilities in the Applicant's Leased Area for the On-Site Alternative..	2-15
12	Overview of Remedial Investigation Testing Locations in the Applicant's leased area for the On-Site Alternative	2-19
13	Previous Cleanup, Removal Areas, and Remedial Investigation Areas in the Applicant's leased area for the On-Site Alternative.....	2-20
14	2012 Groundwater Testing Results in the Applicant's leased area for the On-Site Alternative—Total Free Cyanide	2-22
15	2012 Groundwater Testing Results in the Applicant's leased area for the On-Site Alternative—Total Free Fluoride.....	2-23
16	2007–2012 Groundwater Testing Results in the Applicant's leased area for the On-Site Alternative—Total cPAHs as Toxic Equivalents	2-25
17	City of Longview Wellhead Protection Area.....	2-32

Acronyms and Abbreviations

AFY	acre-feet per year
Applicant	Millennium Bulk Terminals—Longview, LLC
ARARs	Applicable or Relevant and Appropriate Requirements
BMPs	best management practices
BNSF	BNSF Railway
CDID	Consolidated Diking and Improvement District
CFR	Code of Federal Regulations
Corps	U.S. Army Corps of Engineers
cPAH	carcinogenic PAHs
CRB	Columbia River basalt
Ecology	Washington State Department of Ecology
EPA	U.S. Environmental Protection Agency
LMC	Longview Municipal Code
LVSF	Longview Switching Company
gpm	gallons per minute
MCL	maximum contaminant level
MTCA	Model Toxics Control Act
NEPA	National Environmental Policy Act
NPDES	National Pollutant Discharge Elimination System
PAH	polycyclic aromatic hydrocarbon
PCBs	polychlorinated biphenyls
Reynolds facility	Reynolds Metals Company facility
RCW	Revised Code of Washington
RI/FS	Remedial Investigation/Feasibility Study
SEPA	Washington State Environmental Policy Act
SPL	spent potliner
TPH	total petroleum hydrocarbons
UP	Union Pacific
USC	United States Code
WAC	Washington Administrative Code
WRIA	Water Resource Inventory Area

This technical report assesses the potential impacts on groundwater associated with the proposed Millennium Bulk Terminals—Longview project (On-Site Alternative), Off-Site Alternative, and No-Action Alternative. For the purposes of this assessment, groundwater refers to subsurface waters held in soils or interstitial spaces of rocks. This report describes the regulatory setting, establishes the method for assessing potential impacts on groundwater, presents the historical and current groundwater conditions in the study areas, and assesses potential impacts.

1.1 Project Description

Millennium Bulk Terminals—Longview, LLC (Applicant) proposes to construct and operate an export terminal in Cowlitz County, Washington, along the Columbia River (Figure 1). The export terminal would receive coal from the Powder River Basin in Montana and Wyoming and the Uinta Basin in Utah and Colorado via rail shipment, then load and transport the coal by ocean-going ships via the Columbia River and Pacific Ocean to overseas markets in Asia. The export terminal would be capable of receiving, stockpiling, blending, and loading coal by conveyor onto ships for export. Construction of the export terminal would begin in 2018. For the purpose of this analysis, it is assumed the export terminal would operate at full capacity by 2028. The following subsections present a summary of the On-Site Alternative, Off-Site Alternative, and No-Action Alternative.

1.1.1 On-Site Alternative

Under the On-Site Alternative, the Applicant would develop an export terminal on 190 acres (project area). The project area is located within an existing 540-acre area currently leased by the Applicant at the former Reynolds Metals Company facility (Reynolds facility), and land currently owned by Bonneville Power Administration. The project area is adjacent to the Columbia River in unincorporated Cowlitz County, Washington near Longview city limits (Figure 2).

The Applicant currently and separately operates at the Reynolds facility, and would continue to separately operate a bulk product terminal on land leased by the Applicant. Industrial Way (State Route 432) provides vehicular access to the Applicant's leased land. The Reynolds Lead and the BNSF Spur rail lines, both operated by Longview Switching Company (LVSW), provide rail access to the Applicant's leased area from the BNSF Railway Company (BNSF) main line (Longview Junction) located to the east in Kelso, Washington. Ships access the Applicant's leased area including the bulk product terminal via the Columbia River and berth at an existing dock (Dock 1) operated by the Applicant in the Columbia River.

Figure 1. Project Vicinity





Figure 2. On-Site Alternative

Under the On-Site Alternative, BNSF or Union Pacific Railroad (UP) trains would transport coal in rail cars from the BNSF main line at Longview Junction to the project area via the BNSF Spur and Reynolds Lead. Coal would be unloaded from rail cars, stockpiled and blended, and loaded by conveyor onto ocean-going ships at two new docks (Docks 2 and 3) on the Columbia River for export to Asia.

Once construction is complete, the export terminal would have an annual throughput capacity of up to 44 million metric tons of coal. The export terminal would consist of one operating rail track, eight rail tracks for the storage of rail cars, rail car unloading facilities, stockpile areas for coal storage, conveyor and reclaiming facilities, two new docks in the Columbia River (Docks 2 and 3), and ship-loading facilities on the two docks. Dredging of the Columbia River would be required to provide access to and from the Columbia River navigation channel and for berthing at the two new docks.

Vehicles would access the project area from Industrial Way (State Route 432). Ships would access the project area via the Columbia River and berth at one of the two new docks. Trains would access the export terminal via the BNSF Spur and the Reynolds Lead. Terminal operations would occur 24 hours per day, 7 days per week. The export terminal would be designed for a minimum 30-year period of operation.

1.1.2 Off-Site Alternative

Under the Off-Site Alternative, the export terminal would be developed on an approximately 220-acre site adjacent to the Columbia River, located in both Longview, Washington, and unincorporated Cowlitz County, Washington, in an area commonly referred to as Barlow Point (Figure 3). The project area for the Off Site Alternative is west and downstream of the project area for the On-Site Alternative. Most of the project area for the Off-Site Alternative is located within Longview city limits and owned by the Port of Longview. The remainder of the project area is within unincorporated Cowlitz County and privately owned.

Under the Off-Site Alternative, BNSF or UP trains would transport coal from the BNSF main line at Longview Junction over the BNSF Spur and the Reynolds Lead, which would be extended approximately 2,500 feet to the west. Coal would be unloaded from rail cars, stockpiled and blended, and loaded by conveyor onto ocean-going ships at two new docks (Docks A and B) on the Columbia River. The Off-Site Alternative would serve the same purpose as the On-Site Alternative.

Once construction is complete, the Off-Site Alternative would have an annual throughput capacity of up to 44 million metric tons of coal. The export terminal would consist of the same elements as the On-Site Alternative: one operating rail track, eight rail tracks for the storage of rail cars, rail car unloading facilities, stockpile areas for coal storage, conveyor and reclaiming facilities, two new docks in the Columbia River (Docks A and B), and ship-loading facilities on the two docks. Dredging of the Columbia River would be required to provide access to and from the Columbia River navigation channel and for berthing at the two new docks.

Vehicles would access the project area via a new access road extending from Mount Solo Road (State Route 432) to the project area. Trains would access the terminal via the BNSF Spur and the extended Reynolds Lead. Ships would access the project area via the Columbia River and berth at one of the two new docks. Terminal operations would occur 24 hours per day, 7 days per week. The export terminal would be designed for a minimum 30-year period of operation.

Stockpile Areas
(coal storage pads and
stocking/reclaiming
conveyors)

Rail Loop

Rail Unloading Station

Mount Solo Landfill

Shiploader

Dock A

Dock B

Trestle

New Outfall

Water Management Pond

CDID Reynolds Pump Station

Ditch 10

Ditch 14

DIKE RD

NAVIGATION CHANNEL

Columbia River

WASHINGTON OREGON

MOUNT SOLO RD (SR432)

NEW RAIL ACCESS

Off-Site Alternative Parcels

Project Area

0 500 1,000 1,500 2,000
feet

N

Image: Google Inc. 2015. Google Earth Pro, Version 6.2. Mountain View, CA. Accessed: March 6, 2015.

1.1.3 No-Action Alternative

Under the No-Action Alternative, the U.S. Army Corps of Engineers would not issue the requested Department of the Army permit under the Clean Water Act Section 404 and the Rivers and Harbors Act Section 10. This permit is necessary to allow the Applicant to construct and operate the proposed export terminal.

The Applicant plans to continue operating its existing bulk product terminal located adjacent to the On-Site Alternative project area, as well as expand this business whether or not a Department of the Army permit is issued. Ongoing operations would include storing and transporting alumina and small quantities of coal, and continued use of Dock 1. Maintenance of the existing bulk product terminal would continue, including maintenance dredging at the existing dock every 2 to 3 years. Under the terms of an existing lease, expanded operations could include increased storage and upland transfer of bulk products utilizing new and existing buildings. The Applicant would likely undertake demolition, construction, and other related activities to develop expanded bulk product terminal facilities.

In addition to the current and planned activities, if the requested permit is not issued, the Applicant would intend to expand its bulk product terminal business onto areas that would have been subject to construction and operation of the proposed export terminal. In 2014, the Applicant described a future expansion scenario under No-Action Alternative that would involve handling bulk materials already permitted for off-loading at Dock 1. Additional bulk product transfer activities could involve products such as a calcine pet coke, coal tar pitch, cement, fly ash, and sand or gravel. While future expansion of the Applicant's bulk product terminal business might not be limited to this scenario, it was analyzed to help provide context to a No-Action Alternative evaluation and because it is a reasonably foreseeable consequence of a Department of the Army denial.

1.2 Regulatory Setting

Various jurisdictions have responsibility for the protection and regulation of groundwater. These jurisdictions and the regulations, statutes, and guidelines that apply to groundwater are summarized in Table 1.

Table 1. Regulations, Statutes, and Guidelines for Groundwater

Regulation, Statute, Guideline	Description
Federal	
National Environmental Policy Act (42 USC 4321 <i>et seq.</i>)	Requires the consideration of potential environmental effects. NEPA implementation procedures are set forth in the President's Council on Environmental Quality's Regulations for Implementing NEPA (49 CFR 1105).
U.S. Army Corps of Engineers NEPA Environmental Regulations (33 CFR 230)	Provides guidance for implementing the procedural provisions of NEPA for the Corps. It supplements CEQ regulations 40 CFR 1500–1508.

Regulation, Statute, Guideline	Description
Clean Water Act (33 USC 1251 <i>et seq.</i>)	Establishes the basic structure for regulating discharges of pollutants into waters of the United States and regulating quality standards for surface waters but not groundwater.
Safe Drinking Water Act	Requires the protection of groundwater and groundwater sources used for drinking water. Also, requires every state to develop a wellhead protection program.
National Pollutant Discharge Elimination System Permit	Authorized by the Clean Water Act, the permit program controls water pollution by regulating point sources discharging pollutants into waters of the United States. Industrial, municipal, and other facilities must obtain permits if their discharges go directly to surface waters. Surface water in the study area interacts with groundwater.
State	
Washington State Environmental Policy Act (WAC 197-11, RCW 43.21C)	Requires state and local agencies in Washington to identify potential environmental impacts that could result from governmental decisions.
Water Code (RCW 90.03)	Establishes rules for regulating and controlling water rights, and defines beneficial uses.
Regulation of Public Groundwaters (RCW 90.44)	Regulates and controls groundwater. Extends application of surface water statutes (90.02 RCW) to groundwater.
Water Quality Standards for Groundwaters of the State of Washington (WAC-173-200)	Groundwater standards intended to preserve a level of quality for groundwater capable of meeting current state and federal safe drinking water standards.
Drinking Water/Source Water Protection (RCW 43.20.050)	Requires the Washington State Department of Health assure safe and reliable public drinking water supplies in cooperation with local health departments and water purveyors.
Model Toxics Control Act (RCW 70.105D)	Requires potentially liable persons to assume responsibility for cleaning up contaminated sites.
State Water Pollution Control Law (RCW 90.48)	Grants Ecology the jurisdiction to control and prevent the pollution of streams, lakes, rivers, ponds, inland water, salt waters, watercourses, and other surface and groundwater in the state.
Water Resources Act of 1971 (RCW 90.54)	Sets fundamental policies for the state to insure waters of the state are protected and fully utilized for the greatest benefit.
Washington State Oil and Hazardous Substance Spill Prevention and Response (90.56 RCW)	Requires notification of releases of hazardous substances and establishes procedures for response and cleanup
Model Toxic Control Act Cleanup Regulations (Chapter 173-340 WAC).	Establishes procedures for investigation and site cleanup actions. Requires potentially liable persons to assume responsibility for cleaning up contaminated sites

Regulation, Statute, Guideline	Description
Local	
Cowlitz County SEPA Regulations (CCC Code 19.11)	Provide for the implementation of SEPA in Cowlitz County.
Cowlitz County Critical Areas Ordinance (Cowlitz County Code 19.15)	Designates critical areas and development regulations to assure the conservation of such areas in accordance with best available science.
Longview Water Supply Protection Ordinance (LMC 17.100)	Establishes a Wellhead Protection Program to minimize the risk of groundwater contamination
City of Longview Critical Areas Ordinance (Off-Site Alternative Only) (Longview Municipal Code 17.10)	Identifies resource lands of long-term significance; designates and protects critical resource areas, including wetlands, geologically hazardous areas, critical aquifer recharge areas, fish and wildlife habitat, and frequently flooded areas.
NEPA = National Environmental Policy Act; CFR = Code of Federal Regulations; USC = United States Code; RCW = Revised Code of Washington; SEPA = Washington State Environmental Policy Act; WAC = Washington Administrative Code; EPA = U.S. Environmental Protection Agency; Ecology = Washington State Department of Ecology, LMC = Longview Municipal Code	

1.3 Study Area


The study areas for the On-Site Alternative and Off-Site Alternative are described below.

1.3.1 On-Site Alternative

The study area for direct impacts on groundwater is the project area for the On-Site Alternative. The study area for indirect impacts is the City of Longview-Frontal Columbia River (Hydrologic Unit Code [HUC]-12: 170800030602) (Figure 4).

1.3.2 Off-Site Alternative

The study area for direct impacts on groundwater is the project area for the Off-Site Alternative. The study area for indirect impacts City of Longview-Frontal Columbia River (Hydrologic Unit Code [HUC]-12: 170800030602) (Figure 4).

Figure 4. Groundwater Study Areas for the On-Site Alternative and Off-Site Alternative

Chapter 2

Affected Environment

This chapter describes the methods for assessing the affected environment and determining impacts, and the affected environment in the study areas as it pertains to groundwater resources.

2.1 Methods

This section describes the methods used to characterize the affected environment and assess the potential impacts related to hazardous material under the On-Site Alternative, Off-Site Alternative, and No-Action Alternative.

2.1.1 Data Sources

The following sources of information were used to characterize and evaluate groundwater conditions in the study areas.

- *Remedial Investigation Report* (Anchor Environmental, LLC 2007)
- *Former Reynolds Metals Reduction Plant—Longview, Draft Remedial Investigation and Feasibility Study* (Anchor QEA 2014a).
- *Millennium Coal Export Terminal Longview, Washington, Affected Environment Analysis Water Resources Report* (URS Corporation 2014a)
- *Millennium Coal Export Terminal Longview, Washington, Water Resource Report* (URS Corporation 2014b)
- *Millennium Coal Export Terminal Longview, Washington, Surface Water Memorandum* (URS Corporation 2014c).
- *Millennium Coal Export Terminal Longview, Washington Surface Water Memorandum, Second Supplement to Water Resource Report Water Collection and Drainage* (URS Corporation 2014d)
- *Millennium Coal Export Terminal Longview, Washington, Off-Site Alternative – Barlow Point, Appendix M, Water Resource Report* (URS Corporation 2014e).
- City of Longview, Mint Farm Regional Water Treatment Plant, Preliminary Design Report, Part 2A, Hydrogeologic Characterization, March 2010.)
- Other scientific literature as cited within the text.

2.1.2 Impact Analysis

This impact analysis evaluates the changes the On-Site Alternative, Off-Site Alternative, and No-Action Alternative could have on existing groundwater conditions and how existing groundwater conditions could affect the project areas. Although the indirect impact study area includes the extent of the City of Longview-Frontal Columbia River watershed (Hydrologic Unit Code [HUC]-12: 170800030602), impacts to groundwater were determined to be limited to the project area and along the rail line that accesses the project area within the watershed. For direct impacts, the

analysis assumes Best Management Practices (BMPs) were incorporated into the project design, operations of the facility, and during construction.

Potential groundwater impacts have been evaluated with respect to several general parameters, including groundwater discharge and recharge, groundwater quality, and groundwater withdrawal and how the On-Site Alternative, Off-Site Alternative, and No-Action Alternative may affect these parameters. The assessment of impacts is also based on regulatory controls and the assumption the On-Site Alternative or Off-Site Alternative would include the following elements.

On-Site Alternative:

- An individual National Pollutant Discharge Elimination System (NPDES) permit for stormwater discharges during construction and operations.
- Remediation of any existing soil and groundwater contamination in the project area prior to and concurrently with project construction.
- Long-term monitoring as part of the remediation of the existing groundwater contamination to verify remedy effectiveness and natural attenuation of groundwater contamination.

Off-Site Alternative:

- An individual NPDES permit for stormwater discharges for construction and operations (both an NPDES Construction Stormwater General and Industrial Stormwater Permit).

For the purpose of this analysis, construction impacts are based on peak construction period and operations impacts are based on maximum throughput capacity (up to 44 million metric tons per year).

2.2 Affected Environment

The affected environment related to groundwater in the study areas is described below.


Groundwater can be described as water that is collected or flows beneath the Earth's surface, filling the porous spaces in soil, sediment, and rocks. Groundwater largely originates from rain or melting snow and ice, and is the source of water for aquifers, springs, and wells (Washington State Department of Ecology 2014a). An aquifer is the underground soil or rock through which groundwater can easily move. The amount of groundwater able to flow through soil or rock depends on the size of the spaces in the soil or rock and how well the spaces are connected. Aquifers consisting of gravel, sand, sandstone, or fractured rock such as limestone are made of materials permeable (or porous) and allow water to flow through the formation. Aquifers that contain materials such as clay or shale have many small pores that are not well connected and are considered impermeable with restricted groundwater flow (U.S. Geological Survey 2001). An unconfined aquifer is recharged directly by infiltration of precipitation or surface water (e.g., rivers). Confined aquifers are overlain by low-permeability material that limits the vertical flow of water into or out of the aquifer. Landowners access groundwater from wells that tap into an aquifer. Most groundwater is better protected from quick contamination than surface water, depending on a contaminant's ability to permeate the overlying soils or rock.

2.2.1 Regional Setting

The project area and Applicant's leased area are within Water Resource Inventory Area (WRIA) 25, also known as the Grays-Elochoman watershed. This watershed encompasses approximately 296,000 acres and is defined by five subbasins: Grays River, Skamokawa Creek, Elochoman River, Abernathy/Germany Creek, and the Coal Creek/Longview Slough. The project area is within the Coal Creek/Longview Slough subbasin. (HDR and EES 2006). Figure 5 depicts the Grays-Elochoman watershed, the five subbasins, and the project areas for the On-Site Alternative and Off-Site Alternative, within the Coal Creek/Longview Slough subbasin.

The principal hydrogeological units that yield the largest quantities of groundwater to wells within WRIA 25 are the unconsolidated sediments (Alluvium Unit) that occur in the valleys of the Cowlitz and Grays river systems and along the Columbia River (HDR and EES 2006). This unit consists of unconsolidated to poorly consolidated Quaternary-age sand, gravel, and silt that form undissected terrace deposits and floodplain deposits within major river and stream valleys. The thickness of this unit is highly variable, commonly ranging from less than 5 feet to more than 100 feet (Lower Columbia Fish Recovery Board 2001).

Other water-bearing units present in this watershed include tertiary continental sedimentary rocks and the Columbia River basalt (CRB) group. The tertiary continental sedimentary rocks are composed of mainly moderately to well indurated fluvial (river/stream deposits) sediments, consisting of sandstone, conglomerates, and siltstones, volcaniclastic sediments, and minor paludal (swamp/marsh) and lacustrine (lake) deposits. The tertiary continental sedimentary rocks occur in the eastern portion of the watershed and can reach more than 2,000 feet thick. The CRB group represents the distal portions of a series of continental flood basalt flows that emanated from linear vent systems in northeastern Oregon, southeastern Washington, and western Idaho between approximately 6 and 17 million years ago. The total thickness of this group is highly variable, ranging from 50 feet to more than 400 feet (Lower Columbia Fish Recovery Board 2001).

Figure 5. Watershed Map

2.2.1.1 Coal Creek/Longview Slough Subbasin

The project areas are within the Coal Creek/Longview Slough subbasin. The principal aquifers mapped in this subbasin are the alluvium and the CRB group. The alluvial aquifer is most extensive in the lower elevations of the subbasin, along streams and their tributaries. The sediments that compose the alluvial aquifer are generally highly permeable. Groundwater in the alluvial aquifer is generally unconfined. Production wells, which produce groundwater for human consumption, are screened in the alluvial aquifer and generally have high yields (to greater than 1,000 gallons per minute [gpm]). The alluvial aquifer is recharged in part by the Columbia and Cowlitz Rivers and tributaries such as Coal Creek (Lower Columbia Fish Recovery Board 2001).

The CRB group is present in the higher elevations of the Coal Creek subbasin. This aquifer is recharged by precipitation, seasonal gains from rivers and streams, and inflow from deeper bedrock aquifers. The number of wells completed in aquifers in the CRB group is unknown; however, groundwater use values presented in the *WRIA 25/26 Grays-Elochoman and Cowlitz Watershed Planning Documents Level 1 Assessment* indicate that significant water withdrawal from the basalt water-bearing zones is not currently occurring. The bulk of the groundwater withdrawal in the Coal Creek/Longview Slough subbasin is currently occurring from the alluvial aquifers where most of the population resides (Lower Columbia Fish Recovery Board 2001).

2.2.2 Local Setting

The project areas for the On-Site Alternative and Off-Site Alternative are located on the northeast shore of the Columbia River. The project areas are situated within the Longview-Kelso basin, a topographic and structural depression formed by the Cascadia subduction zone (Anchor QEA 2013 in URS Corporation 2014a). The Longview-Kelso basin is composed of unconsolidated alluvium (silt, fine-grained sand, and clay) underlain by alluvium (coarse-grained sand and gravel). Groundwater resources in the study areas include an upper alluvium aquifer (i.e., shallow groundwater) and a deeper confined aquifer from which industries, small farms, and domestic well users withdraw groundwater. Shallow groundwater is present in the upper 25 to 100 feet of alluvium and is in direct hydraulic communication with the Columbia River. Preliminary hydrogeologic investigations conducted for the City of Longview indicate that shallow, unconfined groundwater does not significantly contribute to the deeper aquifer as the lower aquifer is primarily recharged by deeper aquifers below the Columbia River (Anchor QEA 2014b).

2.2.2.1 Shallow Aquifer

Groundwater in the shallow aquifer is found at depths less than 5 feet below the ground surface (bgs) (Anchor QEA 2014b). Groundwater flow in the shallow aquifer in the study area is complex due to the competing influences of the Consolidated Diking and Improvement District (CDID) #1 system and, to a lesser extent, the tidally influenced Columbia River (Anchor 2014). Groundwater and stormwater discharged to the CDID #1 ditches are actively pumped from the ditches by the CDID #1 to maintain surface-water levels below those in the Columbia River. Water from the CDID #1 ditches is discharged to the Columbia River. Near the project areas, a CDID #1 pump station is located near the southwest corner of the On-Site Alternative Applicant's leased area boundary (Figure 2) (southeast corner of the Off-Site Alternative project area boundary [Figure 3]).

2.2.2.2 Deep Aquifer

The deep aquifer is located at an approximate depth of 200 feet bgs, with sand coarsening to gravel to a depth of 400 feet bgs (Anchor QEA 2014). The deep aquifer is a source of drinking water in the study area. The City of Longview conducted a pumping test at a production well for the Mint Farm Regional Water Treatment Plant, located approximately 6,000 feet east of the eastern boundary of the On-Site Alternative Applicant's leased area (Figure 2), to characterize the deep aquifer. The test results indicate that the Columbia River recharges the deep aquifer at the Mint Farm site and suggest similar recharge of the deep aquifer in the project areas. Overall, recharge to the deep aquifer in the project areas is expected to be primarily driven by deeper aquifers below the Columbia River and insignificantly from shallow, unconfined aquifers (Anchor QEA 2014b). Discharge from the deep aquifer is from seepage back to the Columbia River, direct discharge to the shallow aquifer, and pumpage from wells (URS Corporation 2014b).

2.2.2.3 Columbia River

The Columbia River flows along the entire south/southwest boundary of both project areas and water levels fluctuate with the tides. The mean annual flow of the Columbia River, measured at the Beaver Army Terminal at river mile 53.8 near Quincy, Oregon, is approximately 236,000 cubic feet per second. The river's annual discharge rate fluctuates with precipitation, snowmelt, and reservoir releases, ranging from 63,600 cubic feet per second in a low water year to 864,000 cubic feet per second in a high water year (U.S. Geological Survey 2014). Tributaries to the Columbia River basin are primarily snow-fed (i.e., precipitation falls mainly as snow). These tributaries typically have low winter flows and strong spring and summer peaks with snowmelt, which concentrates about 60% of the natural runoff to the Columbia River during May, June, and July (URS Corporation 2014b). Tidal influences tend to propagate farthest in the coarse-grained deep aquifer and to a much lesser degree within the shallow aquifer (Anchor QEA 2014a).

2.2.2.4 CDID #1 Ditch System

The CDID #1 is a secondary permittee on the Cowlitz County/Kelso/Longview Municipal NPDES permit. The CDID #1 system is a series of levees and ditches. It consists of approximately 35 miles of drainage ditches for the purpose of flood protection from external flooding (rivers), internal flooding (storm drainage runoff), and flooding from lands adjacent to the levee system (groundwater). Additionally, the U.S. Army Corps of Engineers (Corps) constructed a CDID #1 flood control levee in the 1920s along the Columbia River shoreline at the southern boundary of the On-Site Alternative project area, referred to herein as the Columbia River levee (Figure 2). This levee is part of the larger network of levees designed to protect properties in the Longview area from Columbia River flooding (Anchor QEA 2014a).

The CDID #1 ditch system surrounding the project areas controls flooding and maintains water levels in the CDID #1 ditches below the water surface elevation of the Columbia River, which subsequently influences groundwater flow in the shallow aquifer. The CDID #1 ditch system also discharges to the Columbia River through a network of pump stations and valves. As a result of the CDID #1 ditch system, coupled with the higher water surface elevation of the Columbia River, groundwater flows away from the river (to the north, east, and west) and toward the CDID #1 ditches (Anchor QEA 2014a), except for one localized area: groundwater flow south of the axis of the Columbia River levee is toward the Columbia River (Anchor Environmental 2007). Some groundwater from the deep aquifer may be discharged into the CDID #1 ditches because an upward

vertical gradient also exists in areas near the CDID #1 ditches, causing groundwater in the deep aquifer to move upward into the shallow aquifer (Anchor Environmental 2007).

2.2.2.5 Project Area for the On-Site Alternative

As discussed above, the On-Site Alternative project area is located on the northeast shore of the Columbia River. At the project area, groundwater movement in the shallow aquifer is relatively slow. Groundwater in the shallow aquifer flows north from the Columbia River levee then proceeds northwest toward the regional CDID #1 ditch system (Figure 6) (Anchor Environmental 2007). In areas farther from the CDID #1 ditches, shallow groundwater, fed by precipitation, moves downward into the deep aquifer. In areas near the CDID #1 ditch system, groundwater in the deep aquifer moves upward into the shallow aquifer. The levee recharges the shallow groundwater to the north, while the Columbia River recharges the groundwater south of the levee. Discharge of the shallow aquifer occurs from seepage back to the Columbia River, CDID #1 ditch system extraction, evapotranspiration, and pumping from shallow wells (URS Corporation 2014a).

Localized groundwater recharge and quality in the project area are influenced by the Columbia River, the CDID #1 ditch system, and the on-site drainage ditch system in the Applicant's leased area. The project area is not considered a significant source of groundwater recharge through infiltration due to the hydrology discussed below under *Drainage Basins and Stormwater System*.

Similar to the shallow aquifer, groundwater in the deep aquifer flows from the Columbia River levee northward, then proceeds northwest toward the CDID #1 ditch 14 (Figure 6) (Anchor Environmental 2007). The one exception to this localized flow of deep groundwater away from the Columbia River (at least seasonally) is an area south of the levee where it flows toward the river.

As discussed above, shallow groundwater that is recharged from precipitation moves downward into the deep aquifer if it is not intercepted by the CDID #1 ditches. However, in areas near the CDID #1 ditches an upward vertical gradient exists, causing groundwater in the deep aquifer to move upward into the shallow aquifer (Anchor Environmental 2007).

Drainage Basins and Stormwater System

The on-site drainage ditch system collects all stormwater runoff in the Applicant's leased area. The system includes 12 drainage basins and five outfalls, which the Applicant manages under the NPDES permit (WA-000008-6) for the existing bulk product terminal. The outfalls discharge treated stormwater to the CDID #1 ditches and the Columbia River. One of the five outfalls, 004, has been closed since 1991. The major collection and treatment systems, drainage basins, outfalls, and discharge locations currently managed under the NPDES program are described in the following sections, based on the *Millennium Coal Export Terminal Longview, Washington Surface Water Memorandum* (URS Corporation 2014c), and shown on Figures 7 and 8.

Figure 6. Groundwater Gradients and Flow Direction for the On-Site Alternative






Figure 7. Water Management System in the Project Area for the On-Site Alternative

Figure 8. Schematic of Stormwater Flow in the Project Area for the On-Site Alternative

Basins 1 and 3a

Waters collected from Basins 1 and 3a (approximately 89 and 9 acres, respectively) are collected from facility pumps and ditches and directed to the Facility 77 Sump/Pump Station. An average of approximately 99 million gallons per year of stormwater from Basins 1 and 3a is routed into Facility 77, treated through Facility 73, and then pumped through Outfall 002A to the Columbia River.

Basin 2

Basin 2 (approximately 40 acres) collects stormwater runoff from the top of the cap of the closed Black Mud Pond facility into a sump, where it is routed through a pump station to drainage ditches that gravity flow via the U-Ditch into Facility 77. Approximately 17 million gallons per year (97% of the stormwater runoff from Basin 2) are routed into Facility 77. During heavy storm events, stormwater from off the closed Black Mud Pond facility cap may overflow the Outfall 006 Sump/Pump Station (Figure 7) and flow to CDID #1 Ditch 14. No discharge has been observed through Outfall 006 since the sump/pump station was installed in 2012. Waters collected at Facility 77 are directed to Facility 73 for treatment and then discharged to the Columbia River through Outfall 002A.

Basins 3 and 5

Stormwater generated in Basins 3 and 5 (27 acres and 62 acres, respectively) discharge by gravity drainage to the CDID #1 Ditches 10 and 14, respectively. Ditches 10 and 14 are located at the north and west edges of the Applicant's leased area, respectively. An average of approximately 72 million gallons per year of stormwater flows to the CDID #1 ditches from these areas.

Basin 4

Waters collected from the cryolite area ditches (see *Cryolite Area Ditches* below) are directed to a pump and sent to Facility 71 (Industrial Wastewater Treatment Plant) for treatment. Treated water exiting Facility 71 is then discharged through internal Outfall 002B to Facility 77 where it is comingled with other waters and routed to treatment at Facility 73, eventually discharging to the Columbia River via Outfall 002A.

Stormwater runoff generated in Basin 4, other than in the cryolite area ditches, drains to gravity ditches that convey the flows to Pump Station 004, which discharges to Facility 77. An average of approximately 30 million gallons per year of stormwater from Basin 4 is collected and eventually discharges to the Columbia River via Outfall 002A.

Basins 4A, 5A, 5B, 6A, and 7

Stormwater from Basins 4A, 5A, 5B, 6A, and 7 may pond in these areas and then evaporate or infiltrate into the soil. These basins represent a combined area of approximately 71 acres and generate approximately 37 million gallons per year of stormwater.

Basin 6

Minor amounts of stormwater from Basin 6 may pond locally and evaporate or infiltrate into the soil. During storm events, stormwater from Basin 6 (an area of approximately 40 acres), is collected in the U-Ditch and conveyed to the Facility 77 Sump/Pump Station. An average of approximately 21 million gallons per year of stormwater from Basin 6 is conveyed to Facility 77. Process water and

stormwater collected at Facility 77 is treated through Facility 73 and then discharges to the Columbia River through Outfall 002A.

Facility 71

Facility 71, installed in 1988, is the site's industrial wastewater treatment system.¹ Treated wastewater from Facility 71 is discharged through Internal Outfall 002B to the Facility 77 Sump/Pump Station and is then comingled with the other waters, treated through Facility 73, and discharged through Outfall 002A to the Columbia River.

Facility 73 (Stormwater Treatment System)

Facility 73, the stormwater treatment system, is used to achieve water quality standards required by the existing NPDES permit (WA-000008-6). Facility 73 is located in the southwest portion of the Applicant's leased area and consists of a 1.98-million-gallon retention basin (Figure 7), oil and grease removal, multi-media filters, and a discharge pump station (Pump Station C). The retention basin is sized to handle flows up to 6,000 gpm (8.64 million gallons per day). The retention basin is equipped with an oil and grease removal system. Flows exiting the retention basin are discharged through a 20-inch line to Pump Station C. Pump Station C includes three alternating pumps with a combined discharge capacity of 6,000 gpm under peak flow conditions. Pump Station C pumps the water through an 18-inch line where an in-line turbidity monitor located downstream measures the outgoing water's turbidity. If the turbidity reading is below the turbidity set point, the water in the 18-inch line discharges into the 30-inch Outfall 002A line and then to the Columbia River. If the turbidity reading is above the turbidity set point, a solenoid valve routes the water through multimedia filters before tying back into the 18-inch line for discharge to the Outfall 002A line.

Facility 77 (Sump and Pump Station)

Facility 77 is a large central collection sump and pump station that is the primary stormwater discharge point for the majority of all basins within the southern property of the Applicant's leased area (except for Basins 3 and 5). Facility 77 is outfitted with four operating pumps with varying capacities of up to 2,700 gpm each. The pumps at Facility 77 previously discharged directly to the Columbia River through Outfall 002A; however, since the mid-1990s flows collected at Facility 77 are pumped through a 16-inch line to the stormwater treatment system (Facility 73) before being discharged through Outfall 002A.

Outfall 002A

Outfall 002A is a 30-inch outfall to the Columbia River that discharges the water it receives from Facility 73. As described above, treated wastewater from Facility 71 is discharged through Internal Outfall 002B to Facility 77 and is then comingled with the other waters and treated through Facility 73. The average amount of stormwater runoff generated by the basins discharging to Outfall 002A is 166.3 million gallons per year. The combined average flow to the Columbia River through Outfall 002A is 1.46 million gallons per day or 532.9 million gallons per year.

Outfall 003C

Outfall 003C drains through a 2,500-linear foot vegetated conveyance ditch to CDID #1 Ditch 10.

¹ Facility 71 was destroyed in a fire in June 2011 and reconstructed in February 2012.

Former Outfall 004

Former Outfall 004 was rerouted to Facility 77 with the installation of Pump Station 004, and the outfall was closed in 1991. From Facility 77, the water is routed to Facility 73 for treatment and then discharged to the Columbia River through Outfall 002A.

Outfall 005

Outfall 005 drains to CDID #1 Ditch 14. Stormwater runoff from improved areas ponds locally and infiltrates or evaporates. Runoff from larger events may gravity drain to a vegetated ditch and discharge to CDID #1 Ditch 14.

Rerouted Outfall 006

Outfall 006 was created after the current NPDES permit was issued in 1990 and is not described in NPDES permit WA-000008-6. Outfall 006 has been in multiple NPDES renewal applications submitted to the Washington State Department of Ecology (Ecology) since the Outfall was created. Treatment occurs through stormwater passing through the vegetated conveyance swale. Stormwater flows from Outfall 006 are routed to the U-Ditch and then to Facility 77 where the stormwater is pumped to Facility 73 for treatment and then discharged to the Columbia River through Outfall 002A. Treated stormwater runoff from events larger than the 6-month, 24-hour storm may overflow the Outfall 006 Sump/Pump Station and discharge directly into CDID #1 Ditch 14.

Cryolite Area Ditches

Additionally, a series of ditches, referred to as cryolite area ditches, which are not part of the CDID #1 or system that operates under the NPDES, is located on the east side of the Applicant's leased area (Figure 7). These ditches were constructed to control stormwater and perched shallow groundwater. Although the ditches used to discharge into the CDID #1 system, they are now isolated from it; water from these ditches is pumped via Pump Station 004 (Anchor Environmental 2007) to Facility 77 where it is pumped to Facility 73 for treatment prior to discharge through Outfall 002A.

2.2.2.6 Project Area for the Off-Site Alternative

The project area for the Off-Site Alternative is also located on the northeast shore of the Columbia River. Limited site-specific subsurface information was readily available for this project area at the time of preparation of this report. However, it is understood that the project area and broader lease area are currently undeveloped and vegetated, with grassy areas extending to the shoreline of the Columbia River. A portion of the eastern side of the lease area is in agricultural use, while another portion of the site appears to have been used for recreational motocross use. Agricultural uses have historically included pasture, silage/grass/hay, some food crops, commercial Christmas trees, and two golf courses that are considered turf grass crops (URS Corporation 2014e). The activities that previously occurred associated with the agricultural and recreational motocross uses may have included the use of pesticides, herbicides, fuels, and other related contaminants as noted in the NEPA Hazardous Materials Technical Report (ICF International 2016a).

Surrounding land uses include the residential neighborhoods of Barlow Point, Memorial Park, and West Longview to the north and east of the project area, and the closed Mt. Solo Landfill located immediately north-northeast of the project area. The nearest residential community is the West Longview neighborhood located 1 mile north of the project area. The next nearest residential

communities, located 1 to 2 miles east of the project area toward the Longview city center, include the Olympic West, Highlands, and Columbia Valley Gardens neighborhoods.

Groundwater conditions are anticipated to be similar to those described for the On-Site Alternative (Section 2.2.2.5) because the CDID #1 ditch system borders both project areas (Figure 3). Thus, the groundwater flow gradient beneath the project area is assumed similar to the On-Site Alternative, but this has not been confirmed. It is understood through data collected from the nearby groundwater monitoring wells installed in conjunction with the post-closure monitoring of the Mt. Solo Landfill, that there may actually be a slight groundwater gradient from the closed Mt. Solo Landfill towards the Off-Site Alternative project area, at least within the shallow aquifer. This could be a result of a more pronounced groundwater flow gradient between the Mt. Solo Landfill and the CDID #1 ditch system, caused by the different topographic reliefs between the two adjacent sites, which is more significant (i.e., the Mt. Solo Landfill is higher in elevation than the Off-Site Alternative project area) than observed across the On-Site Alternative site. Therefore, the CDID #1 ditch system may have a reduced impact upon the shallow aquifer in terms of groundwater gradient within this isolated area.

The Mount Solo Slough is a privately owned drainage ditch that forms the northern boundary of the project area and is near the closed Mount Solo Landfill. It is a highly meandering drainage that has been historically managed as a drainage ditch. It connects to CDID #1 Ditch 14 to the east and CDID #1 Ditch 16 to the north, both of which both connect to CDID #1 Ditch 10 (Figure 3).

2.2.3 Groundwater Quality

Groundwater data in WRIA 25 are extremely fragmented and exist for only a few localized areas near Kelso and Longview (Lower Columbia Fish Recovery Board 2001).

2.2.3.1 Regional

Alluvial (Shallow) Aquifers

According to the Lower Columbia Fish Recovery Board (2001), chemical quality of groundwater ranges from excellent to poor in the alluvium units. Shallow wells near streams and rivers typically have excellent water quality, while deeper wells and/or wells located farther from streams and rivers often produce groundwater of lower quality. The problem constituents are typically iron, manganese, and total dissolved solids found at levels that produce undesirable aesthetic/cosmetic (taste, odor, color, discoloration) effects, but do not necessarily pose health risks (Lower Columbia Fish Recovery Board 2001). The source of these elevated constituents is assumed to arise from bedrock groundwater recharge to the alluvial aquifer and/or long residence time for groundwater within the alluvial aquifer, which allows leaching of these constituents from the sediment that hosts the aquifer.

Another groundwater quality problem associated with alluvial aquifers in this area is the potential presence of phenol compounds. These phenol compounds are produced by the decomposition of vegetative materials because of dewatering volcanic lahars/debris flows².

² Lahar is an Indonesian term that describes a hot or cold mixture of water and rock fragments flowing down the slopes of a volcano and/or river valleys. As lahars move downstream from a volcano, their size, speed, and amount of water and rock debris/mudflow is constantly changing as it deposits rocks, boulders, and vegetation across the river valley it enters (USGS 2013).

Tertiary Continental Sedimentary Rock Unit

Limited data exist on the chemical quality of groundwater from the formations found in this aquifer unit. The available data suggest that the chemical quality is often poor. The problem constituents are typically iron and manganese found at levels that produce undesirable aesthetic/cosmetic (taste, odor, color, discoloration) effects, but do not necessarily pose health risks. Similar to the alluvium unit, the likely source of these elevated constituents is due to groundwater from older bedrock units that is entering this aquifer and/or long residence time for groundwater within this aquifer, which would allow leaching of these constituents from the sediment that hosts the aquifer (Lower Columbia Fish Recovery Board 2001).

Columbia River Basalt Group

No data on the chemical quality of groundwater from the Columbia Basin Basalt Group were available at the time of preparation of this document. However, the flood basalt flows of this group often serve as good aquifers capable of producing groundwater of typically good chemical quality (Lower Columbia Fish Recovery Board 2001).

2.2.3.2 Local

Kennedy/Jenks Consultants (2010) completed a water quality and environmental risk assessment as part of the preliminary design report for the Mint Farm Regional Water Treatment Plant. The risk assessment included sampling and water quality analysis of the groundwater from the deeper aquifer of six wells. This study found no chemicals in the groundwater above their respective human health screening levels. Kennedy/Jenks Consultants (2012a) repeated the water quality analysis from the same wells in November 2012 and found manganese and iron at levels above the Washington State Department of Health secondary water quality standards and arsenic in one of the wells but at levels below thresholds established by the U.S. Environmental Protection Agency (EPA) for drinking water quality standards). These levels were found to be naturally occurring and are characteristic of the regional water supply aquifer (Anchor QEA 2014a). Figure 9 shows the locations of the shallow aquifer monitoring wells and groundwater gradients at the Mint Farm. Figure 10 shows the deep aquifer monitoring wells and groundwater gradients at the Mint Farm.

Figure 9. Mint Farm Shallow Aquifer Monitoring Wells and Groundwater Gradients



Figure 10. Mint Farm Deep Aquifer Monitoring Wells and Groundwater Gradients

2.2.3.3 Project Area for the On-Site Alternative

Historical and Existing Sources of Groundwater Contamination

Industrial use of the Applicant's leased area began in 1941 with the development of the aluminum production operations by Reynolds Metals Company. The manufacturing capabilities were expanded in the 1960s and the operations focused primarily on aluminum production. Historical operations in the Applicant's leased area included aluminum production facilities, cable plant operations, cryolite recovery plant operations, and industrial landfills. Figure 11 shows the facilities in the Applicant's leased area. The NEPA Hazardous Materials Technical Report provides a complete description of the history of contamination in the Applicant's leased area (ICF International 2016a).


Aluminum Production Facilities

Initial industrial operations in the Applicant's leased area began with the Reynolds Metals aluminum reduction plant in 1941. The plant is located in the eastern portion of the Applicant's leased area (referred to as South Plant) and was used for aluminum smelting and casting operations (Figure 11). In 1967, Reynolds developed the North Plant in the center of the Applicant's leased area for additional aluminum production (Anchor QEA 2014a).

Smelter operations required an extensive dry-materials handling system for raw materials. Raw materials included alumina ore, petroleum coke, coal tar pitch, anthracite coal, cryolite, and aluminum fluoride. Liquid coal tar was unloaded by rail and transferred into storage tanks, which connected to the greenmill by distribution lines. At the greenmill, pitch (which contains polycyclic aromatic hydrocarbons [PAHs]) was used as a raw material for anode and cathode construction. Pitch was also placed on the ground near the rail unloading area (Anchor Environmental 2007). Smelter operations in the Applicant's leased area have been associated with elevated concentrations of fluoride in soils or solid media (Anchor QEA 2014a). Figure 11 shows the location of the aluminum manufacturing facilities: North Plant and South Plant lie within the project area, while the pitch tanks and unloading area lie near the southern boundary of the project area.

Former Cable Plant Operations

The cable plant, constructed in the late 1960s, was located west of the aluminum production facilities and within the project area boundary (Figure 11). The cable plant produced electrical cable products, including aluminum wire, rods, and insulated (polyethylene and polyvinyl) low- and medium-voltage cable. It received molten aluminum from the aluminum production facilities and processed it in three furnaces: a continuous ingot caster, a rolling mill, and wire drawers. Ancillary structures associated with the cable plant included office buildings, a parking lot, and a sanitary wastewater treatment plant.

Figure 11. Former and Existing Facilities in the Applicant's Leased Area for the On-Site Alternative

Cryolite Recovery Plant

The cryolite recovery plant was constructed in 1953 in the South Plant area (Figure 11). The plant was used as a spent potliner (SPL) recovery and recycling facility for the Reynolds facility and other northwest aluminum reduction plants. SPL is a byproduct of the aluminum manufacturing process. It contains fluoride and PAH compounds and, potentially, varying levels of cyanide. The cryolite recovery plant also recovered reusable fluoride compounds, called underflow solids that were eventually used to control air emissions that occurred during the aluminum manufacturing process. The underflow solids were collected in clarifiers (a type of tank) at two unspecified locations in the Applicant's leased area (Anchor Environmental 2007).

The cryolite recovery process involved multiple steps, resulting in a "black mud," which was disposed of in several fill deposits in the Applicant's leased area. The process also required lime to produce the sodium hydroxide solution. After the 1970s, the spent lime facility was combined and managed with the residual carbon facility.

With the increase in regulatory requirements associated with SPL stockpiling and handling in the 1980s, Reynolds began to bury and cover the stockpiled SPL and install groundwater monitoring wells to address concerns regarding potential impacts on groundwater in the area (Anchor QEA 2014a).

In May 1990, the cryolite recovery plant ceased operation. The SPL generated during aluminum manufacturing was removed and shipped to permitted treatment, storage, and disposal facilities. The cryolite recovery plant facilities were removed in May 1990; the area where they once sat is now vacant (Anchor Environmental 2007). No deposits of SPL are known to remain in the Applicant's leased area (Anchor QEA 2014a).

Residual carbon was generated during the cryolite recovery process. Residual carbon typically includes calcium carbonate, alumina, carbon, fluoride compounds, sodium, iron, and sulfate (URS Corporation 2014b). Test results revealed that shallow groundwater at the former location of the cryolite recovery plant contained fluoride-containing solid media and fluoride and alkalinity releases because of the cryolite plant's operations (URS Corporation 2014b). Additional investigations, findings, and cleanup of the residual carbon deposits are discussed below (*Remedial Actions* and *Remedial Investigation Findings*).

Industrial Landfills

Three historical landfills are located in the Applicant's leased area, outside the project area boundary

- Floor sweeps landfill (Landfill 1) is located east of the former cryolite recovery plant.
- The old industrial landfill (Landfill 2) is located on the southwest side of the former Reynolds facility.
- The construction debris landfill (Landfill 3) is located between the Columbia River levee and the Columbia River.

Landfill 1 received dry materials gathered from floors in the potlines, including alumina, bath, cryolite, and aluminum fluoride. By the mid-1970s, Landfill 1 was no longer in use and Landfill 2 began operation. Landfill 2 accepted scrap coke, ore, cryolite, aluminum fluoride, bath, brick, concrete, and debris from miscellaneous maintenance activities. Landfill 3 contains concrete debris

and other plant wastes, similar to Landfill 2. Use of these landfills ceased in the 1980s prior to implementation of more restrictive regulations. The landfills are still present in the Applicant's leased area; additional investigations, findings, and cleanup are discussed below (*Remedial Actions* and *Remedial Investigation Findings*). Figure 11 shows the locations of the cryolite recovery plant and the three landfills.

Historical Uses after Closure of the Reynolds Facility

In 2000, Alcoa purchased Reynolds Metals Company, which became a wholly owned subsidiary. As part of this transaction, Reynolds was required to divest of its facility on the Applicant's leased area. It sold the facility to Longview Aluminum in 2001 but retained ownership of the land. Longview Aluminum immediately ceased aluminum production operations, and the facility has not produced aluminum since 2001.

In December 2004, Chinook Ventures Inc. purchased the Applicant's leased area assets from a bankruptcy trustee, which took over operations after Longview Aluminum declared bankruptcy in 2003. CVI entered into a long-term ground lease with Reynolds that ran until September 2005 when ownership of the land transferred from Reynolds to Northwest Alloys, both of which are wholly owned subsidiaries of Alcoa.

CVI was sole operator of the facility and associated Northwest Alloys-owned properties between 2004 and 2011. CVI operated a terminal for the import, handling, and export of dry bulk materials, such as alumina, coal, green petroleum coke, cement, fly ash, slag, and other materials. During this time, CVI also decommissioned the majority of the facilities associated with aluminum manufacturing operations and recycled materials from smelters, which were being decommissioned throughout the northwest region. These activities included the removal and disposal or recycling of alumina, electrolyte bath, coal, and carbon products.

On January 11, 2011, CVI sold its Applicant's leased area assets to the Applicant, which has subsequently removed most of the structures constructed by CVI and has continued facility decommissioning, removal, and cleanup activities.

Remedial Action (Cleanup) Process

In January 2015 a remedial investigation/feasibility study (RI/FS) (Anchor QEA 2014a) was prepared per the requirements of Washington State's Model Toxics Control Act (MTCA), which is implemented by Ecology. Under the MTCA, the RI/FS included two parts: completion of the investigation of potential contaminants in the Applicant's leased area and evaluation of the potential options for cleanup. The selection of a final cleanup action occurs in a separate step and will be documented in an MTCA cleanup action plan.³

Prior to preparation of the RI/FS, an initial site assessment was performed by Ecology, which reviewed available data and established the agency's priority ranking for the site investigation and cleanup. During this phase, Ecology ranked the former site as a 5, the lowest priority on its five-point scale.

³ A draft MTCA Cleanup Action Plan, released by Ecology in January 2016, describes proposed cleanup actions to protect human health and the environment, meet state cleanup standards, and comply with other applicable state and federal laws.

Since completion of the initial assessment and site ranking, a number of investigations and cleanup actions have been completed in coordination with Ecology. The previously completed cleanup actions prior to preparation of the RI/FS have resolved cleanup issues for a number of areas within the Applicant's leased area. Extensive quantities of materials have been appropriately reused, recycled, or disposed of at permitted facilities. These actions have improved safety of the Applicant's leased area and helped to return the property to productive reuse.

After Ecology reviewed information from the previous investigation, cleanup, and closure activities, it defined focus areas for further evaluation and defined specific data gaps and testing requirements to be addressed in the RI/FS. Figure 12 shows the locations of the resulting testing that was implemented as part of the RI/FS. The RI/FS included multiple phases of investigation activity, the scope of which was developed and approved by Ecology (Anchor QEA 2014a).

Final cleanup decisions are to be specified in a final MTCA cleanup action plan. Design and implementation of the cleanup action will be performed after finalization of the cleanup action plan and court approval of the consent decree. Long-term management to monitor and/or clean up persistent water quality issues will be addressed in the cleanup action plan.

The RI/FS provides a detailed description of cleanup and remedial actions conducted in the Applicant's leased area (Anchor QEA 2014a). Figure 13 shows the locations of previous cleanup and removal activities and remedial investigation focus areas.

Remedial Investigation Findings

The following sections summarize the RI/FS (Anchor QEA 2014a).

Screening Levels

The groundwater contained in the fill soil and shallow silt/clay/soils of the upper alluvium or shallow aquifer in the Applicant's leased area is not used as a source for drinking water. Furthermore, the fine-grained texture and low hydraulic conductivities of the upper alluvium, in conjunction with the upward groundwater gradients between the lower water supply shallow aquifer and the upper alluvium, severely limit the potential for this shallow groundwater to affect potential sources of drinking water. Regardless, the RI/FS screening levels included consideration of regulatory requirements applicable to groundwater that is used as a drinking water source and include the following.

- **MTCA Method A Groundwater Cleanup Levels.** These levels consider risks associated with ingestion of drinking water.
- **State Drinking Water Maximum Contaminant Levels.** These levels assume drinking water as the highest beneficial use of groundwater and are typically more stringent than the national drinking water standards.
- **Natural Background:** MTCA regulations consider background chemical concentrations as part of data screening and development of cleanup levels for groundwater.

Table 2 shows the RI/FS screening levels for groundwater for the relevant chemicals of concern discussed below. This table lists the relevant chemicals of concern discussed below in *Source Areas and Chemicals of Concern*. For a list of all parameters tested in the Applicant's leased area, refer to the RI/FS (Anchor QEA 2014a).


Figure 12. Overview of Remedial Investigation Testing Locations in the Applicant's leased area for the On-Site Alternative


Figure 13. Previous Cleanup, Removal Areas, and Remedial Investigation Areas in the Applicant's leased area for the On-Site Alternative

Table 2. Screening Levels for Groundwater

Parameter	Screening Level	Unit ^{a,b}	ARAR ^{c,d}
Cyanide	0.2	mg/L	MCL
Fluoride	4.0	mg/L	MCL
Total cPAHs	0.1	µg/L	MTCA Method A
Total PCB Aroclors	0.1	µg/L	MTCA Method A
TPH-Diesel	500	µg/L	MTCA Method A

^a mg/L = milligrams per liter

^b µg/L = micrograms per liter

^c ARAR = Applicable, Relevant, and/or Appropriate Requirement.

^d MCL = State Drinking Water Maximum Contaminant Level

Source Areas and Chemicals of Concern

Testing of groundwater was conducted over a series of multiple sampling events primarily occurring in September and October 2006, July 2011, October 2011, and October 2012 and primarily outside the boundaries of the project area (Anchor QEA 2014a). Specific testing parameters varied by sampling event and were consistent with Ecology testing requirements defined in the RI/FS Work Plan and Addenda (Anchor QEA 2014a).

Cyanide

Groundwater cyanide concentrations in the study areas are very low and have been decreasing over time. None of the groundwater samples collected in the western portion of the study areas near the closed Black Mud Pond facility and Fill Deposit B-3 exceeded the groundwater maximum contaminant level (MCL) for free cyanide. As shown on Figure 14, 2012 free cyanide concentrations in all samples taken in the western portion of the Applicant's leased area were below the groundwater screening level of 0.2 milligrams per liter.

Groundwater cyanide concentrations in samples collected in the eastern portion of the Applicant's leased area have also been decreasing over time. One of the groundwater samples (located near the Former Stockpile Area in the southeast corner of the project area) slightly exceeded the groundwater MCL in 2006, but concentrations decreased significantly by the 2011 and 2012 sampling events. As shown on Figure 14, the 2012 free cyanide⁴ concentrations in most of the eastern portion of the Applicant's leased area were below the groundwater screening level.

Fluoride

Groundwater fluoride concentrations in most of the Applicant's leased area are below the groundwater screening levels. The exceptions are the shallow groundwater located in or immediately adjacent to the landfills and fill deposits (Anchor QEA 2014a). Data from the most recent sample event in 2012 for fluoride are summarized on Figure 15. Green data symbols represent groundwater fluoride concentrations that are below thresholds established for the drinking water MCL.

⁴ Free cyanide refers to the sum of hydrogen cyanide (HCN) and cyanide ion (CN⁻) in a sample. Free cyanide is bioavailable and toxic to organisms in aquatic environments.



Figure 14. 2012 Groundwater Testing Results in the Applicant's leased area for the On-Site Alternative—Total Free Cyanide

Figure 15. 2012 Groundwater Testing Results in the Applicant's leased area for the On-Site Alternative—Total Free Fluoride

In the western portion of the Applicant's leased area, the highest concentrations of fluoride are measured in wells located in Fill Deposit B-3 and adjacent to Landfill 2 (industrial landfill), and in the wells located immediately downgradient of the closed Black Mud Pond facility.

In the eastern portion of the Applicant's leased area outside of the project area boundary, groundwater monitoring data show that fluoride concentrations attenuate rapidly with distance from the fill and landfill deposits (Anchor QEA 2014a), which are summarized as follows.

- **Fill Deposit A (spent lime) and B-1 (residual carbon).** Groundwater fluoride concentrations immediately downgradient of these deposits comply with the groundwater MCL. This is more than 10-fold to 20-fold lower than the fluoride concentrations measured in the fill deposits.
- **Landfill 1 (floor sweeps).** Two well pairs are located immediately adjacent to this landfill (less than 10 feet from the landfill contents). In both well pairs, the deeper groundwater samples comply with the groundwater fluoride concentration MCL, and the fluoride concentration in the shallower groundwater samples slightly exceed the MCL.
- **Fill Deposit B-2 (residual carbon).** The highest groundwater fluoride concentrations in the Applicant's leased area are located in Fill Deposit B-2, located just east of the former cryolite recovery plant. The groundwater wells in this area are located in the fill deposit and immediately adjacent to the former stockpile area and the cryolite area ditches. Groundwater in this area has elevated alkalinity, which enhances fluoride solubility. In contrast, the groundwater fluoride concentrations immediately downgradient of this deposit are consistently below the MCL, showing that fluoride in this area is relatively immobile.

In consideration with other RI/FS monitoring data, the groundwater data for fluoride concentrations demonstrate that the closure of the closed Black Mud Pond facility has been effective, and that the elevated fluoride concentrations present in shallow groundwater adjacent to the other landfill and fill deposits are localized and relatively immobile. The higher concentrations of fluoride present within Fill Deposit B-2 appear to be a function of the fill deposits and the geochemical properties of this area, including the elevated alkalinity of groundwater (Anchor QEA 2014a).


Groundwater fluoride concentrations attenuate rapidly with depth and with distance laterally from these landfills and fill deposits. This has been observed in all parts of the Applicant's leased area, including the areas near Fill Deposit B-2. Surface water monitoring demonstrates the fluoride present in the shallow groundwater is not affecting water quality in the adjacent CDID #1 ditches 10, 5, or 14 (Anchor QEA 2014a).

Polycyclic Aromatic Hydrocarbons

At the request of Ecology, groundwater samples from selected locations were analyzed for PAHs. Figure 16 shows the maximum concentration of carcinogenic PAHs (cPAH)⁵ measured during each of the sampling events (2007, 2011, and 2012). None of the measured cPAH concentrations from the western portion of the Applicant's leased area exceeds groundwater screening levels. In the eastern portion of the Applicant's leased area, and outside the project area boundaries, cPAH concentrations during the 2012 sampling events were below the groundwater screening levels in all locations except for the wells located immediately within or adjacent to fill deposits. These three localized

⁵ cPAHs were used in the RI/FS because they have the most stringent screening levels.

Figure 16. 2007–2012 Groundwater Testing Results in the Applicant's leased area for the On-Site Alternative—Total cPAHs as Toxic Equivalents



areas (purple circles on Figure 16) include wells located immediately adjacent to Landfill 1 and Fill Deposit B-2. The cPAH concentrations in wells located farther downgradient were less than the groundwater screening level and the surface water screening level.

Polychlorinated Biphenyls

As part of the RI/FS testing program, required testing for polychlorinated biphenyls (PCBs) in groundwater at wells located immediately downgradient of the landfills and fill deposits. No PCBs were detected in any of the groundwater samples analyzed (Anchor QEA 2014a).

Heavy Metals

Sampling for heavy metals in groundwater was performed during 2011 and 2012 at selected locations identified by Ecology. Test findings indicate groundwater heavy metals concentrations are below applicable screening levels.

Volatile Organic Compounds

No volatile organic compounds were detected in any of the groundwater samples analyzed.

Total Petroleum Hydrocarbons

The RI/FS testing program included analysis for total petroleum hydrocarbons (TPHs) in the HTM Oil Area. All samples collected were below groundwater screening levels.

Distribution and Movement of Chemicals of Concern

As discussed above, the fluoride and cyanide levels found in the shallow groundwater within or immediately adjacent to Landfills 1, 2 and 3 have limited mobility and are not affecting downgradient groundwater or surface water quality (Anchor QEA 2014a). Groundwater contamination by fluoride and cyanide could occur during leaching when soils or solid media encounter the groundwater. However, the upward hydraulic gradients in the shallow aquifer cause dispersion of fluoride and cyanide and prevent migration into the north-south groundwater flows. This subsequently protects groundwater, surface water, and the Columbia River and limits fluoride and cyanide from traveling to the CDID #1 ditches. Fluoride and cyanide concentrations have been decreasing over time, since the closure of the Reynolds facility. Thus, it is unlikely fluoride and cyanide in the Applicant's leased area affect the surrounding groundwater (Anchor QEA 2014a).

Final Cleanup Actions

The draft MTCA Cleanup Action Plan for the project area, released in January 2016, describes proposed cleanup actions to be protective of human health and the environment, meet state cleanup standards, and comply with other applicable state and federal laws. Cleanup standards will be consistent with the current and anticipated future land use, which will be based on industrial criteria. Ecology's comment period on the draft MTCA Cleanup Action Plan ended March 18, 2016, and the issuance of the final plan is currently pending. Cleanup is estimated to be completed by 2019–2020. Although a final cleanup action plan is still pending, this section discusses the site-specific cleanup action requirements applicable to all the cleanup alternatives.

Table 3 shows the proposed cleanup levels, remediation levels, and conditional points of compliance for groundwater to be implemented as part of the cleanup action plan (Anchor QEA 2014a). Cleanup levels were based on MTCA equations or Applicable or Relevant and Appropriate Requirements (ARARs) to protect groundwater resources for the highest beneficial use (i.e., drinking water) (Anchor QEA 2014a).

Table 3. Groundwater Cleanup Standards

Chemical of Potential Concern	Groundwater Cleanup Level	Protection Basis	Point of Compliance
Fluoride (dissolved)	4 mg/L	State Drinking Water MCL	Conditional point of compliance at property line and groundwater-ditch boundary
Free cyanide (dissolved)	200 µg/L	State Drinking Water MCL	Wells adjacent to where remedial action will occur
cPAHs	0.1 µg/L	MTCA Method A Standard Value	
TPH-D	500 µg/L	MTCA Method A Standard Value	
TPH-O	500 µg/L	MTCA Method A Standard Value	
Source: Anchor QEA 2014a TPH-D = total petroleum hydrocarbon – diesel TPH-O = total petroleum hydrocarbon – oil			

2.2.3.4 Project Area for the Off-Site Alternative

Groundwater quality in the project area for the Off-Site Alternative was not readily available at the time of preparation of this document. Although there are no known sources of environmental contamination in the project area, farming of agricultural lands and operations and maintenance of the former motocross tracks may have included the use of pesticides, herbicides, fuels, and other related contaminants, which have the potential to affect soil, surface water, and groundwater. It is not known if any residual chemicals remain in the project area.

2.2.4 Water Supply

The following discussion provides a summary of the water supply for the On-Site Alternative.

2.2.4.1 Regional

Communities in WRIA 25 rely upon a variety of systems to meet their needs for domestic, commercial, industrial, and agricultural water supply. These systems include large municipal systems, small public water systems, individual domestic wells, and wells and diversions owned by self-supplied industrial and agricultural users. In general, water needs throughout WRIA 25 are met by a combination of both surface and groundwater supplies (HDR and EES 2006). Note that the proposed project will not withdraw any water from the Columbia River. All water supply needs will be met through existing on-site groundwater wells and above ground water storage facilities.

2.2.4.2 City of Longview

The Mint Farm Regional Water Treatment Plant began operation in January 2013, and replaced the Longview water treatment plant (which was located on the shore of the Cowlitz River and treated surface water drawn from the Cowlitz River for municipal water use). The Mint Farm plant is located in the Mint Farm Industrial Park, approximately 6,000 feet east of the project area for the On-Site Alternative. While the On-Site and Off-Site alternatives' direct impact study areas do not extend to the Mint Farm Regional Water Treatment Plant, the indirect impact study areas include the treatment plant and both the direct and indirect impact study areas for both alternatives are within the treatment plant's wellfield Wellhead Protection Area (i.e., the 5-year Wellhead Protection Plan Source Area); thus, the Mint Farm Regional Water Treatment Plant is considered. Groundwater is tapped from wells in the Mint Farm Industrial Park. The water treatment plant consists of four high-capacity (4,000 gpm) groundwater wells (and associated treatment infrastructure) and supplies the City of Longview and the Cowlitz County Public Utility District with municipal water.

The treatment plant ultimately may have as many as six groundwater production wells at the Mint Farm Industrial Park, although the current operation includes four well casings and four well pumps, each capable of pumping approximately 4,000 gpm. Groundwater modeling conducted to evaluate the sustainability of long-term pumping from the wellfield, which draws from the same deep aquifer that underlies the project areas, calculated approximately 6 feet of drawdown to meet the City's 50-year maximum daily demand. Test pumping of a production well showed no drawdown impact 60 feet or more away from the well. The source of water to the wellfield was found to be the Columbia River (Kennedy/Jenks 2010). A water rights permit has been issued for the treatment plant, which has an instantaneous maximum withdrawal rate of 28,250 gpm and a maximum annual withdrawal rate of 13,500 acre-feet per year (Permit No. G2-30521, priority date June 8, 2009).

Under a Water Service Agreement, the three water purveyors in the Longview/Kelso urban area (City of Longview, Cowlitz County Public Utility District No. 1, and the City of Kelso) have a long-term arrangement whereby the three agencies can share each other's facilities when necessary. This agreement provides backup resources in case of emergency, natural disaster, and for scheduled maintenance outages (City of Longview 2006).

2.2.4.3 Project Area for the On-Site Alternative

The Applicant currently holds several water rights to extract groundwater from the deep aquifer (Kennedy/Jenks 2012b) which have been held since at least 1967. Water use in the State of Washington is subject to the "first in time, first in right" clause, historically established by western water law and adopted into Washington State law (RCW 90.44.050). A senior right cannot be impaired by a junior right. Seniority is established by the date an application was filed for a permitted or certificated water right (priority date) or the date that water was first put to beneficial use in the case of claims and exempt groundwater withdrawals. The Columbia River basin is not closed to new water rights, surface or hydraulically connected groundwater, in this reach. When the Reynolds facility was initially developed in 1941, Reynolds was responsible for developing nine water supply wells, and their names are currently listed on the water rights claims and the water rights certificates. In 1945, the state groundwater code was enacted, which required a water right permit or certificate, unless the user was exempt from state permitting requirements. Three of the water rights claims were acquired in 1941, prior to the 1945 requirements; therefore, these claims are not accompanied with a certificate. Details of the water rights claims and certificates, along with the instantaneous and annual withdrawal amounts are provided in Table 4. It is estimated the

Applicant has an existing demand of 1.53 million gallons per day (Chaney pers. comm). As shown in Table 4, the existing demand is well within the Applicant's water right⁶ limits for groundwater pumping. However, if the Applicant does not fully beneficially use each water right within a 5-year period, the Applicant must relinquish the unused portion (RCW 19.14.160).

Table 4. Water Rights Claims and Certificates

Record Number	Certificate Number	Withdrawal		Priority Date
		Instantaneous (gpm)	Annual (acre-feet/year)	
G2-006572CL	-	2,500	2,340	-
G2-006573CL	-	2,500	2,340	-
G2-006574CL	-	2,500	1,614	-
G2-*02244CWRIS	01571	2,500	4,033	1951
G2-*08309CWRIS	06184	2,500	4,000	1966
G2-*08310CWRIS	06185	2,500	4,000	1966
G2-*08367CWRIS	06186	3,000	4,800	1966
G2-*08368CWRIS	06187	3,000	4,800	1966
G2-*09127CWRIS	06427	2,150	3,440	1967
Total		23,150	31,367	

Source: URS Corporation 2014d.

2.2.4.4 Project Area for the Off-Site Alternative

No groundwater wells have been recorded for the project area for the Off-Site Alternative, and no well structures are present on the site.

2.2.4.5 Private Wells

Local industries, small farms, and domestic well users withdraw groundwater from private wells near the project areas. These include the Weyerhaeuser Timber Company and many small farms and exempt domestic well users. The groundwater permit exemption allows certain users of small quantities of groundwater (most commonly, single residential well owners) to construct wells and develop their water supplies without obtaining a water right permit from Ecology (RCW 90.44.050). Any user whose water use that exceeds the exemption limits must apply for and obtain a water right permit before water use is allowed.

A review of Ecology's online Water Rights Tracking System indicated 31 water rights applications were pending in WRIA 25. However, none of these applications was located in the Sections and Townships bordering the project areas (Washington State Department of Ecology 2015).

⁶ The Applicant is responsible for maintaining water rights. The Technical Report did not verify water rights are current.

2.2.4.6 Wellhead Protection Areas and Sanitary Control Areas

The Safe Drinking Water Act requires every state to develop a wellhead protection program. The Washington State Department of Health administers the wellhead protection program in the State of Washington.

Most public water supply wells are located in or near communities. Washington's wellhead protection requirements are designed to prevent contamination of groundwater used for drinking water. A wellhead protection area is the surface and subsurface area around a well or wellfield that a community or water system manages to protect groundwater-based drinking water supplies from contamination.

In Washington, wellhead protection areas are based on horizontal time-of-travel rates for groundwater. Depending on the rate of travel, the wellhead protection area is broken into management zones that correspond to an established time-of-travel rate for water within the aquifer. Each of the management zones represents an interval between the time a particle of water is introduced at the zone boundary and its eventual arrival at the well. These zones create an early warning system that gives a public water system time to respond to a contaminant moving within an aquifer before it arrives at the water supply well. A typical wellhead protection area has four or five management zones (Washington State Department of Health 2010).

- Sanitary control area
- Primary zones, based on 1-, 5-, and 10-year time-of-travel rates
- Buffer zone (if necessary)

The management zones are described in more detail below (Washington State Department of Health 2010).

Sanitary Control Area

The sanitary control area is the area immediately around the wellhead. This area should be tightly controlled to minimize any direct contamination at the wellhead. The purpose of this area is to reduce the possibility of surface flows reaching the wellhead and traveling down the well casing. All public water systems are encouraged to enclose wells in a well house and secure them in a fenced area to help protect individual wells from direct introduction of contaminants.

Zone 1

Zone 1 is based on the 1-year horizontal time-of-travel for groundwater. The purpose of Zone 1 is to protect the drinking water supply from viral, microbial, and direct chemical contamination. Literature suggests that bacteria and viruses survive less than 1 year in groundwater. Because of Zone 1's proximity to the sanitary control area, it includes an additional 6-month time-of-travel boundary.

Zone 2

Zone 2 is based on the 5-year time-of-travel for groundwater. The purpose of Zone 2 is to control potential impacts on groundwater from chemical contaminants. The primary difference between potential contaminant sources in Zones 1 and 2 is the time available to respond to a release. A release in Zone 2 presents a less acute crisis than a release in Zone 1. All potential contaminant

sources within Zone 2 must be identified and managed in a manner that facilitates pollution prevention and risk reduction. Zone 2 also provides information that local planners use to site future high-risk and medium-risk potential contamination sources.

Zone 3

Zone 3 is based on the 10-year time-of-travel for groundwater. Zone 3 is the outer boundary of the wellhead protection area if a Buffer Zone is not present. In Zone 3, potential high- and medium-risk contaminant sources receive increased regulatory oversight and technical assistance, with emphasis on pollution prevention and risk reduction. This allows the community to plan and site future high-risk and medium-risk contamination sources outside the wellhead protection area. It is also used as an educational tool for industry, the public, and others to understand the source of their drinking water and how actions may affect drinking water wells.

Buffer Zone


The buffer zone, if present, is an area of added protection, which helps compensate for error when calculating the time-of-travel boundaries for Zones 1 through 3. The primary goal of the Buffer Zone is to provide information to planners on activities or facilities outside Zone 3 that could release contaminants into the wellhead protection area.

The Washington State Department of Health administers the Wellhead Protection Program, while other state agencies, such as Ecology and the Department of Agriculture, integrate wellhead protection into their programs. Local agencies, such as planning and health departments, play a major role by helping water systems protect their community's drinking water supply and coordinating wellhead protection measures.

2.2.4.7 City of Longview Wellhead Protection Areas

As discussed above, two distinct groundwater systems are present at the city's wellfield: a shallow aquifer and a deep aquifer. A confining unit consisting of clay and silt ranging in thickness from approximately 100 to 200 feet separates the two systems below the project area. The confining unit becomes appreciably thinner beyond the project area, to the north and east near residential areas. Groundwater modeling indicates the source for the deep aquifer is the Columbia River, with a travel time to the wellfield of between 2 and 35 years (Kennedy/Jenks Consultants 2012b). The Columbia River is within approximately 300 feet of the project area's southern boundary.

In 2012, the City of Longview approved its Wellhead Protection Program and established the wellhead protection area, which encompasses and extends beyond the management zones (Figure 17). As shown in Figure 17, the southeast portion of On-Site Alternative project area is within Zone 1 (1-year); most of the On-Site Alternative project area is within Zones 2 and 3 (5- and 10-year, respectively). A southeast portion of the Off-Site Alternative project area is within boundaries of the 5- and 10-year Wellhead Protection Plan Source Area (Figure 17).

Figure 17. City of Longview Wellhead Protection Area

This chapter describes the impacts on groundwater that could result from construction and operation of the On-Site Alternative or the Off-Site Alternative or the conditions under the No-Action Alternative.

3.1 On-Site Alternative

Potential impacts on groundwater from the On-Site Alternative are described below.

The following construction activities could affect groundwater.

- Disturbance of surface soils during construction.
- Release of hazardous and non-hazardous materials during construction.
- Disturbance of previously contaminated sites.
- Use of groundwater for dust control.

The following operations activities could affect groundwater.

- Alteration of surface runoff patterns.
- Use of groundwater for dust control, equipment washdown, and cleanup.
- The water would then be pumped to a surface storage pond. The surface storage pond would have an approximate capacity of 3.6 million gallons and would be used to store the water for reuse. The capacity of the pond would include a reserve of 0.36 million gallons for fire suppression.

3.1.1 Construction: Direct Impacts

Construction of the On-Site Alternative would result in the following direct impacts.

Affect Groundwater Recharge during Construction

Construction of the On-Site Alternative would involve preloading and installation of vertical wick drains to direct groundwater from the shallow aquifer upward toward the surface during pre-loading, where it would discharge. Ground-disturbing activities (excavations, grading, filling, trenching, backfilling, and compaction) could temporarily disrupt the existing drainage and groundwater recharge patterns in the study area. However, as described above, the major sources of groundwater recharge in the project area are the Columbia River, the regional CDID #1 ditch system, and the on-site drainage ditch system. The study area is not considered a major source of groundwater recharge of the deep aquifer through infiltration as the majority of stormwater runoff is managed by the existing NPDES stormwater collection and treatment system with nominal infiltration and evaporation. Therefore, construction of the On-Site Alternative would not be expected to have a measurable impact on groundwater recharge patterns of the deep aquifer.

The shallow groundwater aquifer in the project area is minimally recharged through surface infiltration due to the low recharge rates of the soil characteristics in the study area (URS Corporation 2014c). During construction, impervious surfaces would be sloped to convey surface water to collection sumps on the project area. The collected stormwater would then be conveyed to water collection facilities and discharged through a monitored internal outfall to existing facilities within the project area for treatment prior to discharge to the Columbia River. For more information on the project construction NPDES permit, see the NEPA Water Quality Technical Report (ICF International 2016b). Therefore, drainage and groundwater recharge patterns are expected to be similar to those of the current conditions, with runoff directed to collection and treatment facilities and minimal infiltration to groundwater. There could be a slight reduction on groundwater recharge for the shallow aquifer, but the project area is not considered to be a significant source of groundwater recharge through infiltration; any potential impact would be negligible.

Degrade Groundwater Quality during Construction

Any construction-related contaminant accidentally released on the ground could infiltrate and temporarily degrade groundwater quality if the contaminant were to reach groundwater. This would be a concern primarily for the shallow aquifer and not the deep aquifer because there is a confining, impervious unit consisting of clay and silt that separates the two aquifer systems, and the deep aquifer is primarily recharged by deeper aquifers below the Columbia River (Anchor QEA 2014b). However, as discussed above, the majority of stormwater generated during construction would be collected and treated in compliance with the project construction NPDES permit prior to discharge. For more information on the project construction NPDES permit, see the NEPA Water Quality Technical Report (ICF International 2016b). The existing water treatment plant (Facility 73) is anticipated to be adequate to handle the water generated during construction, including removing contaminants and sediment loads from stormwater prior to discharge. In addition, construction of the coal export terminal would adhere to the best management practices (BMPs) developed by the Applicant as part of the project proposal to avoid and minimize potential impacts on surface and groundwater resources. BMPs would include, but not be limited to, the following.

- BMP C153: Material delivery, storage, and containment would be used to prevent, reduce, or eliminate the discharge of pollutants to the stormwater system or watercourses from material delivery and storage, including the following.
 - Storage of on-site hazardous materials would be minimized to the extent feasible.
 - Materials would be stored in a designated area, and secondary containment would be installed where needed.
 - Refueling would occur in designated areas with appropriate spill control measures.
- BMP C154: A concrete washout area would be constructed near the entrance to the project area to prevent or reduce the discharge of pollutants to stormwater from concrete waste by conducting washout off site, or performing on-site washout in a designated area to prevent pollutants from entering surface waters or ground water.

Site preparation activities would involve preloading and installation of vertical wick drains to aid in the consolidation of low consistency silt and low-density sand. Wick drains would direct groundwater from the shallow aquifer upward toward the surface during pre-loading, where it

would discharge. Water discharged from the wick drains would be captured, tested for contaminants, and treated prior to discharge to any surface waters. These activities could take place adjacent to areas where known groundwater contamination exists and the contaminated groundwater could penetrate these areas. However, the permeability of the earth materials affected by preloading would be relatively low and thus would not be particularly susceptible to the infiltration of contaminated groundwater. Therefore, construction is not expected to result in groundwater degradation as a result of preloading and vertical wick drains and no long-term effects are anticipated.

In addition, as described in the NEPA Hazardous Materials Technical Report (ICF International 2016a), construction of the On-Site Alternative could encounter previously contaminated areas on the project area that are being addressed by the MTCA Cleanup Action Plan, resulting in degradation of groundwater quality. However, with the exception of two small areas—the eastern corner of the Flat Storage Area and the northeastern portion of Fill Deposit B-3 (Figure 11)—no remedial actions are mandated as part of the final cleanup action plan for the project area. For the Flat Storage Area and Fill Deposit B-3, construction and remediation activities would be coordinated to reduce conflicts and minimize any environmental impact. Also, as mentioned above, fluoride and cyanide levels found in shallow groundwater have limited mobility and are not affecting downgradient groundwater or surface water quality. Furthermore, the final cleanup action plan would include minimum thresholds for cleanup, which would be protective of the environment, comply with applicable state and federal laws, and provide for future compliance monitoring. Therefore, construction of the On-Site Alternative would not result in groundwater degradation as a result of disturbing previously contaminated areas.

Construction would be unlikely to affect the wellfield at the Mint Farm Industrial Park. The wellfield draws water from the deep aquifer, and as previously mentioned, there is a confining, impervious unit consisting of clay and silt that separates the two aquifer systems, and the deep aquifer is primarily recharged by deeper aquifers below the Columbia River. Contaminants from a spill would be unlikely to ever reach the groundwater withdrawn by the wellfield.

Affect Groundwater Supply during Construction

Construction would require groundwater for dust suppression. The maximum amount of water to be used for dust suppression is estimated to be 40,000 gallons per day (44.8 AFY). Combined with demand from existing activities in the project area of 1,994 AFY, the total demand for groundwater during construction would be approximately 2,039 AFY. As described above, the Applicant holds water rights for instantaneous extraction from on-site wells of about 23,000 gpm or 31,367 AFY.

A production well from the new Mint Farm Regional Water Treatment Plant was tested by the City of Longview to characterize the deeper confined aquifer. The subsurface conditions within the Mint Farm site are similar to those expected at the Applicant's 540-acre lease area. The production well was drilled to a depth of 385 feet below ground surface and is located approximately 6,000 feet southeast of the Applicant's lease area. The constant rate pumping tests results from this well calculated that the transmissivity values of the aquifer ranged from 3.3 million to 4.5 million gallons per day, per foot, while the hydraulic conductivity values from recovery water level data ranged from 20,000 to 28,000 gallons per day, per foot (2,600 to 3,600 feet per day). The study observed a recharge influent of the Columbia River on the deep aquifer

at the production well; this became apparent after approximately 1.5 days of pumping, when drawdown curves became virtually flat (Kennedy/Jenks 2010 in URS 2014b). The Mint Farm Regional Water Treatment Plant has water rights for an instantaneous maximum withdrawal rate of 28,250 gallons per minute and a maximum annual withdrawal rate of 13,500 acre-feet per year (Permit No. G2-30521, priority date June 8, 2009) (URS 2014b). In 2011, the projected average daily demand was 6.7 million gallons per day with a maximum daily demand of 14.06 million gallons per day.

Water demand for construction-related activities and existing operations would represent only 6.5% of the Applicant's groundwater extraction rights. Construction of the On-Site Alternative is expected to have negligible impacts on groundwater supply, based on the Mint Farm constant rate pumping test results and when compared to existing groundwater use.

Excavation activities could intercept groundwater in low-lying areas, which could result in temporary fluctuations in shallow groundwater in the immediate area. Dewatering effluent would be pumped to temporary containment tanks for settling, where it will be tested for pollutants before being discharged to receiving waters. If pollutants are encountered during testing, dewatering would be suspended and Ecology would be notified. Contaminated water would be treated before being discharged to receiving waters.

3.1.2 Construction: Indirect Impacts

Construction of the On-Site Alternative would not result in indirect impacts on groundwater because construction of the export terminal would be limited to the project area.

3.1.3 Operations: Direct Impacts

Operation of the On-Site Alternative would result in the following direct impacts.

Affect Groundwater Recharge during Operations

Operations of the facility could permanently reduce or impede infiltration due to soil compaction or existence of the facility's impenetrable surfaces (e.g. roads, buildings), which could affect groundwater recharge volumes and patterns. The project area would occupy some of the existing drainage basins in the project area (see Figure 7), effectively eliminating a portion of the runoff volume presently handled under the Applicant's existing NPDES Industrial Stormwater Permit; the Applicant would be required to obtain a separate NPDES Industrial Stormwater Permit and would develop a separate system of stormwater collection and discharge regulated by this permit. However, under existing conditions the project area is not considered a significant source of groundwater recharge through infiltration because of the low recharge rates of the soil characteristics in the study area (URS Corporation 2014c). In addition, runoff is currently directed and collected in a ditch system and operations would not significantly change these conditions; the major sources of shallow groundwater recharge in the project area during operations will not change and would continue to primarily be the Columbia River. During operations, runoff would continue to be directed and collected in the same manner as current conditions and little infiltration would occur; therefore, the direction and volume of groundwater recharge is expected to remain relatively constant during operations. Therefore, operation of the On-Site Alternative is not expected to substantially change shallow groundwater recharge volumes or patterns in the project area.

Operations would not be expected to measurably affect groundwater recharge for the deeper aquifer because the deep aquifer is primarily recharged by deeper aquifers below the Columbia River (Anchor QEA 2014).

Degrade Groundwater Quality during Operations

Spills of contaminants and coal dust generated during operations could potentially degrade groundwater quality if contaminated runoff were to infiltrate into the ground and reach groundwater. However, as described under *Affect Groundwater Recharge during Operations* above, the project area is not considered a significant source of groundwater recharge through infiltration because of the low recharge rates of the soil characteristics in the study area (URS Corporation 2014c). In addition, runoff from the study area, and any contaminants within that runoff, would be directed to on-site drainage systems, treated, and either reused on site or discharged in accordance with a future NPDES permit. Water reused on site would be brought up to Washington State Class A Reclaimed Water standards (URS Corporation 2014c). Excess water not reused on site would be further treated and tested prior to discharge to permitted outfalls (i.e., Outfall 002A) and discharged to the Columbia River. Discharge of water to the Columbia River during project operations would mostly occur during the rainy season when excess surface water is more likely to be generated on site.

Furthermore, as discussed in the NEPA Water Quality Technical Report (ICF International 2016b), the following BMPs would be part of the On-Site Alternative design to maximize the protection of surface-water quality (and thus groundwater via infiltration).

- Enclosed conveyor galleries.
- Enclosed rotary unloader building and transfer towers.
- Washdown collection sumps for settlement of sediment.
- Regular cleanout and maintenance of washdown collection sumps.
- Containment around refueling, fuel storage, chemicals, and hazardous materials.
- Oil/water separators on drainage systems and vehicle washdown pad.
- Requirement that all employees and contractors receive training, appropriate to their work activities, in the BMPs.
- Design of docks to contain spillage, with rainfall runoff and washdown water contained and pumped to the upland water treatment facilities.
- Design of systems to collect and treat all runoff and washdown water for on-site reuse (dust suppression, washdown water or fire system needs) or discharge off site.

Since collected waters would be treated before reuse or discharge to the Columbia River under permits, groundwater quality is not expected to be affected by operation of the On-Site Alternative. The potential for infiltration of surface water containing coal dust would be relatively low based on the low recharge rates of the soil characteristics in the study area, the propensity for soil to filter coal dust out of any water that may infiltrate into the ground, and coal dust being washed away in runoff and collected and treated under the NPDES Industrial Stormwater Permit for the terminal. Thus, it would be unlikely that coal dust would infiltrate into the ground and reach groundwater.

The potential for toxic constituents of coal to reach groundwater is also relatively low. Most coal dust would be washed away prior to the constituents becoming soluble in surface water and infiltrating to groundwater. Toxic constituents of coal include PAHs and trace metals, which are present in coal in variable amounts and combinations dependent on the type of coal. The coal type, along with mineral impurities in the coal and environmental conditions, determine whether these compounds can be leached from the coal. The potential risk for exposure to toxic chemicals contained in coal (e.g. PAHs and trace metals) would be relatively low as these chemicals tend to be bound in the matrix structure and not quickly or easily leached. See the NEPA Water Quality Technical Report (ICF International 2016b) and the SEPA Coal Technical Report (ICF International 2016c) for more information.

In summary, the potential risk for exposure to toxic chemicals contained in coal (e.g., PAHs, trace metals) would be relatively low, as these chemicals tend to be bound in the matrix structure and not quickly or easily leached. Further, particles would likely be transported downstream by the flow of the river and either carried out to sea or distributed over a sufficiently broad area as not to be problematic. See the NEPA Water Quality Technical Report (ICF International 2016b) and the SEPA Coal Technical Report (ICF International 2016c) for more information. In addition, operation of the On-Site Alternative would not encounter or disturb previously contaminated areas that are being addressed by the MTCA Cleanup Action Plan. Operation of the On-Site Alternative would occur concurrently with environmental remediation and monitoring as required in the Final Cleanup Action Plan for the Former Reynolds facility, as described in the NEPA Hazardous Materials Technical Report (ICF International 2016a). The remedial and monitoring activities would be carried out in accordance with all relevant and appropriate regulations, and would be coordinated to avoid further exposure to the environment. Furthermore, the impact of the cleanup activities would result in bringing previously contaminated groundwater to levels that are protective of human health and the environment thereby reducing the potential for exposure for sensitive receptors.

Affect Groundwater Supply during Operations

Process water uses would include dust control, equipment washdown, and cleanup. Water for dust suppression would be applied on the main stockpiles, within unloading and conveying systems, and at the docks. Excess water from dust suppression and washdown would be collected for reuse. Process water supply would come from two sources: the on-site water management system during the wet season and on-site groundwater wells during the dry season.

The on-site water management system would provide process water in the following ways.

- Stormwater and surface water (washdown water) would be collected from the stockpile areas, rail loop, office areas, docks, and other paved surfaces in the project area and directed to a series of vegetated ditches and ponds, then to a collection basin or sump.
- The collected water would be pumped to an on-site treatment facility consisting of retention pond(s) with flocculent added to promote settling as required.
- The water would then be pumped to a surface storage pond. The surface storage pond would have an approximate capacity of 3.6 million gallons (MG), including a reserve of 0.36 MG for fire suppression.

Approximately 1,200 gpm during the wet season and approximately 2,000 gpm during the dry season (approximately 2,034 AFY) would be required on average for dust suppression. On-site groundwater wells would provide approximately 635 gpm (1,025 AFY) to maintain minimum water levels in the storage pond to meet process water demands during the dry season. As mentioned above, the Applicant holds water rights for instantaneous extraction of 23,150 gpm up to a total volume of 31,367 AFY. Combined with the groundwater demand from existing activities in the Applicant's leased area (approximately 1,994 AFY), the total demand on groundwater supplies during operation of the On-Site Alternative would be approximately 3,019 AFY, which is less than 10% of the pumping limit. Therefore, operation of the On-Site Alternative would have a negligible impact on groundwater supply. The Applicant would ensure water rights are current before withdrawing any water for construction or operations; water rights would be maintained for ongoing groundwater use during operation of the On-Site Alternative.

3.1.4 Operations: Indirect Impacts

Operation of the On-Site Alternative would result in the following indirect impact on groundwater related to facility operations in the direct impact study area and increased rail traffic on the BNSF Spur and Reynolds Lead (up to 240 unit trains⁷ arriving and departing per month) within the direct and indirect impact study areas.

Degrade Groundwater Quality during Operations – Mint Farm Industrial Park

The On-Site Alternative likely would not affect groundwater at the Mint Farm Industrial Park because the wellfield draws water from the deep aquifer, and, as previously mentioned, there is a confining, impervious unit consisting of clay and silt that separates the two aquifer systems, and the deep aquifer is primarily recharged by deeper aquifers below the Columbia River. Contaminants from a spill during operations would be unlikely to ever reach the groundwater withdrawn by the wellfield. The majority of the study area is located within what is referred to as Zone 2 of the Mint Farm Industrial Park's wellhead protection and sanitary control areas (Figure 17).⁸ Although it would be unlikely a contaminant would ever reach the deep aquifer, should a release of a potential groundwater contaminant occur during operations, cleanup would occur rapidly to reduce potential risk to groundwater. In addition, all surface water generated on the study area would be collected and reused on site or treated before discharge to the Columbia River, further minimizing the potential for contaminants to infiltrate into the ground.

Degrade Groundwater Quality as a Result of a Collision or Derailment

Spills of fuel or other potentially hazardous materials (i.e., lubricants, hydraulic fluids) could occur if rail cars were to collide and/or derail within the direct and indirect impact study areas. The indirect impact study area begins at the west side of the Cowlitz River where the rail line crosses into the City of Longview-Frontal Columbia River Watershed (HUC-12: 170800030602). Similar to day-to-day rail operations, any materials released to the ground resulting from such collision or derailment could be introduced to groundwater through stormwater runoff or surface infiltration and thereby degrade groundwater quality. As discussed in the NEPA

⁷ A unit train consists of approximately 125 rail cars and three to four locomotives.

⁸ In Washington State, wellhead protection areas are based on horizontal time-of-travel rates for groundwater. Zone 2 areas are based on a 5-year time-of-travel for groundwater.

Hazardous Materials Technical Report (ICF International 2016a), if a release of hazardous materials were to occur, the rail operator would implement emergency response and cleanup actions as required by Occupational Safety and Health Administration rules (29 CFR 1910.120); the Washington State Oil and Hazardous Substance Spill Prevention and Response regulations (90.56 RCW) and the Model Toxic Control Act Cleanup Regulations (Chapter 173-340 WAC). In addition, Federal Railroad Administration accident reporting requirements (49 CFR 225) include measures to avoid or minimize the potential for a spill of fuel or other potentially hazardous materials from affecting groundwater quality, through quick response, containment and cleanup. Thus, a release of potentially hazardous materials would not be expected to affect groundwater.

3.2 Off-Site Alternative

Potential impacts on groundwater from the Off-Site Alternative are described below.

3.2.1 Construction: Direct Impacts

Construction of the Off-Site Alternative would result in the following direct impacts.

Affect Groundwater Recharge during Construction

Construction of the Off-Site Alternative would involve ground-disturbing activities (excavations, grading, filling, trenching, backfilling, and compaction) that would permanently alter the existing drainage and groundwater recharge patterns in the study area. As mentioned above, the project area is currently undeveloped and consists of dense to sparse vegetation and grassy areas. Therefore, it is expected that groundwater recharge occurs in the study area and would essentially be eliminated by construction of a terminal dominated by an impervious surface area.

During construction, a majority of the stormwater runoff would be collected and treated prior to discharge to the Columbia River, which is the major source of groundwater recharge in the area. Although the Off-Site Alternative would permanently modify groundwater recharge through reduced infiltration in the study area, the Off-Site Alternative would still be discharging the majority of construction runoff, after treatment, to the Columbia River, where it would still be available for groundwater recharge.

Degrade Groundwater Quality during Construction

Due to the absence of site-specific groundwater-related information, the quality of groundwater associated with the Off-Site Alternative project area is unknown. Although there are no known sources of environmental contamination on the site, farming of the agricultural lands and the operations and maintenance of the former motocross tracks may have included the use of pesticides, herbicides, fuels, and other related contaminants, which have the potential to affect soil, surface water, and groundwater. It is not known if any residual chemicals remain in the soil. Site assessment would be conducted prior to any ground-disturbing activities, and should any contamination (i.e., soil, surface water, or groundwater contamination) be discovered, the Applicant would be required to coordinate with the appropriate federal, state, and local agencies and identify the appropriate measures to clean up the contamination to acceptable levels.

Furthermore, it is expected impacts on groundwater quality would be minimal due to the required implementation of a construction stormwater pollution prevention plan and BMPs to protect surface waters from discharge of polluted stormwater. Furthermore, similar to the On-Site Alternative, during construction of the Off-Site Alternative, the majority of the stormwater would be collected and treated prior to discharge to any surface water, further reducing the amount of pollutants entering the Columbia River and potentially affecting groundwater quality.

Construction of the Off-Site Alternative could release contaminants into the ground through leaks and spills during construction, similar to the On-Site Alternative, which could be introduced to groundwater through stormwater runoff or infiltration, and potentially degrade groundwater quality. However, as mentioned above, construction activities would be required to comply with a construction stormwater pollution prevention plan and implement BMPs to prevent discharge of polluted stormwater. Furthermore, during construction, a majority of the stormwater would be collected and treated prior to discharge, further reducing the potential for pollutants to enter the Columbia River and/or potentially affect groundwater quality.

Furthermore, similar to the On-Site Alternative, the preparation of the Off-Site Alternative project area for construction would involve the preloading and installation of vertical wick drains to aid in the consolidation of low consistency silt and low-density sand. Some of the construction would occur adjacent to the closed Mt. Solo Landfill. The installation of the vertical wick drains could create a temporary groundwater gradient, or increase the gradient, toward the study area. Due to the proximity of the project area to the closed Mt. Solo Landfill, groundwater quality could be affected. If contaminant concentrations in groundwater are found to be above MTCA screening levels set forth by Ecology, the wick drains would need to be profiled prior to disposal.

Lastly, construction of the Off-Site Alternative is not expected to affect the wellfield at the Mint Farm Industrial Park. While construction-related spills of hazardous materials could occur, the potential consequences of such spills are generally small due to the likely small size of the spills (i.e., less than 50 gallons), as well as the localized and short-term nature of an accidental release. Impacts would be the same as, or similar to, those described above for the On-Site Alternative.

Affect Groundwater Supply during Construction

Less than 40,000 gallons per day would be required for construction of the Off-Site Alternative to minimize the generation of fugitive dust. Water would need to be obtained from a new well or from an off-site source during construction. A new groundwater supply well(s) at the Off-Site Alternative property would require hydrogeology studies and a grant of water rights prior to construction to ensure that groundwater supplies would not be adversely affected.

3.2.2 Construction: Indirect Impacts

No indirect impacts have been identified for groundwater related to construction of the Off-Site Alternative.

3.2.3 Operations: Direct Impacts

Operation of the Off-Site Alternative would result in the following direct impacts.

Affect Groundwater Recharge during Operations

As mentioned above, full build out of the Off-Site Alternative would result in a substantial increase in impervious surfaces compared to current conditions. Stormwater that would have otherwise recharged groundwater through infiltration would be collected at the terminal site and conveyed to a treatment system for reuse related to project operations (i.e., dust suppression, wash-down water, storage) or discharged to the Columbia River. However, the runoff collected in the treatment system and discharged to the Columbia River would be available for groundwater recharge because of the hydrologic connection between the river and the shallow groundwater in the project area. Thus, operation would permanently modify drainage and recharge patterns at the project area.

Degrade Groundwater Quality during Operations

Operation of the Off-Site Alternative could release contaminants onto the ground, which could then infiltrate to groundwater and degrade groundwater quality. However, with the implementation of BMPs, potential impacts are expected to be low and similar to those described above for the On-Site Alternative. Overall, operations of the proposed terminal are not expected to degrade groundwater quality due to the surface runoff drainage and treatment system that would avoid and minimize any infiltration of contaminant-laden runoff into the ground.

Affect Groundwater Supply during Operations

Similar to the On-Site Alternative, operation of the Off-Site Alternative would require process water (e.g., noncontact cooling water, dust control, equipment wash down, cleanup, and fire protection). Implementation of the Off-Site Alternative would require an evaluation of the groundwater hydrology at the site, retention of water rights, and installation of groundwater supply well(s) to accommodate both construction and operations. Therefore, the Off-Site Alternative would affect groundwater supplies through the acquisition of new groundwater rights.

It is anticipated that since the stockpile areas, rail loop, and other impervious surface areas would be similar to the On-Site Alternative, the amount of stormwater generated and water collected for treatment and reuse would also be similar. Operation of the terminal would require process water, which would be drawn, in part, from a new groundwater well; about 334 million gallons per year (MGY) (1,025 AFY) of groundwater would be needed to augment the surface supply. While a new well would tap groundwater supplies, pumping would not be expected to measurably affect groundwater levels given the proximity of the site to the Columbia River and expected recharge rates in the area. In addition, any new wells proposed for the Off-Site Alternative would require an evaluation of the groundwater hydrology at the site, and application and approval for new water rights to ensure there would be no adverse impacts to groundwater supply.

3.2.4 Operations: Indirect Impacts

Operation of the Off-Site Alternative would result in the following indirect impact.

Degrade Groundwater Quality As a Result of a Collision or Derailment

The potential impacts on groundwater quality during operations of the facility and from accidental train collisions or derailment would be the same as those described for the On-Site Alternative (Section 3.1.1.3, *Operations: Indirect Impacts*). A release of potentially hazardous materials would not be expected to affect groundwater.

3.3 No-Action Alternative

Under the No-Action Alternative, the Corps would not issue a Department of the Army permit authorizing construction and operation of the proposed export terminal. As a result, impacts resulting from constructing and operating the export terminal would not occur. In addition, not constructing the export terminal would likely lead to expansion of the adjacent bulk product business onto the export terminal project area. The following discussion assesses the likely consequences of the No-Action Alternative related to groundwater.

Continued use of groundwater would occur under the approved water rights for the existing on-site groundwater wells. The existing NPDES Industrial Stormwater Permit would remain in place, maintaining the water quality of existing stormwater discharges to the Columbia River, which would maintain water quality of groundwater. Any new or expanded industrial uses would trigger a new or modified NPDES permit. Thus, potential impacts on groundwater could occur under the No-Action Alternative similar to those described for the On-Site Alternative, but the magnitude of the impact would depend on the nature and extent of the future expansion.

The following permits would be required in relation to groundwater.

4.1 On-Site Alternative

The On-Site Alternative would require the following permits related to groundwater.

- Cowlitz County Critical Areas permit to address compliance with the County's Critical Areas Ordinance related to the presence and protection of Critical Aquifer Recharge Areas located on site.
- Clean Water Act Section 401 Water Quality Certification would be required to ensure no potential contamination of groundwater resources associated with project construction and operations stormwater discharge.
- National Pollutant Discharge Elimination System (NPDES) Permit would be required for any new stormwater discharges during construction and operation of the export terminal.
- Water Rights—The Applicant would ensure their existing water rights are current prior to use of those rights. If the Applicant's water rights are current, the Applicant must maintain those water rights. If the Applicant's water rights are not current, the Applicant must apply for and obtain the necessary water rights.

4.2 Off-Site Alternative

The Off-Site Alternative would require the following permits related to groundwater.

- City of Longview and Cowlitz County Critical Areas permits may be required to address compliance with the City and County's critical areas ordinances should Critical Aquifer Recharge Areas be located on or adjacent to the Off-Site Alternative.
- Clean Water Act Section 401 Water Quality Certification would be required to ensure no potential contamination of groundwater resources associated with project construction and operations stormwater discharge.
- National Pollutant Discharge Elimination System (NPDES) Permit would be required for any new stormwater discharges during construction and operation of the export terminal.
- Water Rights— The Applicant would ensure water rights are current before exercising those rights; water rights must be maintained for ongoing groundwater use.

5.1 Written References

- Anchor Environmental, LLC. 2007. *Remedial Investigation Report*. June. Chinook Ventures, Inc., and Northwest Alloys, Inc. Seattle, WA.
- Anchor. 2013. RI/FS Report, Former Reynolds Metals Reduction Plant, Longview, Washington. June. As cited in URS Corporation 2014a.
- Anchor QEA. 2014a. *Former Reynolds Metals Reduction Plant—Longview, Draft Remedial Investigation and Feasibility Study*. June. Submitted on behalf of Northwest Alloys, Inc. and Millennium Bulk Terminals—Longview, LLC.
- Anchor QEA. 2014b. *Engineering Report for NPDES Permit Application*. July. Prepared for Millennium Bulk Terminals—Longview, LLC, Longview, WA.
- City of Longview. 2006. *Comprehensive Plan, Chapter 7 Public Facilities, Utilities, Services*.
- City of Longview, Mint Farm Regional Water Treatment Plant, Preliminary Design Report, Part 2A, Hydrogeologic Characterization, March 2010
- HDR and EES. 2006. *Gray-Elochoman and Cowlitz Watershed Management Plan WRIAs 25 and 26*. July.
- ICF International. 2016a. *Millennium Bulk Terminals— Longview, NEPA Environmental Impact Statement, NEPA Hazardous Materials Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016b. *Millennium Bulk Terminals— Longview. NEPA Environmental Impact Statement. NEPA Water Quality Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016c. *Millennium Bulk Terminals—Longview, SEPA Environmental Impact Statement, SEPA Coal Technical Report*. April. Seattle, WA. Prepared for Cowlitz County, Kelso, WA, in cooperation with Washington State Department of Ecology, Southwest Region.
- Kennedy/Jenks Consultants. 2010. *City of Longview Mint Farm Regional Water Treatment Plant, Preliminary Design Report, Part 2A Hydrogeological Characterization*. March.
- Kennedy/Jenks Consultants. 2012a. *City of Longview Mint Farm Regional Water Treatment Plant, Groundwater Quality Sampling Results, November 2012 – Monitoring Event K/J 0997003*1*. April.
- Kennedy/Jenks Consultants. 2012b. *Source Water – Wellhead Protection Program*. Section 5 of 2012 Water System Plan Updated (draft). K/J Project No. 1197009*00. February 1.
- Lower Columbia Fish Recovery Board. 2001. *WRIA 25/26 Grays-Elochoman and Cowlitz Watershed Planning Documents Level 1 Assessment*. Report No 4-00-247. August. Available: http://www.lcfrb.gen.wa.us/document_library_2514%20TM.htm. Accessed: April 16, 2014.

- URS Corporation. 2014a. *Millennium Coal Export Terminal Longview, Washington*. Affected Environment Analysis – Water Resources. January.
- URS Corporation. 2014b. *Millennium Coal Export Terminal Longview, Washington Water Resource Report*. September.
- URS Corporation. 2014c. *Millennium Coal Export Terminal Longview, Washington Surface Water Memorandum*. Supplement to Water Resource Report. November.
- URS Corporation. 2014d. *Millennium Coal Export Terminal Longview, Washington Surface Water Memorandum, Second Supplement to Water Resource Report Water Collection and Drainage*.
- URS Corporation. 2014e. *Millennium Coal Export Terminal Longview, Washington, Off-Site Alternative – Barlow Point, Appendix M, Water Resource Report*.
- U.S. Geological Survey. 2001. *What is Ground Water?* Open-File Report 93-643. April. Available: <http://pubs.usgs.gov/of/1993/ofr93-643/pdf/ofr93-643.pdf>.
- U.S. Geological Survey. 2013. *Lahars and Their Effects*. Last revised: February 21, 2013. Available: <http://volcanoes.usgs.gov/hazards/lahar/>. Accessed: November 7, 2014.
- U.S. Geological Survey. 2014. Stream gage data for Beaver Army Terminal near Quincy, Oregon. Available: <http://waterdata.usgs.gov/nwis/?provisional>.
- Washington State Department of Ecology. 2014a. *Groundwater*. Available: <http://www.ecy.wa.gov/water/groundwater.html>. Accessed: November 6, 2014.
- Washington State Department of Ecology. 2014b. *Reynolds Metals Aluminum Smelter*. Available: <https://fortress.wa.gov/ecy/gsp/Sitepage.aspx?csid=11796>. Accessed: July 16, 2014.
- Washington State Department of Ecology. 2015. *Water Right Tracking System*. Available: <http://www.ecy.wa.gov/programs/wr/rights/tracking-apps.html>. Accessed: February 24, 2015.
- Washington State Department of Health. 2010. *Washington State Wellhead Protection Program Guidance Document*. DOH 331-018 (revised). Olympia, WA. June.

5.2 Personal Communications

- Chaney, Katy. AECOM, Seattle, WA. January 9, 2015—Email to Chris Soncarty, ICF International, regarding existing water demand.

MILLENNIUM BULK TERMINALS—LONGVIEW NEPA ENVIRONMENTAL IMPACT STATEMENT NEPA WATER QUALITY TECHNICAL REPORT

PREPARED FOR:

U.S. Army Corps of Engineers, Seattle District
4735 East Marginal Way South
Seattle, WA 98134

PREPARED BY:

ICF International
710 Second Avenue, Suite 550
Seattle, WA 98104

September 2016



ICF International. 2016. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Water Quality Technical Report*. September. (ICF 00264.13.) Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.

Contents

List of Tables	ii
List of Figures.....	ii
List of Acronyms and Abbreviations.....	iii
Chapter 1 Introduction	1-1
1.1 Project Description	1-1
1.1.1 On-Site Alternative	1-1
1.1.2 Off-Site Alternative	1-4
1.1.3 No-Action Alternative	1-6
1.2 Regulatory Setting	1-6
1.3 Study Area	1-9
1.3.1 On-Site Alternative	1-9
1.3.2 Off-Site Alternative	1-9
Chapter 2 Affected Environment.....	2-1
2.1 Methods	2-1
2.1.1 Data Sources	2-1
2.1.2 Impact Analysis	2-2
2.2 Affected Environment	2-3
2.2.1 On-Site Alternative	2-3
2.2.2 Off-Site Alternative	2-13
Chapter 3 Impacts	3-1
3.1 On-Site Alternative	3-1
3.1.1 Construction: Direct Impacts	3-1
3.1.2 Construction: Indirect Impacts	3-9
3.1.3 Operations: Direct Impacts	3-9
3.1.4 Operations: Indirect Impacts	3-11
3.2 Off-Site Alternative.....	3-17
3.2.1 Construction: Direct Impacts	3-17
3.2.2 Construction: Indirect Impacts	3-18
3.2.3 Operations: Direct Impacts	3-18
3.2.4 Operations: Indirect Impacts	3-18
3.3 No-Action Alternative.....	3-19
Chapter 4 Required Permits.....	4-1
Chapter 5 References	5-1
5.1 Written References	5-1

Tables

1	Regulations, Statutes, and Guidance for Water Quality	1-6
2	Beneficial Uses for the Columbia River	2-6
3	Freshwater Aquatic Life Uses (Weyerhaeuser Longview)	2-7
4	Recreational Uses (Weyerhaeuser Longview)	2-7
5	303(d) Listed Impairments for Surface Waters in the Study Area	2-8
6	Ecology's Wetland Categories Based on Functions	2-11
7	Average Concentration of Trace Elements in Wyodak and Big George Coal Beds, Powder River Basin, Wyoming and Miscellaneous Uinta Basin Coal Beds in Colorado Plateau	3-14
8	U.S. Coast Guard Ballast Water Treatment Standards	3-16

Figures

1	Project Vicinity	1-2
2	On-Site Alternative	1-3
3	Off-Site Alternative	1-5
4	Water Quality Study Area for the On-Site Alternative	1-10
5	Water Quality Study Area for the Off-Site Alternative	1-11
6	Drainage Features of the On-Site Alternative	2-4
7	Drainage Features for the Off-Site Alternative	2-14
8	3-Year Annual Average Coal Dust Deposition Millennium Bulk Terminal – Longview	3-12

Acronyms and Abbreviations

Applicant	Millennium Bulk Terminals—Longview, LLC
BMP	best management practice
BNSF	BNSF Railway Company
CDID	Consolidated Diking and Improvement District
cfs	cubic feet per second
Corps	U.S. Army Corps of Engineers
CRD	Columbia River Datum
DDT	dichlorodiphenyltrichloroethane
Ecology	Washington State Department of Ecology
EPA	U.S. Environmental Protection Agency
FNU	formazin nephelometric units
g/cm ³	grams per cubic meter
g/L	grams per liter
g/m ² /year	grams per square meter per year
LVSW	Longview Switching Company
mg/L	milligrams per liter
NPDES	National Pollution Discharge Elimination System
Oregon DEQ	Oregon Department of Environmental Quality
PAH	polyaromatic hydrocarbon
PBDE	polybrominated diphenyl ether
PCB	polychlorinated biphenyl
Reynolds facility	Reynolds Metals Company facility
SWPPP	stormwater pollution prevention plan
TCDD	tetrachlorodibenzo-p-dioxin
TEEC	trace elements of environmental concern
TMDL	total maximum daily load
UP	Union Pacific
USGS	U.S. Geological Survey
WDNR	Washington State Department of Natural Resources
WRIA	Water Resources Inventory Area

This technical report assesses the potential water quality impacts of the proposed Millennium Bulk Terminals—Longview project (On-Site Alternative), Off-Site Alternative, and No-Action Alternative. For the purposes of this assessment, water quality refers to the overall quality of the water resources of the project area and study area. This report describes the regulatory setting, establishes the method for assessing potential water quality impacts, presents the historical and current water quality conditions in the study area, and assesses potential impacts on water quality.

1.1 Project Description

Millennium Bulk Terminals—Longview, LLC (Applicant) proposes to construct and operate an export terminal in Cowlitz County, Washington, along the Columbia River (Figure 1). The export terminal would receive coal from the Powder River Basin in Montana and Wyoming and the Uinta Basin in Utah and Colorado via rail shipment, then load and transport the coal by ocean-going ships via the Columbia River and Pacific Ocean to overseas markets in Asia. The export terminal would be capable of receiving, stockpiling, blending, and loading coal by conveyor onto ships for export. Construction of the export terminal would begin in 2018. For the purpose of this analysis, it is assumed the export terminal would operate at full capacity by 2028. The following subsections present a summary of the On-Site Alternative, Off-Site Alternative, and No-Action Alternative.

1.1.1 On-Site Alternative

Under the On-Site Alternative, the Applicant would develop an export terminal on 190 acres (project area). The project area is located within an existing 540-acre area currently leased by the Applicant at the former Reynolds Metals Company facility (Reynolds facility), and land currently owned by Bonneville Power Administration. The project area is adjacent to the Columbia River in unincorporated Cowlitz County, Washington near Longview city limits (Figure 2).

The Applicant currently and separately operates at the Reynolds facility, and would continue to separately operate a bulk product terminal on land leased by the Applicant. Industrial Way (State Route 432) provides vehicular access to the Applicant's leased land. The Reynolds Lead and the BNSF Spur rail lines, both operated by Longview Switching Company (LVSW),¹ provide rail access to the Applicant's leased area from the BNSF Railway Company (BNSF) main line (Longview Junction) located to the east in Kelso, Washington. Ships access the Applicant's leased area including the bulk product terminal via the Columbia River and berth at an existing dock (Dock 1) operated by the Applicant in the Columbia River.

¹ LVSW is jointly owned by BNSF Railway Company (BNSF) and Union Pacific Railroad (UP).



Figure 1. Project Vicinity

Figure 2. On-Site Alternative

Under the On-Site Alternative, BNSF or Union Pacific Railroad (UP) trains would transport coal in rail cars from the BNSF main line at Longview Junction to the project area via the BNSF Spur and Reynolds Lead. Coal would be unloaded from rail cars, stockpiled and blended, and loaded by conveyor onto ocean-going ships at two new docks (Docks 2 and 3) on the Columbia River for export to Asia.

Once construction is complete, the export terminal would have an annual throughput capacity of up to 44 million metric tons of coal.² The export terminal would consist of one operating rail track, eight rail tracks for the storage of rail cars, rail car unloading facilities, stockpile areas for coal storage, conveyor and reclaiming facilities, two new docks in the Columbia River (Docks 2 and 3), and ship-loading facilities on the two docks. Dredging of the Columbia River would be required to provide access to and from the Columbia River navigation channel and for berthing at the two new docks.

Vehicles would access the project area from Industrial Way (State Route 432). Ships would access the project area via the Columbia River and berth at one of the two new docks. Trains would access the export terminal via the BNSF Spur and the Reynolds Lead. Terminal operations would occur 24 hours per day, 7 days per week. The export terminal would be designed for a minimum 30-year period of operation.


1.1.2 Off-Site Alternative

Under the Off-Site Alternative, the export terminal would be developed on an approximately 220-acre site adjacent to the Columbia River, located in both Longview, Washington, and unincorporated Cowlitz County, Washington, in an area commonly referred to as Barlow Point (Figure 3). The project area for the Off-Site Alternative is west and downstream of the project area for the On-Site Alternative. Most of the project area for the Off-Site Alternative is located within Longview city limits and owned by the Port of Longview. The remainder of the project area is within unincorporated Cowlitz County and privately owned.

Under the Off-Site Alternative, BNSF or UP trains would transport coal from the BNSF main line at Longview Junction over the BNSF Spur and the Reynolds Lead, which would be extended approximately 2,500 feet to the west. Coal would be unloaded from rail cars, stockpiled and blended, and loaded by conveyor onto ocean-going ships at two new docks (Docks A and B) on the Columbia River. The Off-Site Alternative would serve the same purpose as the On-Site Alternative.

Once construction is complete, the Off-Site Alternative would have an annual throughput capacity of up to 44 million metric tons of coal. The export terminal would consist of the same elements as the On-Site Alternative: one operating rail track, eight rail tracks for the storage of rail cars, rail car unloading facilities, stockpile areas for coal storage, conveyor and reclaiming facilities, two new docks in the Columbia River (Docks A and B), and ship-loading facilities on the two docks. Dredging of the Columbia River would be required to provide access to and from the Columbia River navigation channel and for berthing at the two new docks.

² A metric ton is the U.S. equivalent to a tonne per the International System of Units, or 1,000 kilograms or approximately 2,204.6 pounds.

Figure 3. Off-Site Alternative

Vehicles would access the project area via a new access road extending from Mount Solo Road (State Route 432) to the project area. Trains would access the terminal via the BNSF Spur and the extended Reynolds Lead. Ships would access the project area via the Columbia River and berth at one of the two new docks. Terminal operations would occur 24 hours per day, 7 days per week. The export terminal would be designed for a minimum 30-year period of operation.

1.1.3 No-Action Alternative

Under the No-Action Alternative, the U.S. Army Corps of Engineers would not issue the requested Department of the Army permit under the Clean Water Act Section 404 and the Rivers and Harbors Act Section 10. This permit is necessary to allow the Applicant to construct and operate the proposed export terminal.

The Applicant plans to continue operating its existing bulk product terminal located adjacent to the On-Site Alternative project area, as well as expand this business whether or not a Department of the Army permit is issued. Ongoing operations would include storing and transporting alumina and small quantities of coal, and continued use of Dock 1. Maintenance of the existing bulk product terminal would continue, including maintenance dredging at the existing dock every 2 to 3 years. Under the terms of an existing lease, expanded operations could include increased storage and upland transfer of bulk products utilizing new and existing buildings. The Applicant would likely undertake demolition, construction, and other related activities to develop expanded bulk product terminal facilities.

In addition to the current and planned activities, if the requested permit is not issued, the Applicant would intend to expand its bulk product terminal business onto areas that would have been subject to construction and operation of the proposed export terminal. In 2014, the Applicant described a future expansion scenario under No-Action Alternative that would involve handling bulk materials already permitted for off-loading at Dock 1. Additional bulk product transfer activities could involve products such as a calcine pet coke, coal tar pitch, cement, fly ash, and sand or gravel. While future expansion of the Applicant's bulk product terminal business might not be limited to this scenario, it was analyzed to help provide context to a No-Action Alternative evaluation and because it is a reasonably foreseeable consequence of a Department of the Army denial.

1.2 Regulatory Setting

Different jurisdictions are responsible for the regulation of water quality. These jurisdictions and their regulations, statutes, and guidance that apply to water quality are summarized in Table 1.

Table 1. Regulations, Statutes, and Guidance for Water Quality

Regulation, Statute, Guideline	Description
Federal	
National Environmental Policy Act (42 USC 4321 et seq.)	Requires the consideration of potential environmental effects. NEPA implementation procedures are set forth in the President's Council on Environmental Quality's Regulations for Implementing NEPA (49 CFR 1105).

Regulation, Statute, Guideline	Description
U.S. Army Corps of Engineers NEPA Environmental Regulations (33 CFR 230)	Provides guidance for implementing the procedural provisions of NEPA for the Corps. It supplements CEQ regulations 40 CFR 1500–1508.
Clean Water Act (33 USC 1251 <i>et seq.</i>)	Authorizes EPA to establish the basic structure for regulating discharges of pollutants into the waters of the United States and regulating quality standards for surface waters.
Safe Drinking Water Act (42 USC 300f <i>et seq.</i>)	Requires the protection of groundwater and groundwater sources used for drinking water. Also, requires every state to develop a wellhead protection program. EPA is the responsible agency.
National Pollutant Discharge Elimination System Permit (40 CFR 122)	Controls water pollution by regulating point sources that discharge pollutants into waters of the United States. Industrial, municipal, and other facilities must obtain permits if their discharges go directly to surface waters. Authorized by the Clean Water Act. EPA is the responsible agency but delegates the authority to state resource agencies.
National Pollutant Discharge Elimination System Vessels Program	Regulates incidental discharges from the normal operation of vessels. These incidental discharges include, but are not limited to, ballast water, bilgewater, graywater (e.g., water from sinks, showers), and antifoulant paints (and their leachate). Such discharges, if not adequately controlled, may result in negative environmental impacts via the addition of traditional pollutants or, in some cases, by contributing to the spread of aquatic invasive species. Authorized by the Clean Water Act. EPA is the responsible agency.
Washington State	
Washington State Environmental Policy Act (WAC 197-11, RCW 43.21C)	Requires state and local agencies in Washington to identify potential environmental impacts that could result from governmental decisions.
Clean Water Act Section 401 Water Quality Certification	Requires a water quality certificate to ensure that a project does not violate state or tribal water quality standards. The CWA directly grants all states Section 401 certification authority. In Washington, Ecology administers the Section 401 Water Quality Certification program. A Section 401 Water Quality Certificate must be issued prior to the issuance of a Section 404 permit or Section 402 permit.
Drinking Water/Source Water Protection (RCW 43.20.050)	Ensures safe and reliable public drinking water supplies in cooperation with local health departments and water purveyors. Ecology is the responsible agency.
Model Toxics Control Act (RCW 70.105D)	Requires potentially liable persons to assume responsibility for cleaning up contaminated sites. Ecology is the responsible agency.
State Water Pollution Control Law (RCW 90.48)	Provides Ecology with the jurisdiction to control and prevent the pollution of streams, lakes, rivers, ponds, inland water, salt waters, watercourses, and other surface and groundwater in the state.
Water Resources Act of 1971 (RCW 90.54)	Sets forth fundamental policies for the state to ensure that waters of the state are protected and fully used for the greatest benefit. Ecology is the responsible agency.
Water Quality Standard for Surface Waters of the State of Washington (WAC 173-201A)	Establishes water quality standards for surface waters of Washington State. Ecology is the responsible agency.

Regulation, Statute, Guideline	Description
Ballast Water Management (RCW 77-120)	Governs discharge of ballast water into waters of the state. Includes reporting and testing requirements. WDFW is the responsible agency.
Washington Administrative Code (WAC 173-340-300)	Requires reporting of hazardous substance releases if they may constitute a threat to human health or the environment.
Washington Administrative Code (WAC 173-204)	Establishes administrative procedural requirements and criteria to identify, screen, evaluate, prioritize, and clean up contaminated surface sediment sites.
Washington State Oil and Hazardous Substance Spill Prevention and Response (90.56 RCW)	Requires notification of releases of hazardous substances and establishes procedures for response and cleanup.
Oregon State	
Treatment Requirements and Performance Standards for Surface Water, Groundwater Under Direct Influence of Surface Water, and Groundwater (OAR 333-061-0032)	Establishes water quality standards for groundwater to meet current state and federal safe drinking water standards. Oregon DEQ is the responsible agency.
Oregon Drinking Water Quality Act (ORS 448.119 to 448.285; 454.235; and 454.255)	Ensures safe and reliable public drinking water supplies in cooperation with local health departments and water purveyors. Oregon DEQ is the responsible agency.
Water Quality Standards: Beneficial Uses, Policies, And Criteria for Oregon Oregon State Legislature: Turbidity Rule (OAR 340-041-0036)	Establishes the following turbidity standard: No more than a 10% cumulative increase in natural stream turbidities may be allowed, as measured relative to a control point immediately upstream of the turbidity-causing activity. However, limited-duration activities necessary to address an emergency or to accommodate essential dredging, construction or other legitimate activities and which cause the standard to be exceeded may be authorized provided all practicable turbidity control techniques have been applied. Oregon DEQ is the responsible agency.
Local	
Cowlitz County SEPA Regulations (CCC Code 19.11)	Provide for the implementation of SEPA in Cowlitz County.
Cowlitz County Stormwater Ordinance (CCC 16.22)	Establishes minimum standards to guide and advise all who make use of, contribute to, or alter the surface waters and stormwater drainage systems in Cowlitz County.
Cowlitz County Critical Areas Ordinance (CCC 19.15)	Requires Cowlitz County to designate critical areas such as wetlands, aquifer recharge areas, geologically hazardous areas, fish and wildlife habitat, and frequently flooded areas; and adopt development regulations to ensure the protection of such areas.
City of Longview Stormwater Ordinance	Establishes methods for controlling the introduction of runoff and pollutants into the municipal storm drain system (MS4) in order to comply with requirements of the Western Washington Phase II Municipal Stormwater NPDES Construction Stormwater General Permit process.

Regulation, Statute, Guideline	Description
Cowlitz County Phase II Municipal Stormwater Management Plan	Requires the Cowlitz County to develop a SWMP and update it at least annually. The SWMP incorporates BMPs to reduce the discharge of pollutants from the regulated area to the maximum extent practicable in order to protect water quality.
Notes: USC = United States Code; NEPA = National Environmental Policy Act; CFR = Code of Federal Regulations; Corps = U.S. Army Corps of Regulations; CEQ = Council on Environmental Quality; EPA = U.S. Environmental Policy Act; NPDES = National Pollutant Discharge Elimination System; WAC = Washington Administrative Code; Ecology = Washington State Department of Ecology; RCW = Revised Code of Washington; Oregon DEQ = Oregon Department of Environmental Quality; ORS = Oregon Revised Statutes; NTU = nephelometric turbidity units; WDFW = Washington Department of Fish and Wildlife; OAR = Oregon Administrative Rules; CCC = Cowlitz County Code; SWMP = stormwater management plan; BMP = best management practice,	

1.3 Study Area

The study areas for the On-Site Alternative and Off-Site Alternative are described below.

1.3.1 On-Site Alternative

The study area for direct impacts on water quality is the project area and an area extending 300 feet from the project area into the Columbia River. This portion of the study area accommodates the analysis of in-water construction and dredging impacts on water quality associated with suspended sediment and elevated turbidity. The study area also incorporates potential in-river dredged material disposal sites and an area extending 300 feet downstream of each disposal site (Figure 4).

The study area for indirect impacts on water quality incorporates the project area, the Consolidated Diking and Improvement District (CDID) #1 stormwater system drainage ditches adjacent to the project area, the Columbia River up to 1 mile downstream of the project area, and potential in-river dredged material disposal sites plus an area extending 300 feet downstream of each disposal site.

1.3.2 Off-Site Alternative

The Off-Site Alternative study area for direct impacts on water quality is the project area and the mixing zone in the Columbia River within 300 feet of the project area, as well as the dredge disposal sites, as described for the On-Site Alternative (Figure 5).

For indirect impacts, the study area includes the project area, CDID #1 stormwater system drainage ditches adjacent to the project area, the Columbia River up to 1 mile downstream of the project area, and potential in-river dredged material disposal sites plus an area extending 300 feet downstream of each disposal site. This study area includes Mount Solo Slough due to its proximity to the Off-Site Alternative project area.



Figure 4. Water Quality Study Area for the On-Site Alternative

Figure 5. Water Quality Study Area for the Off-Site Alternative

Chapter 2

Affected Environment

This chapter describes the methods for assessing the affected environment and determining impacts, and the affected environment in the study area as it pertains to water quality.

2.1 Methods

This section describes the methods used to characterize the affected environment and assess the potential impacts of the On-Site Alternative, Off-Site Alternative, and No-Action Alternative on water quality.

2.1.1 Data Sources

The following sources of information were used to evaluate the characteristics of the study area.

- Anchor QEA. 2011. *Engineering Report for NPDES Application Millennium Bulk Terminals*. Longview, WA. September 2011. Established the baseline water conditions for each project area.
- U.S. Environmental Protection Agency. 2009. *Columbia River Basin: State of the River Report for Toxics*. EPA 910-R-08-004.
- Ewing, Richard. 1999. *Diminishing Returns: Salmon Declines and Pesticides*. Available: <http://www.pcffa.org/salpest.pdf>. Accessed: October 20, 2014.
- Grette Associates, LLC. 2014a. *Millennium Coal Export Terminal Longview, Washington: Permanent Impacts to Aquatic Habitat*. September 2014.
- Grette Associates, LLC. 2014b. *Millennium Coal Export Terminal Longview, Washington: Docks 2 and 3 and Associated Trestle Direct Effects of Construction*. September 2014.
- Grette Associates, LLC. 2014c. *Millennium Coal Export Terminal Longview, Washington: Bulk Product Terminal Wetland and Stormwater Ditch Delineation Report – Parcel 61953*. September 2014.
- National Marine Fisheries Service. 2011. *Columbia River Estuary ESA Recovery Module for Salmon and Steelhead*. Portland, OR. January 2011.
- Oregon Department of Environmental Quality. 2003. *Designated Beneficial Uses Mainstem Columbia River (340-41-0101)*.
- Oregon Department of Environmental Quality. 2012. *303(d)/305(b) Integrated Water Quality Assessment Report*. Established the baseline water conditions for the Columbia River.
- Oregon State Marine Board. 2012. *Best Management Practices (BMP) White Paper for Recreational Boating Facility Construction and Replacement*.
- URS Corporation. 2014a. *Millennium Coal Export Terminal Longview, Washington. Affected Environment Analysis – Water Resources*. January.

- Washington State Department of Ecology. 2014. *Stormwater Management Manual for Western Washington*. Publication No. 14-10-055. Olympia, WA. Established the baseline water conditions for the Columbia River.
- Washington Department of Natural Resources. 2008. *Creosote Cleanup of Puget Sounds and its Beach*. Sedro-Woolley, WA.
- Other sources of relevant information, as cited in the text.

2.1.2 Impact Analysis

The following methods were used to evaluate the potential impacts of the On-Site Alternative, Off-Site Alternative, and No-Action Alternative on water quality. Potential impacts on the quality of groundwater are described in more detail in the NEPA Groundwater Technical Report (ICF International 2016b).

Impacts are based on how the On-Site Alternative, Off-Site Alternative, and No-Action Alternative would consume and discharge water and affect water quality relative to the affected environment and assuming compliance with regulations. Potential water quality impacts were evaluated with respect to existing water quality conditions and project-related water usage and discharge. The assessment also assumes the proposed project would comply with all applicable laws and regulations regarding water quality. For the purposes of this analysis, construction impacts are based on peak construction period and operations impacts are based on maximum throughput capacity (up to 44 million metric tons per year).

The impact assessment assumes that the On-Site Alternative and Off-Site Alternative would include the following elements.

On-Site Alternative:

- An individual National Pollution Discharge Elimination System (NPDES) Construction Stormwater General Permit for stormwater discharges during construction and operations.
- Remediation of any existing soil and groundwater contamination in the project area prior to and concurrently with project construction.
- Long-term monitoring as part of the remediation of the existing groundwater contamination to verify remedy effectiveness and natural attenuation of groundwater contamination.
- Water management would include the collection, conveyance, treatment, and reuse of water. Any water discharged to adjacent waters would be treated prior to discharge.

Off-Site Alternative:

- An individual National Pollution Discharge Elimination System (NPDES) Construction Stormwater General Permit for stormwater discharges during construction and operations.
- Water management would include the collection, conveyance, treatment, and reuse of water. Any water discharged to adjacent waters would be treated prior to discharge.

2.2 Affected Environment

The affected environment related to water quality in the study area is described below.

2.2.1 On-Site Alternative

The project area for the On-Site Alternative is located along the north shore of the Columbia River and lies in CDID #1³. The project area is generally flat at an elevation of +5 to +12 feet above the Columbia River Datum (CRD) and is drained by a system of National Pollution Discharge Elimination System (NPDES) permitted ditches to the Columbia River following treatment and to CDID ditches. Discharges to the Columbia River and CDID (Ditches 10 and 14) are monitored as part of the existing NPDES permit.

2.2.1.1 Project Area Characteristics

The water quality characteristics of the On-Site Alternative project area are described below.

Drainage

Stormwater and shallow groundwater drainage for the Applicant's leased area is controlled by a system of ditches, pump stations, treatment facilities, and outfalls. As shown in Figure 6, all of these facilities operate under a single NPDES permit. All of the Applicant's leased area drainage is either held onsite and evaporates, discharged to surrounding CDID #1 ditches (Ditches 10 and 14) that eventually flow to the Columbia River, or is treated and discharged through Outfall 002A to the Columbia River.

The following is a brief description of drainage components within the Applicant's leased area.

- **Sheet flow and infiltration.** Subbasin 4A, 5, 5A, 5B, 6A, and 7 receive sheet flow from storm events, which subsequently infiltrates or evaporates.
- **Columbia River discharge.** Subbasins 1, 2, 3A, 4, and 6 are conveyed via pumped systems or gravity to Facility 73, where they are treated and then discharged to the Columbia River via Outfall 002A.
- **CDID discharge.** Subbasin 3 flows through a vegetated ditch that discharges to CDID Ditch 10 through Outfall 003C. During larger storm events, a portion of the flows from Subbasin 2 and Subbasin 5 can discharge to the CDID ditch system. Subbasin 2 overflows the rerouted 006 pump station and is discharged to CDID Ditch 14 through Outfall 006. This is a designed overflow system and it is equipped with a high flow alarm to alert staff when it is activated. Subbasin 5 flows can enter a vegetated ditch that discharges to CDID Ditch 10 through Outfall 005. Ultimately, all CDID ditch flows discharge to the Columbia River.

³ Consolidated Diking Improvement District No. 1 (CDID #1) is a special purpose district pursuant to Chapter 85.15 of the Revised Code of Washington (RCW). CDID #1 was formed in 1923 as a consolidation of seven smaller diking and drainage districts in the area. (<http://cdid1.org/>)

Legend:

- Direct Impacts Study Area
- Indirect Impacts Study Area
- Approximate Drainage Delineation
- Stormwater Features
- CDID Ditch
- Tax Parcel Boundary
- Stormwater Culverts
- Pile Dikes to be Removed
- Drainage Flow Direction

Scale: 0, 500, 1,000 Feet

Source: Stormwater Features/Culverts (Grette Assoc.),
Ditches/CDID (City of Longview), Aerial (NAIP, 2015)

Map Labels:

- Ditch 10
- Ditch 16
- Mt. Solo Slough
- Parcel 10213
- BPA
- Industrial Way
- Ditch 5
- Outfall 003C
- Outfall 005
- NPDES Drainage Ditches
- NPDES Drainage Ditch (U-Ditch)
- Industrial WWTP (Facility Y1)
- Facility 77 Sump/Pump Station
- 004 Pump Station
- Outfall 001S
- Outfall 002A
- Gate
- Closed Black Mud Pond (BMP) Facility
- Rerouted Outfall 006
- Former Leachate Collection Ditch
- CDID Reynolds Pump Station
- Stormwater Retention Basin (Facility 73)
- 5A, 5B, 6A, 7, 4A, 1, 3, 3A

- **Drainage features on Parcel 10213.** These features include three vegetated ditches, two unvegetated ditches, and a shallow stormwater pond. Two of the vegetated ditches run north-south across the two larger portions of Parcel 10213. They are narrow and linear and convey stormwater to a culvert approximately 16 inches in diameter located at the north end of these ditches which then empties into CDID Ditch 10. The third vegetated ditch consists of three segments of linear vegetated ditches adjacent to Industrial Way. These three ditches are connected by two culverts that are beneath the site's access roads. This feature likely collects stormwater from Industrial Way and adjacent areas and conveys it to CDID Ditch 10.

One unvegetated ditch runs parallel to CDID Ditch 10 and consists of two sections of a narrow ditch that was likely constructed to intercept shallow groundwater affecting agricultural use of the site. This unvegetated ditch is several feet deep, nearly vertical along its sides, and is bisected by one of the vegetated ditches that runs parallel across the site; however, there is no surface hydrology connection between these two ditches. The other unvegetated ditch serves as the outlet channel for the stormwater pond. This ditch is located at the northeast end of the stormwater pond and conveys excess stormwater from the pond to CDID Ditch 10 through a 16-inch culvert. All six features are privately owned and are not managed by CDID #1.

Consolidated Diking Improvement District # 1

CDID is a secondary permittee on the Cowlitz County/Kelso/Longview Municipal NPDES permit. The CDID system is a series of levees that contain approximately 35 miles of drainage ditches that protect from external flooding (rivers), internal flooding (storm drainage runoff), and flooding from lands adjacent to the levee system (groundwater). The project area lies within the areas served by the CDID series of levees and ditches, which protect the area from flooding.

Water from Ditches 5, 10 and 14 in the study area was tested in 2006, 2011, and 2012 to determine levels of cyanide and fluoride (contaminants associated with the site cleanup). Total suspended solids were also tested. The results showed that water quality standards were met and that there were no exceedances or violations of established Washington State water quality standards (Anchor QEA 2011). The entire CDID #1 ditch system discharge to the Columbia River.

Columbia River

The Columbia River flows along the southwest project area boundary. This part of the river is freshwater and tidally influenced. Washington State Department of Ecology (Ecology) has established instream flow requirements for several locations on the Columbia River. Instream flows are specific streamflow levels that are regulated to protect fish, wildlife, recreation, aesthetics, water quality, and navigation (Washington State Department of Ecology 2014a). The project area is located at approximately river mile 64. The mean annual flow of the Columbia River, measured at the Beaver Army Terminal near Quincy, Oregon (river mile 53.8) is approximately 236,000 cubic feet per second (cfs). The river's annual discharge rate fluctuates with precipitation, snowmelt, and reservoir releases. Flows in the river range from 63,600 cfs to 864,000 cfs depending on conditions in the watershed (U.S. Geological Survey 2014). The Columbia River's annual cycle is driven by snowmelt and general climate of the Pacific Northwest, which produces high flows during the spring snowmelt period and low flows during the late summer and early fall. The river's flow, however, is highly managed through the operations of the many hydroelectric and irrigation dams that exist throughout the basin. The average annual discharge ranges from about 120,000 cfs during a low

water year to about 260,000 cfs during a high water year (Washington State Department of Ecology 2016a).

2.2.1.2 Water Quality Characteristics and Criteria

Water quality characteristics and criteria are described below.

Designated Beneficial Uses

Designated beneficial uses for a water body, as established in the Clean Water Act, are used to design protective water quality criteria, to assess the general health of surface waters, and to establish thresholds for future permit limits. Table 2 provides a list of the beneficial uses for the Columbia River as defined by Ecology and the Oregon Department of Environmental Quality (Oregon DEQ). A designated beneficial use provides a waterbody's assessed function or utility, and if a waterbody fails to meet the established water quality standards, the waterbody's designated use can be adversely affected.

Table 2. Beneficial Uses for the Columbia River

Washington State Department of Ecology^a	Oregon Department of Environmental Quality^b
Domestic water supply	Public domestic water supply; private domestic water supply
Industrial water supply	Industrial water supply
Agricultural water supply	Irrigation
Stock water supply	Livestock watering
Spawning/rearing uses for aquatic life	Fish and aquatic life
Harvesting	Fishing; wildlife and hunting
Boating	Boating
Primary contact for recreation uses	Water contact recreation
Commerce/navigation	Commercial navigation & transportation
Aesthetics	Aesthetic quality
Notes:	
^a Washington State Department of Ecology (2012) approved uses for the Columbia River from its mouth to river mile 309.3	
^b Oregon Department of Environmental Quality (2003) approved uses for the Columbia River from its mouth to river mile 86 (2003)	

Anticipated Designated Beneficial Uses of the Columbia River near the On-Site Alternative

Weyerhaeuser Longview, which is located at river mile 63.5, discharges wastewater from two treatment plants into the Columbia River. Weyerhaeuser's NPDES Permit WA0000124 (Weyerhaeuser 2014) included designated beneficial uses. Because of the proximity of the Weyerhaeuser Longview facility to the project area it is anticipated that the uses and criteria established for Weyerhaeuser may be applicable to the project area. The Weyerhaeuser uses and associated water quality criteria are provided below in Tables 3 and 4.

Table 3. Freshwater Aquatic Life Uses (Weyerhaeuser Longview)

Salmonid Spawning, Rearing, and Migration	
Parameter	Water Quality Criteria
Temperature Criteria – Highest 1-DAD MAX	<ul style="list-style-type: none"> • 1-day maximum (1-DMax) of 20.0 °C • When natural conditions exceed 1-DMax, no temperature increase will raise the receiving water temperature by greater than 0.3 °C
Dissolved Oxygen Criteria – Lowest 1-Day Minimum	To exceed 90 percent saturation
Turbidity Criteria	<ul style="list-style-type: none"> • 5 NTU over background when the background is 50 NTU or less; or • A 10 percent increase in turbidity when the background turbidity is more than 50 NTU.
Total Dissolved Gas Criteria	Total dissolved gas must not exceed 110 percent of saturation at any point of sample collection.
pH Criteria	The pH must measure within the range of 6.5 to 8.5 with a human-caused variation within the above range of less than 0.5 unit.

Table 4. Recreational Uses (Weyerhaeuser Longview)

Parameter/Use	Water Quality Criteria
Primary Contact Recreation	Fecal coliform organism levels must not exceed a geometric mean value of 100 colonies /100 mL, with not more than 10 percent of all samples (or any single sample when less than ten sample points exist) obtained for calculating the geometric mean value exceeding 200 colonies /100 mL

In addition to the designated beneficial uses listed in Tables 3 and 4, water supply uses established for Weyerhaeuser include domestic, agricultural, industrial, and stock watering and miscellaneous freshwater uses include wildlife habitat, harvesting, commerce and navigation, boating, and aesthetics.

Water Quality Impairments in the Study Area

The Columbia River faces water quality issues that endanger the health of important habitats found throughout the basin. Land use practices have increased the level of nutrients and pesticides and water temperature and instream structures such as dams and irrigation impoundments have affected water quality by inhibiting mixing, introducing dissolved gases, and trapping contaminated sediments. Industrial, municipal, and agricultural practices have introduced toxic contaminants from point and nonpoint sources (U.S. Geological Survey 2005).

Portions of the Columbia River are considered impaired for a number of water quality factors, according to the EPA-approved 303(d) lists for Washington and Oregon. Table 5 shows the 303(d) listed impairments for water quality factors in the study area. The State of Washington recently finalized the state's 2012 water quality assessment 303 (d) list of impaired waters. According to the 303(d) list, in the study area the Washington State portion of the Columbia River is impaired (i.e., Category 5) for water temperature and bacteria (Washington State Department of Ecology 2016b). In addition, Ditch 5 in the study area is impaired by bacteria. Oregon has listed the Columbia River in the study area as impaired for arsenic, DDE 4,4, and PCB. Arsenic, fecal coliform (indicator of bacteria), and dioxin were detected during monitoring of existing outfalls that would drain the project area (Anchor QEA 2014a).

Sediment sampling from within, adjacent to, and upstream of the Project area (to approximately River Mile (RM) 68, has demonstrated that in deepwater areas of the Columbia River, sediments are typically composed of silty sands with a low proportion of fines and very low total organic carbon. Further, sediments sampled from deepwater areas in the vicinity of the proposed export terminal have consistently met suitability requirements for flow lane disposal or beneficial use in the Columbia River (Grette 2014a: Appendix B). Sediment testing performed by the Applicant in the project area has revealed no exceedance of sediment-management standards at any nearshore or offshore location, except for in a localized area immediately adjacent to the existing Outfall 002A. Testing criteria were exceeded at one location downstream of the outfall, but did not exceed criteria for human health protection (Anchor QEA 2014b in Grette 2014b: Appendix B). The distribution of contamination was limited in area and depth to an isolated layer six inches in thickness, and the contamination source was identified as a historical discharge and not the result of an ongoing release (Grette 2014b: Appendix B).

Table 5. 303(d) Listed Impairments for Surface Waters in the Study Area

Parameter	Washington		Oregon ^c
	Columbia River	Ditch 5	Columbia River
Arsenic	-	-	5
Bacteria	5 ^a	-	-
DDE 4,4	-	-	5
Dioxin (2,3,7,8-TCDD)	-	-	4A ^b
Dioxin	4A ^b	-	-
Dissolved Oxygen	-	5	-
PCB	-	-	5
Temperature	5	-	-
Total dissolved gas	-	-	4A ^b

Notes:

^a Category 5 waters are impaired 303(d) waters, which means water quality standards have been violated for one or more pollutants and a TMDL or other water quality improvement is required.

^b Category 4A listing indicates a TMDL has been developed and is actively being implemented.

^c Oregon 2012 303(d) list is currently pending approval from the EPA. The 2010 effective list for this segment of the Columbia River is the same as the 2014 list that is currently pending approval by EPA.

Sources: Washington State Department of Ecology 2016b; Oregon Department of Water Quality 2012

DDE = Dichlorodiphenyldichloroethylene; TCDD = Tetrachlorodibenzo-p-dioxin; PCB = polychlorinated biphenyl

Baseline Water Quality Conditions in Broader Columbia River Basin

General baseline conditions for the broader Columbia River basin and Lower Columbia River and Estuary near the project are described below, followed by a discussion of specific water quality attributes. These attributes are discussed quantitatively where feasible and qualitatively otherwise. The purpose of this section is to provide some context for the water quality conditions of the study area by describing the conditions of the greater Columbia River basin because the impairments of surface waters in the study area are not entirely connected to activities only occurring in the project area, but can be related to the practices that degrade water quality throughout the greater basin.

Columbia River Basin

A significant focus has been placed on toxics reduction in the Columbia River basin. While many contaminants are found in the Columbia River basin, four main contaminants are found throughout

the basin at levels that could adversely affect people, fish, and wildlife: mercury dichlorodiphenyltrichloroethane (DDT) and its breakdown products, polychlorinated biphenyls (PCBs), and polybrominated diphenyl ether (PBDE) flame retardants. Other contaminants found in the basin include radionuclides, lead, pesticides, industrial chemicals, and newly emerging contaminants such as pharmaceuticals (U.S. Environmental Protection Agency 2009).

Lower Columbia River and Estuary near the Project Area

The lower Columbia River and Estuary is the 235-kilometer reach from the Bonneville Dam downstream to the Pacific Ocean. Monitoring results have shown high levels of contaminants such as PCBs, polyaromatic hydrocarbons (PAHs), DDT, and PBDEs in juvenile salmon tissue, water, and sediment. Studies have shown that flame-retardants and endocrine-disrupting compounds in water, sediment, fish, and osprey eggs increase downstream from Skamania to Longview (Lower Columbia Estuary Partnership 2015). Arsenic is most frequently detected metal in the lower Columbia.

Trace metals such as aluminum, iron, and manganese are predominantly transported in the suspended phase, whereas arsenic, barium, chromium, and copper are transported in the dissolved phase. Highest water temperatures in the lower Columbia generally occur in August where daily mean water temperatures often exceed 20°C. Data collected on September 11, 2015 at river mile 53, near the Beaver Army Terminal, indicated an oxygen saturation of 85.5% (9.17 mg/l), temperature of 20.03°C, and turbidity of 1.61 nephelometric turbidity units (NTUs). For contrast, data collected just below the Bonneville Dam at river mile 145 indicated an oxygen saturation of 97.9% (10.5 mg/l), temperature of 20.07°C, and turbidity of 2.27 NTUs (Center for Coastal Margin Observation and Prediction 2016).

On a more localized basis near the project area, the following average values were recorded in the lower Columbia: oxygen saturation of 73.62% (7.9 mg/l), temperature of 20.96°C, and turbidity of 9.9 NTUs (Weyerhaeuser NPDES 0000124).

Water Quality Attributes

Water Clarity

Water clarity refers to the amount of light that can penetrate water. Water clarity is an important parameter for assessing baseline water quality because lower clarity increases water temperatures, reducing the water's capacity to hold dissolved oxygen; and adversely affects photosynthesis, reducing the production of dissolved oxygen. Suspended sediment can clog the gills of fish and reduce their resistance to disease, cause lower growth rates, and affect egg and larval development. While both suspended sediment concentration and turbidity are common metrics of water clarity, turbidity data are available from a nearby U.S. Geological Survey (USGS) station and are used to characterize baseline conditions.

Background levels of turbidity in the Columbia River vary by season and weather patterns. USGS provisional data from the 2014 water year, collected at Beaver Army Terminal near Quincy, Oregon, reported elevated turbidity⁴ (U.S. Geological Survey 2015) that was generally higher than during the 2007 water year, when water clarity was rated as poor (U.S. Environmental Protection Agency 2007). However, elevated turbidity levels or poor water clarity in rivers such as the Columbia River

⁴ The USGS data presented is defined as "Turbidity, water, unfiltered, monochrome near infra-red LED light, 780-900 nm, detection angle 90 +/-2.5 degrees, formazin nephelometric units (FNU)."

are a natural condition that occurs during storm events and periods of high seasonal runoff and does not necessarily mean the water quality conditions are poor.

Biological Indicators

EPA and the Lower Columbia Estuary Partnership reported the following additional parameters in 2007 (U.S. Environmental Protection Agency 2007).

- **Dissolved nitrogen and phosphorus:** 100% of the estuarine area was rated *good* for dissolved nitrogen while 70% of the estuarine area was rated *fair* for dissolved phosphorus.
- **Chlorophyll *a*:** 29% of the estuarine area was rated *fair* for this indicator, with the remaining 71% of the area rated *good*.
- **Dissolved oxygen:** 99% of the estuarine area was rated *good* for this indicator.
- **Sediment quality:** 89% of the estuary as a whole was rated *good* while 11% was rated *poor*. The sediment quality index is rated based on three component indicators: sediment toxicity, sediment contaminants, and sediment total organic carbon. The estuarine area rated *poor* exceeded thresholds for one or more of these indicators.

Temperature

Water temperature is an important parameter for assessing baseline water quality. The Columbia River is impounded at many locations. These impoundments contribute to elevated water temperature by ponding water and increasing exposure to solar radiation. Although EPA and the Lower Columbia Estuary Partnership did not rate the Columbia River Estuary with respect to water temperature, because water temperature affects the water's capacity for dissolved oxygen, if dissolved oxygen levels are considered good, water temperatures are also fairly good.

Chemical Indicators

USGS conducted a survey of water quality in the Columbia River estuary with data from 2004 and 2005. Major findings of this study are as follows (U.S. Geological Survey 2005).

- The median copper concentration was 1.0 microgram per liter, a level shown to have inhibitory effects on juvenile coho salmon.
- Of the 173 pesticides and degradation products analyzed, 29 were detected at least once, oftentimes with two or more products occurring in a sample together. Fourteen samples with multiple products were detected (no concentrations were provided).
- Of the 54 wastewater products analyzed, eight were detected at least once, usually at trace levels. The known endocrine disruptor, bisphenol A, was detected.
- Of the 24 pharmaceuticals analyzed, acetaminophen, a common analgesic, and diphenhydramine, a widely used antihistamine, were detected. This is an indicator of human sources of water contamination, likely from wastewater treatment plant effluent.
- During the seasonal samplings of suspended sediment at all four sites, no organochlorine compounds or polycyclic aromatic hydrocarbons (PAHs) were detected.

Wetlands

Wetlands provide multiple ecological functions including water purification, flood protection, shoreline stabilization, groundwater recharge, and streamflow maintenance. They can also provide fish and wildlife habitat, recreational opportunities, and aesthetics benefits.

Approximately 96.9 acres of wetland occur in the Applicant's leased area. Ecology requires that all wetlands be rated on three functions: water quality, hydrology, and habitat based on site potential, landscape position, and value of each function. The rating system uses the combined function scores to categorize wetlands. Ecology's wetland categories are summarized in Table 6.

Table 6. Ecology's Wetland Categories Based on Functions

Wetland Category	Total Score for Functions	Category Description
Category I	≥ 70	<ol style="list-style-type: none"> 1. Represent a unique or rare wetland type; or 2. Are more sensitive to disturbance than most wetlands; or 3. Are relatively undisturbed and contain ecological attributes that are impossible to replace within a human lifetime; or 4. Provide a high level of functions.
Category II	51-69	<ol style="list-style-type: none"> 1. Difficult but not impossible to replace, and 2. Provide a high level of some functions.
Category III	30-50	<ol style="list-style-type: none"> 1. Provide a moderate level of functions, 2. Can often be adequately replaced with a well-planned mitigation project, and 3. Interdunal wetlands between 0.1 and 1 acre in size.
Category IV	< 30	<ol style="list-style-type: none"> 1. Often heavily disturbed, 2. May provide some level of functions, and 3. Should be able to replace, and in some cases be able to improve.

Source: Washington State Department of Ecology 2014b.

Based on Ecology's rating system, the wetlands in the project area scored between 20 to 46, indicating that wetlands in the project area are rated as Category III and IV and provide low to moderate water quality functions, low hydrologic functions, and low to moderate habitat functions (Grette Associates 2014d). Additional information on wetlands is described in the NEPA Vegetation Technical Report (ICF International 2016c).

Practices that Degrade Water Quality

Human activity has degraded water quality in the Columbia River estuary. Higher water temperatures, increased nutrient loading, reduced dissolved oxygen, and increases in toxic contaminants pose risks to fish and wildlife, as well as people. Sources of these contaminants include agricultural practices, urban and industrial practices, and riparian practices (National Marine Fisheries Service 2011). Refer to the NEPA Fish Technical Report (ICF International 2016d) for information regarding fish and potential impacts on fish and fish habitat.

Agricultural Practices

Agricultural practices contribute nutrients (i.e., nitrogen and phosphorus), sediment, and organic compounds (e.g., pesticides) and trace metals to runoff (U.S. Environmental Protection Agency

2014). Increased nutrient loads have been found to result in increased phytoplankton concentrations, increased turbidity, and depressed dissolved oxygen levels, especially in areas with lower flows and warmer water temperatures (Fenn et al. 2003). Increased sediment loads into surface waters can cause potential adverse impacts to aquatic resources. Common sediment impacts include deposition and scouring that can smother or dislodge benthic organisms; effects of turbidity (suspended sediment) which can affect aquatic organisms (e.g., clogging fish gills), alter water temperatures (by absorbing and scattering sunlight), and reduce light penetration which alters primary productivity and affects plants' ability to photosynthesize; and sediment binding to chemicals that can have toxic effects on organisms.

Banned pesticides, including DDT, persist in the environment and pesticides currently in use continue to run off into the estuary (Ewing 1999). The pesticides atrazine, simazine, metolachlor, S-ethyl dipropylcarbamothioate, dimethyl tetrachloroterephthalate, and diuron are present at sites throughout the Columbia River estuary, often in combination (U.S. Environmental Protection Agency 2009). Pesticides have the potential to harm benthic invertebrates, fish, amphibians, and various stream microbes.

Trace metals can affect aquatic organisms depending on the metal, the species, and the environment in which it is deposited. Excessive concentrations of some metals can lead to dysfunction of the endocrine system, of reproduction, and growth. Moreover, those metals that can be accumulated in tissues and organs may adversely affect cellular functions by interacting with enzymes, which can lead to disturbances of growth, reproduction, the immune system, and metabolism (Jakimska et al. 2011).

Urban and Industrial Practices

Pollutants sources that affect water quality are separated into two groups, *point sources* and *nonpoint sources*. Point sources are easily identified by a concentrated outlet to a receiving water, where the origin of flow is single known source (e.g., municipal wastewater treatment plant). Nonpoint sources contribute from a variety of locations in a given area. Eventually, nonpoint sources can be concentrated through a single outlet to a receiving water, but each source is not known or difficult to determine (e.g., lawn fertilizer from one or many unknown homes within a watershed).

The Columbia River from Bonneville Dam to the estuary is the most urbanized stretch in the entire basin. Over 100 point sources discharge directly into this stretch, including chemical plants, hydroelectric facilities, pulp and paper mills, municipal wastewater treatment plants, and seafood processors (Ewing 1999).

The largest point source discharger in the Columbia River basin is Portland's wastewater treatment plant (approximately 40 miles upstream of the project area). Nutrient loads from the plant account for 2 to 3% of the annual in-stream nutrient loads at the Beaver Army Terminal water quality sampling site in Quincy, Oregon, downstream of the project area. Another major source of aquatic pollution is the effluent from existing pulp and paper mills, which is highly toxic and contains dioxins and chlorinated phenols. (Ewing 1999). Pulp mill effluent is generally high in organic content and contains pollutants such as absorbable organic halide, toxic dyes, bleaching agents, salts, acids, and alkalis. Heavy metals such as cadmium, copper, zinc, chromium are often also present (Oberrecht 2014). Effluents from these point sources are regulated under NPDES permits and violations can incur significant fines.

Riparian Practices

Shoreline modifications, timber harvest, and agricultural activities in riparian zones and residential, commercial, and industrial development along the Columbia River have resulted in a substantial loss of riparian habitat function in the area (Ewing 1999). Healthy riparian habitat conditions (connected, forested riparian zones) may help to regulate water temperatures (depending on the size of the stream and the extent of shading) and contribute to aquatic habitat conditions and complexity (woody debris, bank stability, allochthonous inputs). In the study area, riparian habitat conditions the functions provided by riparian habitat are degraded. (Ewing 1999).

2.2.2 Off-Site Alternative

The 220-acre project area for the Off-Site Alternative is located along the north shore of the Columbia River and lies in CDID #1. Characteristics of the project area are similar to those described for the On-Site Alternative (Section 2.2.1, *On-Site Alternative*).

The Applicant would be required to lease or purchase various parcels adjacent to the project area to construct and operate the Off-Site Alternative. The project area for the Off-Site Alternative is west and downstream of the project area for the On-Site Alternative. Most of the project area is located in the City of Longview and owned by the Port of Longview. The remainder of the project area is in unincorporated Cowlitz County and privately owned.

2.2.2.1 Project Area Characteristics

The water quality characteristics of the Off-Site Alternative project area are described below.

Project Area Drainage

Stormwater and shallow groundwater drainage for the Off-Site Alternative project area is managed by infiltration and evaporation with overflow directed to the CDID ditches via a network of small excavated conveyance ditches and Mount Solo Slough (Figure 7). The conveyance ditches flow toward Mount Solo Slough, which discharges to Ditch 14, where water is eventually pumped to the Columbia River by the CDID #1 system. The stormwater is not managed under an NPDES permit. Surface water features on or adjacent to the project area include the Columbia River, Mount Solo Slough, and CDID Ditches 10, 14, and 16.

Mount Solo Slough

Mount Solo Slough forms the northern boundary of the project area and is near the closed Mount Solo Landfill. It is a highly meandering drainage that connects to CDID Ditch 14 to the east and CDID Ditch 16 to the north, both of which both connect to CDID Ditch 10.

Figure 7. Drainage Features for the Off-Site Alternative

Consolidated Diking Improvement District # 1

The project area is in CDID #1, which is as described for the On-Site Alternative (Section 2.2.1.1, *Project Area Characteristics*). The study area includes CDID #1 Ditch 14, Ditch 10, and Ditch 16. Ditch 14 crosses a short section of the eastern portion of the project area (for the rail access extension), just south of its confluence with Ditch 10. Ditch 16 extends between the northern end of Mount Solo Slough and Ditch 10, which runs along Mt. Solo Road.

Columbia River

The Columbia River characteristics are the same as described for the On-Site Alternative (Section 2.2.1.1, *Project Area Characteristics*).

2.2.2.2 Water Quality Characteristics and Criteria

All water quality impairments for the Columbia River in the study area are the same as described for the On-Site Alternative's study area (Section 2.2.1.2, *Water Quality Characteristics and Criteria*).

This chapter describes the impacts on water quality that would result from construction and operation of the On-Site Alternative or the Off-Site Alternative or the conditions under the No-Action Alternative.

3.1 On-Site Alternative

Potential impacts on water quality from the On-Site Alternative are described below.

The following construction activities of the On-Site Alternative could affect water quality.

- Ground disturbance associated with construction of the proposed export terminal
- Delivery, handling, and storage of construction materials and waste
- Use of heavy construction equipment
- In- and above-water work and dredging activities
- Demolition of existing structures

The following operations activities of the On-Site Alternative could affect water quality.

- Coal spills from rail and vessel loading and unloading
- Transport of airborne fugitive coal dust from stockpiles
- Operation and maintenance of heavy equipment and machinery
- Maintenance dredging

3.1.1 Construction: Direct Impacts

Construction of the On-Site Alternative would result in the following direct impacts.

Construction projects in Washington State that include clearing, grading, and excavating activities that disturb 1 acre or more and discharge stormwater to surface waters of the state are required to obtain an NPDES Construction Stormwater General Permit from Ecology. Prior to issuance of permits, sites with known contaminated soils or groundwater are required to provide a list of contaminants with concentrations, depths found and boring locations shown on a map with an overlay of where excavation or construction may occur. Additional BMPs may be necessary based on the contaminants and how contaminated construction stormwater would be treated. The permit requires the preparation of a temporary erosion and sediment control plan,⁵ a construction stormwater pollution prevention plan (SWPPP) and BMPs to avoid and minimize the risk of erosion. Guidance for the design and implementation of these BMPs would be sourced from the 2012

⁵ Temporary erosion and sediment control plans are developed and implemented to comply with stormwater pollution prevention planning (SWPPP), discharge sampling and reporting requirements in the National Pollutant Discharge Elimination System (NPDES) construction stormwater general permit, issued by the Washington State Department of Ecology

Stormwater Management Manual for Western Washington (Washington State Department of Ecology 2014a), including but not limited to those developed by the Applicant. The selected BMPs would represent the best available technology that is economically achievable and the best conventional pollutant control technology to reduce pollutants. BMPs would include a wide variety of measures to reduce pollutants in stormwater and other nonpoint source runoff. Construction practices would include measures to avoid and minimize erosion of soils associated with land disturbance and subsequent discharge of sediment-laden stormwater to adjacent surface waters. These requirements were considered when evaluating the potential direct impacts associated with construction.

Temporarily Increase Surface Water Turbidity Because of Upland Soil Disturbance

Construction of the On-Site Alternative would include ground-disturbing activities that would expose soils and generate soil stockpiles. Rain could erode soil and carry it into adjacent waterways (e.g., Columbia River and CDID ditches) and temporarily increase turbidity.

Although background turbidity in the Columbia River may change by orders of magnitude following storm events, if increased turbidity is sustained for several days it could affect surface water quality through interference with photosynthesis, oxygen exchange, and the respiration, growth, and reproduction of aquatic species. The potential for erosion during most ground-disturbing activities is considered low because the project area is relatively level and appropriate erosion and sediment control measures would be required through the NPDES Construction Stormwater General Permit, thus reducing the potential for impacts on water quality.

Both Ecology and Oregon DEQ have standards for turbidity increases from construction (Section 1.2, *Regulatory Setting*). These include the Water Quality Standards for Surface Waters of the State of Washington; Water Quality Standards: Beneficial Uses, Policies, and Criteria for Oregon; and Oregon State Legislature: Turbidity Rule. A project of this size can exceed the standards if erosion control measures are not implemented correctly. Monitoring is required downstream and at an upstream station to establish a baseline to determine if standards are met during construction. Discharge monitoring is required at all discharge points. If turbidity changes violate either Oregon's or Washington's standards, improvements must be made immediately, and all modifications, improvements, and repairs to erosion and sediment controls are to be recorded on the monitoring forms. Violations can result in civil penalties up to \$10,000 per day for violation of a term, condition, or requirement of a permit.

The Applicant identified the following BMPs as an initial list of measures to be implemented during construction to avoid and minimize potential impacts on water quality. This list may be expanded (Millennium Bulk Terminals Longview 2013).

- BMP C105: Stabilized Construction Entrance/Exit—would be installed and maintained through the duration of demolition, site preparation, preloading, and construction.
- BMP C106: Wheel Wash—would be installed and used at the entrance of the project area to prevent sediment from being tracked off site.
- BMP C107: Construction Road/Parking Area Stabilization—roads, parking areas, and other on-site vehicle transportation routes would be stabilized to reduce erosion caused by construction traffic or runoff.

- BMP C140: Dust Control—would be used to prevent wind transport of dust from disturbed soil surfaces. Either water or polyacrylamide would be used prevent soil erosion.
- BMP C153: Material Delivery, Storage and Containment—would be used to prevent, reduce, or eliminate the discharge of pollutants to the stormwater system or watercourses from material delivery and storage.
 - Storage of hazardous materials onsite would be minimized to the extent feasible.
 - Materials would be stored in a designated area, and secondary containment would be installed where needed.
 - Refueling would occur in designated areas with appropriate spill control measures.
- BMP C154: Concrete Washout Area—would be constructed near the entrance to the project area to prevent or reduce the discharge of pollutants to stormwater from concrete waste by conducting washout off site, or performing on-site washout in a designated area to prevent pollutants from entering surface waters or groundwater.
- BMP C162: Scheduling—would reduce the amount and duration of soil exposed to erosion by wind, rain, runoff, and vehicle tracking.
- BMP C200: Interceptor Dike and Swale—a ridge of compacted soil or a ridge with an upslope swale would be provided at the top or base of a disturbed slope or along the perimeter of a disturbed construction area to convey stormwater. The dike or swale would be used to intercept the runoff from unprotected areas and direct it to areas where erosion can be controlled. This would be used to prevent storm runoff from entering the work area or sediment-laden runoff from leaving the construction site.
- BMP C203: Water Bars—a small ditch or ridge of material would be constructed diagonally across roads as needed to prevent gullyng.
- BMP C207: Check Dams—would be constructed to reduce the velocity of concentrated flow and dissipates energy at the check dam.
- BMP C209: Outlet Protection—would prevent scour at conveyance outlets and minimizes the potential for downstream erosion by reducing the velocity of concentrated stormwater flows.
- BMP C220: Storm Drain Inlet Protection—would be installed at several locations across the project area to prevent coarse sediment from entering drainage systems prior to permanent stabilization of the disturbed area.
- BMP C233: Silt Fence—would be constructed around the entire project area to reduce the transport of coarse sediment from a construction site by providing a temporary physical barrier to sediment and reducing the runoff velocities of overland flow.
- BMP C241: Temporary Sediment Pond(s) —would be designed and constructed to remove sediment from runoff originating from disturbed areas of the project area.

Implementation of BMP C241 Temporary Sediment Pond would result in the creation of five water quality ponds (wetponds) based on the proposed site grading and drainage areas. These wetponds would be sized to treat the volume and flow from a water quality design storm event (72% of the 2-year storm). Additional storage would be provided within the coal storage area

such that the runoff would always be treated within the stockpile area, even for larger storm events.

These wetponds are part of Facility 73 and would be designed to provide sufficient capacity for sediment settlement as the stormwater flows through the ponds during construction. Weekly inspection and inspection within 24 hours of a rain event would be required under the NPDES Construction Stormwater General Permit. The inspections would be performed by a Certified Erosion and Sediment Control Lead. In the event that the wetponds reach their capacity, existing wetponds would be expanded or additional wetponds would be constructed sufficient to handle the amount of stormwater and sediment generated. Oil and grease components would be removed by mechanical skimmer. If treatment through the wet ponds is insufficient, filtration treatment would further remove suspended solids, associated particulate metals, and oil and grease. Filtration is initiated when effluent is greater than 15 NTU for 20 minutes; otherwise, if stormwater is below 15 NTU following settling, the filtration plant is bypassed. Subsequently, treated water would be conveyed downstream to the existing pump station outfall 002A that discharges into the Columbia River via an existing 30-inch steel pressure line or harvested for circulation around the site for multiple uses, including dust control measures.

CDID ditches are used for controlling floods, removing stormwater from areas that are protected behind levees, and conveying and discharging that stormwater to the Columbia River. The CDID ditches collect water from roads, parking lots, yards, and other land uses that contribute to elevated turbidity levels and pollutants that are discharged in the Columbia River. Because runoff from the project area would be required to meet the terms and conditions of all permits issued for the On-Site Alternative, construction may provide some improvement to the quality of water that is discharged from the site to the CDID ditches.

Overall, the construction activities associated with the On-Site Alternative would not be expected to cause a measurable impact on water clarity, water quality, or biological indicators; nor would construction affect designated beneficial uses.

Temporarily Release Contaminants Associated with Equipment and Material Use

The delivery, handling, and storage of construction materials and waste, as well as the use of heavy construction equipment could provide sources for stormwater contamination. Use and maintenance of heavy equipment could result in leaks or spills of vehicle fluids (i.e., fuel, lubricants, hydraulic fluid) on exposed parts of the equipment or onto the ground, where it could enter nearby surface water bodies through surface runoff. Constituents in vehicle fluids such as fuel, oil, hydraulic fluid, and grease can be acutely toxic to aquatic organisms and could degrade water quality and bioaccumulate in the environment. Chemicals typically used during construction including paints, solvents, and cleaning agents, which could also enter ground and surface waters through infiltration and stormwater runoff if such substances are spilled or exposed to precipitation. These substances can also be toxic to aquatic organisms and can degrade water quality. Construction waste such as metal, welding waste (e.g., scrap electrodes, slag, flux), and uncured concrete could be a potential source of pollution to water resources. Waste metals and welding wastes contain heavy metals and other chemicals and uncured concrete has a high pH, all of which can degrade water quality and be harmful to aquatic organisms (Washington State Department of Ecology 2014a). Additionally, staging areas or building sites can be sources of pollution because of the use of paints, solvents, cleaning agents,

and metals during construction. Impacts associated with metals in stormwater include bioaccumulation and toxicity to aquatic organisms and contamination of drinking supplies.

Development and implementation of a site-specific construction SWPPP that includes BMPs for material handling and construction waste management would reduce the potential for water quality impacts from these sources because water entering the CDID ditches from the project area would be treated. Typical SWPPP BMPs that would help prevent releases to surface waters include:

- All fuel and chemicals would be stored and handled properly to ensure no opportunity for entry into the water.
- No land-based construction equipment would enter any shoreline body of water except as authorized.
- Equipment would have properly functioning engine closures (i.e., hydraulic, fuel, lubricant reservoirs) according to federal standards; the contractor would inspect fuel hoses, oil or fuel transfer valves, and fittings on a regular basis for drips or leaks in order to prevent spills into the surface water.
- The contractor would have a spill containment kit, including oil-absorbent materials, on site to be used in the event of a spill or if any oil product is observed in the water.

Furthermore, the spill response time would be relatively quick and proper spill response equipment would be labeled and available. Quantities of hazardous materials is likely to be relatively small during construction (i.e., typically fewer than 50 gallons). If this volume were discharged directly to the Columbia River, it could affect water quality.

Construction activities would involve preloading and installing vertical wick drains to aid in the consolidation of low-consistency silt and low-density sand (i.e., unconsolidated materials). Wick drains would direct groundwater from the shallow aquifer upward toward the surface during preloading, where the water would discharge. Water discharged from the wick drains would be captured, tested for contaminants, and treated prior to discharge to any surface waters.

Temporarily Mobilize Pollutants or Increase Turbidity from In-Water Work and Dredging

The On-Site Alternative would dredge an estimated 500,000 cubic yards of sediment from the Columbia River to provide berthing at Docks 2 and 3. The work necessary to construct the approach trestle and entire dock structures for Docks 2 and 3 would require in-water work that could resuspend pollutants and sediment and increase turbidity.

Dredging would permanently deepen a 48-acre area, all of which is in deep water (at least -20 feet) to a target depth of -43 feet CRD with a 2-foot overdredge allowance. The deepening would require dredging depths that range from as little as a few feet to approximately 16 feet. It is anticipated that the sediment within the dredge prism⁶ for Docks 2 and 3 would be deemed suitable for flow-lane disposal or beneficial use in the Columbia River. Dredging would be conducted using a barge-mounted mechanical clamshell dredge with material loaded into a bottom-dump barge for transport to an approved dredge material disposal site once the barge is full. Dredging could also be conducted using a hydraulic dredge. These methods do not require dewatering.

⁶ Total volume, typically trapezoidal in shape of the channel bottom to be removed by the dredging process.

Dredged material would be suitable for flow-lane disposal or beneficial use in the Columbia River based on recent sediment sampling that suggests that sediments from the deepwater areas of the Columbia River are composed of silty sands with a low proportion of fines and low total organic carbon (Grette Associates 2014e). The Sediment Evaluation Framework for the Pacific Northwest was developed by EPA and the Corps as a toolbox for determining the proper disposal method for dredge material including flow-lane disposal. This framework is designed to allow for project-specific concerns and can adapt to projects of any size. Generally, the framework outlines the level of detail required for the sediment characterization study to determine the presence or extent of contamination based on initial sampling. The disposal area for this dredging action is anticipated to be approximately 80 to 110 acres, based on recent flow-lane disposal for disposing of material from the adjacent Dock 1 (Grette Associates 2014a). However, the actual acreage of the disposal site would be determined by the permitting agencies and would be based on sediment characteristics (i.e., consistency and density of sediments). Recent authorizations for flow-lane disposal of dredged materials in the Columbia River near the project area were generally in or adjacent to the navigation channel between approximately river mile 60 and 66) (Grette Associates 2014c).

Dredging and in-water work would result in temporary increases in turbidity. Sediment sampling from within, adjacent to, and upstream of the project area has demonstrated that in deepwater areas of the Columbia River, sediments are typically composed of silty sands with a low proportion of fines (e.g., silt or mud) and very low total organic carbon. Further, sediments sampled from deepwater areas near the project area have consistently met suitability requirements for flow-lane disposal or beneficial use in the Columbia River (Grette Associates 2014c). Thus, it is anticipated that sediment within the dredge prism for Docks 2 and 3 would be deemed suitable for flow-lane disposal or beneficial use in the Columbia River. However, prior to obtaining any permit for the On-Site Alternative, including dredging, the Applicant would conduct site-specific sediment sampling to characterize the proposed dredge prism and ensure compliance with the Dredged Materials Management Plan (Grette Associates 2014c).

Standard BMPs for working in aquatic areas would be followed to maintain acceptable water-quality conditions, including but not limited to maintaining appropriate standards for construction-related turbidity (including during active dredging and flow-lane disposal), minimizing the risks of unintended discharges of materials such as fuel or hydraulic fluid, and managing construction debris. In addition, typical construction BMPs for working over, in, and near water would be applied, including checking equipment for leaks and other problems that could result in discharge of petroleum-based products, hydraulic fluid, or other material to the Columbia River. The following BMPs related to in-water work so apply during the construction period:

- The contractor would use tarps or other containment methods when cutting, drilling, or performing over-water construction that might generate a discharge to prevent debris, sawdust, concrete and asphalt rubble, and other materials from entering the water.
- The contractor would retrieve any floating debris generated during construction using a skiff and a net. Debris would be disposed of at an appropriate upland facility. If necessary, a floating boom would be installed to collect any floated debris generated during in-water operations.

Construction of the approach trestle and entire dock structure for Docks 2 and 3 would require construction activities both in-water and over-water and waterward of the ordinary high water

line, which is 11.1 feet CRD. The Applicant currently anticipates the in-water work will require up to 2 years (over two approved in-water work windows) to complete Docks 2 and 3 and the associated trestlework, depending on permit restrictions. Work windows would be scheduled to avoid and minimize impacts on various natural resources, most notably federally protected fish species, as described in the NEPA Fish Technical Report (ICF International 2016d). In-water construction would primarily involve dredging, pile driving and removal of pile dikes and would use barge-based equipment and purpose-built vessels, although some work would likely be supported from land. A total of 603 of the 622 36-inch diameter steel piles required for the trestle and docks would be placed below the ordinary high water mark, permanently removing an area equivalent to 0.10 acre (4,263 square feet) of river bottom. The construction would also remove 225 feet of the deepest portion of timber pile dikes (Grette Associates 2014a). Piles would be driven and removed via vibratory methods. Piles would be driven and removed using vibratory methods. Vibratory methods are likely to result in localized, short-term resuspension of sediment but to a lesser extent than would be caused by impact methods. Vibration methods reduce friction between the pile and substrate to avoid disturbing large amounts of sediment (Oregon State Marine Board 2012).

According to hydrodynamics modeling from Grette Associates (2014a), strong down-current flow is evident by erosional scour marks along the dredge cut. Therefore, contaminants disturbed during dredging activities would be expected to move downstream. However, initial sediment physical and chemical characterization at the project area shows sediments are typically silty sands with low proportions of fines and organic material, thus reducing the potential to increase turbidity as compared to silty mud or sediments with high concentrations of organic material. Therefore, the period of increased turbidity at the project area is anticipated to be relatively short as sandy particles settle out of suspension more quickly than fine-grained materials. Furthermore, the vast majority construction would occur at relatively deep (less than 20 feet CRD) locations, which also reduces the potential for sediment disturbance during vessel maneuvering (Grette Associates 2014a).

The remobilization of nutrients would be temporary and not likely in quantities large enough to cause algal blooms due to the river's continual flow. Furthermore, dissolved oxygen depletion during dredging is not typically a concern in the Columbia River because of the sandy characterization of river sediments. Any in-water construction impacts would be highly localized and confined within the area around the in-water work. Furthermore, the Applicant identified the following BMPs to avoid and minimize potential impacts from pile removal and installation activities.

- Pile would be removed slowly to minimize sediment disturbance and turbidity in the water column.
- Prior to pile extraction the operator would vibrate the pile to break the friction between the pile and substrate to minimize sediment disturbance and to avoid pulling out large blocks of soil.

Another potential water quality impact from in-water work is the possibility for creosote releases resulting from the removal of existing creosote-treated timber piles associated with two pile dikes. Creosote is a wood preservative that has been used for over a century to treat wood, including piles. Creosote is composed of more than 300 chemicals, including PAHs. PAHs at sufficient levels have been shown to be fatal to marine life (Washington Department of Natural Resources 2008). The removal of creosote-treated piling would result in temporary

suspension of sediments and a potential long-term increase in the exposure of creosote in the study area. Over the long-term, the source of creosote would be removed or capped by the sediment falling into the hole left by the extracted pile. The concentration of creosote in the sediment would decrease, water quality would improve, and the pathway of exposure for fish through contamination of prey would be reduced. The exposure of creosote would be caused by the removal of piles that have been buried in an anoxic zone that leaves the creosote highly volatile when re-exposed to water. This creosote could be suspended in the water column and contaminate the adjacent sediments. Additionally, droplets of previously unexposed creosote could be released from the piling into the surrounding sediments because the droplets are heavier than water. To minimize this impact, the contractor would follow the following standard BMPs for removal of creosote-treated wooden piles.

- Pile removal. Vibratory extraction is the preferred method of pile removal. A creosote release to the environment may occur if equipment (bucket, steel cable, vibratory hammer) pinches the creosoted piling below the water line. Therefore, the pile extraction equipment must be kept out of the water to the extent practicable to remove the piling. Cutting is necessary if the pile has broken off at or near the existing substrate, which means it cannot be removed without excavation, or below the water line. Pile cutoff is an acceptable alternative if vibratory extraction or pulling is not feasible. The piling would be cut two feet below the riverbed and the subsequent hole would be capped/filled with clean sand.
- Disposal of piling, sediment, and construction residue. Pulled pile would be placed in a containment basin to capture any adhering sediment. This would be done immediately after the pile is initially removed from the water. Containment basins typically have continuous sidewalls and controls as necessary (e.g., straw bales, oil absorbent boom, plastic sheeting) to contain all removed materials and prevent re-entry into the water. The type and location (e.g., barge, land) of the containment basin would be determined when the contractor's work plan is developed. Piling would be cut into 4-foot lengths with a standard chainsaw. Cut-up piling, sediments, construction residue, and plastic sheeting from the containment basin would be packed into a container. For disposal, materials would be shipped to Rabanco/Seattle, Weyco facility at Longview Washington, or to another facility complying with federal and state regulations.

Above-water work would include installing the pile-supported elements of the dock structures and coal-handling infrastructure and equipment. Some concrete components (such as the dock decking, crane rail supports, and pile caps) would need to be cast in place. Appropriate techniques and BMPs, such as the use of a bib, would minimize the potential for wet or uncured concrete to encounter the Columbia River.

Materials handling infrastructure and equipment such as shiploaders and conveyors would be delivered by barge and off-loaded by crane directly to the docks and trestle. Barges would not offload materials or equipment to any area below the ordinary high water mark of the Columbia River. As much as practicable, infrastructure would be prefabricated so that above-water work would largely consist of installation and assembly.

Impacts on water quality from in-water and over-water work would be addressed in the Water Quality Monitoring and Protection Plan to be prepared by the Applicant. Impacts on water quality from dredging would be minimized with the implementation of a dredging and disposal quality control plan in compliance with the dredged material management program as required by State agencies (Ecology and Washington State Department of Natural Resources) and federal

agencies (the Corps and EPA). Dredging and disposal activities would be assessed and evaluated in the dredged material management program based on established policies and guidelines. The *Dredged Material Management Program User Manual* provides technical and policy guidance on the preparation of the quality control plan.

The quality control plan would include dredging methods and procedures to minimize water quality impacts, disposal protocols (whether upland or in-water), a water quality monitoring plan, and contingencies for water quality exceedances. Adhering to the plan would avoid and minimize impacts, ensuring potential impacts are temporary and localized in nature. No long-term changes in the baseline conditions within the study area would be expected to occur.

Temporarily Introduce Hazardous or Toxic Materials from Demolition Activities

Demolition of the existing structures in the project area (e.g., cable plant building, potline buildings, and small ancillary structures) has the potential to affect water quality by disturbing soil or building parts and debris that may contain hazardous or toxic materials. The existing structures are primarily made from steel, aluminum, concrete, and wood and may contain asbestos and lead. As discussed in the NEPA Hazardous Materials Technical Report (ICF International 2016e), a survey of each existing on-site structure has identified if asbestos or lead is present. In addition to disturbing soil, demolition of the existing buildings would result in a substantial amount of debris that may contain hazardous materials such as asbestos or lead. Demolition of buildings with concrete components would also generate concrete dust.

Concrete dust from demolition produces a strong alkaline solution that can drastically increase pH and cause chemical burns to fish, insects, and plants. If concrete dust is not properly contained during demolition, it can run off in stormwater and cause substantial harm to aquatic environments and organisms.

This impact would be minimized by the collection and removal of all concrete and other structural debris and the collection and treatment of all stormwater from the site prior to discharge to surface waters. The implementation of BMPs in compliance with the NPDES Construction Stormwater General Permit that would be obtained for the On-Site Alternative would reduce the potential for demolition-related pollutants to enter and contaminate surface waters. Overall, the demolition activities associated with the On-Site Alternative would not be expected to cause a measurable impact on water quality or biological indicators, nor would they affect designated beneficial uses.

3.1.2 Construction: Indirect Impacts

Construction of the On-Site Alternative would not result in indirect impacts on water quality because construction impacts are immediate and no construction impacts would occur later in time or farther removed in distance than the direct impacts.

3.1.3 Operations: Direct Impacts

Operation of the On-Site Alternative would result in the following direct impacts.

Although most operations impacts would be as described below, relatively large-scale coal spills could occur in the study area. The trains proposed to bring coal to the project area would hold approximately 122 tons per car and there would be 125 cars per train. The Panamax shipping

vessels, with an average capacity of 65,000 deadweight tonnage would be used to transfer the coal to its final destination (Maritime Connector 2015). A large-scale coal spill could affect water resources for extended periods. Refer to the NEPA Rail Transportation Technical Report and the NEPA Vessel Transportation Technical Report for more discussion of potential spills.

Introduce Contaminants from Stormwater Runoff

Stormwater would be managed in accordance with the requirements of a new NPDES Industrial Stormwater Permit obtained for the water management facilities of the proposed export terminal. Contaminants such as oil and grease, coal dust, and other chemicals could accumulate on the ground and facility surfaces and become constituents of site stormwater. All stormwater runoff would be collected for treatment before reuse or discharge to the Columbia River. Coal particulates would be removed from stormwater by allowing the coal dust to settle out in stormwater ponds. The coal dust would be removed from the stormwater ponds and placed back in the coal stockpile area during regular maintenance of the stormwater ponds. Other solids accumulated in the treatment systems not acceptable for reuse would be periodically collected and disposed of at an appropriate off-site disposal site.

The following BMPs may be part of the Applicant's facility design.

- Enclosed conveyor galleries to allow for collection of washdown water.
- Enclosed rotary unloader building and transfer towers.
- Washdown collection sumps for settlement of sediment.
- Regular cleanout and maintenance of washdown collection sumps.
- Containment around refueling, fuel storage, chemicals, and hazardous materials.
- Oil/water separators on drainage systems and vehicle washdown pad.
- Requirement that all employees and contractors receive BMP training appropriate to their work activities.
- Design of docks to contain spillage, with rainfall runoff and washdown water contained and pumped to the upland water treatment facilities.

Design of system to collect and treat all runoff and washdown water for either reuse for onsite (dust suppression, washdown water, or fire system needs) or discharge offsite.

As shown in Table 5, the Columbia River and Ditch 5 are listed as impaired for pollutants. Some of these pollutants may be introduced from stormwater runoff from the project area. The following pollutants were detected during monitoring of existing outfalls that would drain the project area: arsenic, fecal coliform (indicator bacteria), and dioxin (Anchor QEA 2014a). These pollutants may continue to be introduced as a result of the On-Site Alternative although maximum reported outfall concentrations for these pollutants fall below established water quality standards. Continued discharges at existing levels would not cause a measureable increase in chemical indicators in the Columbia River and would not cause a measurable impact on water quality or biological indicators, nor would they affect designated beneficial uses. Any changes in concentrations of these pollutants that may occur during operations would be addressed under the NPDES Industrial Stormwater Permit to ensure water quality standards continued to be met prior to discharge to the Columbia River.

3.1.4 Operations: Indirect Impacts

Operation of the On-Site Alternative would result in the following indirect impacts on water quality, which could arise as a result of the increase in vessel and rail traffic.

Introduce Contaminants from Coal Spills and Coal Dust


Coal and coal dust could enter the Columbia River directly or via the surrounding drainage channels from accidental spills during loading or through airborne transport of coal dust during operations. The extent of average annual coal dust deposition was modeled and mapped (Figure 8). Coal dust is anticipated to deposit a maximum of 1.45 grams per square meter per year ($\text{g}/\text{m}^2/\text{year}$) adjacent to the project area. The area of coal dust deposition extends past the project area into the Columbia River, with deposition rates decreasing as the distance from the project area increases.

At sufficient quantities, coal and coal dust in marine and estuarine environments have similar adverse effects as elevated levels of suspended sediments on water quality (Ahrens and Morrissey 2005). During periods of lower flow, a smaller amount of coal dust could have a greater impact on water quality. Impacts include increased turbidity, which can interfere with photosynthesis and increase water temperatures (Ahrens and Morrissey 2005). Coal and coal dust in the water column can also affect marine organisms through abrasion of tissue, smothering and clogging of respiratory and feeding organs (Ahrens and Morrissey 2005). However, at a maximum deposition rate of $1.45 \text{ g}/\text{m}^2/\text{year}$ adjacent to the project area, and at the minimum flow⁷ recorded over the 23-year period of record for 1 day, coal dust deposition directly into the river assumed to be an area of approximately 3 million square meters (1.16 square miles) in the study area would result in a change in suspended sediment concentration of less than 1 part per 10 billion ($7.5\text{e-}05$ milligrams per liter (mg/L)). This change would not be measureable and is not anticipated to increase turbidity or water temperature, or affect marine organisms.

Coal and coal dust captured in stormwater (precipitation that falls on the stockpile areas and water used for dust suppression) would be collected within the stockpile pads, conveyed within an enclosed stormwater system and treated at Facility 73 in settling ponds before being discharged from the site. Some settled coal dust from the project area could discharge to the Columbia River through the CDID #1 system. If coal dust from the project area accumulated without being disturbed throughout the dry season (assumed 120 days), the anticipated change in suspended sediment concentration in the Columbia River within the study area for the minimum recorded flow over one day would be 0.0192 mg/L. Again, this change would not be measureable and would not likely increase turbidity or water temperature, or affect marine organisms.

The On-Site Alternative would employ dust suppression systems throughout the proposed export terminal, including the tandem rotary dumpers, all conveyors, stockpile pads, surge bins, transfer towers, and trestle. Approximately 4,900 linear feet of the 16,100 linear feet of conveyor belts would be enclosed, as would the shiploaders, to limit the release of coal dust. The dust suppression system would employ sprayers and foggers to capture coal dust. Dust suppression water would be collected and conveyed through the stormwater collection,

⁷ The minimum recorded flow at the Columbia at Beaver Army Terminal, Quincy, OR is 65,600 cfs (1969 to 2014).

Figure 8. 3-Year Annual Average Coal Dust Deposition Millennium Bulk Terminal – Longview

conveyance, and treatment system. Once treated the water would be reused or, if not needed, discharged to the Columbia River. All water discharged to the Columbia River would be required to meet specific water quality standards in the NPDES permit prior to discharge. The specific standards would be defined within the NPDES Construction Stormwater General Permit to be obtained for the project.

Coal contains trace amounts of toxic elements, but coal is a naturally occurring substance that has not been identified to be toxic or hazardous. Coal has a heterogeneous chemical composition; therefore, specific impacts related to the toxic contaminants of coal are highly dependent on coal composition and source (Ahrens and Morrissey 2005). The majority of coal transloaded at the proposed terminal is expected to be mined in the Powder River Basin, with lesser amounts sourced from the Uinta Basin in Utah and Colorado. Trace elements of environmental concern (TEEC) in Powder River Basin and Uinta Basin coal include antimony, arsenic, beryllium, cadmium, chromium, cobalt, lead, manganese, mercury, nickel, selenium, and uranium. These elements are generally low in coals from both of these basins compared to other mining regions, although exact concentrations are not reported (U.S. Geological Survey 2007). Table 7 presents the average concentrations of each TEEC sampled in parts per million. However, at a maximum coal deposition rate of 1.45 g/m²/year adjacent to the project area and at the minimum flow recorded over the 23-year period of record for 1 day, TEEC deposition directly into the Columbia River assumed to be an area of approximately 3 million square meters (1.16 square miles) in the study area would result in unmeasurable changes in concentration for each of the elements of concern on the order of 1x10⁻¹³ to 1x10⁻¹⁵ g/L. If coal dust from the project area accumulated without being disturbed throughout the dry season (assumed to be 120 days long), the anticipated change in TEEC concentration for the minimum recorded flow over one day would be on the order of 1x10⁻¹⁰ to 1x10⁻¹² g/L. Again, this change would not be measureable and is not anticipated to affect human health or affect marine organism functions (respiration, feeding).

Toxic constituents of coal include PAHs and trace metals, which are present in coal in variable amounts and combinations dependent on the type of coal. The coal type, along with mineral impurities in the coal and environmental conditions, determine whether these compounds can be leached from the coal. Some PAHs are known to be toxic to aquatic animals and humans.

Metals and PAHs could also leach from coal to the pore water of sediments. However, the low aqueous extractability and bioavailability of the contaminants minimizes the potentially toxic effects. Furthermore, the type of coal anticipated to be exported from the proposed export terminal is alkaline and low in sulfur and trace metals. The conditions to produce concentrations in pore waters are not present in a dynamic riverine environment. This would further support the view of Ahrens and Morrissey (2005) that the bioavailability of such toxins would likely be low.

In summary, coal dust from project operations is not expected to have a demonstrable effect on water quality. Additionally, the potential risk for exposure to toxic chemicals contained in coal (e.g., PAHs and trace metals) would be relatively low as these chemicals tend to be bound in the matrix structure and not quickly or easily leached.

Coal spilling into the Columbia River could occur during vessel loading operations. Cleanup efforts would be implemented quickly and it would be expected the majority of the spilled coal would be recovered. However, because toxic chemicals in coal tend to be bound to the matrix

structure of the coal and are not quickly or easily leached, they would likely not result in a substantial increase in chemical indicators in the Columbia River and would likely not cause a measurable impact on water quality or biological indicators nor would they affect designated beneficial uses.

The concentration of PAHs in Powder River Basin Coal was not investigated for this report.

Because the rate of coal dust deposition is so low, it is likely unmeasurable and the concentration of TEEC are considered low. Therefore, impacts of dispersed coal, coal dust, and coal dust constituents on water quality are anticipated to be low.

Table 7. Average Concentration of Trace Elements in Wyodak and Big George Coal Beds, Powder River Basin, Wyoming and Miscellaneous Uinta Basin Coal Beds in Colorado Plateau

Trace Element of Environmental Concern	Average Concentration in Sampled Coal (ppm)	Uinta Basin ^b
	Powder River Basin ^{a, b}	
Antimony	0.10	0.7
Arsenic	1.43	2.2
Beryllium	0.18	1.5
Cadmium	0.06	0.1
Chromium	2.63	6.1
Cobalt	1.93	2.0
Lead	1.26	13.9
Manganese	10.05	28.2
Nickel	1.58	4.5
Selenium	0.57	1.4
Uranium	0.46	1.8

Sources:

^a U.S. Geological Survey 2007

^b Pierce and Dennen, 2009

As part of operations, any stormwater runoff from the storage and stockpile areas would be collected and conveyed to water quality treatment facilities. Stormwater would be treated prior to discharge to surface waters to avoid and minimize water quality degradation. Approximately 4,900 linear feet of the 16,100 linear feet of conveyor belts would be enclosed, as would the shiploaders to limit the potential for coal or coal dust to affect water quality.

Introduce Contaminants from Maintenance Operations

Potential contaminants, including diesel fuel, oils, grease, and other fluids would be required for the operation and maintenance of heavy equipment and machinery used to transport, store, move, and load coal at the proposed terminal. Normal operations and maintenance activities would not result in a direct discharge of pollutants or process water into surface water. Most operation-related impacts would result from inadvertent spills of potentially hazardous materials such as petroleum products (fuel, lubricants, and hydraulic fluids) or industrial solvents either directly into surface waters or in locations where they could be transported and discharged to surface water or groundwater. These potential releases are likely to be relatively small (less than 50 gallons) and limited in their extent and duration (localized and short-term).

Locomotives have a fuel capacity of 5,000 gallons and could also potentially release fuel during operations. Also, fuel trucks would visit the site as required during operations; the frequency would vary based on usage and could range from as often as once or twice per day to once or twice per week. Fuel trucks typically would have a 3,000-to-4,000-gallon capacity. A spill could have potential impacts on water quality. A spill that occurred would be contained, conveyed, and treated within the proposed stormwater system (i.e., material spilled within the project area would be contained and would not be discharged to surface waters outside the project area). The Applicant would be required to manage contaminated stormwater in accordance with the requirements of the NPDES Industrial Stormwater Permit and avoid and minimize impacts on water quality.

Maintenance dredging for Docks 2 and 3 would be expected to occur every few years. Maintenance dredging impacts on water quality would be similar to those discussed for dredging during construction but to a lesser magnitude because the dredging volumes would be considerably smaller than the initial dredging action during construction. Preparation and implementation of a dredging and disposal quality control plan, discussed above for construction dredging, would also be employed for maintenance dredging. Similarly to construction related dredging activities, no long-term changes in the baseline conditions within the study area would be expected to persist because of maintenance dredging.

Sediment accretion in the proposed dredge prism would most likely occur because of bedload transport due to river currents local scour, and sediment redistribution resulting from propeller wash. Hydrodynamic modeling and sediment transport analysis was conducted for the proposed Docks 2 and 3 berthing/navigation basin. Sedimentation is complex in a newly dredged basin. Specific morphologic data are unavailable for the proposed new dredging basin; therefore the rate of accretion can only be estimated. Based on current accretion estimates, a rough estimate for annual accretion height is 0.16 feet (0.07 to 0.26 feet range) and annual accretion volume is 11,675 cubic yards (ranging from 4,670 to 23,350 cubic yards). Maintenance dredging would likely be required on a multiyear basis or following occasions with extreme flow events. Small-scale maintenance dredging could be needed more frequently, especially in the early years following the initial dredging work when higher than normal accretion is more likely (WorleyParsons 2012).

Introduce Contaminants from Shipping Vessels or Rail Transport

Coal would be transported to the terminal via rail, then loaded onto vessels and transported as directed by the purchasers or owners of the coal to its final destination overseas. Water quality could be indirectly affected as a result of transportation of coal within the study area. These impacts are summarized below. Details regarding an operations oil spill while vessels are at dock and bunkering or as a result of a vessel collision are available in the NEPA Vessel Transportation Technical Report (ICF International 2016a). Details regarding a release of hazardous materials during rail operations and accidental collision or derailment are discussed in the Hazardous Materials Technical Report (ICF International 2016e).

- **Propeller wash.** Vessels produce propeller wash, which is the continuous current of fast-moving water generated by a ship's propeller. The propeller wash increases the potential for scour and erosion of the dredged slopes and bottom of the navigation channel, and result in temporary, localized increases in turbidity. The On-Site Alternative would result in increased vessel and increased propeller wash, and in impacts on erosion and turbidity,

particularly from pilot vessels maneuvering near Docks 2 and 3. Cargo vessels are more likely to create turbulence that can erode bottom sediments because the large propellers on these ships are closer to the seafloor as they travel through the Columbia River. The propeller wash from tugboats is nearer the surface so it has less of an erosion effect on bottom sediments. The likelihood of temporary, localized increases in turbidity resulting from propeller wash is considered low based on the magnitude of dredging that would result from the On-Site Alternative. Furthermore, the dredge prism would tie into the navigation channel, thus reducing the potential for propeller wash during vessel movements at Docks 2 and 3. Vessels calling at Docks 2 and 3 would have sufficient depth to minimize the potential for propeller wash. Any increase in turbidity would be temporary, localized, and not expected to be measureable beyond the study area.

- **Ballast water.** Vessels would be expected to discharge ballast water during the loading process to compensate for the cargo being loaded. Ballast water discharges can often contain materials that can harm surface waters. Common contaminants include invasive marine plants and animals, bacteria, and pathogens that can harm or displace native aquatic species. This contaminated water would then be discharged into the Columbia River during coal loading, where it could degrade water quality and harm aquatic organisms. On vessels with segregated ballast tanks, ballast water is kept completely separate from cargo.

While these situations could affect water quality in the Columbia River, the likelihood of such occurrences is considered low. Federal and state regulations protect against the threat of contaminated ballast water and the introduction of exotic species via ballast water (RCW 77.120). Oversight of federal ballast water regulations is provided by the U.S. Coast Guard and the EPA, while Washington State regulations are administered by the Washington Department of Fish and Wildlife. Discharge of ballast water into waters of the state is not allowed unless there has been an open sea exchange (replacing coastal water with open-ocean water to reduce the density of coastal organisms) or the vessel has treated its ballast water to meet state and federal standards set by the U.S. Coast Guard (33 USC 1251–1387). Table 8 identifies the U.S. Coast Guard ballast water treatment standards.

Table 8. U.S. Coast Guard Ballast Water Treatment Standards

Organism Size Class	Biological Discharge Standards
Organisms greater than 50 µm in minimum dimension	< 10 viable organisms/cubic meter
Organisms less than 50 µm and greater than or equal to 10 µm in minimum dimension	< 10 viable organisms/mL
Indicator organisms must not exceed:	
• Toxicogenic <i>Vibrio cholera</i> (Serotypes 01 and 0139):	< 1 cfu/100 mL or <1 cfu/gram wet weight zoo plankton samples
• <i>Escherichia coli</i> :	< 250 cfu/100 mL
• Intestinal enterococci:	< 100 cfu/100 mL
Source: Grette Associates 2014f	
µm = micrometer; mL = milliliter; cfu = colony-forming unit	

In addition, the U.S. Coast Guard sets forth its reporting and recordkeeping requirements in 33 USC 151.2060 and 151.2070 which include the maintenance of written records for 2 years and available upon request.

- **Spills from vessels.** Coal and fuel spills could occur if the cargo tanks on a vessel are ruptured during such events as a grounding or collision. A grounding is when the vessel makes contact with a seabed or channel bottom. The potential for a vessel rupture incident is low. The NEPA Vessel Transportation Technical Report (ICF International 2016a) evaluates the risk of vessel-related incidents. The NEPA Hazardous Materials Technical Report (ICF International 2016e) discusses actions to be taken for emergency response and cleanup. A spill from a vessel could have substantial impacts on water quality based on the location, quantity, and response actions taken.
- **Day-to-day rail operations.** Day-to-day rail operations could release contaminants to stormwater, including coal dust, metals, hydraulic and brake fluid, oil, and grease from track lubrication. If a release of hazardous materials were to occur, the rail operator would implement emergency response and cleanup actions per Federal Railroad Administration requirements and state law, including Washington State regulations under Revised Code of Washington (RCW) 90.56.
- **Spill from train collision or derailment.** Fuel or hazardous material spills could occur if trains or rail cars collide or derail. As discussed in the NEPA Hazardous Materials Technical Report (ICF International 2016e), if a release of hazardous materials were to occur, the rail operator would implement emergency response and cleanup actions as required by the Federal Railroad Administration requirements and state law, including Washington State regulations under RCW 90.56. The NEPA Hazardous Materials Technical Report (ICF International 2016e) also discusses actions to be taken for emergency response and cleanup. Spills of coal from a rail car could affect water quality based on the location, quantity spilled, and response actions taken. While temporary degradation of water quality conditions could result from a spill or release of hazardous materials, it would be expected that cleanup actions would reduce the magnitude of the spill such that no long-term degradation of water quality conditions persisted.

3.2 Off-Site Alternative

Potential impacts on water quality from the Off-Site Alternative are described below.

3.2.1 Construction: Direct Impacts

Construction of the Off-Site Alternative would result in the following direct impacts.

Required features and construction plans for the Off-Site Alternative would be similar to the On-Site Alternative. Therefore, the impacts would be similar to those described for the On-Site Alternative. Substantial differences are identified where applicable.

Increase Surface Water Turbidity Because of Soil Disturbance

The Off-Site Alternative would disturb a smaller area of soil than the On-Site Alternative. The smaller area would result in lower volumes of sediment potentially being mobilized and discharged to surface waters. Like the On-Site Alternative, this potential impact would be temporary and last only for the duration of construction.

Introduce Pollutants Associated with Equipment and Material Use

Impacts on water quality associated with equipment and material use would be similar to the On-Site Alternative. Runoff from the project area during construction would be required to meet the terms and conditions of all permits issued for the Off-Site Alternative; thus, water quality conditions would be expected to be maintained and temporary release of contaminants associated with equipment and material use during construction is not be expected to cause a measurable effect on water quality or affect designated beneficial uses.

Mobilize Pollutants or Increase Turbidity from In-Water Work and Dredging

The Off-Site Alternative would involve dredging an estimated 50,000 cubic yards of material from the Columbia River compared to the 500,000 cubic yards for the On-Site Alternative. This smaller volume of dredged material would likely require less dredging time, resulting in a shorter period of temporary impact to water quality compared to the On-Site Alternative.

Introduce Hazardous or Toxic Materials from Demolition Activities

Current land use at the Off-Site Alternative location is substantially different and the potential for pollution related to demolition would not be the same as the On-Site Alternative. The Off-Site Alternative is primarily vegetated and does not have an existing facility to be demolished in the study area like the On-Site Alternative. Further, no existing hazardous or toxic materials are known to occur at the Off-Site Alternative. Therefore, this potential impact is not anticipated to occur to the extent that it could at the On-Site Alternative.

3.2.2 Construction: Indirect Impacts

Construction of the Off-Site Alternative would not result in indirect impacts on water quality because construction impacts are immediate and no construction impacts would occur later in time or farther removed in distance than the direct impacts.

3.2.3 Operations: Direct Impacts

Direct operations impacts on water quality associated with introduction of contaminants from coal spills and coal dust, maintenance and operations, and stormwater runoff would be similar to the impacts described for the On-Site Alternative. Contaminants in stormwater runoff could reach surface waters and degrade water quality. However, stormwater would be managed in accordance with the requirements of a new NPDES Industrial Stormwater Permit obtained for water management facilities of the proposed export terminal to ensure water quality standards are met prior to discharge to any surface water.

3.2.4 Operations: Indirect Impacts

Indirect operations impacts on water quality associated with introduction of contaminants from coal spills and coal dust, maintenance and operations, and shipping vessels or rail transport would be similar to the impacts described for the On-Site Alternative.

Coal dust is anticipated to deposit a maximum of 1.83 grams per square meter per year (g/m²/year) within the direct and indirect impact study areas, including the Columbia River within the study areas. Coal dust from operations of the terminal is not expected to have a measureable effect on

water quality. Additionally, the potential risk for exposure to toxic chemicals contained in coal (e.g., PAHs and trace metals) would be relatively low as these chemicals tend to be bound in the matrix structure and are not quickly or easily leached.

A contaminant spill during maintenance and operations could potentially reach a surface water. However, inadvertent spills in the project area would be contained, conveyed and treated within the proposed stormwater system and not be discharged to surface waters outside the project area. Maintenance dredging impacts on water quality would be similar to those discussed for the On-Site Alternative.

Potential contaminant spills, propwash impacts, and ballast impacts related to shipping vessels and rail transport would be short-term and temporary and would be minimized through the appropriate state and federal regulations specific to each of these potential impacts.

3.3 No-Action Alternative

Under the No-Action Alternative, the Applicant would not construct the proposed export terminal and impacts on water quality related to the On-Site Alternative and Off-Site Alternative would not occur. The Applicant would continue with current and future operations in the On-Site Alternative project area. If existing industrial import and export activities located adjacent to the On-Site Alternative project area expanded, impacts on water quality could be similar to those described for the On-Site Alternative with respect to potential oil and grease spills from equipment or other raw materials shipped from the terminal. The existing NPDES permit would remain in place, maintaining the water quality of existing stormwater discharges. Maintenance dredging at Dock 1 would likely continue, with dredging occurring every 2 to 3 years. Any new or expanded industrial uses would likely trigger a new or modified NPDES permit. Upland buildings could be demolished and replaced for new industrial uses. Ground disturbance would not result in any impacts on waters of the United States and would not require a permit from the Corps. Any new impervious surface area would generate stormwater, but all stormwater would be collected and treated to meet state and federal water quality requirements prior to discharge to the Columbia River.

If the Off-Site Alternative were developed in the future for industrial uses the potential water quality impacts would be similar to the impacts described for the Off-Site Alternative.

Chapter 4

Required Permits

The On-Site Alternative or Off-Site Alternative would require compliance with the following permits related to water quality.

- **NPDES Construction General Permit.** The construction of the On-Site Alternative would result in an area of ground disturbance greater than 1 acre and would require a construction general permit. This permit is administered by the Washington State Department of Ecology.
- **NPDES Industrial Stormwater Permit.** The On-Site Alternative would result in industrial activities such as the operation of transportation facility or bulk station and terminal and would require an industrial stormwater permit. This permit is administered by the Washington State Department of Ecology.
- **Clean Water Act Section 404—U.S. Army Corps of Engineers.** Construction of the proposed terminal requires Department of the Army authorization from the Corps under Section 404 of the Clean Water Act.
- **Clean Water Act Section 401—Washington State Department of Ecology.** An Individual Water Quality Certification from Ecology under Section 401 of the Clean Water Act and a NPDES permit under Section 402 of the Clean Water Act would also be required for construction of the On-Site Alternative.
- **Rivers and Harbors Act—U.S. Army Corps of Engineers.** Construction of the proposed terminal requires Department of the Army authorization from the Corps under Section 10 of the Rivers and Harbors Act. The Rivers and Harbors Act authorizes the Corps to protect commerce in navigable streams and waterways of the United States by regulating various activities in such waters. Section 10 of the act (33 USC 403) specifically regulates construction, excavation, or deposition of materials into, over, or under navigable waters, or any work that would affect the course, location, condition, or capacity of those waters.
- **Hydraulic Project Approval—Washington Department of Fish and Wildlife.** The On-Site Alternative would require a Hydraulic Project Approval from the Washington Department of Fish and Wildlife. The approval would consider impacts on riparian and shoreline/bank vegetation in issuance and conditions of the permit, including for the installation of the proposed docks and piles, as well as for project-related dredging activities and other project-related in-water work.

The Applicant identified the following measures to be implemented during construction and/or operation. These measures are assumed conditions or requirements of permits identified above that would be required for the project, and thus are described here. These measures were considered when evaluated the potential impacts of the On-Site Alternative.

- Stormwater, sediment, and erosion control BMPs would be installed in accordance with the *Stormwater Management Manual for Western Washington and Cowlitz County*. Water quality management would be performed in accordance with the requirements of the NPDES Industrial Stormwater General Permit. The site's SWPPP will provide details of the site best management practices.

- Drainage systems would be designed such that runoff within the construction site would be collected and treated as necessary before reuse or discharge.
- The treatment facility could treat surface runoff and process/construction waters with capacity to store the water for reuse.
- Water quality management would be performed in accordance with the requirements of the NPDES Industrial Stormwater General Permit. The stormwater pollution prevention plan will provide details of the project area BMPs.
- Construction would be performed in accordance with the requirements of the NPDES Construction Stormwater General Permit
- Drainage systems would be designed such that runoff in the construction site would be collected and treated as necessary, before reuse or discharge.
- The treatment facility could treat surface runoff and process/construction waters with capacity to store the water for reuse.
- Treatment may be as required to meet reuse quality or Ecology requirements for offsite discharge.
- BMP C153: Material Delivery, Storage, and Containment—would be used to prevent, reduce, or eliminate the discharge of pollutants to the stormwater system or watercourses from material delivery and storage.
 - Storage of hazardous materials onsite would be minimized to the extent feasible.
 - Materials would be stored in a designated area, and secondary containment would be installed where needed.
 - Refueling would occur in designated areas with appropriate spill control measures.
 - Typical construction BMPs for working over, in, and near water would be applied, including checking equipment for leaks and other problems that could result in discharge of petroleum-based products, hydraulic fluid, or other material to the Columbia River.
- BMP C154: Concrete Washout Area—Concrete waste and washout waters would be either carried out off site or disposed of in a designated facility on site designed to contain the waste and washout water.
- Based on site grading and drainage areas, five water quality ponds (wetponds) would treat runoff based on Ecology requirements. In general, the ponds are sized for treatment of the volume and flow from the water quality design storm event (72% of the 2-year storm). Additional storage would be provided in the coal storage area so that the runoff is always treated within the stockyard area, even for larger storm events. The ponds are designed to provide settlement as the water passes through. Subsequently, water released from these ponds would be conveyed downstream to the existing pump station outfall 002A that discharges into the Columbia River via an existing 30-inch steel pressure line. The ponds that treat runoff from the coal stockyard would harvest water for circulation around the site for multiple uses, including dust control measures. The Ecology criteria would be used as the basis of design, which uses the Western Washington Hydrology Model computer simulation for facility sizing. Because of the flat nature of the site, some surface ponding would occur in both the yard areas and open conveyance systems. The piped conveyance systems would be sloped at .50% minimum.

- The surface drainage system and features would be designed and constructed in accordance with the *Stormwater Management Manual for Western Washington*.
- The water treatment facility would be designed to treat all surface runoff and process water with capacity to store the water for reuse. Treatment would be as required to meet reuse quality or Ecology requirements for offsite discharge.
- Additional water storage would be provided within the coal storage area in the event of a larger storm event. Water volumes exceeding the demands for reuse would be discharged offsite via the existing outfall 002A into the Columbia River. Water released offsite would be treated and would meet the requirements of Ecology and required discharge permits.
- The water system would be designed and constructed in accordance with or consideration of the latest edition of the following standards, where applicable. In the event of conflict between codes and technical specification, the requirements would be reviewed and a decision made on the action to be implemented with agency of jurisdiction.
 - International Building Code
 - National Fire Protection Association
 - Washington State Department of Ecology *Stormwater Design Manual*
 - U.S. Department of Health, Occupational Safety and Health Standards
 - Washington State Department of Health
- Where possible, pile extraction equipment would be kept out of the water to avoid “pinching” pile below the water line in order to minimize creosote release during extraction
- During pile removal and pile driving, a containment boom would be placed around the perimeter of the work area to capture wood debris and other materials released into the waters as a result of construction activities. All accumulated debris would be collected and disposed of upland at an approved disposal site. Absorbent pads would be deployed should any sheen be observed.
- The work surface on barge deck or pier would include a containment basin for pile and any sediment removed during pulling. Any sediment collected in the containment basin would be disposed of at an appropriate upland facility, as would all components of the basin (e.g., straw bales, geotextile fabric) and all pile removed.
- Upon removal from substrate the pile would be moved expeditiously from the water into the containment basin. The pile would not be shaken, hosed off, stripped, scraped off, left hanging to drip or any other action intended to clean or remove adhering material from the pile.
- Project construction (including pile removal) would limit the impact of turbidity to a defined mixing zone and would otherwise comply with WAC 173-201A
- All dredged material would be contained within a barge prior to flow-lane disposal; dredged material would not be stockpiled on the riverbed.
- The contractor would remove any floating oil, sheen, or debris within the work area as necessary to prevent loss of materials from the site. The contractor would be responsible for retrieval of any floating oil, sheen, or debris from the work area and any damages resulting from the loss.
- Flow-lane disposal would occur using a bottom-dump barge or hopper dredge. These systems release material below the surface, minimizing surface turbidity.

- For work adjacent to water, proper erosion control measures would be installed prior to any clearing, grading, demolition, or construction activities to prevent the uncontrolled discharge of turbid water or sediments into waters of the state. Erosion control structures or devices would be regularly maintained and inspected to ensure their proper functioning throughout this project
- Project construction would be completed in compliance with Washington State Water Quality Standards WAC 173-201A, including but not limited to prohibitions on discharge of oil, fuel, or chemicals into state waters, property maintenance of equipment to prevent spills, and appropriate spill response including corrective actions and reporting as outlined in permits and authorizations (Corps permit, HPA, 401 Water Quality Certification).
- The contractor would have a spill containment kit, including oil-absorbent materials, on site to be used in the event of a spill or if any oil product is observed in the water.
- The contractor would be required to retrieve any floating debris generated during construction using a skiff and a net. Debris would be disposed of at an appropriate upland facility. If necessary, a floating boom would be installed to collect any floated debris generated during in-water operations.
- All fuel and chemicals would be kept, stored, handled, and used in a fashion that assures no opportunity for entry of such fuel and chemicals into the water.
- The contractor would use tarps or other containment methods when cutting, drilling, or performing over-water construction that might generate a discharge to prevent debris, sawdust, concrete and asphalt rubble, and other materials from entering the water.
- The water treatment facility would be designed to treat all surface runoff and process water with capacity to store the water for reuse. Treatment would be as required to meet reuse quality or Ecology requirements for offsite discharge.
- Up to five ponds would treat the runoff. In general, the ponds would be sized for the treatment of the volume and flow from the water quality design storm event (72% of the 2-year storm). The ponds would be designed to be long and narrow to provide sufficient settlement time to clarify the water as it passes through the pond. The ponds that treat runoff from the coal stockyard would harvest water via pump systems to supplement the water supply for dust control measures.
- Additional water storage would be provided within the materials storage area in the event of a larger storm event. Water volumes exceeding the demands for reuse would be discharged offsite treatment via the existing outfall 002A into the Columbia River. Water released offsite would be treated and would meet the requirements of Ecology and required discharge permits. Additional water storage would be provided within the materials storage area in the event of a larger storm event.
- No land-based construction equipment would enter any shoreline body of water except as authorized.
- Equipment would have properly functioning mufflers, engine-intake silencers, and engine closures according to federal standards; the contractor would inspect fuel hoses, oil or fuel transfer valves, and fittings on a regular basis for drips or leaks in order to prevent spills into the surface water.

5.1 Written References

- Agency for Toxic Substances and Disease Registry. 1992. *Toxicological profile for Vinyl Acetate*. Atlanta, GA: U.S. Department of Health and Human Services, Public Health Services.
- Ahrens, Michael J. and Donald J. Morrissey. 2005. Biological Effects on Unburnt Coal in the Marine Environment. *Oceanography and Marine Biology: An Annual Review*. 43: 69–122.
- Anchor QEA. 2011. *Engineering Report for NPDES Application Millennium Bulk Terminals*. Longview, WA. September 2011.
- Anchor QEA. 2014a. *Engineering Report Update for NPDES Application Millennium Bulk Terminals*. Longview, WA. Prepared for Millennium Bulk Terminals—Longview, LLC. Portland, OR. September 2011. July 2014.
- Anchor QEA. 2014b. Former Reynolds Metals Reduction Plant – Longview, Draft Remedial Investigation and Feasibility Study. June 2014. Prepared for Washington State Department of Ecology on behalf of Northwest Alloys, Inc. and Millennium Bulk Terminals – Longview, LLC. Anchor QEA, LLC, Seattle, Washington.
- Center for Coastal Margin Observation and Prediction. 2016. *Land/Ocean Biogeochemical Observatory*. Available: <http://columbia.loboviz.com/>.
- Ewing, Richard. 1999. *Diminishing Returns: Salmon Declines and Pesticides*. Available: <http://www.pcffa.org/salpest.pdf>. Accessed October 20, 2014.
- Fenn, Mark E., Jill S. Baron, Edith B. Allen, Heather M. Rueth, Koren R. Nydick, Linda Geiser, William D. Bowman et al. Ecological effects of nitrogen deposition in the western United States. *BioScience* 53, no. 4 (2003): 404-420.
- Grette Associates, LLC. 2014a. *Millennium Coal Export Terminal Longview, Washington: Permanent Impacts to Aquatic Habitat*. September 2014.
- Grette Associates, LLC. 2014b. *Millennium Coal Export Terminal Longview, Washington: Docks 2 and 3 and Associated Trestle Direct Effects of Construction*. September 2014.
- Grette Associates, LLC. 2014c. *Millennium Coal Export Terminal Longview, Washington: Bulk Product Terminal Wetland and Stormwater Ditch Delineation Report – Parcel 61953*. September 2014.
- Grette Associates, LLC. 2014d. *Millennium Coal Export Terminal Longview, Washington: Coal Export Terminal Wetland Impact Report – Parcel 619530400*. September 2014.
- Grette Associates. 2014e. *Millennium Coal Export Terminal: Docks 2 and 3 and Associated Trestle – Direct Effects of Construction. Appendix B: Recent Sediment Characterizations near Millennium Bulk Terminals – Longview*. September 2014. Prepared for Millennium Bulk Terminals – Longview, LLC. Grette Associates, LLC, Wenatchee, Washington.

- Grette Associates, LLC. 2014f. *Millennium Coal Export Terminal Longview, Washington: Docks 2 and 3 and Associated Trestle Indirect Effects of Structures and Site Operations*. September 2014.
- ICF International. 2016a. *Millennium Bulk Terminals —Longview, NEPA Environmental Impact Statement, NEPA Vessel Transportation Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016b. *Millennium Bulk Terminals —Longview, NEPA Environmental Impact Statement, NEPA Groundwater Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016c. *Millennium Bulk Terminals —Longview, NEPA Environmental Impact Statement, NEPA Vegetation Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016d. *Millennium Bulk Terminals —Longview, NEPA Environmental Impact Statement, NEPA Fish Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016e. *Millennium Bulk Terminals —Longview, NEPA Environmental Impact Statement, NEPA Hazardous Materials Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016f. *Millennium Bulk Terminals —Longview, NEPA Environmental Impact Statement, NEPA Rail Transportation Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- Jakimska, Anna. Piotr Konieczka, Krzysztof Skora, Jacek Nameiesnik. 2011. *Bioaccumulation of Metals in Tissues of Marine Animals, Part I: the Role and Impact of Heavy Metals on Organisms*. Polish Journal of Environmental Studies. Vol. 20, No. 5, pages 1117-1125. Available: <http://www.pjoes.com/pdf/20.5/pol.j.envIRON.stud.vol.20.no.5.1117-1125.pdf> Accessed: April 8, 2016.
- Lower Columbia Estuary Partnership 2015. *20 years of the Estuary Partnership: Did You Know?* Available: <http://www.estuarypartnership.org/20-years-estuary-partnership-did-you-know-toxics>.
- Maritime Connector. 2015. *Ship Sizes*. Available: <http://maritime-connector.com/wiki/ship-sizes/>. Accessed: February 12, 2015.
- Millennium Bulk Terminals Longview, LLC. 2013. *Millennium Coal Export Terminal Longview, Washington: Applicant's Purpose and Need Expanded Project Description Alternatives Considered*. Longview, WA. December 2013.
- National Marine Fisheries Service. 2011. *Columbia River Estuary ESA Recovery Module for Salmon and Steelhead*. Portland, Oregon. January 2011.
- Oberrecht, Kenn. 2014. *Effects of Pulp Mill Effluent*. Available: <http://www.oregon.gov/dsl/SSNERR/docs/EFS/EFS14pulpmill.pdf>
- Oregon Department of Environmental Quality. 2003. *Designated Beneficial Uses Mainstem Columbia River (340-41-0101)*.

- Oregon Department of Environmental Quality (OR DEQ). 2012. *Oregon's 2012 Integrated Report Assessment Database and 303(d) List*. Available: <http://www.deq.state.or.us/wq/assessment/rpt2012/search.asp>. Accessed: February 11, 2015.
- Oregon Department of Water Quality. 2012. *Water Quality Assessment – Oregon's 2010 Integrated Report Assessment Database and 303(d) List*. Submitted to EPA in May 2011. Approved by EPA on March 15, 2012. Available: <http://www.deq.state.or.us/wq/assessment/2010Report.htm>
- Oregon State Marine Board. 2012. *Best Management Practices (BMP) White Paper for Recreational Boating Facility Construction and Replacement*.
- Pierce, B.S., and Denne, K.O., eds., 2009. *The National Coal Resource Assessment Overview: U.S. Geological Survey Professional Paper 1625-F*, 402 p.
- URS Corporation. 2014. *Millennium Coal Export Terminal Longview, Washington. Affected Environment Analysis – Water Resources*. January 2014
- U. S. Environmental Protection Agency. 2007. *Chapter 6: West Coast National Estuary Program Coastal Condition, Lower Columbia River Estuary Partnership*. Available: http://water.epa.gov/type/oceb/nep/upload/2007_05_09_oceans_nepccr_pdf_nepccr_nepccr_west_partc.pdf
- U. S. Environmental Protection Agency. 2009. *Columbia River Basin: State of the River Report for Toxics*. Publication No. EPA 910-R-08-004. EPA Region 10.
- U. S. Environmental Protection Agency. 2014. *Water: Polluted Runoff, Agriculture*. Last revised: July 9, 2014. Available: <http://water.epa.gov/polwaste/nps/agriculture.cfm>. Accessed: February 10, 2015.
- U.S. Geological Survey. 2005. *Water-Quality Data, Columbia River Estuary, 2004-05*. Available: <http://pubs.usgs.gov/ds/2006/213/#download>
- U.S. Geological Survey. 2007. *Coal Quality and Major, Minor, and Trace Elements in the Powder River, Green River, and Williston Basins, Wyoming and North Dakota*. Virginia. 2007-1116.
- U.S. Geological Survey. 2014. *USGS 14246900 Columbia River at Beaver Army Terminal near Quincy, OR*. Available: <http://wdr.water.usgs.gov/wy2013/pdfs/14246900.2013.pdf?1423677243767>.
- U.S. Geological Survey. 2015. *National Water Information System: USGS 14246900 Columbia River @ Beaver Army Terminal NR Quincy, OR*. Last Revised: February 11, 2015. Available: http://waterdata.usgs.gov/nwis/inventory/?site_no=14246900&agency_cd=USGS. Accessed February 11, 2015.
- Washington State Department of Ecology. 2012. *Water Quality Standards for Surface Waters of the State of Washington*. Chapter 173-201A WAC. Revised January 2012. Publication No. 06-10-091. Olympia, WA.
- Washington State Department of Ecology. 2014a. *2012 Stormwater Management Manual for Western Washington*, as Amended in December 2014. Publication No. 14-10-055. Olympia, WA.
- Washington State Department of Ecology. 2014b. *Washington State Wetland Rating System for Western Washington*. 2014 Update. Publication No. 14-06-029. Olympia, WA.

- Washington State Department of Ecology. 2016a. *Columbia River Facts and Maps*. Available: <http://www.ecy.wa.gov/programs/wr/cwp/cwpfactmap.html>. Accessed: April 6, 2016.
- Washington State Department of Ecology. 2016b. 2012 *Washington State Water Quality Assessment and 303(d) List of Impaired Waters*. Available: <http://www.ecy.wa.gov/programs/wq/303d/currentassessmt.html>. Accessed September 1, 2016.
- Washington Department of Natural Resources. 2008. *Creosote Cleanup of Puget Sounds and its Beach*. Sedro-Woolley, WA.
- Weyerhaeuser 2014. NPDES Permit 0000124
- WorleyParsons. 2012. Millennium Bulk Terminals, Longview, LLC. *Hydrodynamic Modeling and Sediment Transport Analysis*.

MILLENNIUM BULK TERMINALS—LONGVIEW NEPA ENVIRONMENTAL IMPACT STATEMENT

NEPA VEGETATION TECHNICAL REPORT

PREPARED FOR:

U.S. Army Corps of Engineers, Seattle District
4735 East Marginal Way South
Seattle, WA 98134

PREPARED BY:

ICF International
710 Second Avenue, Suite 550
Seattle, Washington 98104

September 2016



ICF International. 2016. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Vegetation Technical Report*. September. (ICF 00264.13)
Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.

Contents

List of Tables	iii
List of Figures.....	iv
List of Acronyms and Abbreviations.....	v
Chapter 1 Introduction	1-1
1.1 Project Description	1-1
1.1.1 On-Site Alternative	1-1
1.1.2 Off-Site Alternative	1-4
1.1.3 No-Action Alternative	1-6
1.2 Regulatory Setting.....	1-6
1.3 Study Areas	1-8
1.3.1 On-Site Alternative	1-8
1.3.2 Off-Site Alternative	1-9
Chapter 2 Affected Environment.....	2-1
2.1 Methods.....	2-1
2.1.1 Data Sources	2-1
2.1.2 Vegetation Cover Type Mapping	2-2
2.1.3 Impact Analysis	2-3
2.2 Affected Environment.....	2-3
2.2.1 Regional Context.....	2-3
2.2.2 On-Site Alternative Study Area	2-14
2.2.3 Off-Site Alternative Study Area.....	2-29
Chapter 3 Impacts	3-1
3.1 On-Site Alternative	3-1
3.1.1 Construction: Direct Impacts	3-1
3.1.2 Construction: Indirect Impacts	3-4
3.1.3 Operations: Direct Impacts	3-4
3.1.4 Operations: Indirect Impacts	3-8
3.2 Off-Site Alternative	3-10
3.2.1 Construction: Direct Impacts	3-10
3.2.2 Construction: Indirect Impacts	3-12
3.2.3 Operations: Direct Impacts	3-13
3.2.4 Operations: Indirect Impacts	3-15
3.3 No-Action Alternative	3-16

Chapter 4 Required Permits	4-1
Chapter 5 References	5-1

Appendix A	Descriptions of Special-Status Plant Species with Potential to Occur in the Project Areas
Appendix B	State Noxious Weed List
Appendix C	Cowlitz County Noxious Weed List
Appendix D	Descriptions of Noxious Weeds with Potential to Occur in the Project Areas
Appendix E	Site Photographs

Tables

1	Regulations, Statutes, and Guidance for Vegetation	1-7
2	List of Known Occurrences of Threatened, Endangered, Sensitive, and Rare Plants in Cowlitz County, Washington	2-5
3	Elevation, Habitat, and Geographic Range of Listed Threatened, Endangered, Sensitive, and Rare Plants in Cowlitz County, Washington	2-6
4	Washington State Noxious Weed Classification.....	2-10
5	Wetlands Identified in the Direct Impact Study - On-Site Alternative	2-21
6	Land Cover in the Indirect Impact Study Area – On-Site Alternative	2-24
7	Noxious Weeds Identified in the Project Area	2-27
8	Wetlands Identified in the Project Area—Off-Site Alternative	2-34
9	Land Cover in the Indirect Impact Study Area – Off-Site Alternative	2-36
10	Noxious Weeds Identified in the Project Area—Off-Site Alternative	2-39
11	Permanent Direct Impacts by Land Cover and Vegetation Cover Type in the Project Area	3-3
12	Permanent Direct Impacts by Land Cover and Vegetation Cover Type in the Project Area—Off-Site Alternative	3-12

Figures

1	Project Vicinity.....	1-2
2	On-Site Alternative	1-3
3	Off-Site Alternative.....	1-5
4	Vegetation Study Area for the On-Site Alternative.....	1-10
5	Vegetation Study Area for the Off-Site Alternative	1-11
6	Features in the Project Area for the On-Site Alternative	2-16
7	Existing Land Cover Classes and Vegetation Cover Types in the Direct Impact Study Area – On-Site Alternative.....	2-19
8	Existing Wetlands in the Direct Impact Study Area - On-Site Alternative.....	2-22
9	Features in the Project Area – Off-Site Alternative.....	2-30
10	Existing Land Cover Classes and Vegetation Cover Types in the Direct Impact Study Area – Off-Site Alternative	2-32
11	Existing Wetlands in the Direct Impact Study Area – Off-Site Alternative.....	2-35
12	Impacts on Existing Land Cover Classes and Vegetation Cover Types in the Direct Impact Study Area – On-Site Alternative	3-2
13	Impacts on Existing Land Cover Classes and Vegetation Cover Types in the Direct Impact Study Area – Off-Site Alternative	3-11

Acronyms and Abbreviations

Applicant	Millennium Bulk Terminals—Longview, LLC
BMPs	best management practices
BNSF	BNSF Railway Company
BPA	Bonneville Power Administration
CDID	Consolidated Diking Improvement District
CFR	Code of Federal Regulations
Corps	U.S. Army Corps of Engineers
CRD	Columbia River Datum
Ecology	Washington State Department of Ecology
g/m ² /year	grams per square meter per year
HGM	hydrogeomorphic code
IPaC	Information, Planning, and Conservation
NEPA	National Environmental Policy Act
OHWM	ordinary high water mark
OW	open water
PEM	palustrine emergent
PFO	palustrine forested
PSS	palustrine scrub-shrub
RCW	Revised Code of Washington
Reynolds facility	Reynolds Metals Company facility
SEPA	Washington State Environmental Policy Act
U	upland
USC	United States Code
USFWS	U.S. Fish and Wildlife Service
W	wetland
WAC	Washington Administrative Code
WDFW	Washington Department of Fish and Wildlife
WDNR	Washington Department of Natural Resources

This technical report assesses the potential vegetation impacts of the proposed Millennium Bulk Terminals—Longview project (On-Site Alternative), Off-Site Alternative, and No-Action Alternative. For the purposes of this assessment, vegetation refers to vascular plants¹ growing in upland and wetland areas; it does not include mosses, liverworts, or algae or vegetation growing submerged in the water (aquatic vegetation). This report describes the regulatory setting, establishes the method for assessing potential vegetation impacts, presents the historical and current vegetation conditions in the study areas, and assesses the potential for impacts on vegetation.

Both upland and wetland vegetation are described in this technical report; however, wetlands as a specific resource are also discussed in the multiple wetland delineation reports prepared by Grette Associates.

1.1 Project Description

Millennium Bulk Terminals—Longview, LLC (Applicant) proposes to construct and operate an export terminal in Cowlitz County, Washington, along the Columbia River (Figure 1). The export terminal would receive coal from the Powder River Basin in Montana and Wyoming and the Uinta Basin in Utah and Colorado via rail shipment, then load and transport the coal by ocean-going ships via the Columbia River and Pacific Ocean to overseas markets in Asia. The export terminal would be capable of receiving, stockpiling, blending, and loading coal by conveyor onto ships for export. Construction of the export terminal would begin in 2018. For the purpose of this analysis, it is assumed the export terminal would operate at full capacity by 2028. The following subsections present a summary of the On-Site Alternative, Off-Site Alternative, and No-Action Alternative.

1.1.1 On-Site Alternative

Under the On-Site Alternative, the Applicant would develop an export terminal on 190 acres (project area). The project area is located within an existing 540-acre area currently leased by the Applicant at the former Reynolds Metals Company facility (Reynolds facility), and land currently owned by Bonneville Power Administration. The project area is adjacent to the Columbia River in unincorporated Cowlitz County, Washington near Longview city limits (Figure 2).

The Applicant currently and separately operates at the Reynolds facility, and would continue to separately operate a bulk product terminal on land leased by the Applicant. Industrial Way (State Route 432) provides vehicular access to the Applicant's leased land. The Reynolds Lead and the BNSF Spur rail lines, both operated by Longview Switching Company (LVSW),² provide rail access to the Applicant's leased area from the BNSF Railway Company (BNSF) main line (Longview Junction) located to the east in Kelso, Washington. Ships access the Applicant's leased area including the bulk product terminal via the Columbia River and berth at an existing dock (Dock 1) operated by the Applicant in the Columbia River.

¹ Vascular plants include those plants that have tissues for conducting or transferring water and minerals throughout the plant.

² LVSW is jointly owned by BNSF Railway Company (BNSF) and Union Pacific Railroad (UP).



Figure 1. Project Vicinity

Figure 2. On-Site Alternative

Under the On-Site Alternative, BNSF or Union Pacific Railroad (UP) trains would transport coal in rail cars from the BNSF main line at Longview Junction to the project area via the BNSF Spur and Reynolds Lead. Coal would be unloaded from rail cars, stockpiled and blended, and loaded by conveyor onto ocean-going ships at two new docks (Docks 2 and 3) on the Columbia River for export to Asia.

Once construction is complete, the export terminal would have an annual throughput capacity of up to 44 million metric tons of coal.³ The export terminal would consist of one operating rail track, eight rail tracks for the storage of rail cars, rail car unloading facilities, stockpile areas for coal storage, conveyor and reclaiming facilities, two new docks in the Columbia River (Docks 2 and 3), and ship-loading facilities on the two docks. Dredging of the Columbia River would be required to provide access to and from the Columbia River navigation channel and for berthing at the two new docks.

Vehicles would access the project area from Industrial Way (State Route 432). Ships would access the project area via the Columbia River and berth at one of the two new docks. Trains would access the export terminal via the BNSF Spur and the Reynolds Lead. Terminal operations would occur 24 hours per day, 7 days per week. The export terminal would be designed for a minimum 30-year period of operation.

1.1.2 Off-Site Alternative

Under the Off-Site Alternative, the export terminal would be developed on an approximately 220-acre site adjacent to the Columbia River, located in both Longview, Washington, and unincorporated Cowlitz County, Washington, in an area commonly referred to as Barlow Point (Figure 3). The project area for the Off-Site Alternative is west and downstream of the project area for the On-Site Alternative. Most of the project area for the Off-Site Alternative is located within Longview city limits and owned by the Port of Longview. The remainder of the project area is within unincorporated Cowlitz County and privately owned.

Under the Off-Site Alternative, BNSF or UP trains would transport coal from the BNSF main line at Longview Junction over the BNSF Spur and the Reynolds Lead, which would be extended approximately 2,500 feet to the west. Coal would be unloaded from rail cars, stockpiled and blended, and loaded by conveyor onto ocean-going ships at two new docks (Docks A and B) on the Columbia River. The Off-Site Alternative would serve the same purpose as the On-Site Alternative.

Once construction is complete, the Off-Site Alternative would have an annual throughput capacity of up to 44 million metric tons of coal. The export terminal would consist of the same elements as the On-Site Alternative: one operating rail track, eight rail tracks for the storage of rail cars, rail car unloading facilities, stockpile areas for coal storage, conveyor and reclaiming facilities, two new docks in the Columbia River (Docks A and B), and ship-loading facilities on the two docks. Dredging of the Columbia River would be required to provide access to and from the Columbia River navigation channel and for berthing at the two new docks.

³ A metric ton is the U.S. equivalent to a tonne per the International System of Units, or 1,000 kilograms or approximately 2,204.6 pounds.

Figure 3. Off-Site Alternative

Vehicles would access the project area via a new access road extending from Mount Solo Road (State Route 432) to the project area. Trains would access the terminal via the BNSF Spur and the extended Reynolds Lead. Ships would access the project area via the Columbia River and berth at one of the two new docks. Terminal operations would occur 24 hours per day, 7 days per week. The export terminal would be designed for a minimum 30-year period of operation.

1.1.3 No-Action Alternative

Under the No-Action Alternative, the U.S. Army Corps of Engineers would not issue the requested Department of the Army permit under the Clean Water Act Section 404 and the Rivers and Harbors Act Section 10. This permit is necessary to allow the Applicant to construct and operate the proposed export terminal.

The Applicant plans to continue operating its existing bulk product terminal located adjacent to the On-Site Alternative project area, as well as expand this business whether or not a Department of the Army permit is issued. Ongoing operations would include storing and transporting alumina and small quantities of coal, and continued use of Dock 1. Maintenance of the existing bulk product terminal would continue, including maintenance dredging at the existing dock every 2 to 3 years. Under the terms of an existing lease, expanded operations could include increased storage and upland transfer of bulk products utilizing new and existing buildings. The Applicant would likely undertake demolition, construction, and other related activities to develop expanded bulk product terminal facilities.

In addition to the current and planned activities, if the requested permit is not issued, the Applicant would intend to expand its bulk product terminal business onto areas that would have been subject to construction and operation of the proposed export terminal. In 2014, the Applicant described a future expansion scenario under No-Action Alternative that would involve handling bulk materials already permitted for off-loading at Dock 1. Additional bulk product transfer activities could involve products such as a calcine pet coke, coal tar pitch, cement, fly ash, and sand or gravel. While future expansion of the Applicant's bulk product terminal business might not be limited to this scenario, it was analyzed to help provide context to a No-Action Alternative evaluation and because it is a reasonably foreseeable consequence of a Department of the Army denial.

1.2 Regulatory Setting

Vegetation in general is not a regulated feature of the environment. However, impacts on certain vegetation types or communities are addressed as a component of other regulations, statutes, or guidance focused on a regulated feature (e.g., wetlands), a component of habitat for wildlife, or an environmental element of concern (e.g., noxious weeds). See the NEPA Wildlife Technical Report (ICF International 2016b) and reports prepared by the Applicant (Section 2.1.1, *Data Sources*) for further information. In addition, federally listed endangered or threatened species of plants are regulated under the Endangered Species Act, and some species or vegetation communities are protected at a local or state level. For example, the presence of certain types of wetland vegetation (e.g., old growth forest, estuarine wetlands, bogs) can change the regulatory classification of a wetland. Similarly, some jurisdictions have provisions in their critical areas or land development codes that regulate impacts on significant trees (e.g., native coniferous species over a particular size threshold) and on vegetation located within a stream or wetland buffer.

The jurisdictional authorities and corresponding regulations, statutes, and guidance for determining potential impacts on vegetation are summarized in Table 1.

Table 1. Regulations, Statutes, and Guidance for Vegetation

Regulation, Statute, Guidance	Description
Federal	
National Environmental Policy Act (42 USC 4321 <i>et seq.</i>)	Requires the consideration of potential environmental effects. NEPA implementation procedures are set forth in the President's Council on Environmental Quality's Regulations for Implementing NEPA (49 CFR 1105).
U.S. Army Corps of Engineers NEPA Environmental Regulations (33 CFR 230)	Provides guidance for implementing the procedural provisions of NEPA for the Corps. It supplements Council on Environmental Quality regulations (40 CFR 1500–1508).
Clean Water Act (33 USC 1251 <i>et seq.</i>)	Section 404 regulates discharges into waters of the United States and special aquatic sites, such as wetlands. Also regulates impacts on other vegetated areas such as shoreline vegetation at and below ordinary high water, and vegetated shallows waterward of the shoreline along the Columbia River.
Endangered Species Act	The federal Endangered Species Act of 1973, as amended provides for the conservation of species that are listed and threatened and endangered and the habitat upon which they depend. Section 7 of the federal Endangered Species Act requires that federal agencies initiate consultation with the USFWS and/or NMFS. This will ensure the federal action is not likely to jeopardize the continued existence of any listed threatened or endangered species or result in the destruction or adverse modification of designated critical habitat.
State	
Washington State Environmental Policy Act (WAC 197-11, RCW 43.21C)	Requires state and local agencies in Washington to identify potential environmental impacts that could result from governmental decisions.
Washington State Growth Management Act (RCW 36.70A)	Defines a variety of critical areas, which are designated and regulated at the local level under city and county critical areas ordinances.
Water Quality Standard for Surface Waters of the State of Washington (WAC 173-201A)	Establishes water quality standards for surface waters of Washington State. Washington State Department of Ecology is the responsible agency.
Washington State Shoreline Management Act (90.58 RCW)	Requires cities and counties (through their Shoreline Master Programs) to protect shoreline natural resources against adverse impacts.
Washington Water Pollution Control Act (RCW90.48)	Sets the highest possible water quality standards to ensure purity of waters of the state consistent with public health and public enjoyment, propagation and protection of wildlife, and industrial development of the state.

Regulation, Statute, Guidance	Description
Washington Natural Resource Damage Assessment (RCW 90.56.370)	Establishes liability for damages related to injuries to public resources resulting from oil spills in state waters.
Washington State Noxious Weed Control Act (RCW 17.10, WAC 16-750)	Establishes Noxious Weed Control Boards, which designate certain plant species as Class A, B, or C noxious weeds and authorizes the management, control, and/or elimination of noxious weed populations in the state.
Hydraulic Project Approval (RCW 77.55, WAC 220-110)	Issued by the Washington Department of Fish and Wildlife for projects with elements that could affect the bed, bank, or flow of a water of the state or productive capacity of fish habitat. Considers effects on riparian and shoreline/bank vegetation in issuance and conditions of the permit, including for the installation of piers, docks, pilings, and bank armoring and crossings of streams and rivers (including culverts).
Local	
Cowlitz County SEPA Regulations (CCC Code 19.11)	Provide for the implementation of SEPA in Cowlitz County.
Cowlitz County Critical Areas Protection Ordinance (CCC 19.15)	Regulates activities within and adjacent to critical areas including vegetation occurring in wetlands and their buffers, fish and wildlife habitat conservation areas (including streams and their buffers), frequently flooded areas, and geological hazard areas.
City of Longview Critical Areas Ordinance (LMC 17.10.140)	Regulates activities within and adjacent to critical areas including vegetation occurring in wetlands and their buffers, fish and wildlife habitat conservation areas (including streams and their buffers), frequently flooded areas, and geological hazard areas.
USC = United States Code; NEPA = National Environmental Policy Act; CFR = Code of Federal Regulations; Corps = U.S. Army Corps of Engineers; WAC = Washington Administrative Code; RCW = Revised Code of Washington; CCC = Cowlitz County Code; LNC = Longview Municipal Code	

1.3 Study Areas

The study areas for the On-Site Alternative and Off-Site Alternative are described below.

1.3.1 On-Site Alternative

The study area for direct impacts on vegetation is defined as the 212-acre project area. The study area for indirect impacts on vegetation is defined as the project area, surrounding areas up to 1 mile from the project area, and the Lower Columbia River from the project area to the mouth of the river. The broader 1-mile study area considers the extent to which potential coal dust deposition could affect vegetation during operations (Figure 4). The Lower Columbia River study area was established to evaluate the potential impacts that could occur to shoreline vegetation as a result of project related vessels transiting the Columbia River, from the project area downstream to the mouth of the Columbia River. Wetland vegetation is also covered in this tech report; however, wetlands as a specific resource are also discussed in more detail in the multiple wetland delineation reports prepared by Grette Associates.


The direct impact study area for wetlands is the same as described for overall vegetation, but the wetland indirect impact study area is limited to those wetlands that extend outside of the direct impact study area and are partially affected by the On-Site Alternative because of ongoing effects after construction.

1.3.2 Off-Site Alternative

The study area for direct impacts on vegetation is defined as the 225-acre project area. The study area for indirect impacts is defined as the project area, surrounding areas up to 1 miles from the project area, and the Lower Columbia River from the project area to the mouth of the river (Figure 5). The broader 1-mile study area considers the extent to which potential coal dust deposition could affect vegetation during operations. The Lower Columbia River study area was also established to evaluate the potential impacts that could occur to shoreline vegetation as a result of project related vessels transiting the Columbia River, from the project area downstream to the mouth of the Columbia River. Wetland vegetation is also covered in this tech report; however, wetlands as a specific resource are also discussed in more detail in the multiple wetland delineation reports prepared by Grette Associates.

The direct impact study area for wetlands is the same as described for overall vegetation, but the wetland indirect impact study area is limited to those wetlands that extend outside of the direct impact study area and are partially affected by the Off-Site Alternative because of ongoing effects after construction.

Figure 4. Vegetation Study Area for the On-Site Alternative

Figure 5. Vegetation Study Area for the Off-Site Alternative

Chapter 2

Affected Environment

This chapter explains the methods for assessing the affected environment and determining impacts, and describes the affected environment in the study areas as it pertains to vegetation.

2.1 Methods

This section describes the sources of information and methods used to characterize the affected environment and assess the potential impacts of the On-Site Alternative, Off-Site Alternative, and No-Action Alternative on vegetation.

2.1.1 Data Sources

The following sources of information were used to evaluate the study areas.

- Two reconnaissance level site visits conducted by ICF International biologists on April 8 and December 11, 2014.
- A series of historical aerial photos from various years and months between 1994 and 2014 accessed through Google Earth Pro, a 2010 aerial photo provided by ESRI, and 2012 aerial photo from the North Agriculture Imagery Program.
- Reports prepared by Grette Associates and provided by the Applicant as part of the permit application materials.
 - *Coal Export Terminal Wetland and Stormwater Ditch Delineation Report–Parcel 619530400 and associated appendices including Appendix F: Noxious Weeds and Sensitive Plants* (Grette Associates 2014a)
 - *Bulk Product Terminal Shoreline Wetland Delineation Report–Parcel 61950* (Grette Associates 2014b)
 - *Bulk Product Terminal, Wetland and Stormwater Ditch Reconnaissance Report–Parcel 10213* (Grette Associates 2014c)
 - *Bulk Product Terminal Wetland and Stormwater Ditch Delineation Report–Parcel 61953* (Grette Associates 2014d)
 - *Affected Environment Biological Resources, Addendum Upland Habitat Survey–MBTL Lease Areas* (Grette Associates 2014e)
 - *Affected Environment Biological Resources Report* (Grette Associates 2014f)
 - *Off-Site Alternative–Barlow Point Upland Habitat Survey* (Grette Associates 2014g)
 - *Off-Site Alternative–Barlow Point Shoreline Habitat Inventory* (Grette Associates 2014h)
 - *Off-Site Alternative–Barlow Point Wetland Reconnaissance Report* (Grette Associates 2014i)

- The results of a January 30, 2015, U.S. Fish and Wildlife Service (USFWS) Information, Planning, and Conservation (IPaC) system online database search to determine federally listed endangered or threatened plant species under the jurisdiction of USFWS.
- 2011 National Land Cover Database (Homer et al. 2015) to describe land cover classes in the indirect study area.
- Washington Department of Fish and Wildlife (WDFW) Priority Habitat and Species spatial data provided by WDFW on May 5, 2014, for the 5-mile radius surrounding the project area.
- The Washington Department of Natural Resources (WDNR) Natural Heritage Program Information System (Washington Department of Natural Resources 2015) list of known occurrences of rare plants in Cowlitz County, Washington, and details regarding their occurrence, habitat, and range.
- A limited literature search for information relative to threatened and endangered species.
- Comments received from interested parties during the scoping period relative to vegetation and wildlife, as summarized in the Scoping Reports (ICF International 2014a, 2014b).
- Other literature, as cited in the text.

2.1.2 Vegetation Cover Type Mapping

Vegetation cover type mapping in the direct impact study area was accomplished by initially identifying the major land classification categories present using recent and historical aerial photographs, and the information gathered from the references cited in Section 2.1.1, *Data Sources*. Five categories were identified: developed lands, uplands, wetlands, and open water (Section 2.2.1.4, *Land Cover Classification and Vegetation Cover Types*). Each of these categories was further broken out into different cover types based on the dominant vegetation form (e.g., herbs, shrubs, trees) present. Preliminary boundaries of each cover type were sketched on a recent aerial photograph of the study areas using ArcGIS. Wetland cover types were mapped on the same aerial photo by overlaying the wetland boundaries previously identified (Grette Associates 2014a, b, c, d, i). Cover types in the direct impact study areas were organized and named using land cover classifications similar to those used in the National Land Cover Database (Multi-Resolution Land Characteristics Consortium 2011) and the USFWS *Classification of Wetlands and Deepwater Habitats of the United States* (Cowardin et al. 1979).

Mapped vegetation cover types across the majority of the direct impact study areas were ground-truthed by ICF biologists during reconnaissance-level site visits on April 8 and December 11, 2014. Visual observations of the vegetation present in adjacent areas and along Industrial Way, Mt. Solo Road, and Memorial Park Drive were made during the December 2014 site visit. Where necessary, cover type boundary mapping was adjusted based on field observations. The typical plant species observed in each cover type were recorded and compared with information on the historical vegetation of the Columbia River floodplain to gauge the level of disturbance present across the study areas and the potential to support native vegetation communities.

Land cover types in the indirect impact study area are described primarily based on the 2011 National Land Cover Database GIS data (Homer et al. 2015); land cover classifications described in this data consist of open water, developed, forest, shrub, herbaceous, barren land, agriculture (planted/cultivated and hay/pasture), and wetlands. Definitions of these land cover classifications can be found at Homer et al. (2015).

2.1.3 Impact Analysis

The following methods were used to evaluate potential impacts of the On-Site Alternative, Off-Site Alternative, and No-Action Alternative on vegetation. Direct impacts on vegetation from the clearing of land to construct the export terminal and associated infrastructure were determined by overlaying the direct impact study area on the vegetation cover type map. All cover types that fell within the direct impact study area were considered permanent impacts, because they would be removed during construction and replaced with gravel pads, stockpiles, railroad tracks, buildings, pavement, and other project features. Approximate acreage of each cover type that would be affected by these activities was calculated and expressed as a percentage of the total cover types affected within the study areas. Potential impacts on vegetation in the indirect impact study areas were qualitatively discussed by identifying the potential impact mechanism (i.e., how the impact would occur), describing the potential effects, and by assessing the likelihood of its occurrence after implementation of the proposed construction mitigation measures.

Direct and indirect impacts from operations were qualitatively described, including the impact mechanism, potential effects, duration (i.e., temporary or permanent), and likelihood of occurrence.

For the purposes of this analysis, construction impacts are based on peak construction period and operations impacts are based on maximum throughput capacity (up to 44 million metric tons per year).

2.2 Affected Environment

The affected environment related to vegetation in the study areas is described below.

2.2.1 Regional Context

This section provides general information on the historical vegetation known to be present in the region of the state, the special-status species known to occur in Cowlitz County, and the noxious weeds typically found in this area, and descriptions of the land cover classifications and vegetation cover types present in the project area.

2.2.1.1 Historical Vegetation

The project areas are located in the Western Hemlock (*Tsuga heterophylla*) Forested Zone of the Coast Range physiographic province (Franklin and Dyrness 1988:6, 44–45). The portion of this zone that contains the project areas is characterized by a wet, mild, maritime climate, with a mean average temperature of 46 to 48°F. Annual precipitation averages between 59 and 118 inches per year, with most of it falling in the fall and winter. Most of this zone was historically covered by coniferous forests dominated by Douglas-fir (*Pseudotsuga menziesii*), western hemlock, and western redcedar (*Thuja plicata*). While forests composed of these species are still the primary land cover, most of these areas have been logged or burned (or both) during the last 150 to 175 years (Franklin and Dyrness 1988:71) and many now exist as managed timberlands. Deciduous trees are relatively uncommon in these forests and occur primarily in disturbed area, riparian zones, and floodplains. Dominant trees in such areas commonly include black cottonwood (*Populus trichocarpa*), Oregon ash (*Fraxinus latifolia*), big-leaf maple (*Acer macrophyllum*), and red alder (*Alnus rubra*).

Prior to historic development, the floodplain of the lower Columbia River near the project areas was characterized by deciduous riparian forest and riverine wetlands, emergent wet meadows, and complex mosaics of intertidal marshes and tidal forested wetlands. A 1993 natural area inventory for the Lower Columbia classified the areas around Longview as historically being a mixture of freshwater tidelands that transitioned to overflow plains as you moved further upstream (Christy and Putera 1993:12–13). The wettest tidelands were primarily occupied by freshwater marshes dominated by species such as three-square rush (*Schoenoplectus americanus* formerly *Scirpus americanus*) and Lyngby's sedge (*Carex lyngbyei*), while slightly higher sites were occupied by shrub swamps of red-osier dogwood (*Cornus sericea* formerly *C. stolonifera*), Pacific willow (*Salix lucida* var. *lasiandra*), and Sitka willow (*Salix sitchensis*). Stands of Oregon ash and black cottonwood were also common on natural levees along tidal streams. In nontidal areas, the wettest sites were dominated by creeping spikerush (*Eleocharis palustris*) in the shallows along the river, Columbia River willow (*Salix fluviatilis*) on sandy banks and sandbars, and Pacific willow along channels and around overflow lakes. Oregon ash frequently occurred in association with stinging nettle (*Urtica dioica*) on higher sites that were protected natural levees, and with black cottonwood, red-osier dogwood, snowberry (*Symphoricarpos albus*), and stinging nettle on higher banks and on the tops of natural levees. Plant communities that once occurred in this area that are now extremely rare or extirpated include Columbian sedge (*Carex aperta*) marsh, tufted hairgrass (*Deschampsia cespitosa*) prairie, and Oregon white oak (*Quercus garryana*) savanna. (Christy and Putera 1993)

European colonization and establishment of the City of Longview in 1923 modified the floodplain, particularly with the establishment of the Consolidated Diking Improvement District (CDID) #1 Columbia River flood control levee in the 1920s. This levee, which extends along the shoreline near the project areas, effectively disconnected the floodplain from the river and resulted in the loss of intertidal habitats along the shoreline. Floodplain vegetation was further modified by the hydroregulation (i.e., construction and management of hydroelectric dams) of the Columbia River system and the urbanization of the watershed (Johnson 2010). The construction of multiple stormwater drainage ditches by both CDID #1 and private entities also altered the hydrologic regime and vegetation of these areas, as did the development of the floodplain for industrial, agricultural, residential, and recreational uses.

2.2.1.2 Special-Status Plant Species

The WDNR National Heritage Program database was queried for records of rare plant occurrences in Cowlitz County. As shown in Table 2, 15 species with some type of federal or state status were returned from this query (Washington Department of Natural Resources 2015). None of these species has been recorded in the project areas. The nearest record of occurrence of one of these plants relative to the project areas is for a documented siting of the obligate wetland species Columbia water-meal (*Wolffia columbiana*) approximately 1.5 miles northwest of the project area for the On-Site Alternative (Washington Department of Natural Resources 2015) and outside of the study area. Table 3 provides a summary of the typical elevation, habitat, and geographic range for each of these species, as well as an assessment of their potential to occur on the project areas based on the presence or absence of suitable habitat.

Table 2. List of Known Occurrences of Threatened, Endangered, Sensitive, and Rare Plants in Cowlitz County, Washington

Scientific Name	Common Name	Federal Status ^a	State Status ^b	Historical Record ^c
<i>Agoseris elata</i>	Tall agoseris	--	S	C
<i>Buxbaumia viridis</i>	Buxbaumia moss	--	R1	C
<i>Cimicifuga elata</i>	Tall bugbane	SC	S	H
<i>Corydalis aquae-gelidae</i>	Clackamas corydalis	SC	S	C
<i>Erythronium revolutum</i>	Pink fawn-lily	--	S	C
<i>Euonymus occidentalis</i> var. <i>occidentalis</i>	Western wahoo	--	S	C
<i>Isoetes nuttallii</i>	Nuttall's quillwort	--	S	C
<i>Physostegia parviflora</i>	Western false dragonhead	--	R1	H
<i>Poa laxiflora</i>	Loose-flowered bluegrass	--	S	C
<i>Poa nervosa</i>	Wheeler's bluegrass	--	S	C
<i>Salix sessilifolia</i>	Soft-leaved willow	--	S	C
<i>Sidalcea nelsoniana</i>	Nelson's checker-mallow	LT	E	C
<i>Tetraphis geniculata</i>	Tetraphis moss	--	R1	C
<i>Utricularia gibba</i>	Humped bladderwort	--	R1	C
<i>Wolffia columbiana</i>	Columbia water-meal	--	R1	C

^a Federal Status under the Endangered Species Act:

LE = Listed Endangered (in danger of extinction)

LT = Listed Threatened (likely to become endangered)

PE = Proposed Endangered

PT = Proposed Threatened

C = Candidate species. Sufficient information exists to support listing as Endangered or Threatened.

SC = Species of Concern. An unofficial status, the species appears to be in jeopardy, but insufficient information to support listing.

^b State Status of plant species is determined by the Washington Natural Heritage Program. Factors considered include abundance, occurrence patterns, vulnerability, threats, existing protection, and taxonomic distinctness. Values include:

E = Endangered. In danger of becoming extinct or extirpated from Washington.

T = Threatened. Likely to become Endangered in Washington.

S = Sensitive. Vulnerable or declining and could become Endangered or Threatened in the state.

R1 = Review group 1. Of potential concern but needs more fieldwork to assign another rank.

^c Historical Record refers to when the occurrence was documented:

C = Most recent sightings after 1977.

H = Most recent sighting before 1977.

Source: Washington Department of Natural Resources 2014

Table 3. Elevation, Habitat, and Geographic Range of Listed Threatened, Endangered, Sensitive, and Rare Plants in Cowlitz County, Washington

Scientific Name	Common Name	Elevation Range	Habitat	Geographic Range	Occurrence Relative to Project Areas
<i>Agoseris elata</i>	Tall agoseris	500 to 7,800 feet	Found in meadows, prairies, open woods, and exposed rocky ridges. Occurs in areas with little to no canopy cover and assumed to be shade intolerant.	Throughout California, Oregon, and Washington.	Documented within northeastern part of Cowlitz County. Not likely to occur in the project areas due to elevation.
<i>Buxbaumia viridis</i>	Buxbaumia moss	Low to subalpine elevations	Found in coniferous forests on very well-rotted logs and peaty soil and humus.	Western North America including the western portion of Washington.	Documented in east-central portion of Cowlitz County. Not likely to occur in the project areas due to lack of suitable coniferous habitat.
<i>Cimicifuga elata</i>	Tall bugbane	100 to 2,800 feet, with majority below 700 feet	Occurs in or along margins of mixed mature or old growth forests, including mesic coniferous or mixed coniferous-deciduous stands. Frequently found on north or east-facing slopes.	Southwestern British Columbia to southern Oregon, west of Cascade range.	Documented in western portion of Cowlitz County in areas along the Columbia River. Not likely to occur in the project areas due to lack of appropriate forest habitat.
<i>Corydalis aquae-gelidae</i>	Clackamas corydalis	1,250 to 4,200 feet	Occurs in or near cold flowing water, including seeps and small streams; often occurring in stream channels. Moist shady woods in western hemlock (<i>Tsuga heterophylla</i>) and silver fir (<i>Abies amabilis</i>) zones. Prefers intermediate levels of overstory canopy closure.	Regionally endemic in Washington State and in Clackamas and Multnomah Counties in Oregon.	Documented in eastern portion of Cowlitz County. Not likely to occur in the project areas due to elevation and lack of suitable habitat.

Scientific Name	Common Name	Elevation Range	Habitat	Geographic Range	Occurrence Relative to Project Areas
<i>Erythronium revolutum</i>	Pink fawn-lily	100 to 600 feet	Occurs in high-precipitation areas within 100 km of the coast; in moist soil in open or moderately shaded forests that provide full light at ground level. Habitats in Washington include swampy western red cedar (<i>Thuja plicata</i>)-lodgepole pine (<i>Pinus contorta</i>) forests, Sitka spruce (<i>Picea sitchensis</i>) woods on consolidated sand dunes, Sitka spruce-western hemlock forests, and shaded river bottoms.	Pacific coast region from southern British Columbia to northwestern California.	Documented in northwestern portion of Cowlitz County. Not likely to occur in the project areas due to lack of suitable coniferous forest habitat.
<i>Euonymus occidentalis</i> var. <i>occidentalis</i>	Western wahoo	20 to 600 feet	Occurs in moist woods and forested areas on west side of Cascades. Often found in shaded draws, riparian areas, and ravines. Sometimes found in grassy areas with scattered trees. In Washington, it typically occurs on fine sandy loam, silty loam, and silty clay loams.	British Columbia, western Washington and Oregon, south to central California	Documented in west-central portion of Cowlitz County, potentially near the project areas. Appropriate habitat could occur on and near both project areas.
<i>Isoetes nuttallii</i>	Nuttall's quillwort	200 to 345 feet	Terrestrial species found in seasonally wet ground, seepages, temporary streams, and mud near vernal pools.	Southeast Vancouver Island, British Columbia to southern California	Documented in west-central portion of Cowlitz County, potentially near the project areas. Not likely to occur in the project areas due to elevation.

Scientific Name	Common Name	Elevation Range	Habitat	Geographic Range	Occurrence Relative to Project Areas
<i>Physostegia parviflora</i>	Western false dragonhead	None provided.	Occurs along shores of streams and lakes, marshes, and other low, wet places in the valleys and foothills (Herbarium, Burke Museum of Natural History and Culture 2014).	East of the Cascade summits, British Columbia south through Washington to the Columbia Gorge, then west to Portland, Oregon; east to Idaho and North Dakota. (Herbarium, Burke Museum of Natural History and Culture 2014)	Most recent documentation in Cowlitz County is prior to 1977. Appropriate habitat could occur on and near the project areas.
<i>Poa laxiflora</i>	Loose-flowered bluegrass	50 to 3,700 feet	Found on moss covered rocks and logs, along streams and rivers, and on edges of wet meadows in moist shady woods.	Coastal Alaska, British Columbia, western Washington, and western Oregon	Documented in northwestern portion of Cowlitz County. Appropriate habitat could occur on or near the project areas.
<i>Poa nervosa</i>	Wheeler's bluegrass	10 to 800 feet	Found in low-elevation wet habitats west of the Cascade crest in forest openings with minimal canopy cover, mossy rock outcrops, cliff crevices, and occasionally talus. Sites are often sparsely vegetated with little soil development.	Endemic from Vancouver Island, British Columbia, to northwest Oregon	Documented in west-central portion of Cowlitz County, potentially near the project areas. Unlikely to occur in the project areas due to lack of preferred habitat elements.
<i>Salix sessilifolia</i>	Soft-leaved willow	None provided	Found in wet lowland habitats, including silty or sandy riverbanks, riparian forests, dredge spoils, sandy beaches, and at the upper edge of an intertidal zone.	Southern British Columbia to northern California	Documented in northern portion of Cowlitz County. Appropriate habitat could occur on or near the project areas.

Scientific Name	Common Name	Elevation Range	Habitat	Geographic Range	Occurrence Relative to Project Areas
<i>Sidalcea nelsoniana</i>	Nelson's checker-mallow	None provided	Found in low-elevation meadows, prairie, or grassland, along fencerows, streams, and roadsides, drainage swales, and edges of plowed fields adjacent to wooded areas.	Regionally endemic of Benton County, Oregon, north to Lewis County, Washington, and from central Linn County, Oregon to just west of the crest of the Coast Range.	Documented within northwestern portion of Cowlitz County. Appropriate habitat could occur on or near the project areas.
<i>Tetraphis geniculata</i>	Tetraphis moss	Sea level to subalpine elevations.	Occurs on the cut or broken ends or lower half of large decay class rotten logs or stumps, and occasionally on peaty banks in moist coniferous forests.	From Alaska and British Columbia through western Washington and select sites in Oregon.	Not documented in Cowlitz County. Not likely to occur in the project areas due to lack of suitable coniferous habitat with logs and stumps.
<i>Utricularia gibba</i>	Humped bladderwort	160 to 490 feet	Occurs in lakes and lake edges and in muddy disturbed sites in the lowland zone.	Southern British Columbia south to California.	Documented in the northern portion of Cowlitz County. Not likely to occur in the project areas due to elevation.
<i>Wolffia columbiana</i>	Columbia water-meal	10 to 250 feet	Found in freshwater lakes, ponds, and slow streams.	From California to British Columbia, east to Quebec, and south to Florida, excluding the interior southwestern states.	Occurs within 1.5 miles of the project areas; could occur in ponded habitats on or near the project areas.
Source: Unless noted otherwise, this information came from the Washington Department of Natural Resources, Washington Natural Heritage Program plant species fact sheets; available at: http://www1.dnr.wa.gov/nhp/refdesk/lists/plantsxco/cowlitz.html					

As indicated in Table 3, of the 15 special-status species known to occur in Cowlitz County, six were identified by ICF as potentially occurring in the project areas, based on the presence of potentially suitable habitat in the species range. These include Nelson's checker-mallow, western wahoo, western false dragonhead, loose-flowered bluegrass, soft-leaved willow, and Columbia water-meal. Appendix A, *Descriptions of Special-Status Plant Species with Potential to Occur in the Project Areas*, provides descriptions of these species.

2.2.1.3 Noxious Weeds

Special-status plants can also include species designated as noxious weeds by the Washington State Weed Control Board under Washington State's noxious weed law (Revised Code of Washington 17.10). Noxious weeds are nonnative plants that have been designated as undesirable plants by federal and state laws. Noxious weeds can displace native species; decrease plant species diversity; degrade habitat for rare species and wildlife; decrease productivity of farms, rangelands, and forests; create unattractive areas dominated by a single species; and/or impair full use of the landscape by wildlife and humans. As weed infestations spread, private landowners and public land managers spend increasing amounts of money, time, and resources conducting weed control activities.

Washington Administrative Code (WAC) 16-750 establishes the list of noxious weeds and defines three classes of noxious weeds (A, B, and C), as defined below in Table 4. These classes indicate the level of concern based on the threat to natural systems and current degree of distribution in the area and specify mandatory control and prevention measures associated with each class. Local noxious weed control boards adopt lists specific to their areas, typically at a county level.

Table 4. Washington State Noxious Weed Classification

Class	Definition
A	Nonnative species whose distribution in Washington is still limited. Preventing new infestations and eradicating existing infestations are the highest priority. Eradication of Class A plants is required by law.
B	Nonnative species presently limited to portions of the State. Species are designated for control in regions where they are not yet widespread. Preventing new infestations in these areas is a high priority. In regions where a Class B species is already abundant, control is decided at the local level, with containment as the primary goal.
C	Noxious weeds that are typically widespread in Washington or are of special interest to the state's agricultural industry. The Class C status allows counties to require control if locally desired. Other counties could choose to provide education or technical consultation.

Source: Washington State Noxious Weed Control Board 2015

The Washington State Noxious Weed Control Board maintains the state's official list of noxious weeds (Appendix B, *State Noxious Weed List*) that landowners could be required to control. Local noxious weed boards use the statewide list and classifications to identify noxious weed problems in their jurisdictions and to implement and prioritize control efforts. Cowlitz County's Noxious Weed Control Board maintains a county-specific noxious weed list (Appendix C, *Cowlitz County Noxious Weed List*) and assigns their own control priorities based on the distribution of these weeds in their jurisdiction.

The project areas support plant species regulated as noxious weeds under the law; management of developed areas can affect the spread of noxious weeds to adjacent undeveloped areas of natural plant communities. None of the species designated for Cowlitz County as Class A noxious weeds have been observed in the project areas. Five species documented in or within 1 mile of the project areas are listed as Class B noxious weeds, a classification assigned to plants considered a priority for weed control to prevent new infestations and to contain existing populations: indigobush (*Amorpha fruticosa*), Scotch broom (*Cytisus scoparius*), Policeman's helmet (*Impatiens glandulifera*), Eurasian watermilfoil (*Myriophyllum spicatum*), parrotfeather (*Myriophyllum aquaticum*), and water primrose (*Ludwigia hexapetala*). Eight species documented in the project areas or within 1 mile are listed as Class C noxious weeds, a classification assigned to widespread weeds: Canada thistle (*Cirsium arvense*), bull thistle (*Cirsium vulgare*), English ivy (*Hedera helix*), yellowflag iris (*Iris pseudacorus*), reed canarygrass (*Phalaris arundinacea*), Himalayan blackberry (*Rubus armeniacus*), common tansy (*Tanacetum vulgare*), and nonnative cattail (*Typha angustifolia*). Appendix D, *Descriptions of Noxious Weeds with Potential to Occur in the Project Areas*, provides descriptions of these species.

2.2.1.4 Land Cover Classifications and Vegetation Cover Types

Land cover classifications and vegetation cover types found in the project areas are briefly described in the following sections along with the typical plant species observed in them. A discussion of the location and distribution of these cover types is provided in Section 2.2.2, *On-Site Alternative Study Area* and Section 2.2.3, *Off-Site Alternative Study Area*.

Developed Land

Developed land includes those areas where the majority of the vegetation has been removed and replaced with pavement, buildings, or other types of infrastructure. One vegetation cover type (disturbed) was identified in the project areas.

Disturbed

Scattered vegetation is occasionally present in this community and typically consists of various nonnative grasses, forbs, and shrubs including colonial bentgrass (*Agrostis capillaris*), Kentucky bluegrass (*Poa palustris*), reed canarygrass, Canada thistle, bull thistle, common mullein (*Verbascum thapsus*), Scotch broom, and Himalayan blackberry.

Upland

The upland land cover category includes undeveloped vegetated areas that do not exhibit wetland characteristics. The following upland vegetation cover types are present in the project areas.

Forested Upland

The forested upland cover type includes areas where trees greater than 16 feet in height provide greater than 20% canopy cover (Multi-Resolution Land Characteristic Consortium 2011). Trees commonly found in this cover type include black cottonwood, red alder, Oregon ash, and Pacific willow in floodplain areas and Douglas-fir, big-leaf maple, and red alder in off-site areas. Planted rows of Sitka spruce (*Picea sitchensis*) along roadways and ditches are also present. Understory shrubs typically include Himalayan blackberry, trailing blackberry (*Rubus ursinus*), red elderberry (*Sambucus racemosa*), red-osier dogwood, and occasionally Pacific crabapple (*Malus fusca*) and cascara (*Rhamnus purshiana*). Reed canarygrass is typically the dominant plant in the understory,

with bedstraw (*Galium aparine*), stinging nettle, Canada thistle, and climbing nightshade (*Solanum dulcamara*) also common.

Scrub-Shrub Upland

The scrub-shrub upland cover type includes areas with greater than 20% canopy cover of shrubs or small trees that are less than 16 feet in height (Multi-Resolution Land Characteristic Consortium 2011). Like forested uplands, this cover type typically occurs in isolated patches surrounded by previously disturbed or developed lands. It is also commonly found in association with wetlands and drainage ditches. Dominant species are similar to those found in forested uplands including young black cottonwood, red alder, various willows, red-osier dogwood, and red elderberry. Himalayan blackberry is also common in more disturbed areas, as is Scotch broom.

Herbaceous Upland

The herbaceous upland cover type includes those areas dominated by native and nonnative grasses and forbs that are not maintained or managed (e.g., mowed) on a regular basis. Dominant vegetation in these areas is primarily reed canarygrass. Other common species include perennial ryegrass (*Lolium perenne*), colonial bentgrass, haired bentgrass (*Agrostis scabra*), Kentucky bluegrass, fowl bluegrass (*Poa palustris*), orchard grass (*Dactylis glomerata*), short-awn foxtail (*Alopecurus aequalis*), western bittercress (*Cardamine occidentalis*), common horsetail (*Equisetum arvense*), soft rush (*Juncus effusus*), Queen Anne's lace (*Daucus carota*), velvetgrass (*Holcus lanatus*), hairy cat's ear (*Hypochaeris radicata*), English plantain (*Plantago lanceolata*), Canada thistle, bull thistle, black medic (*Medicago lupulina*), red clover (*Trifolium pratense*), and American vetch (*Vicia americana*).

Managed Herbaceous Upland

The managed herbaceous upland cover type is a subset of the herbaceous upland cover type and includes herbaceous areas that are regularly managed by mowing, grazing, or other activities. Dominant vegetation in these areas is nonnative grasses, with some scattered native and nonnative forbs. Species are the same as described above for the herbaceous upland cover type. Shrubs are typically lacking in these areas.

Wetland

The wetland category includes areas that exhibit the three diagnostic wetland characteristics required by state and federal wetland delineation manuals: hydrophytic vegetation, hydric soils, and wetland hydrology.

Forested Wetland

The forested wetland cover type includes palustrine forested (PFO) wetland areas where trees 16 feet in height or higher provide greater than 20% or more canopy cover (Multi-Resolution Land Characteristic Consortium 2011). Dominant vegetation in this cover type includes black cottonwood, Pacific willow, red alder, and Oregon ash, over a shrub layer that includes such species as salmonberry (*Rubus spectabilis*), Himalayan blackberry, other willows, red-osier dogwood, and red elderberry. Scattered Sweetbriar rose (*Rosa eglanteria*) and Douglas spiraea (*Spiraea douglasii*) shrubs are occasionally present. The understory of most of the forested wetland community is dominated by reed canarygrass. Soft rush, fowl bluegrass, and stinging nettle are also common.

Scrub-Shrub Wetland

The scrub-shrub wetland cover type includes palustrine scrub-shrub (PSS) wetland areas where shrubs or small (less than 16 feet in height) trees provide greater than 20% canopy cover (Multi-Resolution Land Characteristic Consortium 2011). Scrub-shrub wetlands are typically dominated by red osier dogwood, Douglas spiraea, Himalayan blackberry, Hooker's willow (*Salix hookeriana*), Pacific willow, Sitka willow, and saplings of red alder, Oregon ash, black cottonwood, Columbia River willow, Nootka rose (*Rosa nutkana*), creeping buttercup (*Ranunculus repens*), and slough sedge (*Carex obnupta*). The understory of such areas is often dominated by reed canarygrass, with narrowleaf cattail (*Typha angustifolia*) common in wetter areas.

Herbaceous Wetland

Herbaceous or palustrine emergent (PEM) wetlands are found in the floodplain of the Columbia River, often along drainage ditches and in areas that were previously disturbed by agriculture and past borrow activities. Most are dominated by a near monoculture of reed canarygrass, with soft rush and narrow-leaf cattail commonly present in wetter areas. Other species noted in herbaceous wetlands include English plantain, curly dock (*Rumex crispus*), common plantain, slough sedge, and giant horsetail (*Equisetum telmateia*). Various willows, red elderberry, Himalayan blackberry, and Canada thistle are often present around their edges where herbaceous wetlands transition into uplands.

Managed Herbaceous Wetland

The managed herbaceous wetland cover type represents a subset of the herbaceous wetlands identified by Grette in their multiple wetland reports (Grette Associates 2014a, b, c, d, i). This cover type includes those herbaceous wetlands that exhibit evidence of regular management by mowing. These areas are typically dominated by reed canarygrass.

Disturbed Wetland

The disturbed wetland cover type represents wetlands that have been altered by past industrial activities to such an extent that they could no longer exhibit the three diagnostic wetland characteristics (i.e., hydrophytic vegetation, hydric soils, and wetland hydrology). For example, a wetland that has been subject to repeated disturbance from surface clearing or grading activities could be largely devoid of hydrophytic vegetation but still exhibit hydric soils and wetland hydrology. If the disturbance was to cease and the area was allowed to revegetate naturally, hydrophytic vegetation would likely become prevalent once again, and all three characteristics would then be present.

Riparian Land

The riparian land cover category includes those areas located along the shoreline of the Columbia River between the ordinary high water mark (OHWM) and the top of the CDID levee. It includes the vegetation growing adjacent to the active channel margin in riparian zones identified by Grette in their upland and shoreline habitat inventories (Grette Associates 2014e, g, h). Vegetation in these areas interacts directly with the Columbia River, with growth and habitat function heavily influenced by river flows, the rise and fall of water levels, and the erosion and deposition of materials along the shoreline. For the purposes of this analysis, riparian vegetation communities are limited to uplands located in the riparian zone; therefore, riparian lands are reported as part of the

upland land cover class. Wetlands located in the riparian zone are included in the wetland vegetation community mapping and discussed under those sections.

Riparian Forest

The riparian forest cover type includes upland areas that have greater than 30% canopy cover of trees 20 feet in height or higher growing along the shoreline of the Columbia River, between the OHWM and the levee. This cover type is found growing within both sandy substrates and amongst riprap and other types of shoreline armoring (i.e., Reno mattress⁴). Dominant vegetation typically includes black cottonwood, Oregon ash, Himalayan blackberry, Scotch broom, Scouler's willow, Hooker's willow, Columbia River willow, Sitka willow, red-osier dogwood, and false indigo bush (*Amorpha fruticosa*). Big-leaf maple, Pacific crabapple, and Douglas hawthorn (*Crataegus douglasii*) are also present in some areas. Underlying herbaceous vegetation typically includes reed canarygrass along with various other grasses and forbs include various bromes (*Bromus* spp.), velvetgrass, red clover, Canada thistle, gumweed (*Grindelia* sp.), poverty rush (*Juncus tenuis*), and stinging nettle, among others.

Riparian Scrub-Shrub

The riparian scrub-shrub cover type includes upland areas that have greater than 30% canopy cover of shrubs or small trees (less than 20 feet in height) growing along the shoreline of the Columbia River, between the OHWM and the levee. It is found in similar substrates as the forest vegetation community and contains similar species.

Riparian Herbaceous

The riparian herbaceous cover type is generally dominated by mown grasses and weeds including reed canarygrass, velvet grass, common horsetail, and English plantain. It is only found in the project areas. It occurs in scattered areas that are too small to be seen on the vegetation cover type figures.

Open Water

The open water land cover category includes the various surface and stormwater ditches and ponds that are present in the project areas. It is described in more detail in the NEPA Surface Water and Floodplains Technical Report (ICF International 2016c). Species present in these fringe areas typically include reed canarygrass, cattails, creeping spikerush, yellowflag iris, and slough sedge.

2.2.2 On-Site Alternative Study Area

The following sections describe the existing conditions relative to vegetation for the On-Site Alternative.

2.2.2.1 General Description of On-Site Alternative Area

The 212-acre direct impact study area lies within the 540-acre site currently leased by the Applicant; the lease area includes Parcels 10213, 61950, 61953, and 619530400, as well as two parcels that are currently owned by Bonneville Power Administration (BPA) (Parcels 6195303 and

⁴ Reno mattress is a type of gabion, a wire cage or basket filled with rock that is used for river bank and scour protection, where the depth of the basket is less than its width and length, creating a permeable, flexible 'mattress'.

61954) (Figure 6). Parcel 10213 is located on the north side of Industrial Way (i.e. outside of the direct impact study area) and Parcels 61950, 61953, 6195303, 619530400, and 61954 are located on the south side of Industrial Way. Parcel 10213 is undeveloped; Parcels 619530400, 6195303, and 61953 contain the former Reynolds Metals Aluminum Reduction Plant; Parcel 61950 contains the CDID levee and Columbia River shoreline; and Parcels 6195303 and 61954 are primarily occupied by electrical substations/switchyards. The export terminal would be constructed on portions of Parcels 619530400, 6195303, 61950, and 61954. These parcels are within the direct impact study area and include two parcels of the former Reynolds Metals Aluminum Reduction Plant, a shoreline parcel, and two parcels that are currently owned by BPA.

Parcel 10213

Parcel 10213 is located on the north side of Industrial Way, between the roadway and segments of CDID Ditch 5 and CDID Ditch 10 (Figure 6). It is broken into three portions by 38th Avenue and Parcel 1021401, which contains a part of the BPA Longview Substation. The largest portion is the northern part, which is bounded by Ditch 10 on the north, 38th Avenue on the southeast, and Industrial Way on the southwest. The next largest part is the central portion, an arrow-shaped section that is bounded by 38th Avenue on the northwest, Ditch 5 on the east, and Parcel 1021401 on the south. The third portion is a small, triangular section on the southeast end that is bounded by Industrial Way to the southwest, Parcel 1021401 to the northwest, and Ditch 5 to the east.

With the exception of a former commercial office building at the corner of Industrial Way and 38th Avenue, an overgrown softball field along the north side of 38th Avenue, and multiple transmission lines supported on both wooden pole structures and steel towers, Parcel 10213 is undeveloped. It primarily consists of former agricultural land that is now dominated by a near monoculture of reed canarygrass, with a few areas of trees and shrubs in various locations around its perimeter (Appendix E, *Site Photographs*, Photos 1 and 2).

Surface-water features on or adjacent to Parcel 10213 include CDID Ditch 5 and Ditch 10, and six unnamed privately owned drainage features. These features are described in the NEPA Surface Water and Floodplains Technical Report (ICF International 2016c)

Parcels 619530400 and 61953 (Former Reynolds facility)

Parcels 619530400 and 61953 are located on the south side of Industrial Way and contain the former Reynolds Metals Company Aluminum Reduction Plant (Figure 6). Roughly half of this site is devoid of vegetation having been previously developed as large industrial buildings, parking lots, storage areas, disposal sites, stormwater ponds, interior roads, and railroad tracks. Moving northwest to southeast across the central portion of the site, major structures and facilities remaining include the Cable Plant, outdoor storage area, North Plant Potlines, various maintenance and administrative buildings, coal storage silos, cast houses, and remnant portions of the South Plant Potlines and Cryolite Recovery Plant (Figure 6). Structures bordering the landward side of the CDID levee include the Stormwater Retention Basin and Filter Plant (Facility 73), Wastewater Treatment Facility, alumina storage silos, coal tar pitch tanks, and the sanitary sewer treatment plant. The alumina and coal storage silos, associated conveyors and transloading facilities, and Dock 1 are used by the Applicant for their existing bulk terminal operations. Aside from these structures, the administrative offices, and a few maintenance areas, the remainder of the facility is currently unused. Many of the former plant buildings and other infrastructure is in the process of being demolished.

Figure 6. Features in the Project Area for the On-Site Alternative



Surface-water features on or adjacent to these parcels include two drainage ditches managed by CDID #1 (Ditch 10 and Ditch 14); an off-site, privately owned ditch; the U-Ditch, Interception Ditch, Cryolite Recovery Ditches, and various stormwater conveyance ditches. These features are described in NEPA Surface Water and Floodplains Technical Report (ICF International 2016c).

Parcel 61950

Parcel 61950 includes the shoreline of the Applicant's leased area and the levee, which runs along the entire length of the Applicant's leased area along the Columbia River (Figure 6). The top of the levee lies at an elevation of +30 feet Columbia River Datum (CRD) (Grette Associates 2014e). It is topped by a paved road (Dike Road) along its length, with its riverward and landward faces maintained in grass cover by regular mowing (Appendix E, Photo 37), consistent with U.S. Army Corps of Engineers (Corps) standards for vegetation maintenance on flood control levees.

The project area is located approximately 30 miles upstream of the extent of tidal salinity in the river. The portion of the project area that includes the nearshore zone of the Columbia River is thus characterized as tidal freshwater habitat. The tidal amplitude—the difference between mean lower low water and mean higher high water—is 4.6 feet, creating a daily rise and fall of water levels along the shoreline of approximately 2.3 feet (on average) around the average water level (Grette Associates 2014e). The shoreline along the project area is characterized by a narrow, steep sloping sandy beach, with scattered areas of woody debris and herbaceous, scrub-shrub, and forested vegetation (Appendix E, Photos 32 through 38). Two rock groins and two wooden pile dikes extend out into the river from the shoreline along the Applicant's leased area boundary. Existing facilities located in the river and riparian zone include Dock 1, a trestle-supported access ramp, and an overhead conveyor that extends across the levee and shoreline to the shiploader on Dock 1. The area around Dock 1 and navigation channel in the river are both actively maintained by regular maintenance dredging.

A linear ponded area is located at the southeastern corner of the Applicant's leased area between the river and the CDID levee (Figure 6; Appendix E, Photos 39 and 40). This area was previously used by the Corps as a dredged material disposal site for spoils from routine maintenance dredging of the Columbia River Federal Navigation Channel. Past excavation of the dredged sands from this site by the previous site tenant created a large pond that is separated from the river by a steep shoreline berm. This berm is primarily covered with invasive vegetation such as Scotch broom and Himalayan blackberry on the pond side, and by native willows and black cottonwood trees which overhang the shoreline on the river side (Attachment E, Photo 12).

Parcels 6195303 and 61954

Parcels 6195303 and 61954 (Figure 6) are owned and maintained by BPA. Parcel 6195303 is 2.31 acres in size and currently consists of a fenced-in gravel pad that is partially vegetated with scattered weedy grasses and forbs. Parcel 61954 is located near the center of the project area, between Industrial Way and the South Plant Potlines. It is approximately 22 acres in size and primarily occupied by paved areas and a large electrical substation, which is part of the Longview Substation. The southeastern quarter of this parcel consists of an herbaceous wetland field that contains several high-voltage transmission lines supported on wooden pole structures and metal towers (Appendix E, Photos 41 and 42). Part of a smaller electrical substation owned by the Cowlitz County Public Utilities Department is also present on this and the adjacent parcel (Parcel 61953).

Both of these parcels are accessible from Industrial Way and from internal roads in the Applicant's leased area (Figure 6). Surface-water features are limited to a stormwater conveyance ditch located between Parcel 6195303 and the Reynolds Lead.

2.2.2.2 Land Cover Classification and Vegetation Cover Types in the Direct Impact Study Area

Figure 7 shows land cover classifications and vegetation cover types identified in the direct impact study area. The most dominant land cover class is developed lands, which accounts for 71% of the direct impact study area. This is followed by the upland, wetland, and open water land cover classes. The following sections provide the general locations and descriptions of each of these communities in the direct impact study area.

Developed Lands

Approximately 151.14 acres of the direct impact study area (71.0%) were identified as developed. These lands comprise only one vegetation cover type: disturbed (Figure 7; Appendix E, Photos 7 through 9, 12, 20 through 22, 28, and 29). Widely scattered patches of invasive shrubs such as Himalayan blackberry and Scotch broom occur on higher mounds, and around derelict structures and pieces of equipment. The disturbed cover type occurs on all of the areas previously developed for the former Reynolds facility, with the exception of the closed Black Mud Pond facility, which is classified as a managed herbaceous upland area. The BPA and Cowlitz County Public Utility District substations were also classified as disturbed areas.

Upland

Approximately 26.26 acres of the direct impact study area area (12.0%) were identified as uplands. Of the four upland cover types present, the herbaceous upland cover type was the most prevalent, followed by forested upland, managed herbaceous, and scrub-shrub upland.

Herbaceous Upland

Approximately 10.88 acres of the direct impact study area (5.0%) were identified as herbaceous uplands. These areas occur on the former Reynolds facility and BPA Parcel 61954 (Figure 7).

Herbaceous uplands in the direct impact study area occur along CDID Ditch 10 to the northwest of the former Cable Plant; in the former borrow area to the east of the closed Black Mud Pond facility (Appendix E, Photo 14); and along the Reynolds Lead (Figure 7). These areas are primarily dominated by reed canarygrass.

Herbaceous uplands on BPA Parcel 61954 are located in a transmission line easement to the northwest of the Longview Substation (Figure 7). This area is dominated by reed canarygrass, scotch broom, and bentgrass, as well as Himalayan blackberry.

Figure 7. Existing Land Cover Classes and Vegetation Cover Types in the Direct Impact Study Area – On-Site Alternative

Forested Upland

Approximately 8.90 acres of the direct impact study area (4.0%) were identified as forested upland.

Forested upland occurs around Wetlands A, C, and Y (described in *Wetlands* below) between the closed Black Mud Pond facility and the former Cable Plant and along the U-Ditch and Interceptor Ditch (Figure 7). Some of these areas are shown in Photos 15 through 17 and 23 through 26 (Appendix E). Dominant trees in the uplands adjacent to Wetlands A, C, and Y include black cottonwood, some Pacific willow, and Oregon ash. Common shrubs include Himalayan blackberry, red elderberry, and sweetbriar rose, with black cottonwood and Oregon ash sapling present. Dominant trees in the forested corridor along the U-Ditch and Interceptor Ditch include black cottonwood, red alder, and some Oregon ash along the ditch banks. Himalayan blackberry is the most common plant in the shrub layer, but has been recently cleared from some areas on the western end of the U-Ditch. Red osier-dogwood is also common. Several types and sizes of down wood are present in this forested corridor, as are various snags. Reed canarygrass is common in the herbaceous layer in all of these forested upland areas.

Forested upland in the direct impact study area includes a small area (0.05 acre) of forest in the riparian zone along the Columbia River between the ordinary high water mark (OHWM) and the top of the CDID #1 levee.

Managed Herbaceous Upland

Approximately 4.37 acres of the direct impact study area (2.0%) were identified as managed herbaceous upland cover type. As shown in Figure 7, managed herbaceous upland land cover occurs on the CDID levee, the lawns around the administrative and maintenance buildings, and on the caps of the closed Black Mud Pond facility (Appendix E, Photos 10 and 11). All of these areas are dominated by grasses and forbs that are regularly mown. Species present include reed canarygrass, haired bentgrass, colonial bentgrass, American plantain, orchard grass, short-awn foxtail, western bittercress, blue wildrye (*Elymus glaucus*), common horsetail, Queen Anne's lace, scouring rush (*Equisetum hyemale*), bedstraw, velvetgrass, perennial ryegrass, Kentucky bluegrass, and American vetch.

Scrub-Shrub Upland

Approximately 2.11 acres of the direct impact study area (1.0%) were identified as scrub-shrub upland.

As shown in Figure 7, scrub-shrub uplands on the former Reynolds facility occur around the former Cable Plant (Appendix E, Photo 22) and to the north of the closed Black Mud Pond facility around Wetland Y (Appendix E, Photos 18 and 19). Common species in these areas include young black cottonwood, willows, and Himalayan blackberry. Reed canarygrass is also common in the herbaceous layer.

Wetlands

Approximately 26.93 acres of the direct impact study area were identified as wetland (Table 5, Figure 8). The most prevalent wetland type present is herbaceous wetlands followed by forested wetlands, and scrub-shrub wetlands. As described in Section 2.1.1, *Data Sources*, wetland mapping was based on the wetland delineation and determination studies previously conducted by Grette Associates.

Table 5 provides a summary of the wetlands identified in the direct impact study area during the Grette Associates determinations and delineations.

Table 5. Wetlands Identified in the Direct Impact Study - On-Site Alternative

Wetland	Location (Parcel)	Cowardin Classification ^a	HGM Classification ^b	Category ^c	Area (acres)
A	619530400	PFO	Depressional	III	6.28
C	619530400	PEM/PFO	Depressional	III	3.38
Y	619530400	PEM/PSS	Depressional	III	3.40
Z	619530400	PEM	Depressional	III	11.22
P2	619530400	PEM	Depressional	IV	2.65
Total					26.93
^a Cowardin classification per Classification of Wetland and Deepwater Habitats of the United States (Cowardin et al. 1979). Values include: PFO = palustrine forested; PSS = palustrine scrub-shrub; and PEM = palustrine emergent					
^b Hydrogeomorphic (HGM) classification per the Washington State Wetland Rating System for Western Washington (Hruby 2006).					
^c Wetland category determined by Grette Associates using the Washington State Wetland Rating System for Western Washington (Hruby 2006).					
Source: Grette Associates 2014a, b, c, d.					

Forested Wetland

Approximately 6.28 acres of the direct impact study area were identified as forested wetland including all of Wetland A (Figure 8).

This wetland is depressional and is supported primarily by high groundwater and direct precipitation. Common plant species observed in the forested wetlands include a predominately native overstory of black cottonwood (*Populus balsamifera*), Pacific willow (*Salix lucida*), red alder (*Alnus rubra*), and Oregon ash (*Fraxinus latifolia*) trees, overlying a shrub layer dominated by salmonberry (*Rubus spectabilis*) and nonnative Himalayan blackberry (*Rubus armeniacus*). Reed canarygrass (*Phalaris arundinacea*), an invasive grass, is the common herbaceous plant (Appendix E, Photos 15 through 17).

Figure 8. Existing Wetlands in the Direct Impact Study Area - On-Site Alternative

Emergent/Forested Wetlands

Approximately 3.38 acres of emergent/forested wetland occur in the study area including all of Wetland C (Figure 8). This wetland is depressional and is supported primarily by high groundwater and direct precipitation. The emergent portion of the wetland is dominated by reed canarygrass. Common plant species observed in the forested portion include a predominately native overstory of black cottonwood (*Populus balsamifera*), Pacific willow (*Salix lucida*), red alder (*Alnus rubra*), and Oregon ash (*Fraxinus latifolia*) trees, overlying a shrub layer dominated by salmonberry (*Rubus spectabilis*) and nonnative Himalayan blackberry (*Rubus armeniacus*).

Emergent/Scrub-Shrub Wetlands

Approximately 3.40 acres of emergent/scrub-shrub wetland occur in the study area including all of Wetland Y. Wetland Y is north of the closed Black Mud Pond facility and is the only wetland in the direct impact study area that extends outside of the direct impact study area (Figure 8). This wetland is depressional and is supported primarily by high groundwater and direct precipitation. The scrub-shrub component is dominated by Himalayan blackberry, red osier dogwood (*Cornus sericea*), Douglas spirea (*Spiraea douglasii*), and narrowleaf cattail (*Typha angustifolia*). The emergent component is dominated by reed canarygrass and an unidentified bryophyte; some nonnative narrowleaf cattail is also present.

Emergent (Herbaceous) Wetlands

Approximately 13.87 acres of emergent wetland occur in the study area including all of Wetlands Z and P2 (Figure 8). These wetlands are depressional and are supported primarily by high groundwater and direct precipitation. Wetland Z is dominated by reed canarygrass and soft rush (*Juncus effusus*) and contains several brush piles left over from past clearing activities. Wetland P2 is also dominated by reed canarygrass and soft rush.

Open Water

Approximately 10.78 acres of the direct impact study area (5.0%) were identified as open water areas (Figure 7), and include the Columbia River and various ditches and ponds (Appendix E, Photos 2, 16, 23 through 31, 39, and 40). The ditches and ponds are artificially created features; with the exception of the Columbia River, no natural streams or drainages are present in the direct impact study area.

Aquatic Vegetation

Aquatic vegetation was not assessed or quantified in the aquatic portions of the study area during either the Grette Associates studies or the ICF field visits. Grette Associates (2014e) states that curly pondweed (*Potamogeton crispus*) was observed at approximately -1 foot CRD downstream of Dock 1 during a period of high visibility. The report states it is possible that the gently sloping portion of the shallow water habitat area between the east and west pile dikes near the project area could support a narrow band of sparse aquatic vegetation in the upper most elevations where increased light penetration and reduced river velocity are present, relative to the deeper portions of the river in this area.

2.2.2.3 Indirect Impact Study Area Vegetation Communities

Table 6 summarizes the areas and percent cover of land cover classes in the On-Site Alternative's indirect impact study area within 1 mile of the project area. Approximately 70% of the indirect impacts study area is occupied by developed lands, open water (primarily the Columbia River) and agricultural lands; the remaining 30% consists of forest, shrub, herbaceous, wetlands, and barren lands.

Table 6. Land Cover in the Indirect Impact Study Area – On-Site Alternative

Land Cover Classification	Area in Indirect Impact Study Area (acres)	Percent Cover in Indirect Impact Study Area
Developed	1631	37
Forest	347	8
Shrub	106	2
Herbaceous	62	1
Agriculture	573	13
Wetlands	719	16
Open Water	880	20
Barren land	83	2
TOTAL	4401	100

Source: National Land Cover Data Base 2011 (Homer et al. 2015)

Land use adjacent to the direct impact study area is described in detail in the NEPA Land Use Technical Report (ICF International 2016d). In general, land use north of the direct impact study area includes a mix of undeveloped forested areas, rural residences, and lands previously disturbed by various industrial and agricultural activities. Land to the east and southeast is primarily developed for marine industrial and commercial uses and include the Mint Farm Industrial Park and the Weyerhaeuser wood/paper products facility. Land to the northwest includes undeveloped properties that were previously disturbed by agriculture and other recreational activities (project area for the Off-Site Alternative) and a closed construction debris/nonhazardous industrial waste landfill (Mount Solo Landfill). A mix of smaller rural-residential, small-scale industrial, and agricultural sites are also present in this area.

Land cover in the indirect impact study area immediately surrounding the direct impact study area is similar to what is described for the direct impact study area, mostly consisting of developed areas, managed/unmanaged herbaceous areas, wetlands, and open water of the Columbia River. Riparian lands are found predominantly along the Columbia River between the ordinary high water mark (OHWM) and the top of the CDID #1 levee, and include vegetation growing adjacent to the active channel margin in riparian zones identified in the previous upland and shoreline habitat inventories (Grette Associates 2014e, 2014g, 2014h). These riparian lands consist of three vegetated types – forest, scrub-shrub, and herbaceous.

- Riparian forest.** Riparian forest extends in a band of varying width along most of the shoreline, with the widest areas found on the southern portion of the shoreline near the Dredged Material Storage Area. Dominant vegetation in this cover type includes 12- to 16-inch-diameter black cottonwood and various willow trees, underlain by a mixture of native shrubs such as red osier dogwood and invasive shrubs such as Himalayan blackberry and Scotch broom (Appendix E,

Photos 32 through 36 and 38). Scattered accumulations of large woody material are present in these areas.

- **Riparian scrub-shrub.** Riparian scrub-shrub contains similar species as riparian forest. Two scrub-shrub riparian areas are found on Parcel 61950, between the Columbia River and the levee. These areas are dominated by black cottonwood saplings, various willow, and nonnative vegetation including Himalayan blackberry and Scotch broom (Appendix E, Photos 32 and 42). Native and nonnative herbaceous species are also present.
- **Riparian herbaceous.** Riparian herbaceous areas are generally dominated by grasses and weeds including reed canarygrass, velvet grass, common horsetail, and English plantain. These sparse patches of emergent vegetation occur under the existing Dock 1 conveyor and trestle, and on the sandy flats laying between OHWM and the approximate elevation of mean high water (Appendix E, Photos 36 and 37).

The following areas in the indirect impact study area contain higher-quality vegetation communities and generally represent contiguous forest and other intact vegetation communities.

- **Mount Solo upland forest.** Mount Solo is a forested ridge that lies to the north of the project area (Appendix E, Photos 18, 20, 22, and 23). It is covered with a large area (around 505 acres) of native forest intermixed with rural residential areas and some light industrial uses. Vegetation observable from Mt. Solo Road and Memorial Park Drive includes Douglas fir (*Pseudotsuga menziesii*), big leaf maple, red alder, and western hemlock. Other native tree, shrub, and herbaceous species are likely present. This area is the largest inland forested area in the indirect study area and likely provides habitat for a variety of wildlife species.
- **Mint Farm wetland mitigation sites.** Two compensatory wetland mitigation sites for the Mint Farm Industrial Park are located to the east of the project area, in or within 1 mile of the project area. These sites were constructed by the City of Longview in the late 1990s and early 2000s under federal and state permits as compensation for the authorized placement of fill material into wetlands and wetland ditches to construct a light industrial park. The Phase I mitigation site is 4.28 acres in size and has developed into a complex of forested, scrub-shrub and emergent wetlands; the Phase II mitigation site is 67 acres in size and includes a mixture of PEM, PSS, and PFO wetlands intermixed with forested uplands. ICF was unable to determine the current quality and species composition of these areas; however, it is likely that they contain a higher percentage of native vegetation and provide enhanced wetland and habitat functions over other, disturbed wetlands, uplands, and developed areas in the vicinity.
- **Lord Island.** Lord Island is located in the Columbia River near the project area. It consists of a 234-acre island that was previously used for dredge material disposal. It is densely forested and bisected by various high-flow channels that support tidal marshes and shallow habitat areas. Vegetation on the island is largely native. Lord Island provides significant wildlife values including habitat for bald eagles and significant numbers of wintering waterfowl (Oregon Wetlands Joint Venture 1994:20).

2.2.2.4 Special-Status Species

Of the 15 special-status plant species known to occur in Cowlitz County (Table 2), six were identified by ICF as potentially occurring in the project area. These include Nelson's checker-mallow, western wahoo, western false dragonhead, loose-flowered bluegrass, soft-leaved willow, and Columbia water-meal. Botanical surveys for these species have not been conducted in the project area or

vicinity. Based on the typical habitat description, soil type, and associated plant species presented in Table 2, ICF identified potential habitats in the project area that could support these species. Approximate blooming times are provided and typically correspond with the best timeframe for field surveys.

- **Western wahoo.** Potential habitat for western wahoo could exist in and around the forested wetlands (Wetlands A and Y) between the closed Black Mud Pond facility and the former Cable Plant. Grette Associates (2014a) states that presence of suitable habitat for this species in the project area is unlikely because the site is largely constructed from dredge spoils and is not associated with a remnant oak savannah or high-quality forest. Western wahoo blooms between May to June (Washington Department of Natural Resources 2015).
- **Western false dragonhead.** Potential habitat for western false dragonhead could occur in and around the forested wetlands (Wetlands A and Y) between the closed Black Mud Pond facility and the former Cable Plant, along the bank of CDID Ditches 10 and 14, and in other low, wet places in the project area. Western false dragonhead blooms between July and September (Herbarium, Burke Museum of Natural History and Culture 2014).
- **Loose-flowered bluegrass.** Potential habitat for loose-flowered bluegrass exists in the forested wetland and emergent/scrub-shrub wetlands (Wetlands C and Z) located between the closed Black Mud Pond facility and the former Cable Plant. Such habitat could also occur along CDID Ditch 10, Ditch 14, and along the U-Ditch and Interception Ditch. Loose-flowered bluegrass flower between from late May through June (Washington Department of Natural Resources 2015).
- **Soft-leaved willow.** Potential habitat for soft-leaved willow occurs along the Columbia River, in and around the Dredged Material Storage Area, and possibly in the wetlands (Wetland A, C, Z, and Y) located between the closed Black Mud Pond facility and the former Cable Plant. Soft-leave willow flowers from May to June (Washington Department of Natural Resources 2015).
- **Nelson's checker-mallow.** Given its regional distribution, documented occurrence within Cowlitz County, and association with semi disturbed habitats and species; Nelson's checker-mallow could occur in the project area. Potential occurrence locations include the outer edges of the project area in relatively undisturbed habitats along Industrial Way, adjacent to the CDID and privately owned ditches that fringe the northern edge of the project area, and/or adjacent to Wetlands A and Y in the northern portion of the area. Nelson's checker-mallow typically blooms between May and September (Washington Department of Natural Resources 2015).
- **Columbia water-meal.** Given its regional distribution, documented occurrence within 1.5 miles of the project area, and its known association with ponded habitats and more common species such as duckweed, this species could occur in the pond at the Dredged Material Storage Area and in the ditches maintained by CDID #1 and private entities. Bloom time of Columbia water-meal in Washington is unknown but not necessary for identification (Washington Department of Natural Resources 2015).

2.2.2.5 Noxious Weeds

Table 7 presents the noxious weed species identified in the project area during various site investigations. The project area supports plant species regulated as noxious weeds under the law. Fourteen noxious weed species have been documented in the project area (Table 7) (Cowlitz County Noxious Weed Control Board 2015; Washington State Noxious Weed Control Board 2015).

Table 7. Noxious Weeds Identified in the Project Area

Noxious Weed Species		Location Observed ^{a, b, c}	Classification		State/County Priority Weed for Control ^e
Common Name	Scientific Name		State ^d	Cowlitz County ^e	
Indigobush	<i>Amorpha fruticosa</i>	Riparian ^b	B	B	Yes/No
Scotch broom	<i>Cytisus scoparius</i>	W/U ^{a, b}	B	B	No/Yes
Policeman's helmet	<i>Impatiens glandulifera</i>	W/U ^a	B	B	Yes/Yes
Eurasian water milfoil	<i>Myriophyllum spicatum</i>	W/OW ^a	B	B	Yes/No
Parrotfeather	<i>Myriophyllum aquaticum</i>	W/OW ^a	B	B	No/No
Water primrose	<i>Ludwigia hexapetala</i>	D ^c	B	B	No/No
Canada thistle	<i>Cirsium arvense</i>	W/U ^{a, b}	C	C	No/Yes
Bull thistle	<i>Cirsium vulgare</i>	W/U ^{a, b}	C	C	No/No
English ivy	<i>Hedera helix</i>	W/U ^{a, b}	C	C	No/No
Yellowflag iris	<i>Iris pseudacorus</i>	W/D ^b	C	C	No/No
Reed canarygrass	<i>Phalaris arundinacea</i>	W/U ^{a, b}	C	Not listed	No/No
Himalayan blackberry	<i>Rubus armeniacus</i>	U ^{a, b}	C	C	No/No
Common tansy	<i>Tanacetum vulgare</i>	U ^a	C	C	No/Yes
Nonnative cattail	<i>Typha</i> spp.	W ^{a, b}	C	C	No/No

^a Observations made by Grette Associates, as presented in *Appendix F: Noxious Weeds and Sensitive Plants* in Grette Associates 2014a. Location values: W = wetland; U = upland; D = Ditches; OW = open water
^b Observations made by ICF during site investigations in April and December 2014
^c Observations by Washington State Noxious Weed Control Board (2015)
^d State noxious weed classification based on Washington State Noxious Weed Control Board 2015 Noxious Weed List
^e Noxious weed classification and priority for weed control (state and county level) based on Proposed 2015 Cowlitz County Noxious Weed List (Cowlitz County Noxious Weed Control Board 2015)

None of the species designated as Class A noxious weeds by the Cowlitz County Noxious Weed Control Board have been observed in or within 1 mile of the project area. Six species documented in the project area are listed Class B noxious weeds, a classification assigned to plants considered a priority for weed control to prevent new infestations and to contain existing populations.

- **Indigobush.** Indigobush was observed by ICF in the riparian plant community along the western shoreline of the project area, near the outlet of CDID #1's Reynolds Pump Station. It likely occurs along other portions of the shoreline of the project area.
- **Scotch broom.** As noted by Grette Associates (2014a) and ICF during the 2014 field reconnaissance, Scotch broom is present in scattered patches throughout the project area in disturbed uplands including the former Outdoor Storage Area, north end of U-Ditch, along the outer edges of Wetland Z, throughout Landfill 2 (Industrial Landfill), Fill Deposit A (White Mud Pond), Fill Deposits B-1 and B-2 (Eastern Black Mud Ponds), portions of Fill Deposit B-3 (Black Mud Deposits), and along the berm around the Dredged Material Storage Area (Figure 7).

- **Policeman's helmet.** Policeman's helmet was listed as being present in the project area by Grette Associates (2014a), but no specific locations for this species were provided. Based on documented habitat preferences and site conditions, policeman's helmet could be present in the understory/herbaceous layer of Wetlands A and Y.
- **Eurasian watermilfoil and parrotfeather.** Both of these species were identified by Grette Associates (2014a) as being present in or within 1 mile of the project area. However, no specific location for where these species were observed was provided. These aquatic species typically occur in permanently ponded areas. Given their habitat requirements, they could occur in CDID Ditch 4, 10, and 14, and possibly in part of the Dredged Material Storage Area pond.
- **Water primrose (*Ludwigia hexapetala*).** Water primrose has been identified by as occurring in drainage ditches within the CDID # 1. Water primrose is typically found creeping along the shoreline, floating on the water surface, or growing upright. It is possible that water primrose could occur in CDID Ditches 4, 10 and 14, and possibly the Dredged Material Storage Area pond.

Eight species present in this study area are listed Class C noxious weeds, a classification assigned to weeds that are not typically considered a priority for weed control because they are already widespread throughout the state.

- **Canada thistle and bull thistle.** Both of these species are listed as being present in the project area by Grette Associates (2014a) and recorded in the uplands of Parcel 10213 and former Reynolds facility (Grette Associates 2014e). Canada thistle was also observed by ICF in Wetland Z during the December 2014 site visit.
- **English ivy.** English ivy was identified by Grette Associates (2014a) as being present in the project area; however, they did not state where it was observed. Given its habitat preferences, it could be present in Wetland A, as well as in scattered forested areas along Industrial Way and Memorial Park Drive in Parcel 10213.
- **Yellowflag iris.** Yellowflag iris was observed by ICF along the edges of the U-Ditch and Interception Ditch during the December 2014 site visit. Grette Associates (2014b) also recorded it in Wetland X along the shoreline of the Columbia River.
- **Reed canarygrass and Himalayan blackberry.** Both of these species are present in disturbed areas, uplands, and wetlands throughout the project area, including in Wetlands A, C, and Z, as well as along the shoreline of the river, and within the herbaceous wetland and upland areas north of Industrial Way (Grette Associates 2014c). Reed canarygrass is a dominant understory species in forested Wetland A and is a dominate species in emergent Wetlands P2, C, Y, and Z (Grette Associates 2014a). Blackberry occurs in scattered areas throughout the project area, particularly along the U-Ditch/Interception Ditch, off the southeast corner of the former Cable Plant, along the margins of various stormwater conveyance features, along the south side of Industrial Way, and along the Reynolds Lead (Grette Associates 2014a).
- **Common tansy.** Grette Associates (2014a) lists this species as present in the project area but does not indicate where this species was observed.
- **Nonnative cattail.** Nonnative cattails were recorded within Wetland Y (Grette Associates 2014a) and are a dominate species in Wetland E and in the stormwater conveyance features of the far eastern end of the project area (Grette Associates 2014d); cattails were also observed at the eastern end of the Dredged Material Storage Area pond at the southeastern end of the

project area, as well as at the eastern end of the U-Ditch and in a shallow ponded area off the project area.

2.2.3 Off-Site Alternative Study Area

2.2.3.1 General Description of Off-Site Alternative Area

The Off-Site Alternative is adjacent to the project area for the On-Site Alternative. Therefore, some of the regional context provided in Section 2.2.2.1, *General Description of On-Site Alternative Area*, applies to this alternative as well.

The project area is located to the west or downstream from the project area for the On-Site Alternative, between the Columbia River and Mt. Solo Road (Figure 9). It is entirely within the historical Columbia River Floodplain and, with the exception of the shoreline, is protected by the CDID levee. The project area is generally bounded on the north by a hay field; on the northeast by Mount Solo Slough and the closed Mount Solo Landfill; on the east by CDID Ditch 14 and the closed Black Mud Pond facility; and on the southwest by the Columbia River. It includes all or portions of Parcels 106990100, 107110100, 107150100, 107160100, 107170100, 107180100, 107840100, 608600100, and WL2608003 and is within the City of Longview.

The project area is currently undeveloped and vegetation primarily consists of grassy fields that extend to the CDID levee along the Columbia River (Appendix E, Photos 43 through 54). Forested areas occur in one location near the center of the project area and along the shoreline, riverward of the levee. Individual trees and clumps of shrubs are also present in scattered locations throughout the project area and along Mount Solo Slough. Much of the project area appears to have been previously used for agricultural purposes including hay production and grazing. Between the early 2000s and 2012, multiple motocross tracks and a sand drag strip were also present in the project area, per aerial photographs. These facilities have since been abandoned and are now revegetated with herbaceous vegetation. One agricultural building (likely a pole-barn) is present in the northwest portion of the project area (Appendix E, Photo 50). Overhead BPA power lines and an associated easement run diagonally at the southeast end of the project area and converge with other power lines north of Mt. Solo Road (Appendix E, Photos 43, 44, and 54).

Access to the project area is currently provided from the east by a gravel road that extends from Mt. Solo Road through the Mount Solo Landfill site. It can also be accessed via both Dike Road and Barlow Point Road on the west. No rail service currently exists to the project area.

Surface-water features on or adjacent to the project area include the Columbia River, Mount Solo Slough, and CDID Ditches 10, 14, and 16 (Figure 9). The project area is also crossed by a network of smaller excavated ditches that drain into Mount Solo Slough. Each of these is briefly described below. These features are described in the NEPA Surface Water and Floodplains Technical Report (ICF International 2016c).

Figure 9. Features in the Project Area – Off-Site Alternative

2.2.3.2 Land Cover Classification and Vegetation Cover Types in the Indirect Impact Study Area

Figure 10 shows land cover classifications and vegetation cover types identified in the direct impact study area. The approximate acreage and relative cover for each of these cover classes and types is summarized below. As indicated, the most dominant land cover class is upland, which accounts for 69% of the direct impact study area. This is followed by the wetland, developed land, and open water cover classes.

Developed Land

Approximately 9.62 acres of the project area (4%) were identified as developed. It includes an existing residence and a few outbuildings in the northwest corner of the project area (Appendix E, Photo 50); fill stockpile areas, gravel lots, and equipment storage areas around the site entrance; and several areas within the meanders of Mount Solo Slough where recent land clearing and woody debris placement has occurred. All of these areas are considered to be within the disturbed vegetation cover type (Figure 10).

Disturbed

The disturbed cover type in the project area (Figure 10) includes sparsely vegetated areas dominated by nonnative species including Himalayan blackberry, Scotch broom, reed canarygrass, other common grasses, and weedy forbs. Many of these areas are unvegetated. These areas also include several brush piles that have been placed along Mount Solo Slough (Appendix E, Photos 47 and 48).

Upland

Approximately 155.46 acres of the direct impact study area (69%) were identified as upland, the most extensive cover class in the direct impact study area (Figure 10). Of the four upland cover types present, the herbaceous upland cover type was the most prevalent, followed by managed herbaceous, forested upland, and scrub-shrub upland.


Forested Upland

Approximately 6.74 acres of the direct impact study area (3%) were identified as forested upland. This cover type occurs in the south-central portion of the site, adjacent to Wetland 2 (Figure 10). Dominant species include black cottonwood and red alder, with some willow present (Appendix E, Photos 51 and 53). At the time of the December 2014 site visit, this area had little to no understory present.

Scrub-Shrub Upland

Approximately 4.42 acres of the direct impact study area (2%) was identified as scrub-shrub upland. These areas occur near the center of the project area and near the existing agricultural complex in the northwestern portion (Figure 10). Dominant vegetation includes young cottonwood, red alder, and willows.

Figure 10. Existing Land Cover Classes and Vegetation Cover Types in the Direct Impact Study Area – Off-Site Alternative



Scrub-shrub upland in the direct impacts study area also includes a small area (0.01 acre) of scrub-shrub riparian lands along the Columbia River shoreline.

Herbaceous Upland

Approximately 126.57 acres of the direct impact study area (56%) were identified as herbaceous uplands, the largest cover type present. These areas occur throughout the majority of the project area where previous agricultural and recreational (motocross) uses have occurred (Figure 10). Dominant vegetation is primarily reed canarygrass mixed with other common grasses and weedy forbs including bentgrass, Canada thistle, soft rush, orchard grass, velvetgrass, hairy cat's ear, perennial ryegrass, English plantain, broad-leaf plantain, fowl and Kentucky bluegrass, curly dock, red clover, and American vetch (Appendix E, Photos 43 through 50).

Managed Herbaceous Upland

Approximately 17.73 acres of the project area (8%) were identified as managed herbaceous upland cover type. This cover type was mapped for a recently mown area in the southern portion of the project area and for the CDID levee (Figure 10). These areas are dominated by grasses and forbs that are regularly mown (Appendix E, Photos 43, 44, and 52 through 54). Reed canarygrass is the dominant species present with the remaining vegetation similar to that found in the herbaceous upland cover type.

Wetlands

Approximately 64.76 acres of the direct impact study area were identified as wetland by Grette (Figure 11). The most prevalent wetland type present is herbaceous wetland followed by forested wetland, and scrub-shrub wetland. Because they did not have permission to access the project area, Grette Associates' wetland mapping was limited to reconnaissance-level surveys using aerial photographs, existing resource maps (e.g., National Wetland Inventory), LiDAR, and limited field verification.

Wetlands identified in the project area during these studies are summarized in Table 8.

Forested/Emergent

Approximately 17 acres of forested/emergent wetland occur in the study area (Table 8) and includes all of Wetland 2. Wetland 2 is behind the levee with dominant vegetation that includes black cottonwood, Oregon ash, and red alder underlain by a shrub layer composed of saplings of these species as well as various willows. The emergent layer consists of reed canarygrass.

Scrub-Shrub

Approximately 9 acres of the project area were identified as scrub-shrub wetlands (Table 8) including all of Wetland 3. Wetland 3 is behind the levee with dominant vegetation that includes young black cottonwood, red alder, and Oregon ash, as well as red osier dogwood, Nootka rose, willows, and Himalayan blackberry. Approximately 4.98 acres of this wetland was identified as disturbed from vegetation clearing within the last year from the date of the field effort. Remnant vegetation around the edges of the disturbed area includes black cottonwood, red alder, Pacific willow, Himalayan blackberry, and soft rush.

Herbaceous

Approximately 32 acres of the project area were identified as emergent wetlands (Table 8), including all of Wetlands 1, 4, 5, and 6. These wetlands are behind the levee and are dominated by reed canarygrass. Approximately 6.76 acres of Wetlands 4 and 5 were identified as managed wetlands because they appear to be regularly mowed.

Forested/Scrub-Shrub

Approximately 3.36 acres of the project area were identified as forested/scrub wetlands (Table 8), including all of Wetland B. Wetland B is riparian wetlands that are along the Columbia River on the waterward side of the levee. This wetland is dominated by black cottonwood, Oregon ash, red osier dogwood, Pacific willow, Nootka rose, Columbia River willow, reed canarygrass, creeping buttercup, and slough sedge.

Emergent/Scrub-Shrub

Approximately 3.4 acres of the project area were identified as emergent/scrub-shrub wetlands (Table 8), including all of Wetland Y. This wetland is behind the levee and is dominated by reed canarygrass, Himalayan blackberry, red osier dogwood, rose spiraea, and narrowleaf cattail.

Table 8. Wetlands Identified in the Project Area—Off-Site Alternative

Wetland	Location (Parcel)	Cowardin Classification ^a	HGM Classification ^b	Category ^c	Area (acres)
1	107150100	PEM	Depressional	III	3
2	107150100, 10716011	PFO/PEM	Depressional	III	17
3	106990100, 107170100	PSS	Depressional	III	9
4	107170100	PEM	Depressional	III	8
5	107170100, 107180100	PEM	Depressional	III	15
6	107840100	PEM	Depressional	III	6
B	107140100, 107190100	PFO/PSS	Riverine	III ^d	3.36
Y	106980100, 106970100	PEM/PSS	Depressional	III	3.4
Total					64.76


^a Cowardin classification per Classification of Wetland and Deepwater Habitats of the United States (Cowardin et al. 1979). Values include PFO = palustrine forested; PSS = palustrine scrub-shrub; PEM = palustrine emergent

^b Hydrogeomorphic (HGM) classification per the Washington State Wetland Rating System for Western Washington (Hruby 2006).

^c Wetland Type determined by Grette using the Washington State Wetland Rating System for Western Washington (Hruby 2006).

^d Wetland B was not rated by Grette. Rating shown were determined by ICF based on wetland descriptions provided in Off-Site Alternative—Barlow Point Shoreline Habitat Inventory (Grette Associates 2014h).

Source: Grette Associates 2014h, i

Figure 11. Existing Wetlands in the Direct Impact Study Area – Off-Site Alternative

Open Water

Approximately 8.61 acres of the project area (4%) were identified as open water areas. These areas include the sections of Mount Solo Slough (Appendix E, Photos 47 through 51) and portions of CDID Ditches 14 and 16 that fall within the site boundary (Figure 10).

Aquatic Vegetation

Aquatic vegetation was not assessed or quantified in the study area during either the Grette studies or the ICF field visits. However, Grette Associates (2014e) states that during a separate study near the project area, curly pondweed was observed in an unspecified location off the shoreline in shallow-water habitat (Grette Associates 2014e). Given this observation, it is possible that a narrow band of similar aquatic vegetation could similarly exist along other areas of the shoreline.

Indirect Impact Study Area Vegetation Communities

Table 9 summarizes the areas and percent cover of the different land cover classes in the Off-Site Alternative's indirect impact study area within 1 mile of the project area. Approximately 60% of the indirect impacts study area is occupied by developed lands, open water (primarily the Columbia River) and agricultural lands; and 24% is occupied by wetlands. The remaining 16% consists of forest, shrub, herbaceous, and barren lands.

Table 9. Land Cover in the Indirect Impact Study Area – Off-Site Alternative

Land Cover Classification	Area in Indirect Impact Study Area (acres)	Percent Cover in Indirect Impact Study Area
Developed	978	21
Forest	389	8
Shrub	110	2
Herbaceous	72	2
Agriculture	645	14
Wetlands	1145	24
Open Water	1164	25
Barren land	183	4
TOTAL	4686	100

Source: National Land Cover Data Base 2011 (Homer et al. 2015)

Land use adjacent to the direct impact study area includes agricultural lands and the former Mount Solo Landfill to the north, the closed Black Mud Pond facility and former industrial land of the project area for the On-Site Alternative to the east, and the Columbia River to the south and west. Low-density residential neighborhoods at Barlow Point, Memorial Park, and West Longview also exist further to the north of the project area on the other side of Mt. Solo Road. Adjacent lands within Cowlitz County are zoned for Heavy Manufacturing (Cowlitz County 2015a, b), while those within the Longview city limits are designated as Mixed Use Commercial/Industrial (City of Longview 2015).

Land cover in the indirect impact study area immediately surrounding the direct impact study area is similar to what is described for the direct impact study area, mostly consisting of managed and unmanaged herbaceous areas, wetlands, and open water of the Columbia River. Riparian lands are found predominantly along the Columbia River shoreline and include vegetation growing adjacent to the active channel margin in the riparian zone. These riparian lands consist of two vegetated types, forest and scrub-shrub, with the forested riparian cover type the most prevalent.

- **Riparian forest.** Riparian forest vegetation is dominated by black cottonwood, Oregon ash, red osier dogwood, Columbia River willow, Sitka willow, and Pacific willow. Other species present include big leaf maple, Nootka rose, Himalayan blackberry, trailing blackberry, Scouler's willow, and various native and nonnative grasses and forbs.
- **Riparian scrub-shrub.** Riparian scrub-shrub vegetation consists of relatively sparse shrubs including noxious weeds (primarily indigobush and Himalayan blackberry), as well as native shrubs such as Pacific crabapple and big leaf maple. Occasional black cottonwood trees are also present. Scattered patches of spikerush occur in the herbaceous layer along with other native and nonnative grasses and forbs. Standing snags also occur in this area.

Higher quality vegetation communities in the indirect impact study area include the plant communities described for the On-Site Alternative (Section 2.2.2.3 *Indirect Impact Study Area Vegetation Communities*): Mount Solo, Mint Farm Wetland Mitigation Sites, and Lord Island. In addition, three other high-quality vegetation communities are present.

- **Walker Island.** Walker Island is a 190-acre island in the Columbia River that is downstream from Lord Island and connected to that island by a narrow sand spit. Like Lord Island, it was previously used for dredged material disposal but is now heavily forested. It includes tidal marshes on its southern shoreline that provide high-quality habitat for a variety of waterfowl and other wildlife species (Oregon Wetlands Joint Venture 1994:20).
- **Willow Grove Wetland Complex.** The Willow Grove Wetland Complex consists of 388 acres of Category I tidal fringe wetlands that are indirectly connected to the Columbia River by Coal Creek Slough (Ecological Land Services, Inc. 2014:6). Vegetation includes a mix of native and nonnative emergent plants, with native shrubs and trees dominant along tidal channels and shoreline areas. Although the vegetation in this area has been degraded by past grading and ditching activities, it is still a high-quality vegetation community because it is a relatively intact and functional intertidal wetland area that provides habitat for a variety of species including bald eagle, peregrine falcon, and a variety of waterfowl, as well as ESA-listed salmonids. The Willow Grove Wetland Complex is owned by Columbia Land Trust (312 acres) and Port of Longview (76 acres) and is used for wetland preservation and mitigation purposes (Ecological Land Services, Inc. 2014:6).
- **Hump-Fisher Islands.** Hump-Fisher Islands are a 400-acre island complex located in the Columbia River downstream from the project area and from Lord and Walker Islands. Similar to Lord and Walker Islands, Hump-Fisher Islands support native forested vegetation, as well as tidal marshes and provides important wildlife habitat.

2.2.3.3 Special-Status Species

Botanical surveys for special-status species have not been conducted in the project area or in its vicinity. Based on the typical habitat description, soil type, and associated plant species presented in

Table 3, ICF identified potentially suitable habitats in the project area that could support the following species.

- **Nelson's checker-mallow.** Given its regional distribution, documented occurrence within Cowlitz County, and association with semidisturbed habitats and species, Nelson's checker-mallow could occur in the project area. Potential occurrence locations in the project area include within and around the edges of the herbaceous fields, along the drainage ditches, and around the perimeter of the forested areas.
- **Western wahoo.** Potential habitat for western wahoo in the project area exists in and around Wetlands B and 2 and in the forested riparian areas.
- **Western false dragonhead.** Potential habitat for western false dragonhead occurs in and around Wetlands B and 2 and in other low, wet places in the project area.
- **Loose-flowered bluegrass.** Potential habitat for loose-flowered bluegrass in the project area exists in and around Wetlands 2 and Y, and possibly along Mount Solo Slough and the CDID ditches bordering the project area.
- **Soft-leaved willow.** Potential habitat for soft-leaved willow in the project area occurs in the forested and scrub-shrub areas along the Columbia River and possibly in and around Wetlands B and Y.
- **Columbia water-meal.** Given its regional distribution, documented occurrence within 0.5 mile of the project area, and its known association with ponded habitats and more common species such as duckweed, this species could occur in Mount Solo Slough and the CDID ditches on the site.

Refer to Section 2.2.2.4, *Special-Status Species* for the blooming/optimal field survey times for these species.

2.2.3.4 Noxious weeds

Table 10 presents the noxious weed species identified in the project area during various site investigations, along with the typical vegetation communities in which they have been observed.

Three of the same Class B noxious weed species documented in the project area for the On-Site Alternative have been documented in the project area for the Off-Site Alternative; these plants are considered a priority by the Cowlitz County Noxious Weed Control Board for weed control to prevent new infestations and to contain existing populations.

- **Indigobush.** Indigobush occurs along the shoreline edge of the project area, along the active channel margin of the Columbia River and in the riparian plant community, continuing east into the riparian plant community along the shoreline of the project area for the On-Site Alternative (Grette Associates 2014h).
- **Scotch Broom.** Scotch broom is present in scattered patches throughout the project area, including in the wetland buffers. It is also a component of the forested and scrub-shrub upland areas (Grette Associates 2014g, i).
- **Eurasian Watermilfoil.** Eurasian watermilfoil is present in the CDID Ditch 10 along the south side of Industrial Way/Mt. Solo Road (Grette Associates 2014i).

Table 10. Noxious Weeds Identified in the Project Area—Off-Site Alternative

Noxious Weed Species		Location Observed ^{a, b}	Classification		State/County Priority Weed for Control? ^d
Common Name	Scientific Name		State ^c	Cowlitz County ^d	
Indigobush	<i>Amorpha fruticosa</i>	Riparian ^{a, b}	B	B	Yes/no
Scotch broom	<i>Cytisus scoparius</i>	U ^{a, b}	B	B	No/Yes
Eurasian water milfoil	<i>Myriophyllum spicatum</i>	OW ^a	B	B	Yes/No
Canada thistle	<i>Cirsium arvense</i>	W/U ^{a, b}	C	C	No/Yes
Reed canarygrass	<i>Phalaris arundinacea</i>	W/U ^{a, b}	C	Not listed	No/No
Himalayan blackberry	<i>Rubus armeniacus</i>	U ^{a, b}	C	C	No/No
Nonnative cattail	<i>Typha angustifolia</i>	W ^a	C	C	No/No

^a Observations made by Grette Associates, as presented in in Grette Associates 2014g, h, i, Location: W = wetland; U = upland; and OW = open water.
^b Observations made by ICF during visual reconnaissance of project area without site access in December 2014;
^c State noxious weed classification based on Washington State Noxious Weed Control Board 2015 Noxious Weed List.
^d County noxious weed classification and priority for weed control (state and county level) based on Proposed 2015 Cowlitz County Noxious Weed List (Cowlitz County Noxious Weed Control Board 2015)

Four of the same Class C noxious weed species documented in the project area for the On-Site Alternative have been documented in the project area for the Off-Site Alternative; these plants are not typically considered a priority by the Cowlitz County Noxious Weed Control Board for weed control because they are already widespread throughout the state.

- **Canada thistle.** Canada thistle is present in the riparian zone along the Columbia River (Grette Associates 2014h) and was observed by ICF during the December 2014 site visit as a scattered component of the disturbed upland areas of the project area.
- **Reed canarygrass.** Reed canarygrass is the dominant plant species in several of the wetlands in the project area, including Wetlands 1, 4, 5, and 6 (Grette Associates 2014i). It is also present in Wetlands 2 and 3 and in riparian zone within Wetland B and throughout the understory of the riparian zone (Grette Associates 2014h). Reed canarygrass is also a common component of the disturbed uplands throughout the project area (Grette Associates 2014g).
- **Himalayan blackberry.** Himalayan blackberry is present in Wetland 6 and is a common component in the understory of the upland forested and scrub-shrub areas of the project area, particularly along the northern edge of the site (Grette Associates 2014g).
- **Nonnative cattail.** Nonnative cattail was recorded within Wetland 6 (Grette Associates 2014g) and could be present in the stormwater conveyance feature along the northern edge of the project area.

This chapter describes the impacts on vegetation that could result from construction and operation of the On-Site Alternative, Off-Site Alternative, or the ongoing activities of the No-Action Alternative.

3.1 On-Site Alternative

Potential impacts on vegetation from the On-Site Alternative are described below.

3.1.1 Construction: Direct Impacts

Construction of the On-Site Alternative would result in the following direct impacts.

Permanently Remove Vegetation

Construction of the On-Site Alternative would require removal of vegetation as shown on Figure 12. Clearing and grading would result in the permanent removal of approximately 212 acres of land cover types from the direct impact study area (Table 11). The majority (71%) of the total impact would occur in areas occupied by the disturbed cover type (i.e., scattered grasses and weeds in and around the developed portions of the project area). These areas of disturbed vegetation are early successional and weedy areas that generally do not support native plant species or provide suitable wildlife habitat.

Under the On-Site Alternative, approximately 26.26 acres of upland vegetation or 12% of the total upland vegetation within the project area would be removed (Table 11). Herbaceous upland vegetation surrounding Wetlands A, C, and Z make up the majority of this acreage. These herbaceous upland areas are generally dominated by reed canarygrass. Approximately one-third of the upland forest in the project area would be removed. The majority of the 8.90 acres of upland forest impacts would occur to the upland forested areas surrounding Wetland A and the upland forested areas surrounding the interception ditch and stormwater conveyance feature SC11. These areas are dominated by native trees, primarily black cottonwood, red alder, Oregon ash, and Pacific willow trees, with an understory of mixed native and invasive shrubs dominated by red elderberry, sweetbriar rose, and Himalayan blackberry. The impacts would occur because of construction of the rail loop, stockpile pads, and a series of stacking and reclaim conveyors.

Approximately 0.05 acre of upland forest impact consists of riparian forest. These impacts would occur because of construction of the trestle conveyor that connects the surge bin to Docks 2 and 3, and would include the removal and trimming of black cottonwood and willow trees and understory shrubs such as red-osier dogwood and Himalayan blackberry.


Figure 12. Impacts on Existing Land Cover Classes and Vegetation Cover Types in the Direct Impact Study Area – On-Site Alternative

Table 11. Permanent Direct Impacts by Land Cover and Vegetation Cover Type in the Project Area

Land Cover Category	Vegetation Cover Type	Impacts (Acres)^b	Percentage of Cover Type^{c, d}
Developed land	Developed land total	151.14	71
Upland	<i>Forested</i>	<i>8.90</i>	<i>4</i>
	<i>Scrub-shrub</i>	<i>2.11</i>	<i>1</i>
	<i>Herbaceous</i>	<i>10.88</i>	<i>5</i>
	<i>Managed herbaceous</i>	<i>4.37</i>	<i>2</i>
	Upland total	26.26	12
Wetlands ^a	PFO	<i>6.28</i>	<i>3</i>
	PEM/PFO	<i>3.38</i>	<i>2</i>
	PEM	<i>13.87</i>	<i>7</i>
	PEM/PSS	<i>0.57</i>	<i>0</i>
	Wetlands total	24.10	11
Open water	Open water total	10.78	5
Total		212.28	100

^aCowardin classification per Classification of Wetland and Deepwater Habitats of the United States (Cowardin et al. 1979). Values include PFO = palustrine forested; PSS = palustrine scrub-shrub; PEM = palustrine emergent

^bThese are direct impacts on vegetation in the 212-acre project area, which includes the 190 acre terminal plus additional elements (e.g. access roads, docks, and rail line).

^cThis column represents the percent of cover type in the direct impacts study area affected by construction.

^dTotal does not equal sum of values due to rounding.

Affect Special-Status Plants

Although no special-status plant species have been recorded in the project area, potentially suitable habitat is present. Should any special-status plant species occur in the project area, they would likely be permanently removed as a result of project construction. As mentioned previously, six special-status plant species were identified as potentially occurring in the study area for direct impacts, based on the presence of potentially suitable habitat. These plant species are Nelson's checker-mallow, western wahoo, western false dragonhead, loose-flowered bluegrass, soft-leaved willow, and Columbia water-meal. The spatial extent of any impact on special-status plants cannot be quantified until a special-status plant survey is conducted. Such surveys would be required mitigation. These surveys would occur during the appropriate time of year, prior to any On-Site Alternative-related construction activities beginning. If special-status plants are identified by the survey, the impact would be mitigated through Cowlitz County's Critical Areas Ordinance mitigation requirements for special-status plants (19.15.170).

Temporarily Disturb Adjacent Vegetation during Construction

Construction activities could temporarily affect vegetation adjacent to the project area, including wetland and riparian vegetation, through vehicle usage, material storage and stockpiling, and

ground disturbance. Construction and staging activities along the edges of the project area could result in the crushing and burying of adjacent vegetation and compaction of soil by construction equipment and material staging. Such impacts are not likely to permanently alter the vegetation in these areas, as the areas would likely revegetate with similar species following completion of construction. Ground disturbance related to these activities could also increase the opportunity for stormwater runoff to carry sediments, spilled vehicle fluids, or other construction materials into areas outside of the project area, potentially affecting the health and vigor of the vegetation in these areas. Depending on the extent, duration, and content of this runoff, vegetation could be affected through interference with photosynthesis, respiration, growth, and/or reproduction. Dust from construction activities could also affect vegetation by collecting on leaves and other plant surfaces, potentially inhibiting photosynthesis and other plant functions. Depending on the material used and the BMPs employed, the 35-foot-high preload material piles could provide an area for invasive plant species, including noxious weeds, to temporarily colonize. Such conditions would provide a seed source that could be readily dispersed into adjacent areas by wind and runoff, increasing the potential for invasive species and noxious weeds to spread and displace native vegetation.

The potential for temporary construction impacts on vegetation would be minimized by adhering to permit conditions, such as those required by the National Pollutant Discharge Elimination System Construction Stormwater General Permit from Washington State Department of Ecology (Ecology) and the Fill and Grade Permit, Critical Areas, Shoreline Development, and Floodplain Development permits issued by Cowlitz County. Compliance with these permits would require implementation of the Stormwater Drainage Control Plan, Temporary Erosion and Sedimentation Control Plan, and other relevant BMPs to reduce the potential for soil erosion during construction and related impacts on water quality or adjacent vegetated areas. This would also require developing and implementing a Spill Prevention, Control, and Countermeasures Plan and a site-specific Construction Stormwater Pollution Prevention Plan that includes BMPs for equipment and material handling and construction waste management. Implementation of the measures outlined in these plans would reduce the potential for temporary construction impacts on vegetation from construction equipment and materials usage.

3.1.2 Construction: Indirect Impacts

Construction of the On-Site Alternative would not result in indirect impacts on vegetation because the effects of construction would be limited to the project area.

3.1.3 Operations: Direct Impacts

Direct impacts on vegetation from operation of the terminal at the On-Site Alternative location would likely be limited to the continued existence or possible colonization by noxious weeds around the periphery of the project area, impacts from vessel loading and transport along rail tracks, and control of vegetation under the conveyor and along the rail tracks and rail loop.

Operation of the On-Site Alternative would result in the following direct impacts.

Colonization by Noxious Weeds

Because the project area would be mostly developed, colonization of the project area by native plants would not likely occur during operations. Invasive plant species, including several of the noxious weed species already present in and around the project area, are generally adapted to colonize highly disturbed areas and could thus colonize the periphery of the project area. Reed canarygrass, Himalayan blackberry, Canadian and/or bull thistle, and Scotch broom are the noxious weed species most likely to occur in and around the project area. These species are already present on the project area and are common in adjacent areas, and would likely continue to persist during operations. Areas along rail tracks, along stacking conveyors, and between tracks of the rail loop would be most likely to support such noxious weed species in scattered patches.

Disturb Vegetation As a Result of Rail Transport and Vessel Loading in the Project Area

Operation of the terminal could disturb upland, wetland, and riparian vegetation along the rail tracks entering the project area and along the shoreline of the Columbia River, as well as scattered areas of aquatic vegetation that could be present in the shallow waters of the Columbia River near the site. Such impacts could occur as the result of potential spills of coal or other materials or fluids associated with operation of the machinery and equipment associated with the trains and rail cars, the export terminal's conveyor and stockpiling systems, the mobile equipment used to maintain the facilities, and the shiploaders. Direct impacts on aquatic vegetation along the shoreline of the Columbia River cannot be quantified until an aquatic vegetation survey(s) is conducted and occurrence of aquatic vegetation is determined.

Impacts on water quality associated with the routine movement of coal across the shoreline zone and along the shiploaders into vessels at the docks could also affect vegetation along or in receiving waters. However, stormwater runoff would be collected at the project area and treated to remove potential contaminants associated with the operations and maintenance activities (e.g., coal, diesel fuel, oil, hydraulic fuel, antifreeze, tire, and brake dust, exhaust particulates) prior to discharge to the Columbia River. BMPs and mitigation to reduce potential water quality impacts are detailed in the NEPA Water Quality Technical Report (ICF International 2016e).

Although spills or leaks could occur as the result of human error or minor equipment failure, the potential for these to occur and affect the environment would be minimized by appropriate training and the implementation of prevention and control measures. BMPs and mitigation to reduce potential impacts from spills and leaks are detailed in the NEPA Hazardous Materials Technical Report (ICF International 2016f), the NEPA Vessel Transportation Technical Report (ICF International 2016g) and the NEPA Rail Transportation Technical Report (ICF International 2016h). Specifically, prior to the commencement of operations, all personnel would be trained in proper operating and spill-prevention procedures. Specific prevention and response actions would be described in the export terminal's spill prevention, control, and countermeasure plan. All conveyors and loading equipment would be regularly inspected and promptly repaired as necessary. During loading operations, the dock would be constantly attended to by the terminal operator who would have the ability to immediately stop a transfer if a spill or leak occurred from the conveyors, shiploaders, or other equipment. If a spill occurs, it must be reported and cleanup actions taken. Depending on the spill, a natural resource damage assessment could be required under WAC 173-183, Oil Spill Natural Resource Damage Assessment.

Affect Vegetation during Maintenance of Vegetation under Conveyor to Docks 2 and 3

Vegetation maintenance during operation of the terminal could affect riparian trees and tall shrubs beneath and adjacent to the conveyor that would be used to transport coal from the storage facility to the shiploaders on Docks 2 and 3. Trees and tall shrubs in the approximately 45- to 50-foot-wide area beneath and around the conveyor would likely be regularly trimmed and/or removed to ensure that branches and leaves do not interfere with the operation of the conveyor. This maintenance would limit the height of trees and the aerial spread of shrubs that develop in this location, slightly reducing the ability of the site's shoreline to provide organic material to the river, shade the upper beach and shoreline, and provide native foraging, resting, and perching opportunities for passerine birds. This area is small, however, relative to the total length of vegetated shoreline.

Affect Vegetation during Maintenance of Vegetation along Rail Tracks and Rail Loop

Routine vegetation maintenance during operation of the terminal could affect both upland and wetland vegetation along the perimeter road and rail tracks entering the project area and along the rail loop used to stage trains within the site. Trees and tall shrubs within approximately 25 feet of either side of the perimeter road surrounding the tracks would likely be trimmed to ensure branches and leaves do not interfere with the movement of the rail cars into and through the site. Similarly, any vegetation that colonizes the interior of the site along the rail loop would likely also be removed, controlled, or trimmed to eliminate any interference with the movement of the rail cars, equipment, or personnel. This maintenance would result in artificial stunting of tree and shrub species in these areas; it would not reduce the functions of native plant communities, however, because it would be confined to the outermost edges of such communities.

Affect Special-Status Plants

Any special-status plants that occur in areas along the periphery of the project area, along the rail tracks and rail loop, or under the conveyor would be affected by operation of the export terminal in the same manner as described above. The potential for and spatial extent of any such impact cannot be quantified until a special-status plant survey(s) is conducted and occurrence of special-status species is determined.

Deposit Coal Dust on Vegetation during Operations

Under the On-Site Alternative, the movement of coal into and around the project area, creation of large stockpiles of coal within the project area, and use of 29,100 linear feet of open conveyors to move coal within the project area and onto vessels, create the potential for coal particles and fugitive coal dust to be generated. For example, coal dust deposition was noted within 8 months of the start of coal stockpiling in areas adjacent to and downwind of coal stockpiles associated with a Portland General Electric coal-fired power plant near Boardman, Oregon (approximately 158 miles southeast and across the Columbia River from the project area) (Spencer and Tinnin 1997:476). Similarly, air quality sampling conducted by concerned citizens in Seward, Alaska, downwind of the Seward Coal Loading Facility, indicated that the air samples collected on windy days while coal was being loaded or unloaded at the facility were highly enriched with total carbon in the form of particulate matter. Most of the total carbon in the air samples was organic carbon, indicating the presence of coal dust in the air (Zimmer

2014:4–10). Similarly, coal concentration in estuarine sediments doubled from 1.8 to 3.6% in the uppermost 2 to 3 centimeters of sediment within about 3 square kilometers of the Roberts Bank coal loading terminal in British Columbia, Canada, between 1975 and 1999 (Johnson and Bustin 2006:67).

Although concerns regarding coal dust are commonly articulated relative to air quality and human health concerns, wind-born coal dust can also deposit on vegetation, soils, and sediments. The potential extent and deposition rate of coal dust particles less than 75 microns in diameter was modeled as part of the analysis conducted relative to air quality; see the NEPA Air Quality Technical Report (ICF International 2016a) for additional details.

Based on this modeling, the highest rate of coal dust deposition would be expected in the area adjacent to the project area, but smaller particles would also be expected to deposit in a zone extending around and downwind of the project area. Deposition rates could range from 1.45 grams per square meter per year ($\text{g}/\text{m}^2/\text{year}$) closest to the project area, gradually declining to less than $0.01 \text{ g}/\text{m}^2/\text{year}$ approximately 2.41 miles from the project area.

The zone of deposition includes the coniferous forest vegetation on the hills adjacent to the northern extent of the project area, as well as the riparian vegetation along the shoreline of the river. Deposition rates of less than $0.1 \text{ g}/\text{m}^2/\text{year}$ are projected to occur over the forested communities on Lord Island within the Columbia River just east of the project area, with declining concentrations across the island and to the south and west toward Walker Island.

The effects of dust (arising from a variety of sources) on vegetation vary depending on dust load, climatic conditions, and the physical characteristics of the vegetation. Effects can be physical, such as blocked stomata which alters gas diffusion into/out of the leaves, causing reduced respiration (smothering of leaves) or increased transpiration (water loss), alteration in leaf surface reflectance and light absorption potential, and increased in leaf temperature due to optical properties of the dust including its particle size and color (Chaston and Doley 2006:42–44, Doley 2006:38–41; Farmer 1993:63–66). Such effects can be complex. Experimental manipulation of desert soil dust deposition on the leaves of the endangered Lane Mountain milk-vetch (*Astragalus jaegerianus*), a Mohave desert perennial affected by U.S. Army training center vehicular traffic, showed a decrease in average shoot growth but an increase in seasonal net photosynthesis (Wijayratne et. al. 2009:84–86). Increased leaf temperature caused increased photosynthesis early in the growing season but ultimately resulted in reduced shoot growth as seasonal air temperatures increased.

Research conducted in the more arid climates of eastern Oregon investigated species composition and plant growth of vegetation growing on and off a plume of coal dust, which had deposited adjacent to a coal yard holding area for the Portland General Electric power plant near Boardman, Oregon. Coal dust deposition was correlated with increases in soil temperature and moisture holding capacity; accumulation of iron, copper, zinc, lead, and sulfates; and lower soil pH (Spencer 2001:847–848). While studies did not find significant differences in total plant biomass within and outside of the dust deposition plume, significantly lower frequency of occurrence and lower percent cover of lichens in areas within the coal dust plume was documented (Spencer 2001:847–848; Spencer and Tinnin 1997:479).

It is not known whether the climatic conditions in the area where these studies occurred are directly applicable to the climatic conditions in the study area. Neither the specific mechanisms of effect nor a threshold for potential physical or biological effects of coal dust deposition has

been studied and/or identified relative to the climate and native vegetation of the Columbia River Gorge or the study area. Similarly, there are no studies relative to the deposition rate or particle size at which impacts on native Pacific Northwest tree, shrub, or herbaceous plants would occur. Given the number and variety of environmental, climatic and plant factors affecting the deposition of dust (Doley 2006:36), information regarding foliage density, leaf dimensions and characteristics, as well as particle size distribution, dust color and climatic conditions would likely be needed to determine the level of dust deposition that might potentially affect sensitive plant species or functions.

Cause Release of Coal from a Spill

Direct impacts resulting from a coal spill during coal handling at the export terminal would likely be negligible because the amount of coal that could be spilled would be relatively small. Also, impacts would be minor because of the absence of vegetation in the project area and the contained nature and features of the terminal (e.g., fully enclosed belt conveyors, transfer towers, and shiploaders).

Coal spilled into terrestrial environments could impact vegetation. Herbaceous vegetation would be more susceptible to damage and smothering from a coal spill compared to more rigid, woody vegetation like shrubs and trees, which could be better able to withstand the weight and force of a coal spill, depending on the magnitude of the spill. The magnitude of potential impacts would depend on the size (volume) and extent (area) of the coal spill. The physical impact of coal spilled on vegetation would range from minor plant damage to complete loss of vegetation. Some plant species could be more sensitive to coal than other species. Coal dust associated with a coal spill could also cover vegetation, resulting in reduced light penetration and photosynthesis, which could lead to reduced vegetation density and plant diversity. The magnitude of a coal dust impact would depend on duration of exposure, tolerance of vegetation, and aggressiveness of nonnative species. Cleanup of coal spilled during operations could further affect vegetation by either removing or further damaging vegetation because of ground disturbance related to cleanup activities. Any pieces of residual coal that might remain on the ground after a cleanup effort could leach chemicals from exposure to rain, which could damage or kill vegetation. However, if this were to occur, the impact area would generally be highly localized, limited to the extent of the spill, and unlikely to disrupt the overall plant ecosystem.

3.1.4 Operations: Indirect Impacts

Operation of the On-Site Alternative would result in the following indirect impacts.

Deposit Coal Dust on Vegetation

The movement of coal by rail along the BNSF spur and Reynolds Lead could generate coal particles and fugitive coal dust, which could be deposited on vegetation, soil, and sediments in the study area. Coal transported by vessel would be in enclosed cargo holds and is not likely to result in deposition of coal on vegetation along the vessel route in the Columbia River. Potential impacts from coal dust deposition on vegetation is described the *Operations—Direct Impacts* section.

Cause Erosion of Vegetation due to Vessel Wakes during Operations

Operation of the On-Site Alternative could result in indirect impacts on vegetation along the shoreline of the Columbia River related to increased vessel traffic and associated vessel wakes and sediment erosion.

There could be an increase in the potential for impacts on vegetation associated with vessel wakes compared with current conditions. Approximately six vessels per year currently deliver alumina over Dock 1 to the existing bulk product terminal. Operation of the On-Site Alternative at maximum throughput would result in the loading and movement to and from the export terminal of 70 vessels per month (80% Panamax size; 20% Handymax size) at Docks 2 and 3 or 1,680 vessel transits a year. Shoreline erosion is a natural process that removes sediments from the shoreline; it is caused by a number of factors including storms, wave action, and wind. The removal of shoreline sediment can remove the substrate in which vegetation grows, eventually leading to loss of plants. Although erosion is not intrinsically harmful, it can be increased by vessel wakes, which can intensify the effects and/or rate of the erosion process. In riverine environments the wave periods of vessels are longer compared to waves generated by wind. River bank vegetation is naturally adapted to shorter period of wind waves, but not to long periods, which may be present in vessel wakes. The introduction of long-period waves brings a new erosion mechanism to which the riverbank vegetation may be susceptible (Macfarlane and Cox 2004 in Gourlay 2011). While vessel wakes and associated shoreline erosion of the Columbia River currently occurs due to existing vessel traffic, the operations of the proposed export terminal would increase vessel traffic and could potentially increase or intensify the extent and/or rate of shoreline erosion process and subsequent loss of shoreline vegetation.

Increased vessel traffic in the Columbia River has the potential to increase vessel wakes, which could cause an increase in shoreline erosion and possibly affect vegetation. The average number of annual vessel transits in the Columbia River over a 5-year period (2010–2014) is approximately 3,358 (ICF International 2016g). With operation of the On-Site Alternative at maximum throughput and projected growth in other commercial vessel traffic, annual transits are expected to increase up to 7,342 by 2024–2027 when the export terminal becomes operational and up to 8,672 moving beyond 2028. The potential for vessel wake impacts on vegetation along the shoreline in the immediate vicinity of the project area is limited due to the slope of the shoreline and the general lack of aquatic vegetation near the docks. Additionally, On-Site Alternative-related vessels maneuvering near the docks would be moving slowly as they prepare to dock, and likely not putting out a wake sufficient to cause shoreline erosion. However, there could be a potential for such impacts on the thin strip of shoreline vegetation along the northern end of Lord Island from large wakes, and/or wakes oriented perpendicular to the main navigation channel and docks, such as those that can occur when tugs are oriented perpendicular to the shoreline as they push vessels into position at docks. However, the impact on shoreline vegetation associated with vessel wakes cannot be quantified or measurably attributed to potential On-Site Alternative-related vessels.

The actual extent, location, and magnitude of shoreline erosion impacts is influenced by the complex interaction of multiple factors that affect when, where, and with what intensity vessel wakes would interact with the shorelines of the river. Such factors can include vessel design, hull shape, vessel weight and speed, angle of travel relative to the shoreline, proximity to the shoreline, currents and waves, and water depth (Jonason 1993:29–30; MARCOM 2003). The potential for shoreline erosion can also be influenced by the slope and physical character of the

shoreline (i.e., soil susceptibility to erosion), as well as the amount and type of vegetation that occurs along the shoreline. Measures that could be implemented to reduce shoreline erosion and impacts to vegetation could include actions outside the control of the applicant and permitting agencies; these actions include, but are not limited to; soft beach armoring, planting of native vegetation, and bank armoring.

Affect Special-Status Plants

Any special-status plants that occur in areas along the along the rail tracks entering the project area, along the shoreline of the Columbia River, or in any area receiving coal dust deposition could be indirectly affected by operation of the export terminal in the same manner as described above. The potential for and spatial extent of any such impact cannot be quantified until a special-status plant survey(s) is conducted and occurrence of special-status species is determined.

3.2 Off-Site Alternative

Potential impacts on vegetation from the Off-Site Alternative are described below.

3.2.1 Construction: Direct Impacts

Construction of the Off-Site Alternative would result in the following direct impacts.

Permanently Remove Vegetation

Vegetation would be removed from the project area as depicted in Figure 13.

Construction of the Off-Site Alternative would result in the permanent removal of a total of approximately 225 acres of land cover types, from the project area (Table 12), similar to the removal of 212 acres under the On-Site Alternative. However, the majority of the vegetation impact (56%) under the Off-Site Alternative would occur in areas characterized as herbaceous upland vegetation (i.e., large areas of unmaintained grasses that support a mixture of native and invasive plant species that provide some wildlife habitat); under the On-Site Alternative, the majority of the impact (71%) would be to developed lands mostly characterized as disturbed vegetation areas.

The impacts on these forested areas would occur as a result of construction of the buildings and surge bin components and the southeastern end of the stockpiles. Vegetation removed would include black cottonwood, willow, and red alder trees. Approximately 0.01 acre of upland scrub-shrub impact consists of riparian scrub-shrub vegetation. Vegetation removed would include noxious weed species (indigobush and Himalayan blackberry) and native species such as Pacific crabapple and big-leaf maple. The impacts would occur as a result of installation of the new stormwater outfall.

The Off-Site Alternative would remove nearly six times the area of upland vegetation compared to the On-Site Alternative (155.46 acres compared to 26.26 acres).

Figure 13. Impacts on Existing Land Cover Classes and Vegetation Cover Types in the Direct Impact Study Area – Off-Site Alternative

Table 12. Permanent Direct Impacts by Land Cover and Vegetation Cover Type in the Project Area—Off-Site Alternative

Land Cover Category	Vegetation Cover Type	Impacts (Acres)	Percentage of Cover Type
Developed Land	Developed Land Total	9.62	4
Upland	<i>Forested</i>	<i>6.74</i>	<i>3</i>
	<i>Scrub-Shrub</i>	<i>4.42</i>	<i>2</i>
	<i>Herbaceous</i>	<i>126.57</i>	<i>56</i>
	<i>Managed Herbaceous</i>	<i>17.73</i>	<i>8</i>
	Upland Total	155.46	69
Wetlands	PEM	<i>30</i>	<i>13</i>
	PSS	<i>3</i>	<i>1</i>
	PFO/PEM	<i>17</i>	<i>8</i>
	PFO/PSS	<i>0.08</i>	<i><.001</i>
	PEM/PSS	<i>1.2</i>	<i>1</i>
	Wetland Total	51.28	23
Open Water	Open Water Total	8.61	4
Total		224.97	100

Affect Special-Status Plants

Any special-status plants that occur within the footprint of project construction would be permanently affected by construction in the same manner as described for the various vegetation cover types. The potential for and spatial extent of any such impact cannot be quantified until a special-status plant survey(s) is conducted and occurrence of special-status species is determined.

Temporarily Disturb Adjacent Vegetation during Construction

Construction activities could temporarily affect vegetation adjacent to the project area. This could include temporary disturbance to riparian vegetation along the shoreline of the Columbia River, which is closer to the outer extent of the rail loop configuration under the Off-Site Alternative than for the On-Site Alternative. Temporary disturbance could occur through the same mechanisms described for the On-Site Alternative.

The potential for temporary construction impacts on vegetation would be avoided and minimized by adhering to permit conditions described for the On-Site Alternative (Section 3.1.1.1, *Construction: Direct Impacts*).

3.2.2 Construction: Indirect Impacts

Construction of the Off-Site Alternative would not result in indirect impacts on vegetation because effects of construction would be limited to the project area.

3.2.3 Operations: Direct Impacts

Operation of the Off-Site Alternative would be similar to that described for the On-Site Alternative (Section 3.1.1.2, *Operations: Direct Impacts*) and result in the following direct impacts.

Result in Colonization by Noxious Weeds

The potential for the Off-Site Alternative to result in colonization by noxious weeds would be the same as described for the On-Site Alternative. The magnitude of the potential impacts could be greater under the Off-Site Alternative because of the extent of the vegetation, the relatively lower occurrence of noxious weeds, and the larger extent of ground disturbance that would occur at the Off-Site Alternative project area. Colonization by noxious weeds could increase the prevalence of such species in an area of closer proximity to intact native vegetation (e.g., Willow Grove Wetland Complex).

Disturb Vegetation as a Result of On-Site Rail Transport and Vessel Loading during Operations

Operation of the Off-Site Alternative could affect riparian forested and scrub-shrub vegetation along the shoreline of the Columbia River, as well as scattered areas of aquatic vegetation that could be present in the shallow waters of the Columbia River near the project area. The mechanisms and likelihood of these impacts is the same as described for the On-Site Alternative.

Affect Vegetation during Maintenance of Vegetation under Conveyor to Docks A and B

The potential for the Off-Site Alternative to affect vegetation during maintenance of vegetation under the proposed docks would be the same as described for the On-Site Alternative (Section 3.1.1.3, *Operations: Direct Impacts*).

Affect Vegetation during Maintenance of Vegetation along Rail Tracks and Rail Loop

Operation of the Off-Site Alternative could affect both upland and wetland vegetation along the rail tracks entering the project area, including a large portion of Wetland Y, and along the rail loop used to stage coal within the site. Trees and tall shrubs within approximately 25 feet of either side of the perimeter road surrounding the tracks would likely be trimmed to ensure branches and leaves do not interfere with the movement of the rail cars into and through the site. This maintenance would result in direct impacts on the shrubs in Wetland Y and a degree of artificial stunting of tree and shrub species in the adjacent affected uplands by reducing the ability of this largely native plant community to provide wildlife habitat for songbirds and other animals and shading for this linear wetland.

Affect Special-Status Plants

Any special-status plants that occur in areas along the periphery of the project area, along the rail tracks and rail loop, or under the conveyor would be affected by operation of the export terminal in the same manner as described above. The potential for and spatial extent of any such impact cannot be quantified until a special-status plant survey(s) is conducted and occurrence of special-status species is determined.

Deposit Coal Dust on Vegetation during Operations

As described for the On-Site Alternative, the movement of coal into and around the project area, and the creation of large stockpiles of coal within the site, and the use of 17,900 linear feet of open conveyors within the site create the potential for coal dust could become wind-born and deposit on vegetation (ICF International 2016a).

The highest rate of coal dust deposition would be expected in the immediate area surrounding the project area, but smaller particles would also be expected to deposit in a zone extending around and downwind of the export terminal. Deposition rates could range from 1.83 g/m²/year closest to the export terminal, gradually declining to less than 0.01 g/m²/year at approximately 2.98 miles from the terminal.

As noted for the On-Site Alternative, neither the mechanisms of effect nor a threshold for any potential physical or biological effects of coal dust deposition have been studied relative to the climate and native vegetation of the Pacific Northwest. Similarly, there are no studies relative to the deposition rate or particle size at which impacts on native Pacific Northwest vegetation species would occur.

The potential effect of coal dust would be similar to that expected from the On-Site Alternative but would include an area extending further downriver. The zone of deposition includes the coniferous forest vegetation on the hills adjacent to the northern extent of the project area, as well as the riparian vegetation along the shoreline of the river. Coal dust would be expected to temporarily settle on some areas of higher quality native vegetation in the study area at a rate of approximately less than 0.1 g/m²/year, including the native wetland vegetation communities of the Willow Grove Wetland Complex, as well as the native forested communities on Walker Island, Fisher Island, and Hump Island within the Columbia River, which could affect vegetation. However, given the number and variety of environmental and plant factors that affect the deposition of dust (Doley 2006:36), information regarding foliage density, leaf dimensions and characteristics, and particle size distribution and dust color would likely be needed in order to determine the level of dust deposition that might pose a potential to affect sensitive plant species or functions.

Cause Release of Coal from a Spill

Direct impacts on the natural environment from a coal spill during operations of the Off-Site Alternative could occur. Direct impacts resulting from a spill during coal handling at the export terminal would likely be negligible because the amount of coal that could be spilled would be relatively small. Also, impacts would be minor because of the absence of terrestrial environments in the project area and the contained nature and features of the terminal (e.g., fully enclosed belt conveyors, transfer towers, and shiploaders).

Coal released as the result of a spill into terrestrial environments could result in impacts. Herbaceous vegetation would be more susceptible to damage and smothering from a coal spill compared to more rigid, woody vegetation like shrubs and trees, which could be better able to withstand the weight and force of a coal spill, depending on the magnitude of the spill. The magnitude of potential impacts would depend on the size (volume) and extent (area) of the coal spill. The physical impact of coal spilled on vegetation would range from minor plant damage to complete loss of vegetation. Some plant species could be more sensitive to coal than other species. Coal dust associated with a coal spill could also cover vegetation, resulting in reduced

light penetration and photosynthesis, which could lead to reduced vegetation density and plant diversity. The magnitude of a coal dust impact would depend on duration of exposure, tolerance of vegetation, and aggressiveness of nonnative species. Cleanup of coal spilled during operations could further affect vegetation by either removing or further damaging vegetation as a result of ground disturbance related to cleanup activities. Any pieces of residual coal that might remain on the ground after a cleanup effort could leach chemicals from exposure to rain, which could damage or kill vegetation. However, if this were to occur, the impact area would generally be highly localized and limited to the extent of the spill and unlikely to disrupt the overall plant ecosystem.

3.2.4 Operations: Indirect Impacts

Operation of the Off-Site Alternative would result in the following indirect impacts.

Cause Erosion of Vegetation due to Vessel Wakes during Operations

Operation of the Off-Site Alternative could result in indirect impacts on tidal marsh vegetation along the shoreline of the Columbia River related to increased vessel traffic and associated vessel wakes and sediment erosion. Like the On-Site Alternative, there would be 1,680 vessel transits per year at the Off-Site Alternative.

Increased vessel traffic in the Columbia River has the potential to increase the impact of vessel wakes, which could cause an increase in shoreline erosion and affect vegetation in low-lying areas along the shoreline of the river through the same mechanisms and to the same extent as could occur under the On-Site Alternative, in that the impact on shoreline vegetation associated with vessel wakes cannot be quantified or measurably attributed to potential project related vessels.

The actual extent, location, and magnitude of potential shoreline erosion impacts is influenced by the complex interaction of multiple factors that affect when, where, and with what intensity vessel wakes would interact with the shorelines of the river, including vessel design, hull shape, vessel weight and speed, angle of travel relative to the shoreline, proximity to the shoreline, currents and waves, and water depth (Jonason 1993:29–30; MARCOM 2003). The potential for shoreline erosion can also be influenced by the slope and physical character of the shoreline (i.e., soils susceptibility to erosion), as well as the amount and type of vegetation that occurs along the shoreline.

There could be a potential for such impacts on the thin strip of shoreline vegetation along the north\eastern end of Walker Island from large wakes, and/or wakes oriented perpendicular to the main navigation channel and docks, such as those that can occur when tugs are oriented perpendicular to the shoreline as they push vessels into position at docks.

Affect Special-Status Plants

Any special-status plants that occur in areas along the along the rail tracks entering the project area, along the shoreline of the Columbia River, or in any area receiving coal dust deposition could be indirectly affected by operation of the export terminal in the same manner as described above. The potential for and spatial extent of any such impact cannot be quantified until a special-status plant survey(s) is conducted and occurrence of special-status species is determined.

3.3 No-Action Alternative

Under the No-Action Alternative, impacts on vegetation related to construction and operation of the export terminal would not occur. The Applicant would continue to operate the existing bulk product terminal and could develop the project area for another use.

If the On-Site Alternative project area is developed for another use, these activities would not trigger a Clean Water Act permit, a new waste discharge permit, or shoreline permit; thus, no impacts on wetland vegetation or riparian vegetation within the shoreline zone would occur. Continued industrial use of the project area would likely result in the redevelopment of the largely developed upland areas of the project area. New construction, demolition, and activities related to this development could result in impacts on the areas of disturbed vegetation (i.e., scattered grasses and weeds) that are present throughout the developed portions of the site.

Although construction of the export terminal would not occur, it is assumed that growth in the region would continue, which would allow continued operations in the project area within the 20-year analysis period (2018 to 2038). Cleanup activities, relative to past industrial uses, would continue to occur. This could result in impacts on developed areas and associated disturbed vegetation in a similar manner as described for the On-Site Alternative and Off-Site Alternative

Chapter 4

Required Permits

Either the On-Site Alternative or the Off-Site Alternative would require the following permits related to vegetation.

- **Clean Water Act Section 404 Permit and Rivers and Harbors Act Section 10 Permit.** The Corps must issue a Section 404 Permit for all work in waters of the United States and a Section 10 permit for all work within navigation waters. The On-Site Alternative or Off-Site Alternative would affect wetlands (waters of the United States) and would require work within the Columbia River (navigable waters). Therefore, either alternative would require both a Clean Water Act Section 404 permit and a Rivers and Harbors Act Section 10 Permit.
- **Local Critical Areas and Construction Permits.** The On-Site Alternative or Off-Site Alternative would require local permits related to clearing and grading of the project area and relative to impacts on regulated critical areas. Cowlitz County would require an application for planning clearance, a fill and grade permit, and a shoreline permit. The County would review either the On-Site Alternative or the Off-Site Alternative for consistency with the County's critical areas ordinance.

The Applicant will implement proposed BMPs that minimize the potential for erosion, including a stormwater pollution prevention plan. The Applicant will complete these activities far in advance of construction.

Chapter 5

References

- Chaston, K. and D. Doley. 2006. Mineral particulates and vegetation: Effect of coal dust, overburden and flyash on light interception and leaf temperature. *Clean Air and Environmental Quality* 40:1
- Christy, J.A. and J.A. Putera. 1993. Lower Columbia River Natural Area Inventory. Report to the Nature Conservancy, Washington Field Office, Seattle. February. 89 pp.
- City of Longview. 2015. *Community View Online Maps: Zoning*. Available: <http://mylongview.com/index.aspx?page=349>. Accessed: March 2, 2015.
- Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of Wetlands and Deepwater Habitats of the United States. Government Printing Office, Washington D.C.
- Cowlitz County. 2015a. *Official Zoning Map Book: 26-8-3W*. Available: <http://www.co.cowlitz.wa.us/DocumentCenter/View/3030>. Accessed: March 2, 2015.
- Cowlitz County. 2015b. *Official Zoning Map Book: 27-8-3W*. Available: <http://www.co.cowlitz.wa.us/DocumentCenter/View/3032>. Accessed: March 2, 2015.
- Cowlitz County Noxious Weed Control Board. 2015. 2015 *Cowlitz County Noxious Weed List, proposed*. Available: <http://www.co.cowlitz.wa.us/index.aspx?NID=1349>; Accessed: January 23, 2015.
- Doley, D. 2006. Airborne particulates and vegetation: Review of physical interactions. *Clean Air and Environmental Quality* 40:2.
- Ecological Land Services, Inc. 2014. *Addendum to the Shoreline Analysis Report: Shoreline Analysis Report, City of Longview Shorelines: Columbia River, Cowlitz River, and Lake Sacajawea*. Longview, WA. Prepared for City of Longview, Longview, WA. 7 pp. Available: <http://www.mylongview.com/modules/showdocument.aspx?documentid=1546>. Accessed: February 10, 2015.
- Farmer, A.M. 1993. The effects of dust on vegetation – A review. *Environmental Pollution* 79:63-75.
- Franklin, J.F. and C.T. Dyrness. 1988. *Natural vegetation of Oregon and Washington*. Oregon State University Press, Corvallis, OR.
- Gourlay. 2011. Notes on Shoreline Erosion Due to Boat Wakes and Wind Waves. CMST Research Report 2011–2016. November. Available: http://cmst.curtin.edu.au/wp-content/uploads/sites/4/2016/05/Gourlay_2011_Notes_on_shoreline_erosion.pdf.
- Grette Associates, LLC. 2014a. Millennium Coal Export Terminal, Wetland and Stormwater Ditch Delineation Report – Parcel 619530400 Appendix F, Noxious weeds and sensitive plants. Prepared for Millennium Bulk Terminals—Longview, LLC. September 1, 2014. Pages 1–2.
- Grette Associates, LLC. 2014b. Bulk Product Terminal, Shoreline Wetland Delineation Report – Parcel 61950; prepared for Millennium Bulk Terminals—Longview, LLC. September 1, 2014. Page 10.

- Grette Associates, LLC. 2014c. Bulk Product Terminal, Wetland and Stormwater Ditch Delineation Report – Parcel 10213; prepared for Millennium Bulk Terminals—Longview, LLC. September 1, 2014. Pages 14–20.
- Grette Associates, LLC. 2014d. Bulk Product Terminal, Wetland and Stormwater Ditch Delineation Report – Parcel 61953; prepared for Millennium Bulk Terminals—Longview, LLC. September 1, 2014. Pages 14–19.
- Grette Associates, LLC. 2014e. Affected Environment Biological Resources, Addendum Upland Habitat Survey- MBTL Lease Areas; prepared for Millennium Bulk Terminals—Longview, LLC. September 1, 2014. Pages 3–14.
- Grette Associates, LLC. 2014f. Millennium Coal Export Terminal Longview, Washington: Affected Environment Biological Resources Report. January 2014. Revised March 2014.
- Grette Associates, LLC. 2014g. Off-Site Alternative—Barlow Point Upland Habitat Survey. Prepared for Millennium Bulk Terminals—Longview, LLC. September 1, 2014. Pages 4–7.
- Grette Associates, LLC. 2014h. Off-Site Alternative—Barlow Point Shoreline Habitat Inventory. Prepared for Millennium Bulk Terminals—Longview, LLC. September 1, 2014. Pages 20–30.
- Grette Associates, LLC. 2014i. Off-Site Alternative—Barlow Point Wetland Reconnaissance Report. Prepared for Millennium Bulk Terminals—Longview, LLC. September 1, 2014. Pages 13–16.
- Herbarium, Burke Museum of Natural History and Culture. 2014. *Physostegia parviflora*: western false dragonhead, purple dragon head. Available: <http://biology.burke.washington.edu/herbarium/imagecollection.php?SciName=Physostegia%20parviflora>. Accessed: April 18, 2014.
- Homer, C.G., Dewitz, J.A., Yang, L., Jin, S., Danielson, P., Xian, G., Coulston, J., Herold, N.D., Wickham, J.D., and Megown, K., 2015, Completion of the 2011 National Land Cover Database for the conterminous United States-Representing a decade of land cover change information. Photogrammetric Engineering and Remote Sensing, v. 81, no. 5, p. 345–354.
- Hruby, T. 2006. *Washington State Wetland Rating System for Western Washington – Revised: Annotated Version*. August. Washington State Department of Ecology Publication #04-06-025. Olympia, WA.
- ICF International. 2014a. *Scoping Report Millennium Bulk Terminals-Longview NEPA Environmental Impact Statement*. Prepared for the U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2014b. *Scoping Summary Report Millennium Bulk Terminals—Longview. NEPA Environmental Impact Statement*. May. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016a. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Air Quality Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016b. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Wildlife Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.

- ICF International. 2016c. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Surface Water and Floodplains Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016d. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Land Use Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016e. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Water Quality Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016f. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Hazardous Materials Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016g. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Vessel Transportation Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016h. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Rail Transportation Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- Johnson, L.K. 2010. *Ecology and natural history of the freshwater tidal forested wetlands of the Columbia River estuary*. (Masters Thesis). University of Washington. Available: http://fish.washington.edu/research/publications/ms_phd/Johnson_L_MS_Sp10.pdf. Accessed: April 28, 2014.
- Johnson, R. and R. M. Bustin. 2006. Coal dust dispersal around a marine coal terminal (1977–1999), British Columbia: The fate of coal dust in the marine environment. *International Journal of Coal Geology*. 68: 57–69.
- Jonason, O. 1993. *Ferry Wake Study: Final Report*. Research Project T9903, Task 3, Subtask 8. Washington State Transportation Center, University of Washington. Seattle, WA. Prepared for: Washington State Transportation Commission. Olympia, WA. 64 pp.
- MARCOM. 2003. *Guidelines for Managing Wake Wash from High-Speed Vessels*. International Navigation Association, Maritime Navigation Commission. Report of Working Group 41. Brussels, Belgium. 32 pp.
- Macfarlane, G.J., Cox, G., 2004. The development of vessel wave wake criteria for the Noosa and Brisbane Rivers in Southeast Queensland. Fifth International Conference on Coastal Environment – Environmental Problems in Coastal Regions, Alicante.
- Multi-Resolution Land Characteristics Consortium. 2011. National Land Cover Database 2011: Product Legend. Available: http://www.mrlc.gov/nlcd11_leg.php. Accessed: February 26, 2015.
- Oregon Wetlands Joint Venture. 1994. *Joint Venture Implementation Plans - Lower Columbia River*. Prepared for Pacific Coast Joint Venture. Available: http://www.ohjv.org/pdfs/lower_columbia_river.pdf. Accessed: February 10, 2015.

- Spencer, S. 2001. Effects of coal dust on species composition of mosses and lichens in an arid environment. *Journal of Arid Environments*. 49: 843–853.
- Spencer, S. and R. Tinnin. 1997. Effects of coal dust on plant growth and species composition in an arid environment. *Journal of Arid Environments*. 37: 475–485.
- Washington Department of Natural Resources. 2014. Washington Natural Heritage Program. Reference Desk. List of Known Occurrences of Rare Plants in Washington. September. Cowlitz County.
- Washington Department of Natural Resources. 2015. Washington Natural Heritage Program. Available: <http://www1.dnr.wa.gov/nhp/refdesk/lists/plantsxco/cowlitz.html>. Accessed: February 2015.
- Washington State Noxious Weed Control Board. 2015. *2015 Washington State Noxious Weed List*. Available: <http://www.nwcb.wa.gov/printable.htm> Accessed: January 23, 2015.
- Wijayratne, U.C., S. J. Scoles-Sciulla, and L. A. Defalco. 2009 Dust Deposition Effects on Growth and Physiology of the Endangered *Astragalus jaegerianus* (Fabaceae). *Madroño* 56(2): 81–88.
- Zimmer, H. 2014. Coal Dust in Alaska: Hazards to Public Health, Community Air Quality Monitoring in Seward, AK. Alaska Community Action on Toxics and Global Community Monitor. June 2014. Available: <http://www.gcmonitor.org/alaska-coal-dust-report-web/>. Accessed: December 3, 2014.

Appendix A

**Descriptions of Special-Status Plant Species
with Potential to Occur in the Project Areas**

- **Western wahoo (*Euonymus occidentalis* var. *occidentalis*)**. Western wahoo is a deciduous, opposite-leaved shrub that grows up to 6 to 15 feet in height. It has a straggling or sometimes climbing growth form, with hairless branches that have narrow, parallel, longitudinal ridges. Flowers are greenish- and purplish-mottled to purplish red. Flowering typically occurs between May and June. Fruits are a 3-lobed capsule with a reddish-orange seed coat. Western wahoo does not have a federal status but is considered to be a *sensitive* species by Washington State.



Photo source:
<http://www.northbanknow.com/2014/07/save-western-wahoo/> [permission pending]

Western wahoo typically grows in moist woods and forested areas on the west side of the Cascades, often in shaded draws, riparian areas and ravines and sometimes in grassy areas with scattered trees. In Washington, it typically grows in fine sandy loams, silty loams, and silty clay loams. Associated plant species include Oregon white oak (*Quercus garryana*), Douglas-fir (*Pseudotsuga menziesii*), western redcedar (*Thuja plicata*), big-leaf maple (*Acer macrophyllum*), red alder, vine maple (*Acer circinatum*), service berry (*Amelanchier alnifolia*), salmonberry, and sword fern (*Polystichum munitum*). Occurrence records indicate that this species has been previously recorded near the Columbia River in the general vicinity of Longview.

- **Western false dragonhead (*Physostegia parviflora*)**. Western false dragonhead is a perennial herb that grows approximately 8 to 12 inches tall. It blooms between July and September, with lavender-purple flowers occurring in a close-flowered, elongate, terminal raceme. Leaves are stem-borne, opposite and linear-oblong, with serrate or nearly entire leaf margins. (Herbarium, Burke Museum of Natural History and Culture 2014). Western false dragonhead has no federal status but is considered a *Review Group 1* species by Washington State. Such species are considered to be of potential concern, but in need of more field work to more definitively assign it a status under the Washington Natural Heritage Program.



Photo source: Clarence A. Rechenthin, hosted by the USDA-NRCS PLANTS Database:
http://plants.usda.gov/java/largeImage?imageID=phpa10_001_ahp.tif

Western false dragonhead is known to occur along the shores of streams and lakes, marshes, and other low, wet places in the valleys and foothills (Herbarium, Burke Museum of Natural History and Culture 2014). It was last documented in Cowlitz County prior to 1977.

- **Loose-flowered bluegrass (*Poa laxiflora*).** Loose-flowered bluegrass is a perennial grass with creeping rhizomes that typically grows in single stalks between 3 and 4 feet in height. Stems and sheaths are rough to the touch when pulling upward. Leaf blades are flat, loosely arranged, and strongly roughened on both sides, with abruptly prow-like tips. Flowers are borne in an open loose panicle, with widely spreading branches. Loose-flowered bluegrass flowers from late May through June. This species has no federal status under but is considered to be a *sensitive* species by Washington State.



© Mary Clay Stensvold

Photo source: Mary Clay Stensvold, hosted by the USDA-NRCS PLANTS Database:

http://plants.usda.gov/java/usageGuidelines?imageID=pola3_002_ahp.tif

In the Pacific Northwest, loose-flowered bluegrass is commonly found on moss covered rocks and logs, along streams and rivers, and on edges of wet meadows in moist shady woods. Associated species include red alder, red elderberry, buttercup (*Ranunculus uncinatus*), sword fern, monkeyflower (*Mimulus dentatus*), little-leaf miner's lettuce (*Montia parvifolia*), reed canarygrass, and other grasses. Documented occurrence in Cowlitz County is in the northwestern portion of the county in the general vicinity of Longview.

- **Soft-leaved willow (*Salix sessilifolia*).** Soft-leaved willow grows as a shrub or small tree that varies in height between 6 and 24 feet tall. Its leaves, young twigs, and capsules are copiously covered with long, soft, loose, unmated hairs, which become less apparent as the plant ages. Leaf blades are lance-shaped to oblong, with widely spaced teeth along the margins. Flowering typically occurs between May and June. Soft-leaved willow has no federal status but is considered to be a *sensitive* species by Washington State.

Soft-leaved willow typically occurs in wet lowland habitats, including silty or sandy riverbanks, riparian forests, dredge spoils, sandy beaches, and at the upper edge of an intertidal zone. Documented occurrence in Cowlitz County is limited to the northern portion of the county; however, this species has been found along the Columbia River in multiple locations in adjacent Wahkiakum County.



Photo source: Stephen Laymon, Bureau of Land Management -

http://www.blm.gov/ca/st/en/fo/bakersfield/Programs/atwell_island/atwellplantlist/salix_sessilifolia.html

- **Nelson's checker-mallow (*Sidalcea nelsoniana*).** Nelson's checker-mallow is a perennial herb that grows from 16 to 40 inches in height. Flowers are pinkish-lavender in color and are borne on a spike-like raceme. Flowering occurs in mid-May to September. Nelson's checker-mallow is listed as *threatened* by the federal government and *endangered* by Washington State.

Nelson's checker-mallow is known to occur in two populations in Washington—one in Cowlitz County and one in Lewis County. It is a regionally endemic species and is rare throughout its range from Benton County, Oregon north to Lewis County, Washington, and from central Linn County, Oregon to just west of the crest of the Coast Range. The known habitat of Nelson's checker-mallow includes low-elevation meadows, prairie or grassland habitats, along fencerows, streams, and roadsides, drainage swales, and edges of plowed fields adjacent to woodland areas (Table 2). Standing water is present in some sites. It is associated with wetland species such as western buttercup (*Ranunculus occidentalis*), sedges (*Carex* spp.), and common rush (*Juncus effusus*), as well as drier species such as tall fescue (*Schedonorus pratensis*), velvetgrass (*Holcus lanatus*), and oxeye daisy (*Leucanthemum vulgare*).



Photo source: United States Fish and Wildlife Service:
<http://www.fws.gov/oregonfwo/Species/Data/NelsonsCheckerMallow/>

- **Columbia water-meal (*Wolffia Columbiana*).** Columbia water-meal is a tiny, perennial aquatic plant that floats just below the water surface in colonies in freshwater lakes, ponds, and slow-moving streams. It consists of a transparent green spherical plant body that lacks roots, definite leaves, or stems. Bloom time in Washington is unknown. Columbia water-meal has no federal status but is considered a *Review Group 1* species by Washington State.



Photo source: http://fieldguide.mt.gov/detail_PMLEM03030.aspx [permission pending]

Columbia water-meal is found in association with common duckweed (*Lemna minor*) in freshwater lakes, ponds and slow streams. It has been found in Clark, Cowlitz, and Wahkiakum Counties in Washington, but is known from fewer than five occurrences across the state.

Appendix B

State Noxious Weed List

- **Indigobush (*Amorpha fruticosa*).** Indigobush, also known as false indigobush and desert false indigo, is an introduced, leguminous shrub native to the southern United States and Atlantic coast. The shrub is typically three to ten feet in height, with showy purplish-blue, scented flowers that appear in upright spikes; it grows along streams and canyons, as well as in disturbed areas with infertile, dry and sandy soils (U.S. Department of Agriculture Plant Guide 2015). In Washington, indigobush has been documented along the Columbia River in Wahkiakum, Cowlitz, Clark, Skamania, and Klickitat counties, as well as in the extreme southeastern corner of the state in Adams, Franklin, Whitman, Columbia, and Asotin counties (Herbarium, Burke Museum of Natural History and Culture 2015a).




Photo Source: Jennifer Anderson 2002, hosted by the USDA-NRCS PLANTS Database. Available: http://plants.usda.gov/java/largeImage?imageID=amfr_003_avp.tif

- **Scotch broom (*Cytisus scoparius*).** Scotch broom is an introduced, now widely distributed, tall shrub with showy yellow flowers that is native to Europe. It occurs throughout western Washington, especially in disturbed lowlands, along roadsides, in pastures, grasslands, and open areas of recent soil disturbance (Herbarium, Burke Museum of Natural History and Culture 2015b). It is able to fix nitrogen and is thus able to colonize poor soils.



Photo source: Danny S 2012 Available: http://en.wikipedia.org/wiki/Cytisus_scoparius

- **Policeman's helmet (*Impatiens glandulifera*).** Policeman's helmet is an introduced annual herbaceous species, with large white to pink/red 'touch-me-not' flowers that was introduced into western Washington and British Columbia from Asia; it has been recorded in Whatcom, Skagit, Snohomish, King, Clallam and Pacific counties (Herbarium, Burke Museum of Natural History and Culture 2015c), as well as in Cowlitz county (Cowlitz County Noxious Weed Control Board 2015). It commonly invades the herbaceous layer in seasonally saturated wetlands.



Photo source: http://en.wikipedia.org/wiki/Policeman%27s_helmet

- **Eurasian watermilfoil (*Myriophyllum spicatum*).**
Eurasian watermilfoil is a perennial, submersed, aquatic plant with dissected leaves that forms dense mats in streams, lakes, ponds, quiet streams, and ditches. It is an ornamental aquatic plant native to Europe, Asia, and Northern Africa that escaped cultivation and is now widely distributed throughout Washington with records of occurrence in multiple counties including Cowlitz, Wahkiakum, and Skamania (Herbarium, Burke Museum of Natural History and Culture 2015d).
- **Parrotfeather (*Myriophyllum aquaticum*).**
Parrotfeather is a submersed aquatic plant with both emergent and submersed feather-like leaves. It is usually found on mud banks along the edges of freshwater ponds, streams, lakes, and canals. It is an escaped ornamental plant native to South America that is now found in several Washington counties on both sides of the Cascade Crest (Herbarium, Burke Museum of Natural History and Culture 2015e). In 2011, Cowlitz County was known to have one of the higher distributions of this species in the state (Washington State Department of Agriculture 2011a).



Photo source: Alison Fox, University of Florida, Bugwood.org. Available: <http://www.invasive.org/weedcd/images/1536x1024/1624031.jpg> [permission pending]



Photo source: André Karwath. 2005. Available: http://en.wikipedia.org/wiki/Myriophyllum_aquaticum

Eight species present in the study areas are listed as Class C noxious weeds, a classification assigned to weeds that are not typically considered a priority for weed control because they are already widespread throughout the state. Brief descriptions for each of these species are provided below.

- **Canada thistle (*Cirsium arvense*).** Canada thistle is an aggressive colony-forming perennial weed with a deep root system characterized by extensive horizontal spreading roots. It grows 2 to 5 feet tall and frequently occurs in cultivated fields, riparian areas, pastures, rangeland, forests, lawns, gardens, roadsides, and waste areas. Canada thistle is an introduced species native to Europe and Asia that is now widespread in Washington, inhabiting nearly every county in the state (Washington State Department of Agriculture 2011b).



Photo source: Al Schneider, hosted by the USDA-NRCS PLANTS Database. Available: <http://plants.usda.gov/core/profile?symbol=ciar4> [permission pending]

- **Bull thistle (*Cirsium vulgare*).** Bull thistle is a many-branched biennial herbaceous plant growing from 3 to 7 feet tall, with coarsely lobed leaves tipped with spines. It commonly occurs in disturbed areas including pastures, roadsides, hayfields, and ditch banks. Bull thistle is native to Europe, Asia, and Northern Africa but is now widespread in Washington, commonly occurring in most counties. As of 2011, distribution in Cowlitz was known to be less than other counties in the state (Washington State Department of Agriculture 2011c).



Photo source: ICF International. 2012.

- **English ivy (*Hedera helix*).** English ivy is a highly invasive woody, evergreen vine native to most of Europe that has leathery broadly ovate to triangular leaves that can occur both in vine (juvenile) and shrub (adult) form. It spreads rapidly by vegetative stem growth, aggressively climbing on other plants and trees and outcompeting native vegetation. Adult plants can also spread by seed. English ivy is an introduced ornamental plant that is widely established in most counties in western Washington including Cowlitz, Wahkiakum, Clark, Skamania, and Lewis counties (Herbarium, Burke Museum of Natural History and Culture 2015f).
- **Yellowflag iris (*Iris pseudacorus*).** Yellowflag iris is a large, introduced perennial iris native to North Africa and Europe. It is highly tolerant of low oxygen conditions in the soils with high levels of soluble organics; it is also very efficient at absorbing heavy metals. It forms dense clumps in shallow water and along the edges of rivers, ponds, and lakes, as well as in the understory of wetlands (U.S. Department of Agriculture Plant Guide 2015b). Yellowflag iris is widely distributed throughout western and central Washington including Cowlitz, Wahkiakum, and Skamania counties, among others (Herbarium, Burke Museum of Natural History and Culture 2015g).
- **Reed canarygrass (*Phalaris arundinacea*).** Reed canarygrass is a rhizomatous, perennial, cool season grass native to Eurasia that spreads both by seed and creeping rhizomes. It is known to form dense, monotypic stands in wetlands but can also be found in roadside ditches, along river and streams, and in upland meadows. It is widely distributed throughout Washington and present in nearly every county in the state (Washington State Department of Agriculture 2011d).



Photo source: ICF International. 2015.



Photo source: Robert H. Mohlenbrock, hosted by the USDA-NRCS PLANTS Database / USDA NRCS. 1995. Northeast wetland flora: Field office guide to plant species. Northeast National Technical Center, Chester. Available: http://plants.usda.gov/java/largeImage?imageID=irps_002_ahp.tif



Photo source: ICF International. 2012.

- **Himalayan blackberry (*Rubus armeniacus*).** Himalayan blackberry is rambling evergreen, perennial, wood shrub with stout stems that are armed with stiff, hooked thorns. It commonly grows in dense, often nearly impenetrable thickets in a variety of disturbed habitats including roadsides, field margins, riparian areas, and around the edges of both upland and wetland forests. Native to Asia, it is now widespread in western Washington, including Cowlitz, Lewis, and Skamania counties, among others (Washington State Department of Agriculture 2011e).
- **Common tansy (*Tanacetum vulgare*).** Common tansy is an introduced aromatic, upright perennial herb with fern-like foliage and yellow flowers. It is common in open herbaceous areas on disturbed sites and can be found along roadsides, in waste areas, along stream banks, and in pastures. It was introduced from Europe and Asia and is now common throughout Washington including Cowlitz, Wahkiakum, Skamania, Clark, and Lewis counties, among others (Washington State Department of Agriculture 2011f).



Photo source: Robin R. Buckallew, hosted by the USDA-NRCS PLANTS Database. Available: http://plants.usda.gov/java/largeImage?imageID=ruar9_001_ahp.jpg [permission pending]



Photo source: William S. Justice, hosted by the USDA-NRCS PLANTS Database. Available: http://plants.usda.gov/java/largeImage?imageID=tavu_1v.jpg [permission pending]

- **Nonnative cattail (*Typha angustifolia*) and Hybrids.** Cattails are a perennial emergent species that grow in fresh to slightly brackish wetlands. They are characterized by erect, linear, sheathed leaves that are thickened and spongy, with flowers borne in dense cylindrical spikes. They most commonly spread by rhizomes and frequently form dense monocultures in saturated soils and wetlands. “Nonnative cattail species and hybrids” are considered Class C noxious weeds in Cowlitz County (Cowlitz County Noxious Weed Control Board 2015) and include narrow-leaf cattail and similar species introduced from Europe and/or eastern North America. Nonnative cattails species are frequently found in marshes, wet meadows, lakeshores, pond margins, estuaries, ditches, bogs, and fens.



Photo source: Nelson DeBarros, hosted by the
USDA-NRCS PLANTS Database Available:
http://plants.usda.gov/java/largeImage?imageID=tyan_006_avp.tif [permission pending]

Cowlitz County Noxious Weed List

Class A Weeds : Non-native species whose distribution in Washington is still limited. Preventing new infestations and eradicating existing infestations are the highest priority. Eradication of all Class A plants is required by law.

Class B Weeds: Non-native species presently limited to portions of the State. Species are designated for control in regions where they are not yet widespread. Preventing new infestations in these areas is a high priority. In regions where a Class B species is already abundant, control is decided at the local level, with containment as the primary goal. Please contact your County Noxious Weed Control Coordinator to learn which species are designated in your area.

Class C Weeds: These are noxious weeds typically widespread in WA State or are of special interest to the state's agricultural industry. The Class C status allows counties to require control if locally desired. Other counties may choose to provide education or technical consultation.

*Class A Weeds Eradication is required	
common crupina	<i>Crupina vulgaris</i>
cordgrass, common	<i>Spartina anglica</i>
cordgrass, dense-flowered	<i>Spartina densiflora</i>
cordgrass, saltmeadow	<i>Spartina patens</i>
cordgrass, smooth	<i>Spartina alterniflora</i>
dyer's woad	<i>Isatis tinctoria</i>
eggleaf spurge	<i>Euphorbia oblongata</i>
false brome	<i>Brachypodium sylvaticum</i>
floating primrose-willow	<i>Ludwigia peploides</i>
flowering rush	<i>Butomus umbellatus</i>
French broom	<i>Genista monspessulana</i>
garlic mustard	<i>Alliaria petiolata</i>

giant hogweed	<i>Heracleum mantegazzianum</i>
goatsrue	<i>Galega officinalis</i>
hydrilla	<i>Hydrilla verticillata</i>
Johnsongrass	<i>Sorghum halepense</i>
knapweed, bighead	<i>Centaurea macrocephala</i>
knapweed, Vochin	<i>Centaurea nigrescens</i>
kudzu	<i>Pueraria montana</i> var. <i>lobata</i>
meadow clary	<i>Salvia pratensis</i>
oriental clematis	<i>Clematis orientalis</i>
ravenna grass	<i>Saccharum ravennae</i>
purple starthistle	<i>Centaurea calcitrapa</i>
reed sweetgrass	<i>Glyceria maxima</i>
ricefield bulrush	<i>Schoenoplectus mucronatus</i>
sage, clary	<i>Salvia sclarea</i>
sage, Mediterranean	<i>Salvia aethiopis</i>
silverleaf nightshade	<i>Solanum elaeagnifolium</i>
Spanish broom	<i>Spartium junceum</i>
spurge flax	<i>Thymelaea passerina</i>
Syrian beancaper	<i>Zygophyllum fabago</i>
Texas blueweed	<i>Helianthus ciliaris</i>
thistle, Italian	<i>Carduus pycnocephalus</i>
thistle, milk	<i>Silybum marianum</i>
thistle, slenderflower	<i>Carduus tenuiflorus</i>
variable-leaf milfoil	<i>Myriophyllum heterophyllum</i>
wild four-o'clock	<i>Mirabilis nyctaginea</i>

Class B Weeds	
*blueweed	<i>Echium vulgare</i>
*Brazilian elodea	<i>Egeria densa</i>
*bugloss, annual	<i>Anchusa arvensis</i>
*bugloss, common	<i>Anchusa officinalis</i>
*butterfly bush	<i>Buddleja davidii</i>
*camelthorn	<i>Alhagi maurorum</i>
*common fennel , (except bulbing fennel)	<i>Foeniculum vulgare</i> (except <i>F. vulgare</i> var. <i>azoricum</i>)

*common reed (nonnative genotypes only)	<i>Phragmites australis</i>
Dalmatian toadflax	<i>Linaria dalmatica</i> ssp. <i>dalmatica</i>
*Eurasian watermilfoil	<i>Myriophyllum spicatum</i>
*fanwort	<i>Cabomba caroliniana</i>
*gorse	<i>Ulex europaeus</i>
*grass-leaved arrowhead	<i>Sagittaria graminea</i>
*hairy willowherb	<i>Epilobium hirsutum</i>
*hawkweed, oxtongue	<i>Picris hieracioides</i>
*hawkweed, orange	<i>Hieracium aurantiacum</i>
*hawkweeds : All nonnative species and hybrids of the meadow subgenus	<i>Hieracium</i> , subgenus <i>Pilosella</i>
*hawkweeds : All nonnative species and hybrids of the wal subgenus	<i>Hieracium</i> , subgenus <i>Hieracium</i>
herb-Robert	<i>Geranium robertianum</i>
*hoary alyssum	<i>Berteroa incana</i>
*houndstongue	<i>Cynoglossum officinale</i>
*indigobush	<i>Amorpha fruticosa</i>
*knapweed, black	<i>Centaurea nigra</i>
*knapweed, brown	<i>Centaurea jacea</i>
knapweed, diffuse	<i>Centaurea diffusa</i>
knapweed, meadow	<i>Centaurea x moncktonii</i>
*knapweed, Russian	<i>Acroptilon repens</i>
knapweed, spotted	<i>Centaurea stoebe</i>
knotweed, Bohemian	<i>Polygonum x bohemicum</i>
knotweed, giant	<i>Polygonum sachalinense</i>
*knotweed, Himalayan	<i>Polygonum polystachyum</i>
knotweed, Japanese	<i>Polygonum cuspidatum</i>
*kochia	<i>Kochia scoparia</i>
*lesser celandine	<i>Ficaria verna</i>

*loosestrife, garden	<i>Lysimachia vulgaris</i>
loosestrife, purple	<i>Lythrum salicaria</i>
*loosestrife, wand	<i>Lythrum virgatum</i>
parrotfeather	<i>Myriophyllum aquaticum</i>
perennial pepperweed	<i>Lepidium latifolium</i>
poison hemlock	<i>Conium maculatum</i>
*policeman 's helmet	<i>Impatiens glandulifera</i>
*puncturevine	<i>Tribulus terrestris</i>
*rush skeletonweed	<i>Chondrilla juncea</i>
*saltcedar	<i>Tamarix ramosissima</i>
Scotch broom	<i>Cytisus scoparius</i>
shiny geranium	<i>Geranium lucidum</i>
*spurge laurel	<i>Daphne laureola</i>
*spurge, leafy	<i>Euphorbia esula</i>
*spurge, myrtle	<i>Euphorbia myrsinites</i>
*sulfur cinquefoil	<i>Potentilla recta</i>
tansy ragwort	<i>Senecio jacobaea</i>
*thistle, musk	<i>Carduus nutans</i>
*thistle, plumeless	<i>Carduus acanthoides</i>
*thistle, Scotch	<i>Onopordum acanthium</i>
*velvetleaf	<i>Abutilon theophrasti</i>
water primrose	<i>Ludwigia hexapetala</i>
*white bryony	<i>Bryonia alba</i>
wild chervil	<i>Anthriscus sylvestris</i>
yellow archangel	<i>Lamiastrum galeobdolon</i>
*yellow floatingheart	<i>Nymphoides peltata</i>
*yellow nutsedge	<i>Cyperus esculentus</i>
*yellow starthistle	<i>Centaurea solstitialis</i>

Class C Weeds	
buffalobur	<i>Solanum rostratum</i>
nonnative cattail species and hybrids	<i>Typha</i> spp.
common groundsel	<i>Senecio vulgaris</i>
common St. Johnswort	<i>Hypericum perforatum</i>
common tansy	<i>Tanacetum vulgare</i>
common teasel	<i>Dipsacus fullonum</i>
English ivy - four cultivars only	<i>Hedera helix</i> 'Baltica', 'Pittsburgh', and 'Star'; <i>H. hibernica</i>

	'Hibernica'
evergreen blackberry	<i>Rubus laciniatus</i>
field bindweed	<i>Convolvulus arvensis</i>
Himalayan blackberry	<i>Rubus armeniacus</i>
Italian arum	<i>Arum italicum</i>
Jubata grass	<i>Cortaderia jubata</i>
old man's beard	<i>Clematis vitalba</i>
oxeye daisy	<i>Leucanthemum vulgare</i>
Pampas grass	<i>Cortaderia selloana</i>
Russian olive	<i>Elaeagnus angustifolia</i>
scarlet centless mayweed	<i>Matricaria perforata</i>
spiny cocklebur	<i>Xanthium spinosum</i>
Swainsonpea	<i>Sphaerophysa salsula</i>
thistle, bull	<i>Cirsium vulgare</i>
thistle, Canada	<i>Cirsium arvense</i>
tree-of-heaven	<i>Ailanthus altissima</i>
white cockle	<i>Silene latifolia</i> ssp . <i>alba</i>
wild carrot (except where commercially grown)	<i>Daucus carota</i>
yellow flag iris	<i>Iris pseudacorus</i>
yellow toadflax	<i>Linaria vulgaris</i>

New additions to the 2015 List

Changes in class for 2015

*

State designated high priority for control and enforcement

Control required along transportation right-of-ways, near residential communities (fire danger), areas where plants create a significant impact to managed pastures or farmland.

Bold listings - documented plant species in Cowlitz Co.

Highlighted listings - County select class B and C high priority weeds for control and enforcement action.

Noxious Weeds are non-native plants introduced to Washington State that can be highly destructive, competitive, and difficult to control. These plants invade our croplands, rangeland, forests, parks, rivers, lakes, wetlands, and estuaries causing both ecological and economical damage that affects us all. Noxious weeds can:

- Lower crop yields
- Reduce forage quality
- Destroy plant and animal habitat
- Displace native plants
- Reduce recreational opportunities (e.g., fishing, hunting, swimming and hiking)
- Clog waterways
- Decrease land values
- Increase erosion and wildfire risk
- And some are toxic to humans and livestock

Please help protect Washington's economy and environment from noxious weeds!

To help protect the State's resources and economy, the Washington State Noxious Weed Control Board adopts a State Noxious Weed List each year (WAC 16-750). This list classifies weeds into three major classes – A, B, and C – based on the stage of invasion of each species and the seriousness of the threat they pose to Washington State. This classification system is designed to:

- Prevent small infestations from expanding by eradicating them when they are first detected
- Restrict already established weed populations to regions of the state where they occur and prevent their movement to un-infested areas
- Allow flexibility of weed control at the local level for weeds that are already widespread.



To learn more about noxious weeds and

noxious weed control in Washington State, please contact:

**Cowlitz County
Noxious Weed Control Board**
207 Fourth Ave. N.
Kelso, WA 98628-4124
Tel. (360)577-3117

Email: noxiousweeds@co.cowlitz.wa.us
Website: <http://co.cowlitz.wa.us>

Or

WA State Noxious Weed Control Board
P.O. Box 42560
Olympia, WA 98504-2560
(360) 725-5764

Email: noxiousweeds@agr.wa.gov
Website: <http://nwcb.wa.gov>

Or

WA State Department of Agriculture
Natural Resource Building
P.O. Box 42560
1111 Washington St. SE
Olympia, WA 98504-2560
Tel. (360)902-1800

Website: <http://agr.wa.gov>

20 15

Cowlitz County Noxious Weed List



Arum italicum
Brigitte E.M. Daniel SBA (Beaconsfield 1959); Her work is held in the RHS Lindley Library, The National Gallery and Museum of Wales.

**List arranged alphabetically by:
COMMON NAME**

Appendix D

**Descriptions of Noxious Weeds
with Potential to Occur in the Project Areas**

- **Indigobush (*Amorpha fruticosa*).** Indigobush, also known as false indigobush and desert false indigo, is an introduced, leguminous shrub native to the southern United States and Atlantic coast. The shrub is typically three to ten feet in height, with showy purplish-blue, scented flowers that appear in upright spikes; it grows along streams and canyons, as well as in disturbed areas with infertile, dry and sandy soils (U.S. Department of Agriculture Plant Guide 2015). In Washington, indigobush has been documented along the Columbia River in Wahkiakum, Cowlitz, Clark, Skamania, and Klickitat counties, as well as in the extreme southeastern corner of the state in Adams, Franklin, Whitman, Columbia, and Asotin counties (Herbarium, Burke Museum of Natural History and Culture 2015a).



Photo Source: Jennifer Anderson 2002, hosted by the USDA-NRCS PLANTS Database. Available: http://plants.usda.gov/java/largeImage?imageID=amfr_003_avp.tif

- **Scotch broom (*Cytisus scoparius*).** Scotch broom is an introduced, now widely distributed, tall shrub with showy yellow flowers that is native to Europe. It occurs throughout western Washington, especially in disturbed lowlands, along roadsides, in pastures, grasslands, and open areas of recent soil disturbance (Herbarium, Burke Museum of Natural History and Culture 2015b). It is able to fix nitrogen and is thus able to colonize poor soils.



Photo source: Danny S 2012 Available: http://en.wikipedia.org/wiki/Cytisus_scoparius

- **Policeman's helmet (*Impatiens glandulifera*).** Policeman's helmet is an introduced annual herbaceous species, with large white to pink/red 'touch-me-not' flowers that was introduced into western Washington and British Columbia from Asia; it has been recorded in Whatcom, Skagit, Snohomish, King, Clallam and Pacific counties (Herbarium, Burke Museum of Natural History and Culture 2015c), as well as in Cowlitz county (Cowlitz County Noxious Weed Control Board 2015). It commonly invades the herbaceous layer in seasonally saturated wetlands.



Photo source: http://en.wikipedia.org/wiki/Policeman%27s_helmet

- **Eurasian watermilfoil (*Myriophyllum spicatum*).**
Eurasian watermilfoil is a perennial, submersed, aquatic plant with dissected leaves that forms dense mats in streams, lakes, ponds, quiet streams, and ditches. It is an ornamental aquatic plant native to Europe, Asia, and Northern Africa that escaped cultivation and is now widely distributed throughout Washington with records of occurrence in multiple counties including Cowlitz, Wahkiakum, and Skamania (Herbarium, Burke Museum of Natural History and Culture 2015d).
- **Parrotfeather (*Myriophyllum aquaticum*).**
Parrotfeather is a submerged aquatic plant with both emergent and submersed feather-like leaves. It is usually found on mud banks along the edges of freshwater ponds, streams, lakes, and canals. It is an escaped ornamental plant native to South America that is now found in several Washington counties on both sides of the Cascade Crest (Herbarium, Burke Museum of Natural History and Culture 2015e). In 2011, Cowlitz County was known to have one of the higher distributions of this species in the state (Washington State Department of Agriculture 2011a).



Photo source: Alison Fox, University of Florida, Bugwood.org. Available:
<http://www.invasive.org/weedcd/images/1536x1024/1624031.jpg> [permission pending]



Photo source: André Karwath. 2005. Available:
http://en.wikipedia.org/wiki/Myriophyllum_aquaticum

Eight species present in the study areas are listed as Class C noxious weeds, a classification assigned to weeds that are not typically considered a priority for weed control because they are already widespread throughout the state. Brief descriptions for each of these species are provided below.

- **Canada thistle (*Cirsium arvense*).** Canada thistle is an aggressive colony-forming perennial weed with a deep root system characterized by extensive horizontal spreading roots. It grows 2 to 5 feet tall and frequently occurs in cultivated fields, riparian areas, pastures, rangeland, forests, lawns, gardens, roadsides, and waste areas. Canada thistle is an introduced species native to Europe and Asia that is now widespread in Washington, inhabiting nearly every county in the state (Washington State Department of Agriculture 2011b).



Photo source: Al Schneider, hosted by the USDA-NRCS PLANTS Database. Available: <http://plants.usda.gov/core/profile?symbol=ciar4> [permission pending]

- **Bull thistle (*Cirsium vulgare*).** Bull thistle is a many-branched biennial herbaceous plant growing from 3 to 7 feet tall, with coarsely lobed leaves tipped with spines. It commonly occurs in disturbed areas including pastures, roadsides, hayfields, and ditch banks. Bull thistle is native to Europe, Asia, and Northern Africa but is now widespread in Washington, commonly occurring in most counties. As of 2011, distribution in Cowlitz was known to be less than other counties in the state (Washington State Department of Agriculture 2011c).



Photo source: ICF International. 2012.

- **English ivy (*Hedera helix*).** English ivy is a highly invasive woody, evergreen vine native to most of Europe that has leathery broadly ovate to triangular leaves that can occur both in vine (juvenile) and shrub (adult) form. It spreads rapidly by vegetative stem growth, aggressively climbing on other plants and trees and outcompeting native vegetation. Adult plants can also spread by seed. English ivy is an introduced ornamental plant that is widely established in most counties in western Washington including Cowlitz, Wahkiakum, Clark, Skamania, and Lewis counties (Herbarium, Burke Museum of Natural History and Culture 2015f).
- **Yellowflag iris (*Iris pseudacorus*).** Yellowflag iris is a large, introduced perennial iris native to North Africa and Europe. It is highly tolerant of low oxygen conditions in the soils with high levels of soluble organics; it is also very efficient at absorbing heavy metals. It forms dense clumps in shallow water and along the edges of rivers, ponds, and lakes, as well as in the understory of wetlands (U.S. Department of Agriculture Plant Guide 2015b). Yellowflag iris is widely distributed throughout western and central Washington including Cowlitz, Wahkiakum, and Skamania counties, among others (Herbarium, Burke Museum of Natural History and Culture 2015g).
- **Reed canarygrass (*Phalaris arundinacea*).** Reed canarygrass is a rhizomatous, perennial, cool season grass native to Eurasia that spreads both by seed and creeping rhizomes. It is known to form dense, monotypic stands in wetlands but can also be found in roadside ditches, along river and streams, and in upland meadows. It is widely distributed throughout Washington and present in nearly every county in the state (Washington State Department of Agriculture 2011d).



Photo source: ICF International. 2015.



Photo source: Robert H. Mohlenbrock, hosted by the USDA-NRCS PLANTS Database / USDA NRCS. 1995. Northeast wetland flora: Field office guide to plant species. Northeast National Technical Center, Chester. Available: http://plants.usda.gov/java/largeImage?imageID=irps_002_ahp.tif



Photo source: ICF International. 2012.

- **Himalayan blackberry (*Rubus armeniacus*).** Himalayan blackberry is rambling evergreen, perennial, wood shrub with stout stems that are armed with stiff, hooked thorns. It commonly grows in dense, often nearly impenetrable thickets in a variety of disturbed habitats including roadsides, field margins, riparian areas, and around the edges of both upland and wetland forests. Native to Asia, it is now widespread in western Washington, including Cowlitz, Lewis, and Skamania counties, among others (Washington State Department of Agriculture 2011e).
- **Common tansy (*Tanacetum vulgare*).** Common tansy is an introduced aromatic, upright perennial herb with fern-like foliage and yellow flowers. It is common in open herbaceous areas on disturbed sites and can be found along roadsides, in waste areas, along stream banks, and in pastures. It was introduced from Europe and Asia and is now common throughout Washington including Cowlitz, Wahkiakum, Skamania, Clark, and Lewis counties, among others (Washington State Department of Agriculture 2011f).



Photo source: Robin R. Buckallew, hosted by the USDA-NRCS PLANTS Database. Available: http://plants.usda.gov/java/largeImage?imageID=ruar9_001_ahp.jpg [permission pending]



Photo source: William S. Justice, hosted by the USDA-NRCS PLANTS Database. Available: http://plants.usda.gov/java/largeImage?imageID=tavu_1v.jpg [permission pending]

- **Nonnative cattail (*Typha angustifolia*) and Hybrids.** Cattails are a perennial emergent species that grow in fresh to slightly brackish wetlands. They are characterized by erect, linear, sheathed leaves that are thickened and spongy, with flowers borne in dense cylindrical spikes. They most commonly spread by rhizomes and frequently form dense monocultures in saturated soils and wetlands. “Nonnative cattail species and hybrids” are considered Class C noxious weeds in Cowlitz County (Cowlitz County Noxious Weed Control Board 2015) and include narrow-leaf cattail and similar species introduced from Europe and/or eastern North America. Nonnative cattails species are frequently found in marshes, wet meadows, lakeshores, pond margins, estuaries, ditches, bogs, and fens.



Photo source: Nelson DeBarros, hosted by the
USDA-NRCS PLANTS Database Available:
http://plants.usda.gov/java/largeImage?imageID=tyan_006_avp.tif [permission pending]

Appendix E

Site Photographs

Appendix E – Site Photographs



Photo 1. Photo shows typical vegetation present on Parcel 10213 of the MBTL Site including reed canarygrass and Himalayan blackberry growing in upland areas along CDID Ditch 10 and Memorial Park Drive, reed canarygrass in Wetland LW1, and forested uplands. (Photo Date: 12/12/2014)



Photo 2. Photo shows typical vegetation on Parcel 10213 of the MBTL Site including reed canarygrass and Himalayan blackberry growing in upland areas around CDID Ditch 10 and forested upland areas. (Photo Date: 12/12/2014)




Photo 3. Photo shows herbaceous wetland vegetation cover type in Wetland D between Fill Deposit A (White Mud Pond) and Reynolds Lead Track on the MBTL site. (Photo Date: 12/12/2014)




Photo 4. Photo shows scrub-shrub and herbaceous wetland vegetation cover types of Wetland D on the MBTL Site. (Photo Date: 12/12/2014)




Photo 5. Photo shows herbaceous and scrub-shrub wetlands cover types in Wetlands F (foreground) and G (background) along the south rail spur on the MBTL Site. Wetland F is characterized as a disturbed wetland cover type. (Photo Date: 12/12/2014)



Photo 6. Photo shows typical herbaceous wetland vegetation cover type in Wetland F between the South Rail Spur and Fill Deposit B-1 (East Black Mud Pond) on the MBTL Site. Wetland F is characterized as a disturbed wetland cover type. (Photo Date: 12/12/2014)



Photo 7. Photo shows disturbed cover type around the railroad tracks that extend from the South Rail Spur through the transloading area. (Photo Date: 12/4/2013)



Photo 8. Photo shows typical vegetation present in Fill Deposit B-3 (Black Mud Deposits) area, which is located between the U-Ditch and CDID levee on the MBTL Site. Landfill #2 (Industrial Landfill) can be seen in the background. (Photo Date: 12/12/2014)



Photo 9. Photo shows typical disturbed vegetation cover type present on Landfill #2 (Industrial Landfill) and central portion of Fill Deposit B-3 (Black Mud Deposits) on the MBTL Site. (Photo Date: 12/12/2014)



Photo 10. Photo shows managed herbaceous vegetation growing on Closed BMP Facility on the MBTL Site. This area is regularly mown. (Photo Date: 12/12/2014)




Photo 11. Photo shows typical managed vegetation cover type growing on Fill Deposit A (White Mud Pond) on the MBTL Site. (Photo Date: 12/12/2014)



Photo 12. Photo shows managed herbaceous vegetation cover type growing on Fill Deposit B-2 (Eastern Black Mud Pond) on the MBTL Site. (Photo Date: 4/8/2014)




Photo 13. Photo shows typical conditions present in southern portion of the former Borrow Area located between Closed BMP Facility and Former Cable Plant on the MBTL Site. This area includes Wetland Z and a portion of Wetland C (not visible in photo), and is bordered by the upland edge of the Remnant Forest Area. (Photo Date: 12/12/2014)



Photo 14. Photo shows northern portion of Borrow Area, which contains the herbaceous portion of Wetland C, as well as adjacent uplands dominated by reed canarygrass and Himalayan blackberry in the foreground and between the wetland and the Closed BMP Facility. (Photo Date: 12/12/2014)



Photo 15. Photo shows typical conditions present in the Remnant Forest Area that lies between the Closed BMP Facility and Former Cable Plant on the Former Cable Plant on the MBTL Site. Most of this area consists of forested wetlands. (Photo Date: 12/12/2014)




Photo 16. Photo shows Wetland A and a stormwater conveyance ditch in Remnant Forest Area on MBTL Site. (Photo Date: 12/12/2014)



Photo 17. Photo shows forested portion of Wetland C in the Remnant Forest Area on the MBTL Site. (Photo Date: 12/12/2014)




Photo 18. Photo shows the herbaceous and scrub-shrub areas of Wetland Y and surrounding upland vegetation on the MBTL Site. Some of the forested uplands on Mount Solo can be seen in the background on the other side of Mount Solo Road. (Photo Date: 12/12/2014)



Photo 19. Photo shows typical wetland and upland vegetation cover types present in and around Wetland Y on the MBTL Site. This wetland extends onto the Barlow Point Site. (Photo Date: 12/12/2014)




Photo 20. Photo shows typical disturbed vegetation cover type in southern portion of Outdoor Storage Area between the Cable Plant and North Plant Potlines on the MBTL Site. Upland forested areas on Mount Solo are visible in the background (Photo Date: 12/12/2014)



Photo 21. Photo shows typical disturbed vegetation cover type in central portion of Outdoor Storage Area between the Cable Plant and North Plant Potlines on the MBTL Site. (Photo Date: 4/8/2014)



Photo 22. Photo shows upland scrub-shrub cover type along the edge of the former Cable Plant parking lot on the MBTL Site. Parking lot and Cable Plant are classified as disturbed lands. Forested uplands on Mount Solo are visible in the background. (Photo Date: 12/12/2014)




Photo 23. Photo shows CDID's Reynolds Pump Station and CDID Ditch 14 on the MBTL Site. Forested uplands of Mount Solo are visible in the background (Photo Date: 12/12/2014)



Photo 24. Photo shows typical forested upland vegetation along the south channel of the U-Ditch on the MBTL Site. (Photo Date: 12/12/2014)



Photo 25. Photo shows forested uplands adjacent to the north channel of the U-Ditch on the MBTL Site. The earthen embankment that separates the U-Ditch from the Interception Ditch is visible on the right. (Photo Date: 12/12/2014)



Photo 26. Photo shows forested uplands along the Interception Ditch, which lies to the south of the Closed BMP Facility on the MBTL Site. (Photo Date: 12/12/2014)



Photo 27. Photo shows typical vegetation present around the western end of the U-Ditch near the confluence of the north and south channels on the MBTL Site. (Photo Date: 12/12/2014)



Photo 28. Photo shows combined channel of the U-Ditch that flows to the stormwater treat facility on the MBTL Site. Adjacent areas are classified as the disturbed cover type (Photo Date: 12/12/2014)



Photo 29. Photo shows typical disturbed vegetation cover type growing around one of the Cryolite Recovery Ditches on the MBTL site. Fill Deposit B-1 (Eastern Black Mud Pond) can be seen in background. (Photo Date: 4/8/2014)



Photo 30. Photo shows unnamed stormwater conveyance ditch to south of Cable Plant on MBTL Site. This ditch flows through Remnant Forest Area and into Wetland Y. (Photo Date: 12/12/2014)



Photo 31 Photo show vegetation in a roadside ditch between Fill Deposit A (White Mud Pond) and the eastern access road. This area is mapped as an herbaceous upland cover type. (Photo Date: 12/12/2014)



Photo 32. Photo shows typical conditions present along the southern shoreline of the MBTL Site including the scrub-shrub riparian cover type on the berm around the Dredged Material Disposal Area and a forested riparian area. (Photo Date: 12/12/2014)



Photo 33. Photo shows forested riparian cover type along southern portion of the MBTL Site shoreline. (Photo Date: 12/12/2014)



Photo 34. Photo shows typical managed herbaceous vegetation cover type growing on the river side of the CDID Columbia River Levee. Existing rock groin and pile dikes are also visible. (Photo Date: 12/12/2014)



Photo 35. Photo shows typical managed herbaceous vegetation cover type growing on the river side of the CDID Columbia River Levee downstream of the existing Dock 1 conveyor and trestle on the MBTL Site. Forested riparian areas are also shown. (Photo Date: 4/8/2014)




Photo 36. Photo shows typical managed herbaceous vegetation cover type growing on the river side of the CDID Columbia River Levee and in the vicinity of the existing Dock 1 conveyor and trestle on the MBTL Site. Forested riparian vegetation cover types are also shown (Photo Date: 4/8/2014)




Photo 37. Photo shows typical managed herbaceous vegetation cover type growing on the river side of the CDID Columbia River Levee and herbaceous riparian area along shoreline. Existing pile dikes are also visible. (Photo Date: 4/8/2014)



Photo 38. Photo shows typical conditions present along the northern shoreline of the MBTL Site near the CDID Reynolds Pump Station outfall. (Photo Date: 12/12/2014)



Photo 39. Photo shows the typical conditions present in the Dredged Material Storage Area on the MBTL Site. (Photo Date: 12/12/2014)



Photo 40. Photo shows typical vegetation growing on the landward side of the berm around the Dredged Material Storage Area on the MBTL site. This area was classified as scrub-shrub riparian (Photo Date: 12/12/2014)



Photo 41. Photo shows typical herbaceous wetland vegetation cover type in the northern portion of Wetland E on Parcel 61954 of the MBTL Site (Photo Date: 12/12/2014)



Photo 42. Photo shows typical herbaceous wetland vegetation cover type in the southern portion of Wetland E on Parcel 61954 of the MBTL Site (Photo Date: 12/12/2014)




Photo 43. Photo shows disturbed, herbaceous upland, managed herbaceous upland, and herbaceous wetland cover types present in the southern portion of Barlow Point Site, as viewed from the Mount Solo Landfill. Wetlands 3 and 5 are present in the center of the photo but are not readily discernable. (Photo Date: 12/12/2014)



Photo 44. Photo shows disturbed, herbaceous upland, managed herbaceous upland, and herbaceous wetland cover types present in the southern portion of Barlow Point Site, as viewed from the Mount Solo Landfill. (Photo Date: 12/12/2014)




Photo 45. Photo shows disturbed, herbaceous upland, managed herbaceous upland, and herbaceous wetland cover types present in the southern portion of Barlow Point Site, as viewed from the Mount Solo Landfill. Wetland 4 is present on both sides of the excavated ditch. (Photo Date: 12/12/2014)




Photo 46. Photo shows multiple vegetation cover types present in the of central portion of Barlow Point Site including herbaceous upland and the herbaceous and forested wetland cover types in Wetland 2, as viewed from the Mount Solo Landfill. (Photo Date: 12/12/2014)




Photo 47. Photo shows typical herbaceous upland vegetation cover type of central portion of Barlow Point Site as viewed from the Mount Solo Landfill. Recently placed brush piles in the disturbed cover type, Mount Solo Slough, and an excavated drainage ditch are also shown. (Photo Date: 12/12/2014)




Photo 48. Photo shows recently placed brush piles in the disturbed cover type along Mount Solo Slough. (Photo Date: 12/12/2014)



Photo 49. Photo shows herbaceous upland cover type present in the central portion of Barlow Point Site, as viewed from the Mount Solo Landfill. Excavated ditch draining to Mount Solo Slough is also shown. (Photo Date: 12/12/2014)




Photo 50. Photo shows herbaceous upland cover type present in the central portion of Barlow Point Site, as viewed from the Mount Solo Landfill. Existing agricultural building is shown on the right in an area classified as disturbed cover type. (Photo Date: 12/12/2014)




Photo 51. Photo shows northern portion of Barlow Point Site as viewed from the Mount Solo Landfill including herbaceous and scrub-shrub wetland cover types in Wetland 6. (Photo Date: 12/12/2014)




Photo 52. Photo shows typical managed herbaceous upland cover type growing on the river side of the CDID Columbia River Levee on the Barlow Point Site. A thin band of scrub-shrub riparian vegetation cover types is also shown (Photo Date: 12/12/2014)




Photo 53. Photo shows typical managed herbaceous upland cover type growing on the river side of the CDID Columbia River Levee on the Barlow Point Site. The scrub-shrub riparian and forested upland cover types are also shown. (Photo Date: 12/12/2014)



Photo 54. Photo shows herbaceous and managed herbaceous upland cover types present in the southern portion of Barlow Point Site, as viewed from the MBTL Site. Wetlands 4 and 5 are present in the background but difficult to discern on the photo. (Photo Date: 12/12/2014)

MILLENNIUM BULK TERMINALS—LONGVIEW NEPA ENVIRONMENTAL IMPACT STATEMENT

NEPA FISH TECHNICAL REPORT

PREPARED FOR:

U.S. Army Corps of Engineers, Seattle District
4735 East Marginal Way South
Seattle, WA 98134

PREPARED BY:

ICF International
710 Second Avenue, Suite 550
Seattle, WA 98104

September 2016



ICF International. 2016. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statements, NEPA Fish Technical Report*. September. (ICF 00264.13.) Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.

Contents

List of Tables	ii
List of Figures	ii
List of Acronyms and Abbreviations	iii
Chapter 1 Introduction	1-5
1.1 Project Description	1-5
1.1.1 On-Site Alternative	1-5
1.1.2 Off-Site Alternative	1-8
1.1.3 No-Action Alternative	1-1
1.2 Regulatory Setting	1-1
1.3 Study Area	1-3
1.3.1 On-Site Alternative	1-3
1.3.2 Off-Site Alternative	1-6
Chapter 2 Affected Environment	2-1
2.1 Methods	2-1
2.1.1 Data Sources	2-1
2.1.2 Impact Analysis	2-2
2.2 Affected Environment	2-3
2.2.1 On-Site Alternative	2-3
2.2.2 Off-Site Alternative	2-24
Chapter 3 Impacts	3-1
3.1 On-Site Alternative	3-1
3.1.1 Construction: Direct Impacts	3-1
3.1.2 Construction—Indirect Impacts	3-20
3.1.3 Operations: Direct Impacts	3-20
3.1.4 Operations: Indirect Impacts	3-23
3.2 Off-Site Alternative	3-31
3.2.1 Construction: Direct Impacts	3-31
3.2.2 Construction: Indirect Impacts	3-33
3.2.3 Operations: Direct Impacts	3-33
3.2.4 Operations: Indirect Impacts	3-33
3.3 No-Action Alternative	3-35
Chapter 4 Required Permits	4-1
Chapter 5 References	5-1
5.1 Written References	5-1

Tables

1	Regulations, Statutes, and Guidance for Fish	1-1
2	Status of Focus Species and Seasonal Presences in the Study Area	2-13
3	Nonfocus Fish Species that May Occur in the Study Area	2-22
4	Underwater Sound-Level Thresholds for Endangered Species Act-Listed Fish	3-8
5	Underwater Noise Thresholds and Distances to Threshold Levels.....	3-10
6	Summary of Salmonid ESUs/DPSs for which Presence is not Discountable during the Impact Pile Driving Proposed Work Window (September 1–December 31) by Life Stage, Month, and Habitat Zone.....	3-11
7	Average Concentration of Trace Elements in Wyodak and Big George Coal Beds, Powder River Basin, Wyoming	3-30

Figures

1	Project Vicinity	1-6
2	On-Site Alternative	1-7
3	Off-Site Alternative	1-9
4	Study Area Boundaries for the On-Site Alternative	1-4
5	Aquatic Study Area for Project-Related Vessel Traffic.....	1-5
6	Study Area Boundaries for the Off-Site Alternative	1-7
7	Cross Section of Shoreline Habitats adjacent to the Project Area.....	2-6
8	Aquatic Habitat Types Potentially Affected by the On-Site Alternative	2-7
9	Fish Stranding Sites.	2-11
10	Aquatic Habitat Types Potentially Affected by the Off-Site Alternative.....	2-26
11	Number of Vessels Entering the Columbia River per Year	3-23
12	Modeled Average Annual Coal Dust Deposition (On-Site Alternative)	3-28
13	Modeled Average Annual Coal Dust Deposition (Off-Site Alternative)	3-34

Acronyms and Abbreviations

ACM	Active Channel Margin
Applicant	Millennium Bulk Terminals—Longview, LLC
bgs	below ground surface
BNSF	Burlington Northern Santa Fe Railway
CDID	Consolidated Diking Improvement District
CEQ	Council on Environmental Quality
CFR	Code of Federal Regulations
cfs	cubic feet per second
Corps	U.S. Army Corps of Engineers
CRC	Columbia River Crossing
CRD	Columbia River Datum
DART	Data Access in Real Time
dB	decibels
DPSs	Distinct Population Segments
dwt	dead weight tons
DWZ	Deep Water Zone
Ecology	Washington Department of Ecology
EFH	essential fish habitat
ESA	Endangered Species Act
ESUs	Evolutionary Significant Units
FR	Federal Register
g/m ²	grams per square meter
HEA	habitat equivalency analysis
HPA	Hydraulic Project Approval
IPaC	Information, Planning, and Conservation
LVSW	Longview Switching Company
mg/L	milligrams per liter
NEPA	National Environmental Policy Act
NMFS	National Marine Fisheries Service
NOAA	National Oceanic and Atmospheric Administration
NTUs	nephelometric turbidity units
OHW	ordinary high water
PAHs	polycyclic aromatic hydrocarbons
PCE	primary constituent elements
PHS	Priority Habitats and Species
Port	Port of Longview
ppm	parts per million
PTS	permanent threshold shifts
RCW	Revised Code of Washington
Reynolds facility	Reynolds Metal Company facility
RM	river miles
RMS	root mean square
SEL	sound exposure level
SEPA	State Environmental Policy Act

SPL	sound pressure level
SWZ	Shallow Water Zone
TEEC	trace elements of environmental concern
TTS	temporary threshold shift
UP	Union Pacific
USC	United States Code
USFWS	U.S. Fish and Wildlife Service
USGS	U.S. Geological Survey
WAC	Washington Administrative Code
WDFW	Washington Department of Fish and Wildlife

This technical report assesses the potential fish and fish habitat impacts of the proposed Millennium Bulk Terminals—Longview project (On-Site Alternative), Off-Site Alternative, and No-Action Alternative. This report describes the regulatory setting, establishes the method for assessing potential fish and fish habitat impacts, presents the historical and current fish and fish habitat conditions in the study area, and assesses potential impacts.

1.1 Project Description

Millennium Bulk Terminals—Longview, LLC (Applicant) proposes to construct and operate an export terminal in Cowlitz County, Washington, along the Columbia River (Figure 1). The export terminal would receive coal from the Powder River Basin in Montana and Wyoming and the Uinta Basin in Utah and Colorado via rail shipment, then load and transport the coal by ocean-going ships via the Columbia River and Pacific Ocean to overseas markets in Asia. The export terminal would be capable of receiving, stockpiling, blending, and loading coal by conveyor onto ships for export. Construction of the export terminal would begin in 2018. For the purpose of this analysis, it is assumed the export terminal would operate at full capacity by 2028. The following subsections present a summary of the On-Site Alternative, Off-Site Alternative, and No-Action Alternative.

1.1.1 On-Site Alternative

Under the On-Site Alternative, the Applicant would develop an export terminal on 190 acres (project area). The project area is located within an existing 540-acre area currently leased by the Applicant at the former Reynolds Metals Company facility (Reynolds facility), and land currently owned by Bonneville Power Administration. The project area is adjacent to the Columbia River in unincorporated Cowlitz County, Washington near Longview city limits (Figure 2).

The Applicant currently and separately operates at the Reynolds facility, and would continue to separately operate a bulk product terminal on land leased by the Applicant. Industrial Way (State Route 432) provides vehicular access to the Applicant's leased land. The Reynolds Lead and the BNSF Spur rail lines, both operated by Longview Switching Company (LVSW),¹ provide rail access to the Applicant's leased area from the BNSF Railway Company (BNSF) main line (Longview Junction) located to the east in Kelso, Washington. Ships access the Applicant's leased area including the bulk product terminal via the Columbia River and berth at an existing dock (Dock 1) operated by the Applicant in the Columbia River.

Under the On-Site Alternative, BNSF or Union Pacific Railroad (UP) trains would transport coal in rail cars from the BNSF main line at Longview Junction to the project area via the BNSF Spur and Reynolds Lead. Coal would be unloaded from rail cars, stockpiled and blended, and loaded by conveyor onto ocean-going ships at two new docks (Docks 2 and 3) on the Columbia River for export to Asia.

¹ LVSW is jointly owned by BNSF Railway Company (BNSF) and Union Pacific Railroad (UP).



Figure 1. Project Vicinity

Figure 2. On-Site Alternative

Once construction is complete, the export terminal would have an annual throughput capacity of up to 44 million metric tons of coal.² The export terminal would consist of one operating rail track, eight rail tracks for the storage of rail cars, rail car unloading facilities, stockpile areas for coal storage, conveyor and reclaiming facilities, two new docks in the Columbia River (Docks 2 and 3), and ship-loading facilities on the two docks. Dredging of the Columbia River would be required to provide access to and from the Columbia River navigation channel and for berthing at the two new docks.

Vehicles would access the project area from Industrial Way (State Route 432). Ships would access the project area via the Columbia River and berth at one of the two new docks. Trains would access the export terminal via the BNSF Spur and the Reynolds Lead. Terminal operations would occur 24 hours per day, 7 days per week. The export terminal would be designed for a minimum 30-year period of operation.

1.1.2 Off-Site Alternative


Under the Off-Site Alternative, the export terminal would be developed on an approximately 220-acre site adjacent to the Columbia River, located in both Longview, Washington, and unincorporated Cowlitz County, Washington, in an area commonly referred to as Barlow Point (Figure 3). The project area for the Off-Site Alternative is west and downstream of the project area for the On-Site Alternative. Most of the project area for the Off-Site Alternative is located within Longview city limits and owned by the Port of Longview. The remainder of the project area is within unincorporated Cowlitz County and privately owned.

Under the Off-Site Alternative, BNSF or UP trains would transport coal from the BNSF main line at Longview Junction over the BNSF Spur and the Reynolds Lead, which would be extended approximately 2,500 feet to the west. Coal would be unloaded from rail cars, stockpiled and blended, and loaded by conveyor onto ocean-going ships at two new docks (Docks A and B) on the Columbia River. The Off-Site Alternative would serve the same purpose as the On-Site Alternative.

Once construction is complete, the Off-Site Alternative would have an annual throughput capacity of up to 44 million metric tons of coal. The export terminal would consist of the same elements as the On-Site Alternative: one operating rail track, eight rail tracks for the storage of rail cars, rail car unloading facilities, stockpile areas for coal storage, conveyor and reclaiming facilities, two new docks in the Columbia River (Docks A and B), and ship-loading facilities on the two docks. Dredging of the Columbia River would be required to provide access to and from the Columbia River navigation channel and for berthing at the two new docks.

Vehicles would access the project area via a new access road extending from Mount Solo Road (State Route 432) to the project area. Trains would access the terminal via the BNSF Spur and the extended Reynolds Lead. Ships would access the project area via the Columbia River and berth at one of the two new docks. Terminal operations would occur 24 hours per day, 7 days per week. The export terminal would be designed for a minimum 30-year period of operation.

² A metric ton is the U.S. equivalent to a tonne per the International System of Units, or 1,000 kilograms or approximately 2,204.6 pounds.

Figure 3. Off-Site Alternative

1.1.3 No-Action Alternative

Under the No-Action Alternative, the U.S. Army Corps of Engineers would not issue the requested Department of the Army permit under the Clean Water Act Section 404 and the Rivers and Harbors Act Section 10. This permit is necessary to allow the Applicant to construct and operate the proposed export terminal.

The Applicant plans to continue operating its existing bulk product terminal located adjacent to the On-Site Alternative project area, as well as expand this business whether or not a Department of the Army permit is issued. Ongoing operations would include storing and transporting alumina and small quantities of coal, and continued use of Dock 1. Maintenance of the existing bulk product terminal would continue, including maintenance dredging at the existing dock every 2 to 3 years. Under the terms of an existing lease, expanded operations could include increased storage and upland transfer of bulk products utilizing new and existing buildings. The Applicant would likely undertake demolition, construction, and other related activities to develop expanded bulk product terminal facilities.

In addition to the current and planned activities, if the requested permit is not issued, the Applicant would intend to expand its bulk product terminal business onto areas that would have been subject to construction and operation of the proposed export terminal. In 2014, the Applicant described a future expansion scenario under No-Action Alternative that would involve handling bulk materials already permitted for off-loading at Dock 1. Additional bulk product transfer activities could involve products such as a calcine pet coke, coal tar pitch, cement, fly ash, and sand or gravel. While future expansion of the Applicant's bulk product terminal business might not be limited to this scenario, it was analyzed to help provide context to a No-Action Alternative evaluation and because it is a reasonably foreseeable consequence of a Department of the Army denial.

1.2 Regulatory Setting

The jurisdictional authorities and corresponding regulations, statutes, and guidance for determining potential impacts on fish are summarized in Table 1.

Table 1. Regulations, Statutes, and Guidance for Fish

Regulation, Statute, Guideline	Description
Federal	
National Environmental Policy Act (42 USC 4321 et seq.)	Requires the consideration of potential environmental effects. NEPA implementation procedures are set forth in the President's Council on Environmental Quality's Regulations for Implementing NEPA (49 CFR 1105).
U.S. Army Corps of Engineers NEPA Environmental Regulations (33 CFR 230)	Provide guidance for implementing the procedural provisions of NEPA for the Corps. It supplements CEQ regulations 40 CFR 1500–1508.

Regulation, Statute, Guideline	Description
Endangered Species Act (16 USC 1531 et seq.)	The federal Endangered Species Act of 1973, as amended, provides for the conservation of species that are listed as threatened and endangered and the habitat upon which they depend. Section 7 of the federal Endangered Species Act requires that federal agencies initiate consultation with the USFWS and/or NMFS. This will ensure the federal action is not likely to jeopardize the continued existence of any listed threatened or endangered animal species or result in the destruction or adverse modification of designated critical habitat.
Magnuson-Stevens Fishery Conservation and Management Act, as amended by the Sustainable Fisheries Act of 1996 (Public Law 104-267)	Requires fishery management councils to include descriptions of essential fish habitat and potential threats to essential fish habitat in all federal fishery management plans. Also requires federal agencies to consult with NMFS on activities that may adversely affect essential fish habitat.
State	
Washington State Environmental Policy Act (WAC 197-11, RCW 43.21C)	Requires state and local agencies in Washington to identify potential environmental impacts that could result from governmental decisions.
Washington State Growth Management Act (RCW 36.70A)	Defines a variety of critical areas, which are designated and regulated at the local level under city and county critical areas ordinances.
Washington State Shoreline Management Act (90.58 RCW)	Requires cities and counties (through their Shoreline Master Programs) to protect shoreline natural resources.
Washington State Hydraulic Code (WAC 220-660)	Under the Hydraulic Code, WDFW issues a hydraulic project approval for certain construction projects or activities in or near state waters. The hydraulic code was specifically designed to protect fish life.
Clean Water Act Section 401 Water Quality Certification	Ecology issues Section 401 Water Quality Certification for in-water construction activities to ensure compliance with state water quality standards and other aquatic resources protection requirements under Ecology's authority as outlined in the federal Clean Water Act.
Local	
Cowlitz County SEPA Regulations (CCC Code 19.11)	Provide for the implementation of SEPA in Cowlitz County.
Cowlitz County Critical Areas Code (19.15)	Regulates activities within and adjacent to critical areas, including those that support fish and fish habitat.
Cowlitz County Shoreline Master Program	Regulates development within shoreline jurisdiction, including the shores of the Columbia River, a Shoreline of Statewide Significance.
City of Longview Shoreline Master Program (Off Site-Alternative only)	Adopts Cowlitz County Shoreline Master Program by reference. The program must be updated to be consistent with Ecology's Shoreline Master Program Guidelines. This update must be completed by July 2015.
City of Longview Critical Areas Ordinance (17.10.140) (Off-Site Alternative only)	Regulates activities within and adjacent to critical areas, including those that support fish and fish habitat.
Notes: NEPA = National Environmental Policy Act; CFR = Code of Federal Regulations; Corps = U.S. Army Corps of Engineers; CEQ = Council on Environmental Quality; USFWS = U.S. Fish and Wildlife Service; NMFS = National Marine Fisheries Service; ESA = Endangered Species Act; USC = United States Code; WAC = Washington Administrative Code; RCW = Revised Code of Washington; WDFW = Washington Department of Fish and Wildlife; Ecology = Washington State Department of Ecology.	

1.3 Study Area

The study areas for the On-Site Alternative and Off-Site Alternative are described below.

1.3.1 On-Site Alternative

The On-Site Alternative project area would be located 63 river miles (RM) upstream of the Pacific Ocean on the northern shoreline of the Columbia River Estuary in Cowlitz County, Washington. The Columbia River estuary extends upstream from the mouth of the Columbia River to the Bonneville Dam (USGS 2011). The study area accounts for the area where potential underwater noise impacts would likely extend. Underwater noise disturbance thresholds have been established by the National Marine Fisheries Service (NMFS) and U.S. Fish and Wildlife Service (USFWS) for fish, primarily salmonids, which occur in the Columbia River adjacent to the On-Site Alternative; therefore, these thresholds were used to help establish the study area relative to fish. The underwater noise study area includes the Columbia River in which construction noise could disturb fish and extends between the following approximate boundaries: downstream boundaries are near the downstream end of Walker Island (RM 60.4) on the Oregon side and Barlow Point (RM 61.6) on the Washington side, and upstream boundaries are near the City of Rainier (RM 67.0) on the Oregon side and the Lewis and Clark Bridge (RM 66.0) on the Washington side (Grette 2014a) (Figure 4). This area extends a distance of approximately 3.92 miles upstream and downstream of the project area in the Columbia River (measured respectively, from the upstream and downstream extents of the proposed docks at the On-Site Alternative). The study area for direct impacts is based on the distances at which underwater noise generated during project related in-water pile driving is estimated to reach noise disturbance thresholds (i.e., 150 decibels [dB] root mean square³ [RMS]) for fish from impact and vibratory pile driving (Grette 2014b).

At full build out, the On-Site Alternative would load 70 vessels (Panamax and/or Handymax) per month. Vessels of this size generate wakes, which in certain circumstances can strand fish on shallow sloping beaches. Therefore, the study area for indirect impacts on fish extends from the project area downstream to the landward line of the territorial sea (i.e., a line between the western-most end of the north and south jetties), from here on referred to as the mouth of the Columbia River (Figure 5). This study area includes shallow-sloping beaches along the river on which fish could be stranded by the wakes of passing vessels.

³ Root Mean Square (RMS) is the square root of the energy divided by the impulse duration. This level is the mean square pressure level of the pulse.




Figure 4. Study Area Boundaries for the On-Site Alternative

Figure 5. Aquatic Study Area for Project-Related Vessel Traffic

1.3.2 Off-Site Alternative

The study area for Off-Site Alternative is similar to that described for the On-Site Alternative. The study area includes the main channel of the Columbia River and a small section of the Fisher Island Slough side channel (located between Fisher Island and Washington) in which construction noise could disturb fish. The extent of the main channel study area extends between the following approximate boundaries: downstream boundary is near the upstream end from Crims Island (RM 57.0), and upstream boundary is downstream from the Lewis and Clark Bridge (RM 65.7) (Grette 2014b) (Figure 6). This area extends a distance of approximately 3.92 miles upstream and downstream in the Columbia River (measured, respectively, from the upstream and downstream extents of the proposed docks at the Off-Site Alternative). As mentioned for the On-Site Alternative, the study area is based on the distances at which underwater noise is estimated to reach noise disturbance thresholds (i.e., 150 dB_{RMS}) for fish from impact and vibratory pile driving (Grette 2014b).

Similar to the On-Site Alternative, the study area for fish has been expanded to include the Columbia River downstream from the Off-Site Alternative to the Columbia River mouth to accommodate an analysis of the potential effects of fish stranding on shallow sloping beaches. This portion of the study area is not depicted on Figure 6 due to the scale, but is similar to the aquatic study area shown on Figure 5.

Figure 6. Study Area Boundaries for the Off-Site Alternative

Chapter 2

Affected Environment

This chapter describes the methods for assessing the affected environment and determining impacts, and the affected environment in the study areas as it pertains to fish and fish habitat.

2.1 Methods

This section describes the sources of information and methods used to characterize the affected environment and assess the potential impacts of the proposed export terminal on fish and fish habitat.

This assessment is based on information collected specifically for this technical report, as well as available information concerning fish and aquatic resources in the Columbia River. It specifically addresses existing aquatic and shoreline habitat conditions within the project areas, as well as areas adjacent to the project areas potentially affected directly and indirectly by construction and operation. This includes the shoreline and offshore areas associated with the proposed deepwater terminals, aquatic habitats subject to temporary impacts during construction, aquatic habitats affected by construction and maintenance dredging to create and maintain vessel access to the export terminal, and impacts of vessels transiting within the Columbia River between the project areas and the mouth of the Columbia River.

2.1.1 Data Sources

The following sources were used to evaluate fish and fish habitat characteristics of the study area.

- One site visit conducted by ICF fish biologists on January 29, 2014.
- Reports prepared by Grette Associates for the Applicant as part of the permit application supporting materials.
 - *Docks 2 and 3 and Associated Trestle Direct Effects of Construction* (Grette 2014a).
 - *Off-Site Alternative – Barlow Point Pile Driving and Underwater Sound* (Grette 2014b).
 - *Affected Environment Biological Resources. Technical Report* and associated appendices (Grette 2014c).
 - *Docks 2 and 3 and Associated Trestle: Proposed Mitigation Measures to Minimize Construction and Long-Term Effects* (Grette 2014d).
 - *Off-Site Alternative – Barlow Point Permanent Impacts to Aquatic Habitat* (Grette 2014e).
 - *Permanent Impacts to Aquatic Habitat* (Grette 2014f).
- National Oceanic and Atmospheric Administration (NOAA) Fisheries West Coast Region species list (2014a).
- NOAA Fisheries listing packages (2014a, b).
- USFWS (2014) Information, Planning, and Conservation (IPaC) system online database.

- Washington Department of Fish and Wildlife (WDFW) Priority Habitats and Species (PHS) geographic information system (GIS) data for the study area (2015a). The Priority Habitat and Species Program is fulfilled by WDFW to provide important fish, wildlife and habitat information to local governments, state and federal agencies, private landowners, consultants, and tribal biologists for land use planning purposes.
- Washington Department of Fish and Wildlife (2015b) SalmonScape data for the study area and vicinity.
- Washington State Department of Natural Resources, Natural Heritage Program, February 2014 database (accessed by ICF on April 7, 2014).
- Washington State Department of Ecology (Ecology) 303(d) /305(b) Integrated Report Viewer (accessed by ICF in December 2014).
- Fish Passage and Timing Data Columbia River Data Access in Real Time (DART), Columbia Basin Research, University of Washington (juvenile and adult fish passage) (Columbia River Basin 2013).
- Fish Passage Center. Query of adult passage at Bonneville Dam: graph with current year, last year, and 10-year average (Fish Passage Center 2014).
- Comments received from interested parties during the scoping period relative to fish and wildlife, as summarized in the NEPA Scoping Report (February 10, 2014).
- Other scientific literature and sources of technical information as cited in the text.

2.1.2 Impact Analysis

The following methods were used to evaluate the potential impacts of the On-Site Alternative, Off-Site Alternative, and No-Action Alternative on fish and fish habitat. For the purposes of this analysis, construction impacts are based on peak construction period and operations impacts are based on maximum throughput capacity (up to 44 million metric tons per year). For direct impacts, the analysis assumes best management practices were incorporated into the design, construction, and operations of the export terminal. More information about best management practices can be found in the NEPA Draft Environmental Impact Statement (Volume 1), Chapter 8, *Minimization and Mitigation*, and Appendix H, *Export Terminal Design Features*.

Potential impacts on fish and fish habitat were determined by considering the species that are likely to occur in the study area based on field surveys, site visits, the presence of suitable habitat and geographic range, and documented species occurrences and habitat conditions. For documented occurrences, focus was on fish species identified in the WDFW PHS database. The PHS program provides comprehensive information on important fish, wildlife, and habitat resources in Washington. It is the principal means by which WDFW provides fish, wildlife, and habitat information to public and private entities for planning purposes. In addition, the USFWS list of federally listed species in Cowlitz County and the NMFS West Coast Region species list of fish (which are also included in the PHS database) were also considered.

WDFW maintains a PHS geospatial database that maps likely locations of priority species occurrences and priority habitats. Priority species in the PHS program include fish and wildlife species classified under state law (WAC 232-12-297) as threatened, endangered, or sensitive, as well as species that are candidates for such classification. Other PHS species include vulnerable

aggregations of species or groups of animals that are susceptible to significant population declines due to their inclination to aggregate, and species of recreational, commercial, and/or tribal importance. The PHS database also includes state-monitored species, which are not considered special-status but are monitored for status and distribution trends. Geospatial PHS data containing mapped locations of priority species occurrences and priority habitats was obtained from WDFW (Washington Department of Fish and Wildlife 2015a). This PHS data was overlaid with the study area to determine presence of documented priority fish species and habitat occurrences.

A list of special-status fish species was compiled for the study area, consisting of those species federally listed as threatened, endangered, proposed, or candidate species, and fish species listed in the WDFW PHS database.

A list of federally listed fish species for Cowlitz County was generated from the USFWS IPaC online planning tool (U.S. Fish and Wildlife Service 2014).

A list of state priority species that occur in Cowlitz County was obtained from the WDFW PHS program website (Washington Department of Fish and Wildlife 2015a).

A list of federally protected fish and their habitat, including essential fish habitat, that could occur in the study area was also compiled from the NMFS (2015) West Coast Region website.

The impact analysis for fish habitat is quantitative; however, the impact analysis for fish species is qualitative because fish are generally mobile and their presence and abundance within the study area cannot be quantitatively predicted at any one location or time. In addition, a species reaction to an impact mechanism, such as construction-generated noise, can be different for each species given the variability in species' hearing frequencies, mobility, vision, and overall sensitivity (e.g., juvenile fish may be more sensitive and susceptible to potential impacts than adult fish). Therefore, impact mechanisms are identified and a qualitative impact discussion describes the potential effect an impact mechanism could have on species that may be in the study area during construction and operations.

2.2 Affected Environment

The affected environment related to fish and fish habitat in the study areas are described below.

2.2.1 On-Site Alternative

The project area for the On-Site Alternative is located along the north side of the Columbia River at river mile 63, within unincorporated Cowlitz County and adjacent to the City of Longview.

2.2.1.1 Project Area

The project area was once productive marsh and riparian floodplain habitat used by many species of fish for spawning, foraging, and rearing. It is now extensively modified for flood control, industrial development, and deep draft vessel traffic, and its value for fisheries is now primarily as a migratory corridor from upstream spawning areas to downstream rearing and foraging areas in the estuary and marine environments.

Adjacent lands to the north and west are largely undeveloped and are used for a combination of agricultural and recreation activities. Lands to the south and east are heavily industrialized and include a large Weyerhaeuser Lumber processing and export terminal and the Port of Longview (Port). The Port is a multipurpose deep-draft terminal encompassing 478 acres and over one mile of waterfront at RM 66 on the Columbia River. The marine terminal includes nine berths handling bulk, break bulk, and cargoes for or from domestic barge and international (Panamax sized) ocean vessels. During 2010, the Port had 154 vessel calls, totaling 2.3 million metric tons of cargo (Port of Longview 2010). In 2012, this number increased to 225 vessel calls, reflecting the increased capacity provided by a new bulk export grain terminal capable of handling more than 8 million metric tons annually (Kulisch 2013).

In the 1920s, Consolidated Diking Improvement District (CDID) #1 constructed a levee along the Columbia River shoreline to protect Longview area properties from Columbia River flooding. In conjunction with the levees, the CDID also excavated a series of ditches to facilitate development of low-lying properties. These ditches, which lie north and west of the project area, drain both stormwater and shallow groundwater from properties within CDID #1. The ditch water is ultimately discharged to the Columbia River through pump stations. The topography of the 540-acre Applicant's leased area varies by location, although overall it is generally flat. Current topography on the property south of Industrial Way indicates the majority of the upland portion of the site is in the range of elevation +5 to +12 feet above the Columbia River Datum (CRD).⁴

This area is currently developed with a variety of facilities and structures associated with the former Reynolds facility. Most of the approximately 540-acre site that is located south of Industrial Way is paved with asphaltic concrete and Portland cement concrete pavements. The western portion of the site extends into wooded areas and grass-covered fields.

2.2.1.2 Study Area

The hydrology of the region, as described in the NEPA Groundwater Technical Report (ICF International 2016a) is characterized by two major aquifers: the upper alluvial aquifer (i.e., shallow groundwater) and a deeper confined aquifer. Shallow groundwater is present in the upper 75 to 100 feet of alluvium, and is in direct communication with the Columbia River. Multiple groundwater zones are present in the upper alluvial aquifer due to the interbedded nature of the alluvium. A deeper confined aquifer is present below approximately 300 feet below ground surface (bgs) in coarser sands and gravels where production and supply wells draw groundwater. Both aquifers are in direct communication with the Columbia River.

The average annual rainfall recorded between 1931 and 2005 for Longview, Washington, is 46.17 inches. Approximately 44% of the total precipitation falls between November and January during winter storms. The average annual snowfall is just less than 5 inches. July and August are typically the two driest months of the year (Western Region Climate Center 2011, as cited in URS 2014).

The study areas have been moderately to highly modified as a result of historical and ongoing human activities that have altered natural habitat conditions. The mainstem Columbia River is deeper than it was historically because of construction and periodic dredging of the Federal navigation channel and the berthing areas along the river. The hydrologic regime and water

⁴ Columbia River Datum (CRD) is a vertical datum that is the adopted fixed low water reference plane for the lower Columbia River. It is the plane of reference from which river stage is measured on the Columbia River from the lower Columbia River up to Bonneville Dam, and on the Willamette River up to Willamette Falls. .

temperature conditions have been altered by the operation of the Federal Columbia River Power System throughout the Columbia River Basin. Floodplain habitats have been disconnected from the riverine environment and in some cases eliminated. Extensive shoreline armoring and protection, overwater structures, and development in adjacent upland and riparian zones have substantially degraded habitat conditions and altered habitat-forming processes, resulting in corresponding changes to the biological communities associated with these habitats. A more thorough discussion of the changes in the vegetation zones can be found in the NEPA Vegetation Technical Report (ICF International 2016b).

By the mid-20th century a significant portion of the study area had been diked, dredged, and filled (Graves et al. 1995 in Johnson et al. 2003). Alteration of the natural hydrograph by the operation of upstream dams and reservoirs, surface water diversions, and other water uses have decreased seasonal and annual flow variability and altered the timing of the hydrograph peak discharge and base discharge. Peak spring flows are now smaller, begin earlier, and last longer than they did historically. Winter flows are generally higher on average, but periodic peaks have been dampened or eliminated (Bottom et al. 2008). Overall, the average daily discharge in the Lower Columbia and the study area has decreased by approximately 16% relative to the historical norm (Bottom et al. 2008). The average annual flow for the Columbia River at Beaver Army Terminal near Quincy, Oregon, is approximately 236,600 cubic feet per second (cfs). The river's annual discharge rate fluctuates with precipitation and ranges from 63,600 cfs in a low water year to 864,000 cfs in a high water year (U.S. Geological Survey 2014). The change in flow conditions has altered estuarine dynamics in the study area. River flows can reverse direction during periods when river flows are low and incoming tides are large, and these reversal events now occur more frequently because the magnitude and timing of minimum flows has changed. Although the flow may reverse in response to tidal fluctuation, salt water does not intrude as far upstream as the study area and the water remains fresh through the tidal cycle. The study area can be considered a high-energy environment, characterized by strong currents, active bedload transport, and variable patterns of sediment of deposition and erosion (Grette 2014c).

2.2.1.3 Aquatic Habitat Types

The aquatic habitat for the study area is discussed in terms consistent with the habitat equivalency analysis (HEA) model, which provides a framework for describing habitat quality in the context of habitat availability and suitability as a function of water depth and physical attributes. The aquatic portion of the study area adjacent to the project area is composed of three broad habitat types (Grette 2014c): the Active Channel Margin (ACM), the Shallow Water Zone (SWZ), and the Deep Water Zone (DWZ). Although not technically an aquatic habitat, the riparian zone is discussed because of its interaction with aquatic habitats, as the riparian zone is the transition zone between aquatic and upland/terrestrial habitats. A cross-section of the aquatic habitat adjacent to the project area is provided in Figure 7, showing the maximum widths and typical depth profiles of each of these habitat types adjacent to the project area near the proposed new docks. Habitat type locations associated with the On-Site Alternative are provided in Figure 8.


Figure 7. Cross Section of Shoreline Habitats adjacent to the Project Area

Figure 8. Aquatic Habitat Types Potentially Affected by the On-Site Alternative

Riparian Zone

The discussion of the riparian zone here is focused on those elements relevant to aquatic habitat important to fish and fish habitat. The riparian zone includes lands less than 200 feet landward from ordinary high water (OHW) (+11.1 feet CRD). Shoreline armoring and CDID dikes have contributed to what is typically low habitat complexity, artificially steepened upper shoreline, and largely cut off floodplain connectivity. Landward of the shoreline, most of the riparian area has been so heavily modified there is little remaining function (Grette 2014c). There is a small area of intact riparian assemblage, immediately upstream of Dock 1; however, it consists primarily of nonnative and invasive species (ICF International 2016b). There is little potential for a remnant area of riparian habitat to contribute biological material (e.g., leaf litter, woody material, and insects) to the aquatic areas, nor does it provide shade or other physical function. In comparison to shoreline areas with intact riparian habitat, the HEA⁵ model would rank shoreline habitat at a relatively lower value, especially when compared to similar areas with intact riparian habitat (e.g., Lord Island, immediately across the river) (Grette2014c).

Active Channel Margin

The ACM is defined as the shoreline and nearshore edge habitat, extending from the OHW line to CRD 0 feet. For comparison purposes, the mean low water line is at approximately +2.7 feet CRD and OHW is at approximately +7.0 feet CRD (National Oceanic and Atmospheric Administration 2013, U.S. Army Corps of Engineers 2004a).⁶ Water levels in the ACM fluctuate continuously and portions are periodically dewatered because of tidal influence and river flow conditions, with the extent and duration of exposure dependent on site-specific topography. The ACM in the vicinity of the proposed docks covers approximately 25 acres and extends from 25 to 350 feet offshore with a typical maximum depth of about 11 feet (Figures 7 and 8), based on Ordinary High Water (OHW) of +11.1 feet CRD. The shoreline portion of the ACM (less than 1.5 acres) is sparsely vegetated and consists of sandy substrate with little organic matter (Grette 2014c). Habitat functions in the ACM are strongly influenced by the condition of the shoreline and adjacent riparian zone. The shoreline in this area is highly modified by dikes and riprap armoring that includes scattered large woody debris.

Generally the ACM provides foraging and rearing habitat for juvenile salmonids, particularly those expressing a stream-type life history (National Marine Fisheries Service 2011). Steelhead trout (*Onchorhynchus mykiss*), lamprey, adult eulachon (*Thaleichthys pacificus*), and sturgeon are less likely to be found in the ACM because these species generally prefer deeper open water habitats (Carter et al. 2009, Gustafson et al. 2010, Independent Scientific Review Panel 2013). However, periodic occurrence of these species cannot be discounted. Larval and juvenile sturgeon may drift or move incidentally into inundated habitats in the ACM. Larval eulachon dispersal into the ACM is also probable.

Shallow Water Zone

The SWZ includes the fully inundated near-shore zone extending from the ACM at 0 feet CRD out to -20 feet CRD. The SWZ is adjacent to the proposed docks and covers approximately 34 acres extending from approximately 25 to 500 feet offshore with maximum depths ranging from 11 to 31

⁵ HEA is a tool that can be used to estimate habitat gains and losses across a range of habitat types

⁶ The OHW line is equivalent to the mean higher high water line in the tidally influenced Lower Columbia River.

feet across this zone, based on OHW of +11.1 feet CRD. The bottom is primarily (90%) flat or shallow sloping substrate, with some moderate slopes out to depths of about 25 feet, where the habitat becomes markedly steeper. There are two pile dikes and one overwater dock that extends into the SWZ that likely provide both cover and refuge for prey and predator species, but they are not likely to substantially inhibit migration past the site. The substrate consists primarily of silty river sand with little organic matter (Grette 2014c).

Deep Water Zone

The third major habitat type in the study area is the DWZ. The DWZ habitat type encompasses about 115 acres in the project area, adjacent to the proposed docks, extending from the edge of the SWZ, beyond 31 feet deep, based on OHW of +11.1 feet CRD. At approximately 450 feet from the shore, this zone is about 31 feet deep, outward to a maximum depth of 56 feet deep approximately 1,200 feet from shore. The DWZ is used as an upstream migration corridor by adult salmonids returning to their spawning grounds and as a downstream corridor by juvenile salmonids of sufficient size to avoid predators and forage in open water. Steelhead are likely to be present periodically throughout the year in the DWZ as different summer and winter-run populations migrate through the area as juveniles and adults. Adult and subadult bull trout (*Salvelinus confluentus*) may also be found foraging in these deepwater habitats, particularly when eulachon, migrating juvenile salmonids, and other potential prey species are present in abundance. Eulachon (adults and larvae) are likely to be present during adult migration and larval dispersal. White sturgeon (*Acipenser transmontanus*) (adults, subadults, larvae, and juveniles) and green sturgeon (*Acipenser medirostris*) (adults and subadults) are likely to occur in the DWZ. Adult and juvenile lamprey may be present in the DWZ in the spring, summer, and fall during migration between freshwater and marine habitats.

There are a two pile dikes and one dock that extend into the DWZ. These structures are likely to influence but not inhibit the migration of juvenile salmonids, and they are likely to provide both resting and ambush habitats for predatory species including pikeminnow, bass, and piscivorous birds.

2.2.1.4 Columbia River Downstream of Project Area

The Columbia River downstream of the project area are considerably degraded compared to 200 years ago. The estuary tidal prism has been reduced by about 20% due mostly to dike and filling practices used to convert the floodplain to agricultural, industrial, commercial, and residential uses. Changes to flow volume and timing are attributed to hydrosystem regulation; water withdrawal for agricultural, municipal, and industrial purposes; and climate fluctuations. The near elimination of overbank flood events and the separation of the river from its floodplain have altered the food web and reduced floodplain habitats of particular importance to ocean-type salmon runs (salmonids that typically rear for a shorter time in tributaries and a longer time in the estuary) (National Marine Fisheries Service 2011).

The estuary also is influenced by a number of physical structures (jetties, pilings, pile dikes, bulkheads, revetments, docks, etc.) that contribute to its overall degradation, but the extent of their impacts is poorly understood. Over-water and instream structures in the estuary number in the thousands and alter river circulation patterns, sediment deposition, and light penetration; they also form microhabitats that often benefit predators. In some cases, structures reduce juvenile access to low-velocity habitats (National Marine Fisheries Service 2011).

Habitat forming processes in the lower river and estuary have also been altered by loss of upstream sediment input (now constrained behind upriver dams), changes in flow patterns that move sediments and modify landforms, and channel deepening and dredging. The full impact of these changes is unknown. Some of the concerns about impacts on sediment transport and channel forming processes have been addressed by the use of instream dredge disposal alternatives and disposal methods to help sustain in-channel islands and shallow water habitats (National Marine Fisheries Service 2011).


Stranding associated with existing ship wakes is an example of another threat to salmon and steelhead in the estuary. A study completed by ENTRIX (2008) identified 217 beach segments (out of 1,046 beach segments assessed) between the project area and the river mouth on which there is more than a minimal likelihood of fish stranding. Seventy of these sites occur in three clusters: Puget Island (RM 43–47), near Pt. Barlow (RM 61–62), and Walker and Lord Islands (RM 61–65) (Figure 9).

2.2.1.5 Focus Fish Species

This summary focuses primarily on fish species of special interest/concern, including federally and state-listed threatened and endangered species, and their designated critical habitat, as well as species of commercial, recreational, or cultural importance. Table 2 outlines the focus fish species, the status of the species (i.e., state and federal), habitat types these species typically occupy, and their seasonal occurrence in the study area. Affected environment and habitat use by focus fish species are described by habitat type in the following sections and summarized in Table 2.

The study area provides habitat for a variety of anadromous and resident fish species found in the Columbia River. Anadromous salmonids occurring within the study area include the following species: Chinook (*Onchorhynchus tshawytscha*), coho (*Onchorhynchus kisutch*), pink (*Onchorhynchus gorbuscha*), sockeye (*Onchorhynchus nerka*), and chum (*Onchorhynchus keta*) salmon; steelhead; bull trout; and coastal cutthroat trout (*Oncorhynchus clarkii clarkii*). Due to variable migration timing and duration of estuarine habitat use, one or more of these anadromous salmonid species are present in the Lower Columbia River throughout the year, as adults migrating upstream to spawning habitats, outmigrating juveniles, juveniles rearing in the estuary for extended periods, or, in the case of cutthroat trout and bull trout, as foraging subadults and adults. The study area also supports a variety of additional native and introduced fish species. Other anadromous or estuarine migrant species include green and white sturgeon, eulachon, shad (subfamily Alosinae), striped bass (*Morone saxatilis*), starry flounder (*Platichthys stellatus*), and Pacific lamprey (*Entosphenus tridentatus*) and river lamprey (*Lampetra ayresii*).

Resident freshwater fish expected to occur in the study area and vicinity include both coldwater (trout) and warmwater (bass, crappie, and bluegill [*Lepomis macrochirus*]) species, and locally migratory species (three spine sticklebacks (*Gasterosteus aculeatus*), peamouth chub [*Mylocheilus caurinus*]). Several resident fish species are predatory, feeding on a variety of small fish, including juvenile salmonids. These predators include the native northern pikeminnow (*Ptychocheilus oregonensis*), and introduced species such as walleye (*Sander vitreus*), crappie, and largemouth bass (*Micropterus salmoides*) and bass (*Micropterus dolomieu*).

Figure 9. Fish Stranding Sites

Salmon and Trout

Eight threatened or endangered salmon Evolutionary Significant Units (ESUs), five threatened steelhead Distinct Population Segments (DPSs), one threatened bull trout DPS, and their designated critical habitats occur in the Lower Columbia River and the study area (Table 2) (Bottom et al. 2008, National Marine Fisheries Service 2011). An ESU is defined as a population of organism that is considered distinct for purposes of conservation. A DPS is defined as the smallest division of a taxonomic species permitted to be protected under the ESA. In addition, essential fish habitat (EFH) has been designated for Chinook and coho salmon in the Lower Columbia River. EFH includes those waters and substrate necessary to fish for spawning, breeding, feeding, or growth to maturity, per the 1996 amendments to the Magnuson-Stevens Fishery Conservation and Management Act. The Columbia River estuary is used primarily as migratory and rearing habitat, and no salmonid spawning takes place in the study area. Adult anadromous salmonids travel through the estuary and lower river relatively quickly during their migration to upstream spawning grounds, remaining primarily in offshore deepwater habitats (Table 2 provides seasonal presence in the study area). In contrast, juvenile salmonids use a wider variety of habitats and exhibit more variable downstream migration speed, taking advantage of shallow water and ACM for foraging and seeking cover.

General salmon reproductive strategies can be divided into two groups: stream-rearing and ocean-rearing (noted in Table 2). Stream-rearing fish tend to spend extended periods, usually more than a year, rearing in fresh water before emigrating to the ocean. Examples of stream-type fish are steelhead, coho, and spring-run Chinook salmon. In contrast, ocean-type juvenile salmonids tend to return to the ocean in the same year they were spawned. Examples of ocean-type fish are chum salmon, and fall-run Chinook salmon. These strategies affect how each population uses the estuary and how it may be affected by the On-Site Alternative. Because stream-type salmon spend more time rearing in their natal streams and associated rivers, they arrive in the estuary at a relatively larger size than ocean-type salmon and therefore use the estuary differently and are affected by different factors. For example, stream-type salmon arrive in the estuary as larger fish and generally use the estuary as a migration route rather than rearing habitat, and are affected mostly by predation and flow. Ocean-type salmon move into the estuary at a smaller size and use the estuary as rearing habitat before entering the ocean. They are also affected by flow, but are more affected by habitat conditions in the estuary than are stream-type fish (Fresh et al. 2005). Salmonid occurrence by species and season are summarized in Table 2 (Bottom et al. 2008, Johnson et al. 2003, Fresh et al. 2005).

Habitat use and timing patterns of nonlisted salmon and steelhead populations are similar to the listed salmonid species (Table 2). Other salmonids, such as cutthroat trout, have complex life histories, consisting of both anadromous and resident populations that make extensive use of the lower river and estuary for foraging (Trotter 1989). Given the diverse run timing and life-history strategies exhibited by salmonids (Fresh et al. 2005) some life stage of salmon or trout could be present in the study area at any time. Salmon and steelhead use of the study area is described in the following sections by aquatic habitat type.

Table 2. Status of Focus Species and Seasonal Presences in the Study Area^a

Species, ESU/DPS	Federal Status ^a	Life Stage	Sept			Oct			Nov			Dec		
			A ^b	S ^b	D ^b	A	S	D	A	S	D	A	S	D
Chinook Salmon														
Snake River fall-run ESU	T	Adults			X ^c			...						
		Subyr		... ^d			
Lower Columbia River ESU	T	Adults			X			X						
		Yrlng												...
Upper Willamette River ESU	T	Subyr			
		Yrlng												...
		Subyr			
Coho Salmon														
Lower Columbia River ESU	T	Adults			X			X			X			X
		Subyr		
Chum Salmon														
Columbia River ESU	T	Adults						X			X			
		Subyr										
Steelhead Trout														
Snake River DPS	T	Adults			X			...						
Upper Columbia River DPS	T	Adults			X			...						
Middle Columbia River DPS	T	Adults			X			... ^e						
Lower Columbia River DPS	T	Adults			X			X			X			X
Bull Trout														
Columbia River DPS	T	Adults	
Cutthroat Trout														
Columbia River DPS	NL	Adults/Juveniles		X	X		X	X		X	X		X	X
Green Sturgeon														
Southern DPS	T	Adults/Sub-Adults		X	X		X	X						
Northern DPS	SOC	Adults		X	X		X	X						
		Sub-Adults		X	X		X	X						

Species, ESU/DPS	Federal Status ^a	Life Stage	Sept			Oct			Nov			Dec		
			A ^b	S ^b	D ^b	A	S	D	A	S	D	A	S	D
White Sturgeon														
Lower Columbia River		Adults		X	X		X	X		X	X		X	X
		Sub-Adults		X	X		X	X		X	X		X	X
Eulachon														
Southern DPS	T	Adults									X	X
		Eggs/Larvae									X	X
Pacific & River Lamprey														
Multiple populations	NL	Adults		X	X		X	X						
		Ammocoetes		X	X		X	X		X	X		X	X

^a "T" denotes federally threatened (no Endangered in this table), "NL" denotes Not Listed, SOC denotes Species of Concern.

^b A, S, and D represent the HEA habitat categories of ACM, SWZ, and DWZ; see Grette (2014c) Section 3.2.3.1 for additional information.

^c "X" denotes expected or potential presence; see Grette Associates (2014c), Section 3.3 for additional information.

^d "..." denotes expected presence but low relative abundance; see Grette Associates (2014c), Section 3.3 for additional information.

^e The Middle Columbia River DPS includes a very small proportion of winter-run fish (Klickitat River, Fifteen Mile Creek); because passage data at Bonneville Dam indicate that the vast majority of steelhead have passed the dam by early October, it is assumed that this includes winter steelhead spawning above it.

ESU = Evolutionary Significant Unit; DPS = Distinct Population Segment; Subyr = subyearling; Yrlng = yearling.

Designated critical habitat for federally protected salmonids within the study area consists of two primary constituent elements; migration corridors and estuarine areas. Migration corridors must be free of obstruction with healthy water quantity and quality conditions and natural cover such as submerged and overhanging large wood, aquatic vegetation, large rocks and boulders, side channel, and undercut banks to support juvenile and adult mobility and survival. Estuarine areas must be free of obstruction with water quality and salinity conditions to support juvenile and adult physiological transitions between fresh and saltwater; with natural cover such as submerged and overhanging large wood, aquatic vegetation, large rocks and boulders, and side channels; and with juvenile and adult forage, including aquatic invertebrates and fishes to support growth and maturation.

Additionally, the Columbia River is also Essential Fish Habitat (EFH), as defined by the Magnuson-Stevens Fishery and Management Conservation Act for Chinook salmon and coho salmon. EFH for Pacific salmon is defined as those waters and substrate necessary to support salmon production, a long-term sustainable salmon fishery, and salmon contributions to a healthy ecosystem. To achieve that level of production, EFH must include those streams, lakes, ponds, wetlands and other currently viable water bodies and most of the habitat historically accessible to salmon in Washington, Oregon, Idaho and California. Thus, any discussion regarding the existing fish habitat conditions as well as potential impacts on fish habitat is applicable to EFH for Pacific salmon (i.e., Chinook salmon and coho salmon).

Active Channel Margin Use by Salmon and Steelhead

A fully functioning ACM provides natural cover, shoreline complexity, shade, submerged and overhanging large woody debris, logjams, and aquatic vegetation. All of these elements are identified in the primary constituent elements (PCEs) of critical habitat for Endangered Species Act (ESA)-listed salmon and steelhead, as well as bull trout (Grette 2014c). The ACM provides important habitat for juvenile salmon, with different species using different habitat types at different life stages. PCEs are defined as those physical and biological features of a landscape that a species needs to survive and reproduce. Table 2 identifies the salmon and steelhead species and season when individuals may be present in the ACM affected by the On-Site Alternative.

Use of the ACM varies both between and within species depending on locally specific adaptation for some life stages. Some salmonid species and populations rear in the lower river and estuary for extended periods (weeks to months) prior to entering the ocean; others spend very little time in the estuary and are unlikely to be present in the ACM for extended periods (Bottom et al. 2008, Johnson et al. 2003). Roegner and Sobocinski (2008) found that subyearling Chinook and chum salmon are the most likely species to be found in the shallow nearshore habitats that compose the ACM. Juvenile chum salmon are abundant in shallow nearshore areas from March through May. Subyearling Chinook (likely ocean-type) are commonly found in the shallow margins of the ACM from March through July. Healthy ACM provides abundant macroinvertebrate forage and cover for protection from predation supporting increased growth, survival, and fitness. Information on use of the Columbia River estuary by the less abundant anadromous salmonid species (cutthroat and bull trout) and those species having life histories with limited freshwater rearing and migration (pink and chum salmon) is limited (Carter et al. 2009), although Carter et al. (2009) do report juvenile cutthroat trout use backwater and channel margin habitats during presmolt and smolt life stages in the Columbia River estuary. In contrast, steelhead and stream-type Chinook salmon are typically

larger when they reach the estuary and are more likely to be found farther offshore in the SWZ or DWZ.

As stated above, the ACM near the proposed docks has been extensively modified. As a consequence, it does not provide high-quality habitat for juvenile salmonids and other species that prefer shallow water habitats. These species are nonetheless likely to occur in the study area as they migrate downstream to better quality rearing in the lower river and estuary and/or during outmigration to the ocean (Table 2).

Shallow Water Zone Use by Salmon and Steelhead

The SWZ is used by adult salmon and steelhead as a migratory corridor and as foraging habitat by larger juveniles that are more capable swimmers in open water environments. Juvenile Chinook salmon, and sockeye salmon and steelhead smolts are typically found in deeper open water areas in the SWZ foraging on phytoplankton, invertebrates, and small fish (Bottom et al. 2008, Carter et al. 2009). Juvenile Chinook salmon are most commonly present from March through July but may be found in the SWZ during any month of the year. Juvenile coho salmon and steelhead are less likely to be found in the shallower areas but are abundant in deep water offshore habitats during their outmigration period (Roegner and Sobocinski 2008), indicating a likelihood of occurrence in the deeper areas of the SWZ.

Subyearling and yearling salmonids typically move offshore into the SWZ as temperatures increase in late spring and summer and as juveniles gain sufficient size to forage within the open water column (Carter et al. 2009). In general, survival and growth of juvenile salmonids is dependent upon habitats with ample food resources, resting areas (i.e., areas of slow current), refuge from predation, shoreline relief, side channels, and overhanging cover and banks. The SWZ near the proposed docks is made up of relatively high-energy habitat, with a sandy and silt bottom, and little organic matter, and is subject to erosion and deposition (National Marine Fisheries Service 2011). Consequently, this area is unlikely to provide substantial forage habitat for juvenile fish within the water column or along the bottom.

Generally, juvenile salmonids do not reside in specific habitats in the Lower Columbia River for extended periods, remaining in a given area for just a day or two before moving downstream to new suitable habitats (Bottom et al. 2008, Johnson et al. 2003). Carter et al. (2009) reported migration rates for tagged yearling and sub-yearling salmon of tens of kilometers per day. Given the simplicity of the shallow water habitat near the proposed docks and poor quality of the adjacent ACM, migratory fish are likely to move quickly through the area.

Deepwater Zone Use by Salmon and Steelhead

The DWZ zone provides a migratory corridor for adult salmon and steelhead and foraging and migratory habitat for larger juvenile Chinook salmon, coho salmon, and sockeye salmon and steelhead smolts pursuing phytoplankton, invertebrates, and small fish (Bottom et al. 2008, Carter et al. 2009, Roegner and Sobocinski 2008). Generally, juvenile salmonids do not reside in specific habitats in the Lower Columbia River for extended periods, remaining in a given area for just a day or two before moving downstream to new suitable habitats (Bottom et al. 2008, Johnson et al. 2003). Juvenile and adult salmon and steelhead are likely to be found in the DWZ during their respective migration and rearing periods (Table 2) as outmigrating salmonids (particularly stream type) tend to use deep water (Carter et al. 2009). The DWZ is also a dynamic environment,

characterized by high flows and sediment transport. Sediment type is composed mostly of fine grain sands with little to no gravel or cobble for structure (Grette 2014c).

Bull Trout (Char)

Columbia River bull trout are listed as threatened, and there is one extant population in a subbasin that drains to the Lower Columbia River below Bonneville Dam; the Lewis River. Bull trout migrate to the mainstem Columbia River to rear, overwinter, or migrate to and from spawning areas. This indicates the possibility that more distant populations (e.g., Klickitat, Deschutes, Willamette) may migrate to and forage in the project vicinity or could in the future, but the extent to which different bull trout populations use the Lower Columbia River is uncertain (Carter et al. 2009). The Lower Columbia Recovery Team considers the mainstem Columbia River to contain core habitat that may be important for full recovery of Columbia River bull trout (U.S. Fish and Wildlife Service 2002). Bull trout have occasionally been observed in the Lower Columbia River as foraging or migrating adults and subadults, most likely originating from accessible Lower Columbia River tributaries with extant bull trout populations. Subadults may occur in the study area throughout the year in shallow rearing habitats of the ACM and SWZ while adults are more likely to occur in the deeper areas of the SWZ and the DWZ (U.S. Army Corps of Engineers 2004b). However, bull trout are opportunistic predators and routinely move between aquatic habitat types in search of prey so they could be present anywhere in the study area during periods when they are likely to occur in the Lower Columbia River (Table 2).

Eulachon

Eulachon are small anadromous fish in the smelt family (*Osmeridae*), sometimes known as Columbia River smelt (among other names), that spawn in coastal rivers and migrate to the ocean to rear to adulthood. The historical range of this species extends from northern California to Bristol Bay, Alaska. NMFS has classified all extant eulachon populations from the southern end of the range in northern California to the Nass River in British Columbia (exclusive) as belonging to the Southern DPS of the species, and has listed this DPS as threatened under the ESA (*Federal Register* [FR], Volume 75, page 13012). Eulachon are a migratory anadromous species that spend the majority of their lives (2 to 5 years) in marine habitats but return to natal tributary rivers to spawn after reaching adulthood (75 FR 13012).

Eulachon reach sexual maturity and typically spawn in mid- to late-winter, spawning may also occur from November to April (Gustafson et al. 2010). Adults congregate in open water and scatter their fertilized eggs over a variety of substrates. The eggs are adhesive, remaining attached to the substrate through a relatively short incubation period lasting about two weeks at typical water temperatures; eggs survive best in pea-sized gravel and coarse sandy substrates. The newly hatched larvae are captured by currents immediately after hatching and are transported rapidly downstream to estuarine and ocean habitats. Larvae that are dispersed into low current areas may remain in the estuary for weeks or months before growing into juveniles large enough to migrate to marine waters on their own. Most larvae are carried directly to the ocean where they rear to adulthood (Carter et al. 2009).

Prior to construction of dams in the Columbia River, eulachon may have migrated as far as Hood River to spawn. Currently eulachon migrate to the base of Bonneville Dam and spawn in the main river channel and many of the downstream tributaries, including the Grays, Elochoman, Kalama, Cowlitz, Lewis, and Sandy Rivers (Washington Department of Fish and Wildlife and Oregon

Department of Fish and Wildlife 2001). The Lower Columbia River up to Bonneville Dam and the lower reaches of those tributary streams that provide potential spawning habitats (i.e., Grays, Elochoman, Cowlitz, Kalama, Lewis, and Sandy Rivers) have been designated as critical habitat (76 FR 65324). Currently, the lower mainstem Columbia River and the Cowlitz River support the majority of eulachon production in the system (Gustafson et al. 2010). However, in years of relative abundance, spawning occurs broadly in the tidally influenced portions of the Columbia River and its tributaries (Grette 2014c). Adult migration in the Columbia River system is likely related to river temperature reaching 39.2°F and may begin in December, usually peaking in February and continuing through May (Washington Department of Fish and Wildlife and Oregon Department of Fish and Wildlife 2001). In 2001, Howell et al. (2001) reported on spawning and distribution of larval eulachon, noting that, while spawning occurred widely in the mainstem and in tributaries as far upstream as the Sandy River (RM 120), the majority of the spawning likely occurred in the Cowlitz River and at a location just downstream of Barlow Point (RM 59.6). During the same spawning season, Romano et al. (2002) used artificial substrates to collect eulachon eggs as a way of identifying spawning sites in the main stem (based on the assumption that if eggs are collected spawning must have occurred nearby). They sampled locations between RM 30 and RM 85 near the mouth of the Lewis River. They collected the greatest number of eggs between RM 56 and RM 61 (Germany Creek to Barlow Point), and to a lesser extent RM 67 through RM 69 (mouth of the Cowlitz River to Cottonwood Island). Howell et al. (2001) took samples at several stations at seven fixed transects to assess the distribution of larvae across the river. They showed larvae were distributed nearer the Washington Shore at transects 7 downstream from Sandy River, and at transects 6 (downstream side of Lewis and Clark Bridge) and transect 5 downstream of Barlow Point. This likely reflects larvae moving downstream from spawning areas in the tributaries. Cross-channel distribution at transects farther downstream was more uniform, reflecting cross channel dispersion of larvae spawned in the tributaries and more intense mainstem spawning between Germany Creek and Barlow Point.

WDFW and ODFW conducted plankton tows to sample for eulachon eggs and larvae between the Port of Longview above Barlow Point and the channel below the Cowlitz River mouth including four sample sites offshore in the vicinity of the project area (Malette 2014). Peak larval abundance occurred in mid-March during two of the three survey years and from late April to early May in the third (Malette 2014). As part of a related on-time sampling effort, eulachon eggs/larvae were documented in plankton tows at six sample sites (inshore and offshore) near the proposed Project between RM 62.8 and 64.0 in February 2012 (Report B in Malette 2014).

Adults deposit eggs in areas where the substrate consists of coarse sand/fine gravel (National Marine Fisheries Service 2010). Eggs are spherical and have a double membrane that, upon fertilization, peels back to form an adhesive peduncle (Howell et al. 2001). Eggs adhere to the surface of the substrate and incubate over a period of about 30 to 40 days, depending on temperature. Upon hatching, the larvae become part of the drift as (presumably) passive plankters and are rapidly transported out to sea (Howell et al. 2001). Larval fish, particularly from spawning aggregations in the Cowlitz River, are likely to pass through the study area as they are transported downstream. Eggs attached to large sand grains and pea-sized gravel may be disbursed from the spawning area flows in the Columbia River. The river channel in the study area is dynamic, with sand waves present in the area indicative of bedload movement. Given that incubation can be 30 to 40 days, there could be regular movement of eggs through the SWZ and DWZ of the study area conveyed by moving currents and bedload transport. Eggs could be present from December through April; however, peak of spawning season is usually in February or March. Larval eulachon,

particularly from spawning aggregations in the Cowlitz River, likely pass through the study area as they are transported downriver. Further, it is likely that at least limited spawning occurs in the mainstem Columbia River, as documented on the Oregon side of the Columbia River by Mallette (2014). Mallette (2014) found the greatest numbers of eulachon larvae were found in samples collected well downstream of the Lewis, Kalama, and Cowlitz rivers and upstream of the Elochoman (rivers with known eulachon spawning). While the relatively distant proximity of sampling events to known spawning areas does not discount the possibility that larvae in samples may be the product of spawning in these tributaries, Mallette (2014) concluded that these findings highlight the potential for at least limited spawning in the mainstem Columbia River.

Sturgeon

Both green and white sturgeon may be present in the deepwater component of the study area as adults and subadults. Two green sturgeon DPSs occur in the Lower Columbia River. The northern DPS, currently listed as a federal species of concern, includes spawning populations from the Eel River in California to the Umpqua River in Oregon. The southern DPS, currently listed as threatened under the ESA, includes spawning populations from the Sacramento River basin. While this species does not spawn in the Columbia River or its tributaries, subadult and adult green sturgeon originating from all major spawning populations are known to use the Lower Columbia River and other coastal estuaries in Oregon and Washington for holding habitat in the summer and early fall (Adams et al. 2002, Lindley et al. 2011, Moser and Lindley 2007). Lindley et al. (2008 and 2011) investigated migration patterns of green sturgeon tagged with acoustic transmitters on their spawning grounds and in known nonspawning aggregation sites. They discovered that green sturgeon undertake long season migrations from spawning grounds to overwinter in marine waters off of the coast of Vancouver Island, British Columbia. In the late spring and summer green sturgeon enter and inhabit a number of estuarine and coastal sites, including the Columbia River estuary, Willapa Bay, Grays Harbor, and the estuaries of certain smaller rivers in Oregon, especially the Umpqua River estuary. Moser and Lindley (2007) suggested that growth opportunities for green sturgeon are higher in estuaries because they are warmer than shelf waters and food is abundant. Green sturgeon from different natal rivers use the Columbia River estuary from May through October (peak in July and August). The most prevalent tags reported by Lindley et al. (2011) were from fish tagged in the Klamath and Rogue Rivers, but fish from the Sacramento River (southern DPS) were also present. Based on the size of green sturgeon and the number of tagged fish reported in the estuary, the Columbia River estuary appears to be an important component of foraging habitat for adult and juvenile green sturgeon belonging to the northern and southern DPSs.

Sturgeon are most commonly found in association with the bottom, where they feed on a mixture of aquatic insects and benthic (i.e., bottom-dwelling) invertebrates (Adams et al. 2002, Independent Scientific Review Panel 2013). Fish become a larger component of the diet as sturgeon increase in size. This species is known to spawn in the mainstem Columbia River in fast flowing waters near Bonneville Dam and in deepwater areas of the lower river (Independent Scientific Review Panel 2013, Parsley et al. 1993). Spawning lasts from 38 to 48 days extending from late April through early July during high runoff periods when water is turbid and turbulent. Adults are broadcast spawners, releasing their adhesive eggs over boulder and cobble substrate in areas with strong currents. Incubation lasts 7 to 14 days. Upon hatching the free-swimming embryos are broadly dispersed by currents as far as 100 miles downstream before settling. Post-settlement embryos seek out deep habitats with low light and large cobble or boulder substrates, remaining in cover for 20 to 25 days before they emerge as actively feeding larvae (Independent Scientific Review Panel 2013).

The DWZ near the proposed docks does not provide suitable substrates for white sturgeon spawning or larval rearing so these life stages are unlikely to occur for extended periods in this area.

In contrast, juvenile white sturgeon are found throughout the Lower Columbia River and use a wide variety of habitats, including both main-channel and off-channel areas. They are most commonly found at depths greater than 33 feet (Independent Scientific Review Panel 2013). White sturgeon adults, sub adults, and young of the year are usually found at depths greater than 36 feet (McCabe and Tracy 1994), but habitat use can vary considerably. For example, Parsley et al. (2008) tracked the movement patterns of subadult and adult white sturgeon ranging from 20 to 48 inches in length in the Columbia River estuary and observed complex daily and seasonal patterns of habitat selection. Tagged sturgeon were readily observed in the study area in summer but virtually absent in winter. When present they exhibited diurnal movement patterns, occupying habitats deeper than 33 feet during the day and moving to shallower waters, sometimes less than 15 feet deep, at night. The tagged fish were broadly distributed across available suitable habitat, but individuals demonstrated strong site fidelity, restricting their daytime and nighttime movements to the same general area. The depth preferences of white sturgeon indicate this species is most likely to be found in the DWZ, but individuals may also be present in the SWZ and, infrequently, in the ACM.

The white sturgeon population in the Columbia River downstream from Bonneville Dam has been among the most productive sturgeon populations in North America. Abundance and biomass have been estimated at 36.1 fish/acre and 88 pounds/acre, respectively (DeVore et al. 1995, cited in Independent Scientific Review Panel 2013). Current white sturgeon biomass in the unimpounded lower mainstem appears to be less than levels seen during pristine conditions before significant exploitation in the late 1800s (Jones et al. 2011). Where habitat is relatively homogenous, such as in marine waters, estuaries, low gradient mainstem areas of the lower basin, and reservoirs, white sturgeon move frequently and range widely, presumably in search of scattered or mobile food resources. Many white sturgeon movement and migration patterns appear to be associated with feeding. Primary prey items appear to be the benthic amphipod *Corophium salmonis* and the opossum shrimp *Neomysis mercedis* (Romano and Rien 2001). In the Lower Columbia River below Bonneville Dam, white sturgeon have been observed migrating upstream in the fall and downstream in the spring (Parsley et al. 2008). During early life stages, white sturgeon in the Lower Columbia River use a variety of habitats. Age-0 fish in the Lower Columbia River prefer deep (30–125 feet), low velocity areas where substrate particle sizes are small (e.g., sand; Parsley et al. 1993). Juvenile and sub-adult white sturgeon occupy a wide variety of depths (7–130 feet; Parsley et al. 1993 and 2008). Some juvenile white sturgeon preferentially used low velocity areas over sandy substrates at depths ranging from 7 to 190 feet in the Columbia River (Fisheries and Oceans Canada 2014), while others exhibited diel depth preferences Parsley et al. (2008). Given the abundance and mobility of white sturgeon in the Lower Columbia River, there likely would be some present during construction and operation of the On-Site Alternative.

Lamprey

Lamprey in general are a primitive anadromous fish species that spend their adult lives in the ocean but return to freshwater habitats for spawning and larval rearing. Two species, Pacific and river lamprey, are known to spawn in tributaries to the Columbia River and therefore migrate through the study area as adults and juveniles. Adults pass through the Lower Columbia River from March through October on their return migration to spawning tributaries (Columbia River Research 2014). Lamprey ascend rivers by swimming upstream briefly, then sucking to rocks, resting, and then proceeding.

Pacific lamprey populations may include mature adults that spawn within a few weeks of entering their spawning tributaries and immature adults that hold in freshwater overwinter and spawn between March and July the following spring (Clemens et al. 2013). Spawning takes place in the spring in low-gradient sections of water, with gravel and sandy bottoms, when water temperatures are between 50 and 60°F. Females are very fecund, depositing between 10,000 and 100,000 extremely small eggs. Adults die within 3 to 36 days after spawning (Clemens et al. 2013).

The young (ammocoetes larvae) hatch in 2 to 3 weeks and are dispersed by currents to slack-water areas with soft substrates, where they settle in sediments, which are soft and rich in dead plant materials. They quickly burrow into the muddy bottom where they live for a period of 3 to 8 years as filter feeders consuming microscopic plants (mostly diatoms) and animals. As filter feeders, they are susceptible to pollutants in the water column and sediments, which originate from various sources such as urban and agricultural runoff. Because this species depends on muddy bottoms, backwater areas, and low gradient areas during its juvenile life stage, it is susceptible to loss or modification of wetlands, side channels, back eddies, and beaver ponds resulting from agricultural, forestry, or urban development practices or channelization for flood control. Late in the ammocoetes life stage, unknown factors trigger a metamorphosis, from which lamprey juveniles emerge. During high water periods, in late winter or early spring, the juveniles migrate to the ocean where they mature. During their ocean phase, Pacific lamprey are scavengers, predators, and/or parasites on larger animals such as salmon and marine mammals. They may undertake migrations in the Pacific Ocean, considerable distances from their natal river (Beamish 1980). After 2 to 4 years in the ocean they return to freshwater to spawn.

River lampreys are associated with large river systems such as the Fraser, Columbia, Klamath, Eel, and Sacramento Rivers. They exhibit a similar life history to the Pacific lamprey, including an ammocoete larval stage lasting 4 to 6 years. River lamprey ammocoetes also settle in slack water areas with muddy sediments and filter feed on microscopic organism (Moyle 2002). They differ from Pacific lamprey in that they are smaller in size, a bit less fecund, with females laying between 12,000 and 37,000 eggs, and they are shorter lived. The length of adult life from the onset of metamorphosis until death following spawning is 2 years (Beamish 1980). The difference in longevity stems from their shorter ocean phase. River lamprey spend only 3 to 4 months in salt water, remaining close to the mouths of their natal rivers and foraging on smaller prey, such as herring and smelt (Beamish 1980).

The study area lacks suitable spawning substrates for either species. Therefore, adults are likely to be present only during upstream migration. Silver et al. (2007) and Jolley et al. (2012) investigated the presence and distribution of larval Pacific lamprey in the Willamette and Columbia Rivers. They found ammocoetes of several age classes in the Willamette River and at a few locations in the Columbia River. They observed anecdotally that larvae were more often found along underwater ledges at relatively steep drop-offs to deep water; and that shallow, flat, and sandy areas that appeared to present suitable habitat, were devoid of larvae. They speculate that those apparently suitable areas may have been dry during the summer months preceding the study because of lower regulated flows. They captured Pacific lamprey ammocoetes at two sites in the Columbia River near the mouth of the Cowlitz River. These ammocoetes were likely spawned in tributaries and either transported or migrated to the Columbia River. Their presence in the study area indicates the possibility that some ammocoetes could settle near the On-Site Alternative. The ACM and SWZ near the proposed docks generally lack the slack water environments required for ammocoete rearing, and the sediments in this area are mobile and lacking in the organic matter associated with suitable ammocoetes rearing habitat. The distribution of ammocoetes reported by Silver et al. (2007)

indicates that ammocoetes may be transported through the area or migrate through the study area to suitable habitat downstream. Juvenile and adult lamprey may be present in the SWZ and DWZ during their respective migration periods (Table 2).

Nonfocus Fish

The nonfocus fish (Table 3) are a mix of fish of interest because they are important food fish (harvested commercially and recreationally), game fish (harvested recreationally only), or on Washington's PHS list. Two of the species, mountain whitefish (*Prosopium williamsoni*) and leopard dace (*Rhinichthys falcatus*), are on Washington's PHS list as state candidate species. Both species are widely distributed in the Columbia and Frasier River basins. The other species in this group are important as commercial or recreational species. Most are abundant and widely distributed in the system, including several introduced species. Some are known predators of juvenile salmonid, such as largemouth bass, northern pikeminnow, smallmouth bass, striped bass, and walleye.

Table 3. Nonfocus Fish Species that May Occur in the Study Area

Species	Reason for Interest	Native or Introduced
Channel catfish (<i>Ictalurus punctatus</i>)	WDFW game fish	I
Common carp (<i>Cyprinus carpio</i>)	WDFW food fish	I
Largemouth bass (<i>Micropterus salmoides</i>)	WDFW game fish	I
Leopard dace (<i>Rhinichthys falcatus</i>)	WDFW PHS	N
Mountain sucker (<i>Catostomus platyrhynchus</i>)	WDFW PHS, WDFW game fish	N
Mountain whitefish (<i>Prosopium williamsoni</i>)	WDFW game fish	N
Northern pikeminnow (<i>Ptychocheilus oregonensis</i>)	WDFW game fish	N
Peamouth (<i>Mylocheilus caurinus</i>)	WDFW game fish	N
Perch (family Percidae)	WDFW game fish	I
Shad (subfamily Alosinae)	WDFW food fish	I
Smallmouth bass (<i>Micropterus dolomieu</i>)	WDFW game fish	I
Suckers (family Catostomidae)	WDFW game fish	N
Sunfish (family Centrarchidae)	WDFW game fish	I
Striped bass (<i>Morone saxatilis</i>)	WDFW game fish	I
Walleye (<i>Sander vitreus</i>)	WDFW game fish	I

Notes:

Source: Grette 2014c.

WDFW = Washington Department of Fish and Wildlife; PHS = Priority Habitats and Species

2.2.1.6 Commercial and Recreational Fishing

Commercial and recreational fisheries in the lower Columbia River are managed by the states of Washington and Oregon and tribes, subject to the terms of the 2008-2017 *United States v. Oregon* Management Agreement (Management Agreement). The Management Agreement establishes tribal harvest allocations and upholds the right of tribes to fish for salmon in their usual and accustomed fishing grounds. Commercial fisheries in these waters are managed under the Columbia River Compact, a congressionally mandated process that adopts seasons and rules for Columbia River commercial fisheries (National Marine Fisheries Service 2015).

In Washington, commercial fishing seasons and rules are established by the Columbia River Compact, which comprises the Washington and Oregon Departments of Fish and Wildlife Directors, or their delegates, acting on behalf of the Oregon and Washington Fish and Wildlife Commission. The Columbia River Compact is charged by congressional and statutory authority to adopt seasons and rules for Columbia River commercial fishers. When addressing commercial seasons for salmon, steelhead and sturgeon, the Columbia River Compact must consider the effect of the commercial fishery on escapement, treaty rights, and sport fisheries, as well as the impact on species listed under the federal ESA. Although the Columbia River Compact has no authority to adopt sport fishing seasons or rules, it is their inherent responsibility to address the allocation of limited resources among users (National Marine Fisheries Service 2015).

In Washington State, recreational fishing seasons and rules are updated annually and presented in the Washington Sport Fishing Rules pamphlet. Sport fishing seasons are generally established from July 1 through June 30 of the following year. The pamphlet covers all fresh waters and marine waters in Washington State, including the lower Columbia River. It establishes the seasons and rules for recreational fishing for finfish and shellfish/seaweed.

Commercial and recreational fishers primarily target hatchery-produced salmon and steelhead, as well as sturgeon and other game fish.

2.2.1.7 Sediment and Water Quality Conditions

Sediment conditions in the study area are generally uniform with slight variations between aquatic habitat types. ACM sediments are primarily sand mixed with silt, SWZ sediments are primarily sand, and DWZ sediments are primarily silt mixed with sand (Grette 2014c). Sediments within the dredge prism meet sediment disposal guidelines and are considered clean by the U.S. Army Corps of Engineers (Corps), EPA, and Ecology (U.S. Army Corps of Engineers Dredged Material Management Office 2010 in Grette 2014c). Recent sediment characterization indicates less than 0.2% organic matter in deep areas and typically less than 0.3% in shallow areas. Eulachon eggs usually settle into coarse sands and gravels in relatively deep water, while the shallow and DWZs are largely made up of silty river sand and therefore not considered high quality habitat for eulachon eggs.

The Lower Columbia River is listed as a Washington State 303(d) impaired water and is classified by Ecology as a Category 5 polluted water for dissolved oxygen, Dieldrin, PCB, and 2,3,7,8 TCDD, and 4,4,4 DDE (Grette 2014c). The nearest measured water quality impairment (for dioxin and bacteria) occurs approximately 2.5 miles upstream of the project area (Washington State Department of Ecology 2014). Turbidity in the study area is variable based on a number of factors. For example, over five days of water quality monitoring for dredging, background levels (upstream of active dredging) ranged from the mid-20s to the mid-60s nephelometric turbidity units (NTUs) at all depths (U.S. Army Corps of Engineers Dredged Material Management Office 2010 in Grette 2014c). Water temperature in the study area ranges from low 40s to low 70s (°F), and while this is slightly warmer than historic values (Bottom et al. 2008), the area is not listed as a Washington State 303(d) impaired water for temperature. Salmonids typically move from habitat areas as temperatures approach 66°F, and the study area habitat within the ACM and upper SWZ likely reaches this threshold and may become unsuitable for juveniles salmonids in the summer months. Refer to the NEPA Water Quality Technical Report (ICF International 2016c) for further information regarding water quality conditions near the project area.

2.2.1.8 Fish Predators

Several bird, mammal, and fish species present in the Columbia River estuary are known to prey on one or more of the focus fish species. For example, cormorants and Caspian terns are significant avian predators that are known to target juvenile salmonids and eulachon. Osprey and bald eagles are also known fish predators, capable of taking both juvenile and smaller adult salmonids. Steller and California sea lions are primary predators on adult fish, including salmon, steelhead, and sturgeon in the Lower Columbia River (National Marine Fisheries Service 2013). However, the study area does not currently or historically support sea lion congregations, and it is unknown whether terns congregate in these areas (Jefferies et al. 2000). Native and nonnative fish species, including northern pikeminnow, smallmouth bass, and walleye, are known to be significant predators on juvenile fish and are capable of exploiting habitats present in the study area. Specifically, pikeminnow and smallmouth bass are known to associate with shoreline and channel modifications like riprap armoring, revetments, and pile dikes, which provide suitable holding habitat for lie-in-wait predation (Pribyl et al. 2004). In contrast, walleye use deeper, open water habitats but they are also known to associate with artificial and natural structures when they are present (Pribyl et al. 2004). The existing dock, pile dikes, and other shoreline and channel modifications are likely to provide suitable habitat for these predatory fish species.

2.2.1.9 Fish Stranding

A growing body of evidence indicates that juvenile salmon and other fish are at risk of stranding on wide, gently sloping beaches because of wakes generated by deep draft vessel passage (Bauersfeld 1977; Hinton and Emmett 1994; Pearson et al. 2006; ENTRIX 2008). Depending on the slope and breadth of a beach, wakes from passing vessels can travel a considerable distance, carrying fish and depositing them on the beach where they are susceptible to stress, suffocation, and predation.

Pearson et al. (2006) published the most detailed study of Columbia River fish stranding completed to date. They evaluated stranding at three sites in the Lower Columbia River: Sauvie Island, Barlow Point (adjacent to the project area), and County Line Park. The sites were chosen because prior work had established them as sites with high risk of stranding (Bauersfeld 1977). Pearson et al. (2006) observed 126 vessel passages, 46 of which caused stranding. From the study, certain sites appear to be more susceptible to stranding than others. For example, the highest occurrence of stranding was at Barlow Point, where 53% of the observed passages resulted in stranding. Stranding occurred less frequently at Sauvie Island (37% of the observed passages resulted in stranding) and County Line Park (15% of observed passages resulted in stranding) (Person et al. 2006). The proposed terminal would add 840 vessel calls, or round-trips to and from the proposed terminal, or 1,680 one-way transits to Columbia River vessel traffic annually at full capacity, which would introduce additional permanent risk of fish stranding in the Columbia River. Many factors affect the risk of fish stranding in the lower Columbia River, including but not limited to vessel size, draft and speed, and beach slope and permeability.

2.2.2 Off-Site Alternative

The affected environment relative to the Off-Site Alternative is similar to the On-Site Alternative based on the proximity of the two sites. The discussion below highlights differences that exist at the Off-Site Alternative.

2.2.2.1 Aquatic Habitat Types

The aquatic portion of the Off-Site Alternative is a functioning, although somewhat modified, habitat complex (riparian, ACM, SWZ, and DWZ) (Figure 10) with varying water-level regimes on daily (tidal) and seasonal (discharge) scales. Modifications (e.g., diking, shoreline armoring) and simplifications (e.g., lack of vegetation) limit habitat development, but functional habitat is present within the ACM and SWZ portions of the study area (Grette 2014b).

Riparian

Shoreline armoring and the CDID dike have contributed to what is typically low-complexity and artificially steepened upper shoreline and no floodplain connectivity in the upstream two-thirds of the Off-Site Alternative. Additionally, landward of the shoreline, dike maintenance has removed and continues to prevent the establishment of riparian habitat (Grette 2014b).

However, the Off-Site Alternative includes relatively intact riparian habitat below the toe of the dike. Approximately the middle one-third of the property contains a band of riparian/wetland habitat, varying from approximately 20 to 140 feet in width, and the downstream one-third contains wide, dense (approximately 250 feet) riparian/wetland habitat. Thus, relative to the dike portion of the Lower Columbia River, much of the Off-Site Alternative contributes moderate to high levels of biological material (e.g., leaf litter, woody material, insects) to the aquatic areas, as well as shade and other physical function (Grette 2014b).

Active Channel Margin

The middle and lower portions of the ACM consist largely of unvegetated, silty sands that provide shallow (e.g., 2 to 6 feet deep) water habitat during high and low water-level seasons. Specifically, the flats in the ACM provide shallow water foraging and refuge opportunities for small salmonids during the early part of the outmigration period (high water levels). This shallow, flat ACM habitat occurs almost exclusively in the downstream portion of the study area, and primarily in the ACM. During low water periods when the ACM is dewatered or very shallow, similar flat habitat in the upper SWZ that provides similar function is scarce because the SWZ is much more steeply sloped (Grette 2014b).

Shallow Water Zone

The HEA model considers shallow-water areas to provide inherently higher biological function than DWZ habitat. In areas with poor quality riparian habitat (e.g., the upstream one-third of the Off-Site Alternative), the overall habitat function of the ACM—and to a lesser extent the SWZ—at the Off-Site Alternative is expected to be relatively less than similar areas with intact riparian habitat (Grette 2014b).

Figure 10. Aquatic Habitat Types Potentially Affected by the Off-Site Alternative

Deepwater Zone

Because depth reduces light penetration, the HEA model considers the quality of benthic habitat in DWZ areas to rank at least ten times lower than that of ACM or SWZ habitats. Though no studies have been conducted at the Off-Site Alternative, it was found at the On-Site Alternative that the quality of DWZ habitat is further reduced due to the highly dynamic nature of currents acting upon it (Grette Associates 2014c). Based on the similar settings and proximity of the sites, this conclusion likely applies to the Off-Site Alternative as well. Areas with dynamic bedload typically express reduced biological productivity due to limited sediment stability and the insufficient buildup of detritus and fine material (McCabe et al. 1997). In addition, the potential for benthic invertebrates to colonize areas exposed to strong currents is challenged by the risk of burial due to accretion and the risk of scouring due to erosion. Therefore, in the context of the HEA model, the quality of DWZ portions of the Off-Site Alternative would rank low in comparison to both SWZ areas and areas of the DWZ that are not exposed to strong downstream flow.

2.2.2.2 Columbia River

The affected environment in the Columbia River at the Off-Site Alternative is the same or similar to that of the On-Site Alternative as described in Section 2.2.1.4, *Columbia River Downstream of Project Area*.

2.2.2.3 Focus Fish Species

The affected environment relative to the focus fish species at the Off-Site Alternative is the same or similar to that of the On-Site Alternative as described in Section 2.2.1.5, *Focus Fish Species*.

2.2.2.4 Commercial and Recreational Fishing

The affected environment relative to the commercial and recreational fishing at the Off-Site Alternative is the same or similar to that of the On-Site Alternative as described in Section 2.2.1.6, *Commercial and Recreational Fishing*.

2.2.2.5 Sediment and Water Quality Conditions

The affected environment relative to sediment and water quality at the Off-Site Alternative is the same or similar to that of the On-Site Alternative as described in Section 2.2.1.7, *Sediment and Water Quality Conditions*.

2.2.2.6 Fish Predators

The affected environment relative to fish predators at the Off-Site Alternative is the same or similar to that of the On-Site Alternative as described in Section 2.2.1.8, *Fish Predators*.

2.2.2.7 Fish Stranding

The affected environment relative to fish stranding associated with the Off-Site Alternative is the same or similar to that of the On-Site Alternative as described in Section 2.2.1.9, *Fish Stranding*.

This chapter describes the impacts on fish and fish habitat that would result from construction and operation of the proposed export terminal.

3.1 On-Site Alternative

Potential impacts on fish from the proposed terminal at the On-Site Alternative location are described below.

3.1.1 Construction: Direct Impacts

Construction of the On-Site Alternative would occur on currently developed and disturbed lands and within the Columbia River. Potential construction impacts on fish and fish habitat would include permanent removal or temporary alteration of habitat, elevated underwater noise associated with pile driving, temporary overwater shading, and spills and leaks of hazardous material.

Aquatic Habitat

Construction would result in the alteration and removal of aquatic habitat in the Columbia River adjacent to the On-Site Alternative. Riparian vegetation at the project area is sparse and riparian habitat conditions are degraded. Project construction would not result in measurable impacts to riparian vegetation or habitat conditions at the project area.

Habitat in the Columbia River would be permanently altered and removed by the placement of piles. A total of 603 of the 622 36-inch-diameter steel piles required for the trestle and docks would be placed below the OHW mark, permanently removing an area equivalent to 0.10 acre (4,263 square feet) of benthic habitat. The majority of this habitat is located in DWZ (Grette 2014a). The placement of piles would displace benthic habitat, and the areas within each pile footprint would cease to contribute toward primary or secondary productivity. Individual pile footprints are relatively small (7.07 square feet) and are spaced throughout the dock and trestle footprint. Benthic, epibenthic (i.e. living at the water-substrate interface), or infaunal (i.e., beneath the surface of the river floor) organisms within the pile footprint at the time of pile driving would likely perish.

Creosote-treated piles would be removed from the deepest portions of two existing timber pile dikes. In total, approximately 225 lineal feet of the dikes would be removed. Overall, the removal of creosote-treated woodpiles from the Columbia River would be a beneficial impact, as any remaining creosote in those piles would be removed from the aquatic environment. However, removal of the piles could result in temporary increases in suspended sediments, short-term contamination of water, and long-term contamination of sediments from creosote released during extraction. Creosote contains a mixture 200 to 250 compounds, with primary components composed of polycyclic aromatic hydrocarbons (PAHs) (Brooks 1995), which are known to be toxic to aquatic organisms including invertebrates and fish and can cause sublethal and lethal effects (Eisler 1987, Brooks 1995).

Creosote and associated chemicals are known to bioconcentrate in many aquatic invertebrates (Eisler 1987, Brooks 1995). This could expose higher trophic level species such as fish to creosote/PAH compounds through the food chain. Many vertebrates, including fish, however, metabolize PAHs and excrete them, reducing the potential risk to higher trophic level species (National Marine Fisheries Service 2009).

Most of the components of creosote are heavier than water and sink in the water column. PAHs from creosote accumulate in sediments and are likely to persist at the site of pile removal or wherever they settle after suspension until they degrade (National Marine Fisheries Service 2009). However, PAHs from sediment are less bioavailable to aquatic species and thus these organisms are not likely to bioaccumulate PAHs from sediments (Brooks 1995).

Over the long term, the source of creosote would be removed or capped by the sediment falling into the hole left by the extracted pile. Water quality would improve over time; the concentration of creosote in the sediment would be expected to decrease, and the potential pathway of exposure for wildlife through contamination of prey would be reduced.

The in-water work windows would be defined by the permits that may be issued for the construction of the project. The in-water work windows presented here are consistent with WAC 220-110-206, which was repealed effective July 1, 2015 by Washington State Rule 15-02-029. No new in-water work windows have been defined and the project specific in-water work periods would be defined during permitting. Dredging is proposed between August 1 and December 31, per the recently repealed WAC 220-110-206) and would permanently alter a 48-acre area of benthic habitat in the DWZ (below -20 feet CRD) by removing approximately 500,000 cubic yards of benthic sediment to achieve a depth of -43 feet CRD, with a 2-foot overdredge allowance. Within the proposed dredge prism (i.e., extent of the area to be dredged), the amount of deepening would vary based on existing depths, from no removal up to approximately 16 feet of removal. The majority of the area of the proposed dredge prism is at or below a depth of -31 feet CRD. Hydrodynamic modeling and sediment transport analysis performed by WorleyParson (2012) evaluated the potential effects that could result from dredging, sediment deposition and maintenance dredging. Overall, WorleyParsons (2012) found that the accretion rate would be approximately 12,000 cubic yards per year within the dredge prism; however, accretion rates could fluctuate significantly year-over-year based on flow conditions. Maintenance dredging would likely only be required on a multi-year basis, or following special extreme flow events (WorleyParsons 2012). The preferred method for disposing of dredge material is flow-lane disposal so those sediments are not removed from the river, but remain in the river and are transported and deposited in areas where they can provide habitat for benthic species and benthic dependent species. Thus dredged materials are expected to be disposed of within the flow lane, adjacent to the navigation channel, allowing these sediments to support the downstream sediment transport system (Grette 2014a, 2014d). This area would be located within an area of approximately 80 to 110 acres between approximately RM 60 and RM 66. However, it could be that some or all of the dredged materials could be used for pre-loading of the stockpile pads and then disposed of at an appropriate off-site upland facility. Specific disposal methods for dredged materials would be determined during permitting and federal ESA Section 7 consultation.

The majority of benthic, epibenthic, and infaunal organisms are nonmotile or slow-moving and become entrained during dredging. Benthic, epibenthic, and infaunal organisms within the proposed dredge prism above -43 feet CRD would be removed during dredging, resulting in

likely mortality. These organisms often serve as prey for larger animal species. Most of the habitat within the proposed dredge prism is in deep water where benthic productivity is expected to be low relative to shallower habitat. Deepwater channels are subjected to higher water velocities that periodically scour bottom sediments, limiting the standing crop of invertebrates and the buildup of detritus and fine materials that support these invertebrates (McCabe et al. 1997). Dredging activities are not typically associated with long-term reductions in the availability of prey resources, and impacts on benthic productivity are expected to be temporary. Disturbed habitats are expected to return to reference conditions with rapid recolonization by benthic organisms (McCabe et al. 1996). Benthic organisms typically recolonize disturbed environments within 30 to 45 days.

Much of the scientific literature evaluating the effects of turbidity on fish is discussed in relation to turbidity concentrations associated with dredging. The dredging that would occur for the On-Site Alternative would remove approximately 500,000 cubic yards of sediments, and temporary increases in turbidity associated with other related activities (e.g., pile driving and pile dike removal) would generally be lower than those associated with larger dredging activities (i.e., dredging of the navigation channel). Several studies indicate that suspended sediment concentrations occurring near dredging activity do not cause gill damage in salmonids. Servizi and Martens (1992) found that gill damage was absent in under yearling coho salmon exposed to concentrations of suspended sediments lower than 3,143 milligrams per liter (mg/L). A negligible risk of gill tissue damage is also expected for adult and subadult salmonids exposed to turbidity generated by dredging activities because salmonids in these life stages are generally more tolerant of elevated suspended sediment levels (Stober et al. 1981) and are generally able to avoid localized areas of elevated turbidity associated with construction activities.

Suspended sediments have been shown to cause stress in salmonids but at concentrations higher than those typically measured during dredging. Subyearling coho salmon exposed to suspended sediment concentrations above 2,000 mg/L were physiologically stressed as indicated by elevated blood plasma cortisol levels (Redding et al. 1987). Although turbidity may cause stress to salmonid species, studies by Redding et al. (1987) found that relatively high suspended sediment loads (2,000–2,500 mg/L) did not appear to be severely stressful to yearling salmon.

As stated previously, the Applicant has proposed to do the in-water work between August 1 and February 28. The Applicant has proposed to do impact pile driving between September 1 and December 31; dredging, including flow lane disposal of dredged material, would be performed between August 1 and December 31. While the specific times dredging activities would be allowed by the permitting agencies has not been determined and would not be defined until permits would be issued for the project, the Applicant proposed timing for performing the dredging activities would avoid and minimize impacts to spawning adult, egg, and larval eulachon. Adult eulachon typically enter the Columbia River and tributaries (i.e., Cowlitz, Kalama, Lewis, Sandy, Elochoman), in December and January. Peak spawning migration occurs in February and March. Peak larval abundance occurred in mid-March during two of three survey years and in late April/early May in the third (Mallette 2014). Eggs could be present from December through April, however. Dredging activities that occur between August 1 and December 31 would minimize potential impacts to adult eulachon that may spawn within 300 feet of the dredge prism. Limiting dredging activities to August 1 and November 30 would further reduce the potential to impact eulachon spawning or migrating adults.

Dredging and dock construction associated with the proposed terminal could impact habitat that may be suitable for eulachon spawning. Spawning substrates include sand, coarse gravel, and detrital substrates. Sand substrate occurs within the dredge prism, and is assumed to provide suitable habitat for eulachon spawning. Project-related dredging would impact approximately 48-acres for the On-Site Alternative. Trestle and Dock construction would install 603 piles below OHW, affecting an additional 0.10 acre (4,263 square feet). The dock, with two Panamax size vessels being loaded simultaneously, would shade approximately 9.83 acres (refer to Section 3.1.3, *Operations: Direct Impacts*). The direct impact study area for the On-Site Alternative is approximately 1,549 acres (Figure 5.7-1). Thus, project-related dredging would modify approximately 3% of the direct impact study area, while dock construction would permanently affect approximately 0.6% of the direct impact study area. The extent of this area that may be used by eulachon for spawning is unknown.

During eulachon spawning eggs are deposited through broadcast spawning and attach to the substrate. After approximately 1 month of incubating the eggs hatch into larvae that drift passively downstream to salt water. It is likely that much of the dredge prism area is used for egg incubation and larval transport/rearing, either from spawning within the dredge prism area or egg drift from areas upstream within the Columbia River, or the Cowlitz River, located approximately 5 miles upstream of the project area.

Eulachon are assumed to occur in the Columbia River adjacent to the project area from December through May. Any project-related work that would occur between December and May could directly impact eulachon. Potential mitigation measures identified in the Draft EIS would reduce the potential impact by confirming the presence/absence of eulachon, and, if present, coordinating with the fish and wildlife agencies (i.e., NMFS and WDFW) on the appropriate course of action to avoid and minimize potential impacts to eulachon. Although it is difficult to determine exactly how much of a temporary increase in turbidity would result from the covered activities, increases in suspended sediments are expected to be relatively short term, occurring during in-water construction activities and maintenance dredging. Thus in-water construction and maintenance activities would not result in chronic sediment delivery to adjacent waters, because sediments would be disturbed only during in-water work. Construction related dredging is proposed to occur from August 1 through December 31, when many fish species would be present within the study area (Table 2). It is assumed that dredging would occur between 7:00 a.m. and 10:00 p.m., Monday through Friday, per the Cowlitz County Code Chapter 10.25, which restricts construction noise to these hours, unless the activity is authorized by a valid conditional use permit, a SEPA determination, or a permit approval condition.

Those fish that are present in the construction area when the effects are manifest are likely to avoid the area until the effects dissipate. Carlson et al (2001) observed out-migrating salmon smolts moving in-shore when encountering either a dredge or discharge plume before resuming their prior distribution a short distance downstream. An evaluation of dredge disposal in the lower Columbia River found that white sturgeon may slightly shift habitat use toward disposal areas during disposal, possibly in response to prey items associated with dredged materials (Parsley et al. 2011). Hence, short-term, localized increases in turbidity associated with the On-Site Alternative dredging and dredge disposal activities would not likely result in significant physiological impacts on fish, their habitat, or their prey.

Behavioral effects related to increased turbidity are another consideration. Some of the documented behavioral effects of turbidity on fish include avoidance, disorientation, decreased

reaction time, increased or decreased predation and increased or decreased feeding activity. However, many fish species (especially estuarine species) have been documented to prefer higher levels of turbidity for cover from predators and for feeding strategies. For example, increased foraging rates for juvenile Chinook salmon were attributable to increase in cover provided by increased turbidity, while juvenile steelhead and coho salmon had reduced feeding activity and prey capture rates at relatively low turbidity levels. Juvenile Chinook salmon were also found to have reduced predator-avoidance recovery time after exposure to turbid water. (ECORP Consulting, Inc. 2009). Thus, while there may be some beneficial behavioral effects from increased turbidity, it is expected that for many of the focus fish species and native non-focus fish species behavior effects from increased turbidity would generally be negative.

The On-Site Alternative would permanently affect approximately 48 acres of benthic habitat due to dredging activities (i.e., removal of benthic habitat and benthic organisms) and construction of the docks (i.e., construction of new in-water structure and related shading of the aquatic environment). Water quality could be affected as a result of coal dust. These potential impacts are discussed below. Other elements of these two PCEs, such as water quantity, natural cover, and salinity would not be impacted by the project.

Response to Underwater Noise during Pile Driving

The following analysis is a summary of the Grette (2014a) evaluation of the potential impacts on fish from underwater noise generated during pile-driving activities. The Grette (2014a) analysis was reviewed and evaluated by ICF, and the approach taken for the analysis is consistent with the current approach for evaluating the effects of underwater noise on fish, specifically underwater noise generated by pile-driving activities.

Docks 2 and 3 and their associated trestle would be supported by 622 36-inch steel piles, 603 of which would be installed in aquatic areas below OHW. The Dock 2 and 3 structures would be located completely within DWZ habitat (below -20 feet CRD) and would comprise the majority of the pile to be installed. Each pile would be installed using a vibratory driver until it meets practical resistance, at which point an impact pile driver would be used to proof the pile and complete installation to the necessary weight-bearing capacity.

Most piles would be driven to a depth of 140 to 165 feet below the mudline to provide the necessary resistance to support the overwater structures (i.e., Docks 2 and 3, the ship loaders, and conveyors) (Grette 2014a). The duration of vibratory and impact pile driving required to install each pile would be dependent upon the depth at which higher density materials (e.g., volcanic ash or dense sand and gravels) are encountered; shallower resistance would require less vibratory and more impact driving, while deeper resistance would require more vibratory and less impact driving.

Sound generated by impact pile driving has the potential to affect fish in several ways, ranging from alteration of behavior to physical injury or mortality, depending on the intensity and characteristics of the sound, the distance and location of the fish in the water column relative to the sound source, the size and mass of the fish, and the fish's anatomical characteristics (Hastings and Popper 2005). Refer to the NEPA Noise and Vibration Technical Report (ICF International and Wilson Ihrig Associates 2016) for further information regarding noise and vibration.

Both peak sound pressure level (SPL) and sound exposure level (SEL) can affect fish hearing through auditory tissue damage or temporary shifts in sensitivity to sounds (referred to as a temporary threshold shift [TTS]). Exposure to very loud noise or loud noise for extended periods may result in permanent reductions in sensitivity or permanent threshold shifts (PTS). Generally TTS would occur at lower levels than those resulting in auditory tissue damage, which result in PTS. The effects of hearing loss in fish may relate to the fish's reduced fitness, which may increase the vulnerability to predators and/or result in a reduced ability to locate prey, inability to communicate, or inability to sense their physical environment (Hastings and Popper 2005). Popper et al. (2005) found fish experiencing TTS were able to recover from varying levels of TTS, including substantial TTS, in less than 18 hours post exposure. Meyers and Corwin (2008) reported evidence that fish can replace or repair sensory hair cells that have been damaged in both the inner ear and lateral line, indicating that fish may be able to recover from PTS over a period of days to weeks.

In June 2008, NMFS, USFWS, the U.S. Federal Highway Administration, and several state transportation agencies agreed to interim criteria intended to protect fish from underwater noise generated by pile driving during bridge construction and retrofitting (Fisheries Hydroacoustic Working Group 2008). In general, the interim criteria establish thresholds for injury and behavioral effects from pile-driving generated underwater noise. There are three criteria for injury related to underwater noise: the first is based on peak pressure levels of 206 dB_{PEAK}⁷ for impulse-type noise (e.g., pile driving), and the other two are based on accumulated sound exposure levels (i.e., sound energy integrated over time), the first of which is 187 dB cumulative SEL⁸ for fish greater than or equal to 2 grams (e.g., most juvenile salmon and trout), and the other is 183 dB cumulative SEL for fish less than 2 grams (e.g., larval lamprey). Underwater noise levels of 150 dB_{RMS} may cause behavioral effects in fish species, such as startle response, disruption of feeding, or avoidance of an area. Depending on site-specific conditions, construction timing, duration, and other factors, exposure to these levels may cause behavioral changes that result in potential injury (Washington State Department of Transportation 2015). Potential adverse behavioral affects include interruption of foraging activities, avoidance of feeding or spawning areas, or movement away from cover, impaired predator avoidance (Washington State Department of Transportation 2015).

This analysis assumes that in-water pile driving would occur over two proposed construction seasons. In order to accomplish impact pile driving during limited work windows, multiple pile-driving rigs are expected to be in use simultaneously on the same day. The simultaneous use of multiple rigs may reduce the total duration of pile driving sound as some overlap in active driving may occur.

Considering the large number of piles to be driven, and the potential for multiple rigs to operate simultaneously, this analysis assumes that vibratory and/or impact pile driving may occur continuously during each working day of the Applicant-proposed in-water construction window (September 1 through December 31). Local Ordinance (Cowlitz County Code: Chapter 10.25) restricts construction noise to the hours of 7 a.m. to 10 p.m. unless the activity is authorized by a valid conditional use permit, a SEPA determination, or a permit approval condition. Various

⁷ dB_{PEAK} is the instantaneous maximum overpressure or underpressure observed during each pulse. When evaluating potential injury impacts to fish, peak sound pressure (dB_{PEAK}) is often used.

⁸ dB cumulative SEL is a metric for acoustic events and is often used as an indication of the energy does. SEL is calculated by summing the cumulative pressure squared (p^2), integrating over time, and normalizing to 1 second.

underwater reference noise values were reviewed, in order to select the appropriate noise values that would likely be generated by pile-driving activities. Of the various reference pile data available (ICF Jones & Stokes and Illingworth and Rodkin 2009, Washington State Department of Transportation 2015), sound levels from the Columbia River Crossing (CRC) 48-inch diameter steel test piling (David Evans Associates 2011) were selected as reference levels for the 36-inch-diameter steel piling proposed for the analysis. Although the pilings were larger for the CRC project, the proximity of the two sites and the similar conditions (i.e., depth, currents, and substrates) are expected to be more comparable than more distant locations such as Puget Sound or areas of California, where other reference data has been obtained for 36-inch-diameter steel piling (Grette 2014a).

Substrate characteristics between the CRC site and the project area are relatively similar, and pile driving conditions and underwater noise levels generated are anticipated to be similar. The greatest per-pile levels for each type of sound (i.e., single strike at 217 dB_{PEAK}, 201 dB_{RMS}, and 185 dB_{SEL}) were selected. These values are generally greater than reference values recorded for 36-inch-diameter piling at various other locations, and thus represent the potential worst-case for noise levels generated during pile driving (Grette 2014a).

Further, the hydroacoustic monitoring conducted for the CRC test pile also tested the efficacy of both confined and unconfined bubble curtains for attenuation of underwater noise from pile driving (David Evans Associates 2011). For 48-inch-diameter steel piling, both confined and unconfined bubble curtains consistently attenuated sound levels by 10 dB or more, measured at a distance of 33 feet from the source. At another Washington State Department of Transportation project completed downstream at Puget Island, the confined bubble curtain attenuated sound levels by 13 dB (measured at 43 feet) after on-site modifications (Washington State Department of Transportation 2010). Thus, the assumption that sound values would be attenuated by 9 dB during use of a confined bubble curtain in this analysis is considered realistic, achievable, and likely conservative (Grette 2014a).

Both the NMFS and the USFWS are concerned with potential impacts of elevated underwater noise levels during pile driving on federally protected fish species, such as salmonids, green sturgeon, and eulachon. NMFS and the USFWS have developed standard thresholds for disturbance/behavioral changes and injury (Table 4). Sound at or above these thresholds is evaluated on a site- and project-specific basis to determine whether potential impacts could occur, and whether any impacts on individuals resulting from underwater noise generated by pile driving could occur. Injury threshold values typically result from impact pile driving, as opposed to vibratory pile driving because sound- or pressure-related injuries, such as barotraumas, are thought to result from the rapid rise times and fluxes in over- versus under-pressure during a pile strike (Grette 2014a).

It is standard practice to use the Practical Spreading Loss model to evaluate the potential effects of pile driving and determine the distance at which sound associated with pile driving would attenuate to specific levels (i.e., effect thresholds), except where cumulative sound is being considered.

Table 4. Underwater Sound-Level Thresholds for Endangered Species Act-Listed Fish

Species	Effect Type	Threshold
All Listed Fish ^a	Injury, cumulative sound (fish ≥ 2 grams): onset of TTS (auditory response), with onset of auditory tissue damage and nonauditory tissue damage with increasing cumulative sound	187dB _{SELcum}
	Injury, cumulative sound (fish < 2 grams): similar to above, onset of nonauditory tissue damage occurs at lower sound levels with smaller fish	183dB _{SELcum}
	Injury, single strike: onset of TTS and auditory tissue damage from single strike	206dB _{PEAK}
	Behavioral Disruption	150dB _{RMS}

Notes:

^a Injury thresholds are based on interim criteria that were developed for salmonids based on data specific to hearing generalists with swim bladders (Carlson et al. 2007). NMFS also applied these thresholds to other listed fish with swim bladders (e.g., green sturgeon) and sometimes conservatively to fish without swim bladders (e.g., eulachon). Injury descriptions are based on information summarized in Carlson et al. (2007).

TTS = temporary threshold shift; dB = decibel; SEL = sound exposure level; cum = cumulative; RMS = root mean square.

Source: Grette 2014a.

The Practical Spreading Loss model is defined as:

$$TL = 15 * \log (R_1/R_2)$$

where:

TL = Transmission Loss, the difference between SPLs in dBs at distances R_1 and R_2 ; also $SPL_2 - SPL_1$

R_1 = distance at which transmission loss is estimated

R_2 = distance from source at which sound is known or measured (typically 10m)

In order to solve for R_1 , the distance required for SPLs to attenuate to a desired level (e.g., threshold or ambient condition) based on reference SPLs at a known distance (R_2 , typically at 10m), the terms are rearranged as follows:

$$R_1 = R_2 * 10^{(TL/15)}$$

In this case, the Practical Spreading Loss model was used to solve for R_1 in order to calculate distance to injury (single strike, 206 dB_{PEAK}) and distance to disturbance (150 dB_{RMS}) for federally protected fish during impact pile driving (Grette 2014a).

In addition to thresholds for single pile strikes, NMFS has established injury thresholds for fish based on cumulative sound exposure to account for the potential effects of impact pile driving over the course of a workday. Cumulative sound exposure is calculated using the NMFS Stationary Fish model (available at <http://www.wsdot.wa.gov/Environmental/Biology/BA/BAGuidance.htm#noise>) (Grette 2014a).

The Stationary Fish model requires the number of pile strikes over an entire work day to determine the potential cumulative injury for fish based on dB_{SEL}. However, NMFS incorporated the concept of “effective quiet” into the model, which assumes that sound cannot accumulate and contribute toward cumulative injury below 150 dB_{SEL}. Because of this, one can calculate the

maximum distance possible for cumulative injury independent of pile strikes. This can be accomplished either using the Practical Spreading Loss model to determine the distance required to attenuate sound at the source to 150 dB_{SEL}, or by iteratively increasing the pile strikes in the Stationary Fish model until it returns a consistent (rather than increasing) distance value because it is basing the calculation on effective quiet (Grette 2014a).

Rather than predicting daily pile strikes (which are anticipated to be highly variable), the Stationary Fish model was used to determine the distance to cumulative injury based on effective quiet. The maximum distance of potential cumulative effects occurred at approximately 5,000 strikes for fish greater than or equal to 2 grams (threshold 187dB_{SELcum}) and at approximately 2,000 strikes for fish less than 2 grams (threshold 183 dB_{SELcum}). This represents a distance of 1,775 feet for both size classes (Grette 2014a).

The model predicts that impacts on fish would not increase for more than approximately 2,000 pile strikes in a day for fish less than 2 grams or 5,000 pile strikes in a day for larger fish. This is because additional pile strikes do not result in additional cumulative energy. Furthermore, this predicted cumulative injury area is a liberal estimate (the largest possible) of the potentially injury area for fish based on the Stationary Fish model. This conservative approach protects fish because, should fewer pile strikes occur on any given day, the area of potentially injurious sound would be smaller. Because there is no assumed upper limit on pile strikes, this approach includes scenarios where multiple pile-driving rigs are used simultaneously on a single day.

NMFS currently assumes a 12-hour recovery period where fish are not exposed to sound from pile driving in order to reset daily accumulated _{SEL} calculations (Stadler and Woodbury 2009). As is standard practice, this analysis assumes that this 12-hour recovery period of nonexposure would occur between pile driving work periods (i.e., 12-hour pile driving days) (Grette 2014a).

Distances to Injury and Disturbance Thresholds

The results of the Practical Spreading Loss and Stationary Fish models using the reference levels for injury and disturbance are summarized in Table 5. Noise attenuation and fish movement models predicted that underwater noise thresholds would be exceeded, resulting in injury or behavior impacts, at distances ranging from 45 feet (single sound strike) to 3.92 miles (cumulative sound). The specific distances and effects for listed fish are provided in Table 5. Because the number of pile strikes per day would be variable, it was assumed that a minimum of 5,000 strikes would occur. Increasing pile strikes beyond 5,000 would not affect the distance at which thresholds would be exceeded for all federally protected fish. Predicted noise reduction using confined or unconfined bubble curtains or similar attenuation devices would be at least 9 dB, based on observations at the Columbia River Crossing (David Evans Associates 2011) and at Puget Island (Washington State Department of Transportation 2010).

Table 5. Underwater Noise Thresholds and Distances to Threshold Levels

Species	Effect Type	Threshold	Distance to Effect Threshold ^a
All Federally Protected Fish	Injury, cumulative sound (≥ 2 grams)	187 dB _{SEL}	1,775 feet ^b
	Injury, cumulative sound (< 2 grams)	183 dB _{SEL}	1,775 feet ^{b,c}
	Injury, single strike	206 dB _{PEAK}	45 feet ^d
	Behavior	150 dB _{RMS}	3.92 miles
^a Impact Pile Driver Operation, 36-inch steel pile with 9 dB attenuation from use of confined bubble curtain.			
^b This represents the point at which the model for distance to threshold for cumulative sound no longer increases with increased pile strikes. For 187 dB _{SELcum} (fish ≥ 2 grams), this is at 5,003 strikes; for 187 dB _{SELcum} (fish > 2 grams), this is at 1,992 strikes. The concept of effective quiet makes the 1,775-foot distance applicable to both thresholds and therefore is applicable to fish both greater than and less than 2 grams.			
^c Given the On-Site Alternative location and adherence to the proposed in-water work window, most salmonids in the area during construction are assumed to be > 2 grams (187 dB _{SELcum} threshold), except possibly for very early subyearling chum salmon in December			
^d Because the distance to cumulative sound thresholds are greater than the distance to the single-strike sound threshold, this analysis follows the NMFS dual criteria guidance and moves forward solely considering the larger values.			

Impact pile driving could occur from September 1 through December 31. To install 603 piles in-water would require two years, based on the proposed in-water work window for impact pile driving. Pile driving would occur during working days, Monday through Friday. Each pile is expected to take between 20 and 120 minutes to set using an impact pile driver, depending on when the resistant layer is met during installation. The contractor would determine the sequencing of the pile driving and the overall number of driving rigs to be used; this analysis assumes that multiple pile-driving rigs may be used simultaneously. It is possible that impact pile driving could occur at any time, as permitted by Cowlitz County Code, during the proposed in-water work window for impact pile driving (September 1 through December 31), and that it could be continuous over some working days, particularly if multiple rigs are operating in areas of shallow practical resistance. However, given variable subsurface conditions, it is expected there would be days where periods of impact driving are shorter and/or intermittent throughout the workday. Pile-driving activities could affect federally protected salmon, steelhead and trout, eulachon and green sturgeon, as well as nonprotected fish species.

Impacts on Salmon and Steelhead

Based on the proposed September 1 through December 31 in-water work window for impact pile driving, all life-history stages of the following ESUs/DPSs are expected to be absent from study area during this period:

Snake River spring-/summer-run ESU Chinook salmon

Upper Columbia River spring-run ESU Chinook salmon

Snake River ESU sockeye salmon

Upper Willamette River DPS steelhead

The potential for pile-driving activities to affect these species is considered negligible, and thus they are not considered further with respect to potential impacts from pile-driving activities.

Sub-adult and adult bull trout are occasionally observed within the Columbia River mainstem within the study area and could be present during any season. However, bull trout are expected to occur infrequently and in very low numbers relative to all other salmonids, and the likelihood of bull trout presence at any given time is very low, and the potential for pile-driving activities to affect bull trout is considered negligible. According to USFWS (2002), bull trout in the Lower Columbia Recovery Unit could have migrated seasonally from tributaries downstream into the Columbia River to overwinter and feed. However, the extent to which bull trout in the Lower Columbia Recovery Unit currently use the mainstem Columbia River is unknown. Therefore, bull trout are not considered further with respect to potential impacts from pile-driving activities.

Federally protected adult and juvenile salmon and steelhead that could be present in the study area during the proposed in-water work windows include juvenile fish from five ESUs and adult fish from eight ESUs/DPSs, as summarized in Table 6.

Table 6. Summary of Salmonid ESUs/DPSs for which Presence is not Discountable during the Impact Pile Driving Proposed Work Window (September 1–December 31) by Life Stage, Month, and Habitat Zone

Species, ESU/DPS	Federal Status ^a	Life Stage	Sept			Oct			Nov			Dec		
			A ^b	S ^b	D ^b	A	S	D	A	S	D	A	S	D
Chinook Salmon														
Snake River fall-run ESU	T	Adults			X ^c			...						
		Subyr	...	^d			
Lower Columbia River ESU	T	Adults			X			X						
		Yrlngr												...
		Subyr	
Upper Willamette River ESU	T	Yrlngr												...
		Subyr	
Coho Salmon														
Lower Columbia River ESU	T	Adults			X			X			X			X
		Subyr	
Chum Salmon														
Columbia River ESU	T	Adults						X			X			
		Subyr										
Steelhead Trout														
Snake River DPS	T	Adults			X			...						
Upper Columbia River DPS	T	Adults			X			...						
Middle Columbia River DPS	T	Adults			X			... ^e						
Lower Columbia River DPS	T	Adults			X			X			X			X

^a "T" denotes federally threatened (no Endangered in this table).

^b A, S, and D represent the HEA habitat categories of ACM, SWZ, and DWZ; see Grette (2014c) Section 3.2.3.1 for additional information.

^c "X" denotes expected presence; see Grette Associates (2014c), Section 3.3 for additional information.

^d "..." denotes expected presence but low relative abundance; see Grette Associates (2014c), Section 3.3 for additional information.

^e The Middle Columbia River DPS includes a very small proportion of winter-run fish (Klickitat River, Fifteen Mile Creek); because passage data at Bonneville Dam indicate that the vast majority of steelhead have passed the dam by early October, it is assumed that this includes winter steelhead spawning above it.

ESU = Evolutionary Significant Unit; DPS = Distinct Population Segment; Subyr = subyearling; Yrlngr = yearling.

Juvenile Chinook Salmon Habitat Use and Timing

In general, juvenile Chinook salmon outmigrate through the study area within SWZ and DWZ habitat during some or all of the September 1–December 31 in-water proposed work window. Overall habitat use and timing for juvenile Chinook salmon is summarized as follows (Grette 2014a).

- Juvenile Chinook salmon from the Snake River fall-run ESU exhibit multiple rearing strategies, but the majority of juveniles outmigrate as yearlings or large subyearlings during a well-defined period between late spring and early fall. These fish move through the tidal freshwater region at a large size and occur primarily in deeper water rather than the shallow margin.
- Juvenile Chinook salmon from the Upper Willamette River ESU exhibit multiple rearing strategies, but the majority of juveniles outmigrate as yearlings or large subyearlings during a well-defined period in late winter and spring. These fish move through the tidal freshwater region at a large size and occur primarily in deeper water rather than the shallow margin.
- Juvenile Chinook salmon from the Lower Columbia River ESU are associated with multiple runs and are thus associated with multiple rearing strategies. However, the majority of juveniles from this ESU outmigrate either as spring-run yearlings during the late winter and spring or as fall-run fry and fingerlings between the late winter and early summer. Any late-season fall-run subyearlings are expected to outmigrate through the tidal freshwater region at a large size and occur primarily in deeper water rather than the shallow margin.

Subyearling coho salmon from the Lower Columbia River ESU and subyearling chum salmon from the Columbia River ESU are expected to occur in the estuary during the proposed in-water work window; however, presence of individuals would represent low relative abundance in comparison to annual outmigration periods for each ESU. Subyearling coho salmon present in the estuary between September and December would represent individuals moving amongst off-channel rearing areas. Any subyearling coho salmon present within the estuary are expected to overwinter in low-velocity tributaries or off-channel habitats prior to outmigrating the following spring as yearlings. Subyearling chum outmigrate soon after emergence and rear in the lower estuary. Any subyearling chum present in the river mainstem of the tidal freshwater region during the in-water work period would therefore be expected to move rapidly through the study area. Mainstem Columbia River habitats are considered to be used by juvenile salmon as a migratory corridor where presence in any given location is temporary and relatively short-term.

Potential Injury Impacts on Juvenile Salmon

Because the distance to cumulative sound thresholds are greater than the distance to the single-strike sound threshold, this analysis follows the NMFS dual criteria guidance and moves forward solely considering the larger values. Sound above the potential cumulative injury threshold (183/187 dB_{SELcum}) may occur within 1,775 feet of impact pile driving (both upstream and downstream), for a maximum distance of 1.1 miles along the shoreline (1,775 feet upstream and downstream, along the 2,300-foot length of Docks 2 and 3 for a total distance 5,850 feet). This is approximately 0.44 square miles.

Approximately 21% (0.09 square mile) of this area is above -20 feet CRD, inclusive of the ACM and SWZ. This area provides relatively low-quality habitat for small (< 4 inches) subyearling salmon. Areas across the river and downstream provide greater (and more diverse) natural cover as well as floodplain connectivity, contributing to higher-quality critical habitat for rearing juvenile salmon.

Any subyearling salmon present in the 0.09-square-mile area during impact pile driving would be susceptible to sound-related injury due to cumulative exposure. The risk of injury for some individual smaller subyearling salmon is low based on relative abundance expected in the study area (Table 5), but not discountable for the following salmon (in decreasing order of likelihood based on timing and relative abundance).

- Lower Columbia River Chinook salmon
- Upper Willamette River Chinook salmon
- Snake River fall-run Chinook salmon
- Lower Columbia River coho salmon
- Columbia River chum salmon

The mainstem Columbia River (Deep Water) comprises the remaining 79% of the aquatic area exposed to potentially injurious sound from impact pile driving. Any yearling or larger (> 4 inches) subyearling salmon present in this area would be susceptible to sound-related injury during pile driving due to cumulative exposure. The risk of injury for some individual yearling and larger subyearling salmon is low but not discountable for the following salmon (in decreasing order of likelihood based on timing and relative abundance).

- Lower Columbia River Chinook salmon (larger subyearlings and yearlings)
- Upper Willamette River Chinook salmon (larger subyearlings and yearlings)
- Snake River Fall-run Chinook salmon (larger subyearlings only)

It is possible that juvenile fish could leave areas of potentially injurious sound, either as an avoidance response or during the course of normal outmigration behavior, in which case they may not experience sufficient cumulative sound to cause injury.

Adult Salmon Habitat Use and Timing

Adult from eight ESUs/DPSs of salmon and steelhead may migrate upstream through the study area within DWZ habitat during some or all of the proposed September 1–December 31 impact pile driving work window.

Adults from three of the eight ESUs/DPSs are expected to be in the Lower Columbia River each of the four months when pile-driving activities are anticipated to occur.

- Adult steelhead from the Lower Columbia River DPS migrate year-round (winter- and summer-run fish); therefore, individuals are expected to be present from September 1 to December 31.
- Adult coho from the Lower Columbia River ESU may migrate through the tidal freshwater region from August through February, and are also expected to be present from September 1 to December 31.
- Adult chum from the Columbia River ESU migrate through the tidal freshwater region during October and November, which is entirely within the September 1–December 31 period.

Adults from the remaining five ESUs/DPSs are expected only in September and October.

- Lower Columbia River Chinook (fall-run component only)
- Snake River fall-run Chinook (in low abundance after September)

- Snake River steelhead (in low abundance after September)
- Upper Columbia River steelhead (in low abundance after September)
- Middle Columbia River steelhead (in low abundance after September)

Based on historical run-timing data from Bonneville Dam, 95% of adult Chinook and steelhead migrating upstream past the dam have done so by the end of the first week of October (inclusive of hatchery fish and nonlisted populations). For Chinook, typically 50% of adults have migrated past the Bonneville Dam by the end of August. For steelhead, that number is closer to 60%.

None of these ESUs/DPSs spawn in the mainstem of the river within the area of elevated sound (Table 5), adult salmonids do not forage in freshwater, and migrating fish are not expected to hold in this section of the river (versus holding near the confluence to a spawning tributary). Therefore, all migrating adult salmon and steelhead are expected to move quickly through the study area.

Migrating Chinook salmon in the Columbia River travel approximately 23 miles per day (median, from Keefer et al. 2004). Migrating steelhead in the Columbia River travel 19–25 miles per day in reaches not adjacent to spawning tributaries (English et al. 2006). Migration rates for coho and chum specific to the Columbia River are not available, but surrogates can be used to estimate them. As reviewed in Sandercock (1991), upstream migration rates for coho may be 0.8–1.7 miles per hour, which results in approximately 9–20 miles per day assuming fish actually migrated 12 hours in each day (see Sandercock 1991). Chum salmon in the Yukon River averaged migration rates of 23 miles per day (Buklis and Barton 1984). In general, Chinook, chum, and steelhead would be expected to travel most swiftly through this section of the river (approximately 23 miles per day), with coho travelling somewhat slower (approximately 9–20 miles per day).

Overall, the proportion of adults from each of the eight ESUs/DPSs that could be present during some or all of the impact pile-driving period would move through the study area rapidly; none are expected to hold within or occupy the study area for extended periods of time.

Potential Injury Impacts on Adult Salmon

Based on habitat use and timing, adult salmonids potentially migrating through the tidal freshwater region during the proposed September through December impact pile-driving work window would include all of the adults from the Columbia River chum salmon ESU, many of the adults from the fall-run component of the Lower Columbia River Chinook salmon ESU, many of the adults from the Lower Columbia River coho salmon ESU, and some of the adults from the Snake River, Upper Columbia River, Middle Columbia River, and Lower Columbia River steelhead DPSs. These fish would be actively migrating upstream at an estimated rate of 9–22 miles per day. The relative amounts (all, many, some) are based on the proportion of the total migration period that occurs within the impact pile-driving period (September through December) for each ESU/DPS (Grette 2014a).

Active pile driving would not occur continuously (all hours, all days) between September 1 and December 31; therefore, not all of the adults migrating upstream during this time would experience sound from pile driving. However, those adult salmon and steelhead that do migrate through the study area during active pile driving could experience potentially injurious sound. Assuming fish were to travel through the entire area (as opposed to avoiding portions of it) this distance traveled would be between 0.67 and 1.1 miles, depending on whether driving occurred at closely or widely spaced locations. Based on the migration speeds reviewed above, adult fish migrating upstream

could pass through these areas in approximately 20 to 90 minutes. It is therefore not discountable that some adult salmonids from these ESUs/DPSs could be susceptible to sound-related injury while actively migrating through the study area, depending on the actual duration of sound exposure and proximity to pile driving for individual fish (Grette 2014a).

Current NMFS guidance is to apply the 187dB_{SELcum} injury threshold to all salmonids greater than 2 grams; however, this is an overly conservative approach (see Carlson et al. 2007). Carlson et al. (2007) conclude that for fish greater than 200 grams (applicable to all adult salmonids considered in this assessment), the threshold for nonauditory tissue injury (including injuries resulting from rapid oscillations in gas-filled spaces) is 213 dB_{SELcum}. The conservative approach used to model sound in this assessment predicts 214 dB_{SELcum} at 10 meters from pile driving. Therefore, because cumulative sound above 214 dB_{SELcum} would be limited to such a small area, it is extremely unlikely that adult fish would experience enough sound to result in injury to nonauditory tissues. However, adult fish could be susceptible to auditory injury (hair cell damage) and hearing effects from TTS from cumulative sound exposure, should sufficient exposure occur (Grette 2014a).

Potential Risk for Behavioral Effects on Salmon

As described in ICF Jones & Stokes and Illingworth and Rodkin (2009), 150 dB_{RMS} is a conservative threshold that is applied in most Biological Opinions to evaluate when impact pile driving/proofing could result in temporary behavioral responses in fish, which could in turn result in such effects as reduced predator avoidance and reduction in foraging efficiency. Also as described in ICF Jones & Stokes and Illingworth and Rodkin (2009), NMFS and USFWS do not provide scientific support for this threshold. Therefore, whether behavioral effects actually occur and then subsequently result in injury through behavioral changes or significant disruption of normal behavioral patterns must be evaluated on a project-specific basis dependent upon factors such as site characteristics, project details, and species life history and habitat use within the potential exposure area (Grette 2014a).

SPLs (not cumulative) may exceed the behavioral disturbance threshold of 150 dB_{RMS} up to 3.92 miles from the site during active pile driving. Underwater noise would only propagate into areas that are within line-of-sight of the noise source, therefore the area affected is less than 3.92 miles because islands and bends in the river prevent sound propagation beyond this distance. As mentioned previously, juvenile salmon from five ESUs and adult salmon and steelhead from eight ESUs/DPSs may migrate through the Columbia River adjacent to the On-Site Alternative during the impact pile-driving period (Table 5). However, juvenile and adult fish are expected to move through the study area relatively quickly as a function of active migratory behavior (Grette 2014a).

Nonlisted Salmon and Steelhead

Several nonlisted salmon ESUs and steelhead DPSs also migrate within the Columbia River through the study area and could be impacted by pile-driving activities, similar to listed salmon and steelhead described above. These include Chinook salmon from three ESUs (Deschutes River summer/fall-run, Middle Columbia River spring-run, and Upper Columbia River summer/fall-run), sockeye salmon from two ESUs (Okanogan River and Lake Wenatchee), as well as a number of artificial propagation programs (e.g., coho salmon re-introduction and/or hatchery programs established by member tribes of the Columbia River Inter-Tribal Fish Commission) (Grette 2014a).

During impact pile driving, adults and subyearlings from the Deschutes River summer-/fall-run and Upper Columbia River summer-/fall-run ESUs may be present in the study area, with timing and presence most similar to Snake River fall-run Chinook. Some adults are expected to be present in the

study area during September, and adult migration through the area could continue into October. Subyearling fish may be present in very small numbers through November (Grette 2014a).

Presence, timing, and use of fish from artificial propagation programs are similar to listed ESUs by species and life-history types. Based on the timing and use summarized in Table 5, during impact pile driving, presence of some adults from these programs is expected; juveniles (subyearling and yearlings) are expected in relatively low numbers with variable timing and use by species and life history (Grette 2014a).

Based on similarities in presence, timing, and use, the analyses for listed salmonids can be generally applied to the nonlisted salmon and steelhead (Grette 2014a).

Impacts on Eulachon

The areas of potentially disturbing and injurious sound described previously for salmonids also can be applied to eulachon. However, because many of the cumulative injuries associated with underwater sound are related to the interaction between SPLs and a fish's swim bladder, the application of the cumulative injury threshold to eulachon is conservative (and therefore protective) as eulachon lack a swim bladder. As described above, the distances to thresholds are 1,775 feet for cumulative injury and 3.92 miles for disturbance. Impact driving would likely occur on most working days (Monday through Friday) within the proposed in-water work window (September 1–December 31). On some days impact driving may occur over most or even all of the day, but during much of the construction period, it would be for shorter durations and at times may be discontinuous (Grette 2014a).

Adult eulachon could arrive in the study area as early as November, although most adults would migrate through the study area later, coincident with peak spawn timing between February and March. Eggs from early spawners could be distributed from the tributaries downstream to portions of the study area where suitable incubation conditions occur (i.e., sand waves) shortly thereafter. Emergent larvae could be present in the study area as early as December. However, based on the timing of peak spawning, and because incubation occurs for one to two months, peak larval transport would not be expected until February or later (Grette 2014a).

Little information exists upon which to base assumptions about eulachon habitat use within the area of potentially elevated sound, such as preferential depths and migration behavior versus spawning for adults. Therefore, in order to present a conservative evaluation that is protective of the species, it is assumed that adult eulachon may be distributed anywhere throughout this area, and that not all adult fish are actively migrating through it. It is also assumed that eggs and incubating larvae, whether spawned in the area or delivered from upstream locations, may be distributed throughout areas where sand wave bed forms occur. As reviewed in Gustafson et al. (2010), larvae in the water column are quickly transported downstream and therefore are assumed to be moving with the current (Grette 2014a).

Potential Injury Impacts on Eulachon

The area of potentially injurious sound is assumed to be the same as that delineated for salmon and steelhead (1,775 feet from pile-driving activities, which would include an area covering approximately 0.44 square mile). Any adult eulachon present during pile driving would be at risk of sound-related injury; therefore, although the risk of injury to individual fish is low, based on relative abundance in the study area during pile driving activities (Table 2), it is not discountable. Some fish

may be moving through the area, reducing their risk of exposure to cumulative sound injury, or adult fish could leave and/or avoid areas of potentially injurious sound, as part of an avoidance response or during the course of normal behavior, in which case they may not experience sufficient cumulative sound to cause injury. However, some adult eulachon present in the area of impact may experience cumulative injury from pile driving in November and December. Nevertheless, based on the timing of adult returns to the Columbia River, this would probably be a very low number of fish relative to the entire annual eulachon run.

Eulachon eggs and larvae could experience sound that is potentially injurious for adult and juvenile fish, but based on the proposed timing for impact pile driving this would be an extremely low proportion of eggs and larvae produced in any given spawning year. Further, it is not appropriate to directly apply the same thresholds to larval fish and eggs. There is little information available on the effects of sound in general on fish eggs and larvae (Popper and Hastings 2009), and almost nothing specific to the effect of sound from pile driving (Bolle et al. 2012). As reviewed by Popper and Hastings (2009), there is some indication in the literature that sound (e.g., broadband noise) or sound pressure (e.g., blasts or even mechanical simulations such as drops) can affect egg, embryo, and larval survival and development. Because eulachon eggs adhere to sediments and therefore stay within or move slowly through areas of elevated sound, they may be more susceptible to prolonged exposure to cumulative sound from pile driving regardless of the distance at which injury may occur. Larvae are more likely to be transported quickly through areas of elevated sound, and may therefore be less susceptible to any cumulative effects. Common sole (*Solea solea*) larvae exposed to cumulative sound in excess of the standard injury threshold exhibited no increase in mortality (Bolle et al. 2012). The risk of injury generally applies to the earliest part of the run, and over a relatively small area of the potential incubation and migration area (Grette 2014a).

Potential Risk of Behavioral Effects on Eulachon

Potentially disturbing sound from impact pile driving may extend up to 3.92 miles from the site during active pile driving; this represents an approximately three square-mile area within which adult eulachon could be affected. As indicated previously, little is known about the behavioral effects of pile driving sound on fish, but it is possible that adult eulachon present in this area could be at greater risk of predation as a result of underwater sound generated during pile-driving activities. This risk is low but not discountable for adult eulachon (Grette 2014a).

Similar to injury thresholds, it is not appropriate to apply the behavioral threshold to larval eulachon, particularly given the paucity of information of the effects of sound in general, and from pile driving specifically. Should sound from impact pile driving affect these fish at any distance from the On-Site Alternative, active behavioral responses would not be expected based upon their small size and weak swimming behavior (Grette 2014a).

Impacts on Green and White Sturgeon

The areas of potentially disturbing and injurious sound described for salmonids can be applied to green and white sturgeon, which also have a swim bladder. Based on the calculations and assumptions described for salmonids, including the maximum pile strike assumptions in the cumulative sound model and use of an attenuation device, the distances to thresholds are 1,775 feet for cumulative injury and 3.92 miles for disturbance (Figure 4).

To minimize the potential for impacts on other fish, impact pile driving would occur between September 1 and December 31. Based on this timing, it is expected that some green sturgeon

may be present in the Lower Columbia River during the early part of the work period but that numbers of fish would decline thereafter as they leave the estuary to winter in the Pacific Ocean. White sturgeon are expected to be present throughout the work period. When present in the Columbia River, green sturgeon are known to occur as far upstream as Bonneville Dam but are predominately present below RM 37 (Adams et al. 2002). The project area is at RM 63. Therefore, while some green sturgeon may be generally present within the area of potentially elevated sound, it is expected that their number would be small. There is a relatively low likelihood of these fish being present in the area of potentially elevated sound during the summer, and that likelihood would further decline throughout the pile-driving period.

White sturgeon on the other hand, are found throughout the lower Columbia River and are expected to be within the study area during pile driving activities.

Potential Injury Impacts on Green and White Sturgeon Threshold

Green sturgeon have been observed swimming at speeds of 1.3–3.9 feet per second in tidal environments in the San Francisco Bay estuary (Kelly and Klimley 2012). White sturgeon are assumed to have similar swimming speeds as green sturgeon. Based on this swimming speed, Southern DPS green sturgeon and white sturgeon would pass through areas of potentially elevated sound within 20 and 75 minutes, depending on speed and distance, and some green and white sturgeon could be susceptible to sound-related injury while actively migrating through the study area. However, given the low number of green sturgeon expected to use areas upstream of the study area and the proposed timing for pile driving, this is expected to be a very low proportion of the Southern DPS green sturgeon using the Columbia River in any given year. White sturgeon are expected to be more abundant and would be likely to occur within the study area throughout the proposed timing for pile driving.

Application of the 187dB_{SELcum} injury threshold to fish > 200 grams is an overly conservative approach (see Carlson et al. 2007). As with salmonids, adult and subadult green and white sturgeon at this location would be expected to be > 200 grams and are expected to have a much higher threshold for nonauditory tissue injury. It is extremely unlikely that subadult or adult green and white sturgeon would experience cumulative sound sufficient to result in injury to nonauditory tissues. However, they could be susceptible to auditory injury (hair cell damage) and hearing effects from TTS from cumulative sound exposure, should sufficient exposure occur (Grette 2014a).

Potential Risk of Behavioral Effects on Green and White Sturgeon

Potentially disturbing sound from impact pile driving may extend up to 3.92 miles from the site. Adult or subadult Southern DPS green sturgeon may move downstream through this area, particularly early in the in-water work period. White sturgeon may occur within the study area and may be moving upstream or downstream. Using the same analysis of distances and swimming speeds, those fish would pass through the study area in less than one day but could experience potentially disturbing sound from pile driving during this migration period. However, the risk that individual adult and subadult green and white sturgeon would experience elevated sound and potentially be at greater risk of predation is considered low (Grette 2014a).

Pacific Lamprey and River Lamprey

It is well documented that hydroacoustic impacts can be significant, causing injury or mortality, for fish with swimbladders. Lampreys do not have swimbladders and it is therefore difficult to

determine the extent of this impact. Fish without swimbladders are thought to be at lower risk from underwater noise than fishes with swimbladders (Hastings and Popper 2005 in Lord 2011). No thresholds for disturbance or injury have been established for such fish. Therefore, hydroacoustic impacts to lamprey should not be discounted, but they cannot be quantified or analyzed with any level of certainty (Lord 2011). Impacts on lampreys from project related pile driving would be expected to be less harmful than impacts to salmon and sturgeon and other fish species with swimbladders.

Temporary Shading

Overwater structures (i.e., docks and large vessels) can increase shading to the aquatic environment beneath and adjacent to the structure, which can result in changes to productivity as well as fish behavior, predation, and migration. Barges necessary for construction of in-water elements of the On-Site Alternative would create temporary overwater structure, which would reduce the amount of light entering the water. This temporary reduction in light level is not anticipated to result in changes to aquatic habitat conditions and therefore would not change the ambient light in the environment.

Juvenile and subadult salmonids use the nearshore areas for feeding and rearing, and as a migratory corridor. As small individuals, they stay in shallow waters to avoid large fish predators found in deeper water. As these fish grow larger, they will feed on the forage fish, such as herring (family Clupeidae), sand lance (family Ammodytidae), and surf smelt (*Hypomesus pretiosus*), that spawn and rear in shallow intertidal areas.

The use of a barge or other similar large vessel could affect juvenile and subadult salmonid migration within the shallow water habitat areas. However, their use would primarily be during the in-water construction period (September 1–December 31) and would be mostly required for installation of support piling for Docks 2 and 3. Pile-driving activities would be expected to be much more disruptive to fish than the shading created by construction-related barges and vessels, and would likely affect migration and foraging opportunities within the study area to a greater extent (i.e., fish migrating within the study area would not be expected to be near construction barges during pile driving due to the elevated noise levels, thus fish would not be expected to be affected by shading associated with construction barges). Barges and similar large vessels may also be used for construction of Docks 2 and 3, which could occur outside of the proposed in-water window and thus could affect juvenile and subadult salmonid migration in the shallow water habitat. However, specific timing and methods for construction of Docks 2 and 3 would be determined during permitting.

Spills and Leaks

Construction activities would occur on land as well as in and over waters of the Columbia River. During all construction-related activities there is the potential risk of temporary water quality impacts resulting from the release of hazardous materials such as fuels, lubricants, hydraulic fluids, or other chemicals as described in the NEPA Hazardous Materials Technical Report (ICF International 2016d). Overall, it is assumed that a spill would be relatively small (e.g., less than 50 gallons) because limited quantities of potentially hazardous materials would be stored and used during construction at the project area. These materials could enter surface waters of the Columbia River or drainage ditches near the On-Site Alternative. Such spills could affect aquatic habitat or fish that could be near the discharge point, resulting in toxic acute or subacute

impacts that could affect the respiration, growth, or reproduction of the affected fish. Over-water and in-water work increases this risk as well as the potential for construction debris or materials to enter the Columbia River. The potential for these types of impacts would be avoided or greatly reduced given protective measures to guard against these risks, including: construction best management practices, avoidance and minimization measures, in-water work restrictions, and regulatory requirements, such as those associated with 401 Water Quality Certification. The NEPA Water Quality Technical Report (ICF International 2016c) includes a detailed discussion on the potential risks to and impacts on water quality associated with the On-Site Alternative.

3.1.2 Construction—Indirect Impacts

Construction of the proposed export terminal would not result in indirect impacts on fish because no construction impacts would occur later in time or farther removed in distance than the direct impacts.

3.1.3 Operations: Direct Impacts

Operations associated with the proposed terminal would occur on land and on dock and trestle structures in the Columbia River. Potential direct impacts related to operations of the On-Site Alternative are discussed below.

Shading

Overwater structures (i.e., docks and large vessels) can increase shading to the aquatic environment beneath and adjacent to the structure, which can result in changes to productivity as well as fish behavior, predation, and migration. The trestle would result in approximately 0.3 acre of new overwater coverage in shallow-water areas above -20 feet CRD (SWZ), while Docks 2 and 3 and a portion of the trestle would result in 4.83 acres of new overwater coverage in DWZ habitat below -20 feet CRD. Vessels loaded at Docks 2 and 3 during project operations would further increase the shading beyond Docks 2 and 3 in DWZ habitat. At full build out, the Applicant anticipates serving 70 vessels per month; thus, it is expected that there would be two vessels at Docks 2 and 3 at all times. The worst case would be two Panamax vessels being loaded simultaneously. Panamax vessels are approximately 965 feet in length with a beam of 106 feet, for an overall area of 102,290 square feet (2.35 acres). Two Panamax ships would add 204,580 square feet (4.7 acres) of overwater surface area located over DWZ habitat, for a total of 9.83 acres being shaded. The study area encompasses approximately 1,300 acres, primarily DWZ habitat. Docks 2 and 3 as well as vessels being loaded at the docks would shade approximately 0.8%. As mentioned above, juvenile salmonids tend to migrate in SWZ habitat, thus shading of DWZ habitat would likely affect juvenile salmonids to a lesser extent than adults or larger juveniles that tend to migrate in DWZ habitat. Overall shading of DWZ habitat would be less likely to affect primary productivity, as primary productivity tends to be higher in SWZ habitat. Based on the location of Docks 2 and 3 over DWZ habitat and the relatively small area shaded in relation to the overall study area, the shading impact would be relatively low.

As reviewed in Carrasquero (2001), light attenuation from overwater structures in freshwater environments can lead to lowered primary productivity (phytoplankton and macrophyte producers). Reduced primary productivity, including reduced stock of algae and macrophytes, can in turn influence the epibenthic community on which other organisms depend. Reduction of

primary productivity in DWZ habitat would not likely translate to reductions of epibenthic communities, which are more prevalent in SWZ habitat.

Light attenuation could affect fish migration, prey capture and predation. Salmon fry are known to use darkness and turbidity for refuge. However, they tend to migrate along the edges of shadows rather than penetrate them (Simenstad et al. 1999). Studies in the northwest have documented this behavioral tendency to use shadow edges for cover during migration (Shreffler and Moursund 1999). The underwater light environment also affects the ability of fishes such as bass, to see and capture their prey, including juvenile salmonids. Foraging opportunities for juvenile fish are generally associated with SWZ habitat (areas above -20 feet CRD), which are expected to provide greater availability of benthic organisms as compared to DWZ habitat (areas below -20 feet CRD). Juvenile salmon primarily migrate in SWZ habitat, although larger juveniles do migrate in DWZ habitat. Juveniles migrating in DWZ habitat are likely migrating relatively quickly and not rearing for extended periods in any particular area. The trestle is the only structure that would generate shade in SWZ habitat. The potential shading created by the trestle would be relatively low because the trestle is elevated over the water surface elevation of OHW by approximately eight feet, allowing light to penetrate beneath the trestle, which would not be expected to have a measurable effect on primary productivity or fish behavior, migration, or predation in SWZ habitat.

The design and orientation of the trestle would further minimize the potential effects of shading. The elevation of the trestle combined with the relatively narrow width of the deck (24 feet), the height, and the width would allow natural light to partially pass beneath the structure during all seasons. In addition, the north-south orientation of the trestle relative to the path of the sun overhead would reduce the amount of shading cast beneath it, as compared to if the structure were oriented east-west.

The docks and vessels would be located over the DWZ, but could provide shaded habitat for larger predatory fishes, such as bass, northern pikeminnow, as well as piscivorous birds (Carrasquero 2001). Support piling for the docks could also create flow shears (i.e. back-eddies), which could increase the potential predation of juvenile salmonids and other fish migrating or otherwise occurring within the SWZ and DWZ (Carrasquero 2001). The extent or magnitude to which an increase in overwater surface area may alter the predator-prey relationship at the On-Site Alternative is unknown, but it is assumed that the relationship would change and an increase in predation would be likely. The extent or magnitude to which an increase in overwater surface area could alter the predator-prey relationship in the study area is unknown, but it is assumed that the relationship would change and an increase in predation would be likely.

Spills or Leaks

Routine operations could result in spills or leaks at the On-Site Alternative from vehicles, trains, or equipment that could affect water quality and the condition of aquatic habitat in the Columbia River and drainage ditches in the vicinity. Overall, it is assumed that a spill would be relatively small (e.g., less than 50 gallons) because limited quantities of potentially hazardous materials would be stored and used during operations at the project area. Refueling of vehicles during operations would occur off site at approved refueling stations, or fuel would be delivered to the project area by a refueling truck (capacity of 3,000 to 4,000 gallons). Refueling trucks are required to carry appropriate spill response equipment, thereby reducing the potential risk and

impact associated with a fuel spill. Vessel bunkering (i.e., a vessel receiving fuel while at the dock) would not occur at the project area. Thus, the risk of spills from vessel transfers would not increase. Potential impacts on fish and fish habitat are similar to those described for construction leaks and spills in Section 3.1.1.1. Appropriate training and implementation of prevention and control measures would guard against these risks, greatly reducing the potential for these types of impacts. Further information is contained in the NEPA Water Quality Technical Report (ICF International 2016c) and NEPA Hazardous Materials Technical Report (ICF International 2016d).

Coal Spills

Direct impacts on the natural environment from a coal spill during operations of the proposed terminal could occur. Direct impacts resulting from a spill during coal handling at the export terminal would likely be minor because the amount of coal that could be spilled would be relatively small. Also, impacts would be minor because of the absence of aquatic environments in the project area and the contained nature and features of the terminal (e.g., fully enclosed belt conveyors, transfer towers, and shiploaders). Potential physical and chemical effects of a coal release on the aquatic environments that occur adjacent to the terminal are described below.

Aquatic environments could potentially be affected by a coal spill both physically and chemically. A coal spill could have physical effects on aquatic environments, including abrasion, smothering, diminished photosynthesis, alteration of sediment texture and stability, reduced availability of light, temporary loss of habitat, and diminished respiration and feeding for aquatic organisms. The magnitude of these potential impacts would depend on the amount and size of coal particles suspended in the water, duration of coal exposure, and existing water clarity (Ahrens and Morrissey 2005). Therefore, the circumstances of a coal spill, the conditions of a particular aquatic environment (e.g., pond, stream, wetland), and the physical effects on aquatic organisms and habitat from a coal spill would vary. Similarly, cleanup of coal released into the aquatic environment could result in temporary impacts on habitat, such as smothering, altering sediment composition, temporary loss of habitat, and diminished respiration and feeding for aquatic organisms. The recovery time required for aquatic resources would depend on the amount of coal spill and the extent and duration of clean-up efforts, as well as the environment in which the incident occurred. It is unlikely that coal handling in the upland portions of the export terminal would result in a spill of coal that would affect the Columbia River. This is unlikely because the rail loop and stockpile areas would be contained, and other areas adjacent to the export terminal are separated from the Columbia River by an existing levee, which would prevent coal from being conveyed from upland areas adjacent to the rail loop to the Columbia River. Coal could be spilled during shiploading operations as a result of human error or equipment malfunction. However, such a spill would likely result in a limited release of coal into the environment due to safeguards to prevent such operational errors, such as start-up alarms, dock containment measures (i.e., containment “gutters” placed beneath the docks to capture water and other materials that may fall onto and through the dock surface) to contain spillage /rainfall/runoff, and enclosed shiploaders.

The chemical effects on aquatic organisms and habitats would depend on the circumstances of a coal spill and the conditions of a particular aquatic environment (e.g., stream, lake, wetland). Some research suggests that physical effects are likely to be more harmful than the chemical effects (Ahrens and Morrissey 2005).

A recent coal train derailment and coal spill in Burnaby, British Columbia, in 2014, and subsequent cleanup and monitoring efforts provide some insight into the potential impacts of coal spilled in the aquatic environment. Findings from spill response and cleanup found there were potentially minor impacts in the coal spill study area, and that these impacts were restricted to a localized area (Borealis Environmental Consulting 2015).

3.1.4 Operations: Indirect Impacts


Potential indirect impacts associated with operation of the proposed terminal could occur as a result of vessel traffic in the Columbia River between the proposed terminal and the confluence with the Pacific Ocean. These potential impacts include fish stranding associated with vessel wakes. Periodic maintenance dredging could result in removal of benthic habitat and associated impacts on aquatic invertebrates. Also, coal dust could indirectly affect fish and fish habitat.

Fish Stranding from Vessel Wakes

Ecology has monitored the number of vessel entries into the Columbia River of commercial cargo and passenger vessels of 300 gross tons or larger and tank vessels carrying oil products of all sizes since 1993. Over that period there has been about a 2% per year decline in the number of vessels crossing the Columbia River Bar (Figure 11). This is in part due the completion of the Columbia River Federal Navigation Channel Improvements Project, which dredged the Columbia River Ship Channel from near the entrance to the Port of Portland near RM 106 to a depth of 43 feet. This allowed the newer and larger Panamax and Handymax vessels to navigate the river and call at Columbia River ports, thereby reducing the number of smaller vessels navigating the Columbia River.

At full build out, the proposed terminal would have the capacity to serve up to 70 vessels per month (840 per year) with a throughput capacity of 44 million metric tons per year of coal.

Figure 11. Number of Vessels Entering the Columbia River per Year



The fleet serving the On-Site Alternative would consist of the newer Panamax and Handymax vessels. Panamax vessels anticipated to use the export terminal average about 65,000 dead weight tons (dwt) and measure approximately 738 feet long by 105 feet wide with a draft of 43 feet. They are designed to fit snugly, but safely in the lock chambers of the Panama Canal. Handymax vessels are the workhorses of the dry bulk market. They are usually less than 60,000 dwt and measure approximately 490 to 655 feet long by 105 feet wide with a draft of 36 feet.

A growing body of evidence indicates that juvenile salmon and other fish are at risk of stranding on wide, gently sloping (i.e., less than 5% slope) beaches as a consequence of wakes generated by deep draft vessel passage (Bauersfeld 1977; Hinton and Emmett 1994; Pearson et al. 2006; ENTRIX 2008). Depending on various factors such as the slope and breadth of a beach, river stage, tidal stage, depth of water vessels are transiting in, and vessel size and speed, wakes from passing vessels can travel a considerable distance. When these wakes meet the shoreline, they can carry fish and deposit them, essentially “stranding” them on the beach where they are susceptible to stress, suffocation, and predation before than can return to the water.

The precise factors that contribute to stranding risk are not well understood. Bauersfeld (1977) observed that “stranded fish are often concentrated along the high-water line, in and around obstructions or debris which impedes return flow, and along the path of return flow. Ship-wash stranding is generally confined to sand beaches with a low slope angle or coves which constrict the waves and force the water onshore.” He also identified a number of sites where stranding was observed. In all, Bauersfeld (1977) observed the passage of 216 ships, and found 2,397 stranded fish, 2,297 of them juvenile Chinook salmon. Hinton and Emmett (1994) sampled eight sites along the reach extending from the upper estuary to Sauvie Island from April through September 1992 and from March through July 1993. They observed the passage of 145 ships, and found five stranded fish. They did not identify factors contributing to stranding, other than those previously noted by Bauersfeld (1977).

Pearson et al. (2006) published the most detailed study of Lower Columbia River fish stranding completed to date. They evaluated stranding at three sites in the Lower Columbia River: Sauvie Island, Barlow Point (adjacent to the On-Site Alternative and the proposed Off-Site Alternative), and County Line Park. The sites were chosen because prior work (primarily Bauersfeld’s work) had established them as sites with high risk of stranding. Pearson et al. (2006) observed 126 vessel passages, 46 of which caused stranding. They also measured numerous site variables including fish density (measured via beach seining), site topography, river stage, current velocity, tidal stage, tidal height, and a variety of vessel variables including direction of movement, velocity, ship type, ship size, and draft. Although the study provides an understanding of the factors that contribute to standing, it does not create a predictive model because it was limited to analysis of known or suspected high-risk sites.

To address this limitation, ENTRIX (2008) conducted a spatial analysis from RM 0 to RM 104 in which a total of 1,634 transects spaced at intervals of 656 feet along both river banks were identified and various risk factors were modeled.

The results of the ENTRIX (2008) analysis supported the statements of Bauersfeld (1977) that not all Lower Columbia River beaches pose a risk of stranding juvenile salmon by ship wakes and of Pearson and Skalski (2006) that their three study sites were not representative of all Lower Columbia River beaches. The ENTRIX (2008) analysis demonstrated that a minimal stranding risk exists along 175 of the 208 miles of shoreline found on the Lower Columbia River.

A more than minimal stranding risk exists along 33 miles of the river, with a high stranding risk (comparable to the risk found at Barlow Point, County Line Park, and Sauvie Island) found along about 8 miles of the river (Figure 9). ENTRIX cautions that this study is best viewed as a systematic analysis using objective, quantitative criteria to identify physically based susceptibility to stranding because it did not include information about nearshore fish density.

Fish stranded by passing deep-draft vessels on the Lower Columbia River have been inventoried by Bauersfeld (1977), Hinton and Emmett (1994), and Pearson et al. (2006). Each of these researchers relied primarily on beach seine data collected at sites where stranding was observed to determine fish species presence adjacent to the sites. Results consistently demonstrated that stranded fish primarily consist of subyearling salmonids. Bauersfeld (1977) found that 86% of all fish collected were in the 1.2 to 2.0 inch size range and of these, 78% were Chinook salmon and 20% were chum salmon. Hinton and Emmett (1994) provide two anecdotal reports of ship wake stranding observed by Earl Dawley in 1977 (Hinton and Emmett 1994) and 1984 (Dawley et al. 1984); in both instances the stranded fish were nearly all subyearling Chinook salmon. Pearson et al. (2006) observed stranding of 520 fish, of which 426 (82%) were subyearling Chinook salmon. Pearson et al. (2006) also performed beach seines to develop an index of fish available for stranding; they found that subyearling Chinook salmon comprised only 49% of the beach seine catch, indicating that these fish are more susceptible to stranding than other salmonid species. This difference was statistically significant at 98% confidence. All salmonids other than subyearling Chinook salmon (yearling Chinook, coho, and chum salmon, and mountain whitefish) collectively comprised only 5% of the stranded fish and 3.3% of the fish sampled by beach seine (Pearson et al. 2006), suggesting that the effects of wake stranding fall primarily upon subyearling Chinook salmon (i.e., ocean-type Chinook salmon).

Although the On-Site Alternative would result in an increase in deep-draft vessel traffic, which characteristically produce wakes that contribute to stranding, many of the sites in the study area where fish stranding could occur are located near the project area; for example, Lord Island is just across the channel from the project area, and Barlow Point is about 1.2 miles downstream (and has also been identified as the project area for the Off-Site Alternative). Vessels maneuvering in the study area would be either slowing to stage nearby if the docks are full, or slowing to prepare for docking. Once vessels are loaded, they would maneuver back to the navigation channel and then proceed downstream toward the Pacific Ocean. Such maneuvering would be unlikely to result in a risk of stranding near the proposed docks, as very little wake would be generated by vessels moving at slow speeds. Sites farther downstream, such as near Puget Island, would be more likely to have a higher risk of fish stranding from vessel wakes because vessels are transiting those areas at higher speeds.

In the Lower Columbia River fish stranding appears to be associated with various factors, as mentioned previously. In general, fish stranding appears to be an issue when wakes produced by deep-draft vessels (those with a draft of 26 feet or more) transiting the river during low tides encounter shorelines with shallow sloping beaches (i.e., less than 5% slope), and particularly on those beaches that are highly permeable (high rates of infiltration due to unconsolidated substrate material). Such conditions appear to increase the potential for fish stranding. However, it should be noted that beaches are not necessarily always conducive to stranding. For example, stranding may occur less frequently or not at all during high tide or during periods when the river is at a certain stage, when the beaches are more inundated and less exposed. Thus, the potential for fish stranding to occur on any given beach is not constant, but likely changes as tides and river stage changes, and as fish migrations change. It is recognized,

however, that in 2028 at full build out, project-related vessels would represent approximately 27% of the expected total vessel traffic in the Lower Columbia River annually. This increase would result in an increased risk in fish stranding.

It is also worth noting that vessel operations in the Lower Columbia River are federally regulated, including; the size, speed, and navigation. Additionally, in the Lower Columbia River, large vessels are required to be operated by pilots licensed by the Coast Guard. The navigation channel is managed and regulated at the federal level, including maintenance dredging and dredged material disposal.

Physical or Behavioral Responses to Vessel Noise

Vessels transit the Columbia River each year carrying oil, freight, and materials to and from ports along the river. Approximately 3,980 commercial vessel transits occurred on the Columbia River in 2014 including approximately 2,750 by cargo and passenger vessel transits above 300 gross tons (Washington State Department of Ecology 2015). Mean source sound levels of bulk carrier vessels were calculated in Puget Sound at between 187.9 and 198.2 dB re 1uPA at 1 meter when vessels were travelling at between 9.0 and 11.1 knots (Hemmera Envirochem et al. 2014). These source sound levels exceed identified thresholds for potential behavioral disturbance for fish and may cause avoidance or other behavioral responses (Fisheries Hydroacoustic Working Group 2008). Therefore, fish in the immediate vicinity of transiting vessels may experience behavioral responses to the vessel noise, but would not likely be injured.

Maintenance Dredging and Aquatic Habitat

Maintenance dredging would likely occur every few years, as needed, to maintain required depths at Docks 2 and 3 and to allow access from the docks to the navigation channel, especially in the years following the initial dredging work (WorleyParsons 2012). Maintenance dredging would require additional permitting, beyond any permits that may be issued to construct the project. It is assumed that flow lane disposal would be the preferred method for disposal of dredge material, provided the sediments were clean.

Sediment accretion in the proposed dredge prism would most likely occur as a result of bedload transport due to river currents, and local scour and sediment redistribution from propeller wash. Hydrodynamic modeling and sediment transport analysis was conducted for the proposed Docks 2 and 3 berthing/navigation basin. Sedimentation is complex in a newly dredged basin. Specific morphologic data is unavailable for the proposed new dredging basin; therefore, the rate of accretion can only be estimated roughly. Based on current accretion estimates, rough estimates for annual accretion height is approximately 0.16 foot (0.07–0.26 foot range), and annual accretion volume is approximately 11,675 cubic yards (4,670–23,350 cubic yard range) (WorleyParsons 2012). WAC 220-660-160 provides general design considerations for new terminals, to minimize impacts fish life that the project would generally comply with, whenever feasible.

Impacts on the benthic invertebrate community would be similar to those described for initial dredging associated with construction activities. Compared to the initial dredging effort, maintenance dredging would remove a relatively small amount of material, including benthic, epibenthic, and infaunal organisms, resulting in some mortality of invertebrate organisms and temporary disruption of benthic productivity. Habitat within the proposed dredge prism is in

DWZ habitat where benthic productivity is expected to be relatively low compared to shallow water habitats (McCabe et al. 1997).

Maintenance-related dredging activities could affect fish in a manner similar to the initial dredging associated with construction activities. Fish could be affected by increased turbidity and noise associated with dredging activities (Todd et al. 2014). Turbidity would be elevated during maintenance dredging and impacts would be similar to those described above for construction under Section 3.1.1.1. Noise could cause masking and behavioral changes in fish but is unlikely to cause auditory damage (Central Dredging Association 2011, Dickerson et al. 2001, Todd et al. 2014).


Coal Dust

Coal dust would be generated during operation of the proposed terminal through the movement of coal into the site, around the site, and onto vessels. Coal dust could also become airborne from the large stockpiles that would be located within the site.

The potential extent and deposition rate of coal dust particles less than 75 microns was modeled as part of the analysis conducted relative to air quality and human health during the preparation of the environmental impact statement as described in the NEPA Air Quality Technical Report (ICF International 2016e) for additional details. Based on this modeling, the highest rate of coal dust deposition would be expected in the immediate area surrounding the export terminal, but smaller particles would also be expected to deposit in a zone extending around and downwind of the export terminal. Deposition rates could range from 1.45 grams per square meter (g/m^2) per year closest to the export terminal, gradually declining to less than $0.01 \text{ g}/\text{m}^2/\text{year}$ approximately 2.41 miles from the export terminal, as described in the SEPA Coal Technical Report (ICF International 2016g).

Based on the models, the zone of deposition would extend primarily northwest of the On-Site Alternative and over the Columbia River, encompassing the Off-Site Alternative and forested hills at the northern extent of the Off-Site Alternative, riparian habitat along the shoreline, and extending across the Columbia River to Lord and Walker Islands. Deposition rates ranging from $0.4 \text{ g}/\text{m}^2/\text{year}$ in the Columbia River adjacent to the project area to $0.1 \text{ g}/\text{m}^2/\text{year}$ in the Columbia River at Lord Island (Figure 12), with declining concentrations moving away from the project area.

Although concerns regarding coal dust are commonly expressed relative to air quality and human health concerns, wind-born coal dust could affect fish through physical or toxicological means. Ahrens and Morrissey (2005) conducted a literature review on the biological effects of unburnt coal in the marine environment. The following discussion is distilled from that review. Coal particles could affect aquatic wildlife in a manner comparable to any form of suspended particulates, such as tissue abrasion, smothering, obstruction, or damage to feeding or respiratory organs, and other effects resulting from reduced quantity or quality of light. Another potential manner in which coal could affect aquatic wildlife is through coal leachates. Unburnt coal can be a source of acidity, salinity, trace metals, hydrocarbons, chemical oxygen demand, and potentially macronutrients if they leach from the coal matrix into aquatic habitats. Toxic constituents of coal include PAHs and trace metals, which are present in coal in variable amounts and combinations dependent on the type of coal. The coal type, the mineral impurities in the coal, and environmental conditions determine whether these compounds can be leached from the coal. Some PAHs are known to be toxic to aquatic animals and humans.

Figure 12. Modeled Average Annual Coal Dust Deposition (On-Site Alternative)

Metals and PAHs could also potentially leach from coal to the pore water of sediments and be ingested by benthic-feeding organisms, providing a mechanism for subsequent ingestion by other organisms throughout the food chain. However, the low aqueous extractability and bioavailability of the contaminants minimizes the potentially toxic effects (Ahrens and Morrissey 2005). The type of coal anticipated to be exported from the On-Site Alternative is alkaline, low in sulfur and trace metals. Furthermore, because the Columbia River is a dynamic riverine system the constituents of the coal dust would be distributed and diluted to even lower concentrations as they are transported downstream.

Coal has a heterogeneous chemical composition and specific impacts related to its toxic contaminants are highly dependent on the specific coal composition and source (Ahrens and Morrissey 2005). The majority of coal transported to and from the site would be from the Powder River basin. A 2007 U.S. Geological Survey (USGS) report investigated the quality of coal from the Powder River basin, including the concentrations of trace elements of environmental concern, which include: antimony, arsenic, beryllium, cadmium, chromium, cobalt, lead, manganese, mercury, nickel, selenium, and uranium. According to the study conducted by the USGS (2007), trace elements of environmental concern (TEEC) are generally low in the Powder River basin coals in comparison to other mining regions, although exact concentrations were not known at the time of this report. Table 7 presents the average concentrations of each TEEC sampled in parts per million. However, at a maximum coal deposition rate of $1.45 \text{ g/m}^2/\text{year}$, a coal density of 0.83 grams per cubic centimeter, and at the minimum flow recorded over the 23-year period of record for one day, TEEC deposition directly into the river assumed to be an area of approximately 3,000,000 square meters would result in a change in concentration for each of the elements of concern on the order of 1×10^{-13} to $1 \times 10^{-15} \text{ g/L}$. If coal dust generated at the project area accumulated without being disturbed throughout the summer dry season (assuming 120 days duration), the anticipated change in TEEC concentration for the minimum recorded flow over one day would be on the order of 1×10^{-10} to $1 \times 10^{-12} \text{ g/L}$. Again, this change would not be measureable and is not anticipated to affect human health or affect aquatic organism functions (i.e., respiration, feeding).

The concentration of PAHs in Power River basin coal was not investigated for this report because PAHs are only released during combustion. Because the rate of coal dust deposition is so low it is likely unmeasurable and the concentration of trace elements of environmental concern are considered low, impacts on water quality are anticipated to be low.

Table 7. Average Concentration of Trace Elements in Wyodak and Big George Coal Beds, Powder River Basin, Wyoming

Trace Element of Environmental Concern	Average Concentration in Sampled Coal (ppm)
Antimony	0.10
Arsenic	1.43
Beryllium	0.18
Cadmium	0.06
Chromium	2.63
Cobalt	1.93
Lead	1.26
Manganese	10.05
Nickel	1.58
Selenium	0.57
Uranium	0.46

Source: U.S. Geological Survey 2007.

ppm = parts per million

Research suggests that the bioavailability of contaminants in coal is limited, and that at levels of coal contamination at which estimates of bioavailable concentrations of contaminants might give cause for concern, the acute physical effects are likely to be more harmful than the chemical effects (Ahrens and Morrissey 2005). However, the variable chemical properties of coal could conceivably result in contaminant mobility and enhanced bioavailability in the aquatic environment. Coal can be a source of acidity, salinity, trace metals, PAHs, and chemical oxygen demand (a measure of organic pollutants found in water). Interactions between coal and water could alter pH and salinity, release trace metals and PAHs, and increase chemical oxygen demand. However, if and how much these alterations occur in the aquatic environment and whether the alterations are significant enough to be potentially toxic to aquatic organisms depends on many factors, including the type of coal, the relative amount of time the coal is exposed to water, dilution, and buffering.

In summary, fugitive coal dust from project operations is not expected to increase suspended solids in the Columbia River to the point that there would be a demonstrable effect on fish distribution, abundance, survival, or acute physical effects. Additionally, the potential risk for exposure to toxic chemicals contained in coal (e.g., PAHs and trace metals) would be relatively low because these chemicals tend to be bound in the matrix structure and not quickly/easily leached. Further, any coal particles would be transported downstream by the flow of the river and either carried out to sea or distributed over a broad area further reducing the potential for adverse impacts on fish from suspended solids.

Commercial and Recreational Fishing

Project-related increases in vessel traffic in the lower Columbia River and associated underwater noise could affect fishing in the study area. Increases in vessel traffic could cause behavioral responses including quicker migration or avoidance of the navigation channel. An average of 70 large commercial vessels would be loaded at the terminal each month. If adult fish targeted in commercial and recreational fishing were to alter behavior in response to increased underwater noise, they may avoid or migrate quickly through the navigation channel.

Commercial and recreational fishing vessels would not likely be fishing in the navigation channel when large vessels are present. Therefore, the On-Site Alternative would be unlikely to significantly reduce commercial or recreational fishing catches or limit access for fishing activities. The potential impacts of the On-Site Alternative on commercial and recreational fishing vessels associated with project-related vessels are addressed in the NEPA Vessel Transportation Technical Report (ICF International 2016f).

3.2 Off-Site Alternative

Potential impacts on fish from the proposed terminal at the Off-Site Alternative location are described below.

3.2.1 Construction: Direct Impacts

Construction of the Off-Site Alternative would occur at the alternate project area, and would affect fish and fish habitats in the Columbia River. The types of construction impacts would be similar to those described under Section 3.1.1, *On-Site Alternative*. Construction of the proposed terminal at the Off-Site Alternative location would result in the following direct impacts.

Aquatic Habitat

Project construction would result in the alteration or removal of aquatic habitat. Aquatic habitat would be permanently removed by the placement of piles for the trestle and docks. A total of 597 36-inch-diameter steel piles would be placed below the OHW mark for the trestle and docks, removing an area equivalent to 0.10 acres of benthic habitat. Approximately 94% of this habitat (3,980 square feet) is located in deep water (Grette 2014e). As with the On-Site Alternative, the placement of piles would displace benthic habitat and the areas within each pile footprint would no longer contribute toward primary or secondary productivity. Individual pile footprints would be relatively small (36 inches in diameter) and would be spaced throughout the dock and trestle footprint. The Off-Site Alternative would require fewer piles (597 compared to 603) below OHW and the area of benthic habitat permanently lost would be less (3,980 square feet compared to 4,263). Benthic, epibenthic, and infaunal organisms within the pile footprint at the time of pile driving would likely perish.

Dredging would permanently alter a 15-acre area of deepwater habitat (below -20 feet CRD) by removing approximately 50,000 cubic yards of benthic sediment to achieve a depth of -43 feet CRD, with a 2-foot overdredge allowance (Grette 2014e). The amount of deepening required to reach target depth would be three feet or less, as the proposed dredge prism is at or below -42 feet CRD (Grette 2014e). Required sediment removal at the Off-Site Alternative site would be approximately 50,000 cubic yards, ten times less than would be required at the On-Site Alternative site, which would involve the removal of approximately 500,000 cubic yards of sediment over an area more than three times larger (48 acres). As with the On-Site Alternative, dredged materials would likely be disposed of within the flow lane in or adjacent to the navigation channel, allowing these sediments to support the downstream sediment transport system (Grette 2014d, 2014e, 2014f). This would be within an area of approximately 80 to 110 acres between approximately RM 60 and RM 66 (Figure 4).

Potential impacts on fish and fish habitat resulting from dredging activities would be similar to those described for the On-Site Alternative in Section 3.1.1.1; however, the extent of the potential impacts would be less than those at the On-Site Alternative because the dredge prism at the Off-Site Alternative is approximately one-third the size of the On-Site Alternative dredge prism and the quantity of sediments that would be removed at the Off-Site Alternative would be approximately one-tenth of what would be removed for the On-Site Alternative.

The majority of benthic, epibenthic, and infaunal organisms are nonmotile or slow-moving and become entrained during dredging. Benthic, epibenthic, and infaunal organisms within the proposed dredge prism above -43 feet CRD would be removed during dredging, resulting in likely mortality. These organisms often serve as prey for larger animal species, such as fish. The habitat within the proposed dredge prism is in deep water where benthic productivity is expected to be low relative to shallower habitat habitats. Deepwater channels are subjected to higher water velocities, which periodically scour bottom sediments, limiting the standing crop of invertebrates and the buildup of detritus and fine materials that support these invertebrates (McCabe et al. 1997, as cited in Grette 2014f). Dredging activities are not typically associated with long-term reductions in the availability of prey resources, and impacts on benthic productivity are expected to be temporary. Disturbed habitats are expected to return to reference conditions with rapid recolonization by benthic organisms (Grette 2014f).

The overall impacts of dredging activities on fish would be the same as or similar to those described for the On-Site Alternative (Section 3.1.1.1).

Potential mitigation measures presented in the NEPA Draft Environmental Impact Statement (Volume 1), Chapter 8, *Minimization and Mitigation* addresses impacts on fish caused by permanently removing or temporarily altering habitat.

Physical or Behavioral Response from Elevated Turbidity during Pile Driving and Dredge Material Disposal

Potential impacts on fish resulting from elevated turbidity from pile driving and dredged material disposal would be the same as or similar to those described for the On-Site Alternative (Section 5.7.2.5.1). However, the Off-Site Alternative would require driving 597 piles, 13 fewer than for the On-Site Alternative. This difference in terms of turbidity from driving 13 fewer piles would be negligible.

Physical or Behavioral Response to Underwater Noise during Pile Driving

Potential impacts on fish resulting from underwater construction noise would be very similar to those described for the On-Site Alternative (Section 3.1.1.1). The Off-Site Alternative would require 597 piles be driven in-water, as opposed to 603 in-water piles for the On-Site Alternative.

Compared to the On-Site Alternative, the overall areas where in-water noise thresholds for fish are exceeded are unchanged, however the duration of pile driving may be slightly reduced due to the reduced number of piles to be driven (13 fewer piles). Potential mitigation measures presented in the NEPA Draft Environmental Impact Statement (Volume 1), Chapter 8, *Minimization and Mitigation* address impacts on fish caused by increased underwater noise during pile driving.

Temporary Shading

Potential impacts on fish resulting from shading would be very similar to those described for the On-Site Alternative (Section 3.1.1.1). The surface area of the docks and trestle for Off-Site Alternative would be 0.01-acres less than the On-Site Alternative. The shading created by the vessels would be the same (4.7 acres for two Panamax vessels) for both alternatives.

Spills and Leaks

Potential impacts on fish resulting from construction-related spills and leaks would be the same as or similar to those described for the On-Site Alternative (Section 3.1.1.1).

3.2.2 Construction: Indirect Impacts

Construction of the proposed terminal would not result in indirect impacts on fish because no construction impacts would occur later in time or farther removed in distance than the direct impacts.


3.2.3 Operations: Direct Impacts

Direct operational impacts of the Off-Site Alternative would result in impacts very similar to those described for the On-Site Alternative (Section 3.1.1.2).

3.2.4 Operations: Indirect Impacts

Overall, indirect operational impacts of the Off-Site Alternative would result in impacts very similar to those described for the On-Site Alternative (Section 3.1.1.3).

However, modeled fugitive coal dust concentrations for the Off-Site Alternative (Figure 13) indicate that deposition rates would range from 1.83 grams per square meter per year ($\text{g}/\text{m}^2/\text{year}$) adjacent to the proposed export terminal to $0.01 \text{ g}/\text{m}^2/\text{year}$ approximately 2.98 miles from the terminal, compared to the On-Site Alternative.

Figure 13. Modeled Average Annual Coal Dust Deposition (Off-Site Alternative)

3.3 No-Action Alternative

Under the No Action Alternative, the Applicant would not construct the On-Site Alternative or the Off-Site Alternative. Current operations would presumably continue. The existing bulk product terminal could be expanded onto the on-site alternative project area. Expansion activities could require a permit from the U.S. Army Corps of Engineers if they result in a discharge of dredged or fill material into onsite wetlands or other waters of the United States. New construction, demolition, or related activities to expand the bulk terminal could occur on previously developed upland portions of the On-Site Alternative. This could affect upland areas and habitats that do not provide suitable fish habitat.

It is assumed that growth in the region would continue, which would allow continued operation of the export terminal site and the adjacent bulk terminal site within the 20-year analysis period (2018–2038). Cleanup activities, relative to past industrial uses, would continue to occur. This could impact developed areas and associated disturbed upland habitats. Vessel traffic volumes are expected to continue and any fish disturbance or injury associated with vessel movements would continue at levels similar to current conditions; however, additional impacts on fish or fish habitat could occur under the No-Action Alternative because in-water work could occur.

Chapter 4

Required Permits

The On-Site Alternative or Off-Site Alternative would require the following permits in relation to fish and fish habitat.

The On-Site Alternative would require the following permits related to fish and fish habitat.

- **Shoreline Management Act Authorization—Cowlitz County.** Cowlitz County administers the Shoreline Management Act (SMA) through its Shoreline Management Master Program (SMP). The On-Site Alternative site would have elements and impacts within SMA jurisdiction (see WAC 90.58.030 for definition of SMA jurisdiction which includes “Shorelands,” “Shorelines,” and “Shorelines of Statewide Significance”) and would thus require a Shoreline Substantial Development and Conditional Use permit from Cowlitz County and the Department of Ecology.
- **Local Critical Areas and Construction Permits—Cowlitz County.** Either Alternative would require local permits related to clearing and grading of the site and relative to impacts to regulated critical areas. Chapter 19.15 of the Cowlitz County Code regulates activities within and adjacent to critical areas and in so doing regulates fish and wildlife habitat conservation areas (including streams and their buffers), frequently flooded areas, and other sensitive areas. Cowlitz County would require an application for Planning Clearance, a Fill and Grade Permit, Building Permits, Shoreline Permit, Floodplain Permit, and Critical Area Permit, and would review the Environmental Impact Statements for consistency with the County’s critical areas ordinance.
- **Construction and Development Permits—Cowlitz County.** Both Alternatives would require fill and grade permits (CCC 16.35) and construction permits (CCC 16.05) for clearing and grading and other ground disturbing activities, as well as construction of structures and facilities associated with the On-Site Alternative.
- **Clean Water Act Authorization-U.S. Army Corps of Engineers.** Construction and operation of the export terminal would involve discharges of dredged and fill material into waters of the United States, including wetlands. Department of the Army Authorization from the U.S. Army Corps of Engineers would be required under Section 404 of the Clean Water Act.

An Individual Water Quality Certification from the Washington State Department of Ecology under Section 401 of the Clean Water Act and a National Pollution Discharge Elimination System permit under Section 402 of the Clean Water Act would also be required. Additional details regarding the permitting process related to the Clean Water Act can be found in the NEPA Water Quality Technical Report (ICF International 2016c).

- **Rivers and Harbors Act—U.S. Army Corps of Engineers.** Construction and operation of the export terminal would take place in navigable waters of the United States (i.e., the Columbia River). The Rivers and Harbors Act authorizes the Corps to protect commerce in navigable streams and waterways of the United States by regulating various activities in such waters. Section 10 of the RHA (33 USC 403) specifically regulates construction, excavation, or deposition of materials into, over, or under navigable waters, or any work that would affect the course, location, condition, or capacity of those waters

- **Hydraulic Project Approval—Washington Department of Fish and Wildlife.** Both Alternatives would require a Hydraulic Project Approval (HPA) from the WDFW due to project elements that would affect and cross the shoreline of the Columbia River. The HPA would consider effects on riparian and shoreline/bank vegetation in issuance and conditions of the permit, including for the installation of the proposed docks and pilings, as well as for project-related dredging activities and other project-related work.
- **Local Critical Areas and Construction Permits—City of Longview (Off-Site Alternative only).** The Off-Site Alternative would require permits from the City of Longview. Chapter 17.10 of the City of Longview Municipal Code regulates activities within and adjacent to critical areas and in so doing regulates vegetation occurring in wetlands and their buffers, fish and wildlife habitat conservation areas (including streams and their buffers), frequently flooded areas, and geological hazard areas. The City of Longview would require Critical Areas and Floodplain permits, as well as a Building Permit for clearing, grading, and construction.
- **Shoreline Substantial Development—City of Longview (Off-Site Alternative only).** A Shoreline Substantial Development permit from the City of Longview would also be required. The City of Longview administers the Shoreline Management Act through its Shoreline Management Master Program. The project area would have elements and impacts within jurisdiction of the act and would thus require a Shoreline Substantial Development permit from the City of Longview. The Off-Site Alternative would not require a Shoreline Substantial Development Permit or Conditional Use Permit from Cowlitz County.

5.1 Written References

- Adams, P. B., C. B. Grimes, J. E. Hightower, S. T. Lindley, and M. L. Moser. 2002. *Status Review for North American Green Sturgeon, Acipenser mediorstris*. National Marine Fisheries Service, Southwest Fisheries Science Center, Santa Cruz, CA.
- Ahrens, M. J., and D. J. Morrissey. 2005. Biological Effects of Unburnt Coal in the Marine Environment. National Institute of Water and Atmospheric Research Ltd. *Oceanography and Marine Biology: An Annual Review* 43:69–122.
- Bauersfeld, K. 1977. *Effects of Peaking (Stranding) of Columbia River Dams on Juvenile Anadromous Fishes below The Dalles Dam, 1974 and 1975*. Report by the State of Washington Department of Fisheries, Olympia, Washington, for the U.S. Army Corps of Engineers, Portland District, Portland, OR.
- Beamish, R. J. 1980. Adult Biology of the River Lamprey (*Lampetra ayresi*) and the Pacific Lamprey (*Lampetra tridentate*) from the Pacific Coast of Canada. *Canadian Journal of Fisheries and Aquatic Sciences* 37(11):1906–1923.
- BergerABAM. 2016. *Millennium Bulk Terminal Longview: Land and Shoreline Use Technical Report*. Prepared for ICF International.
- Bolle, L. J., C. A. De Jong, S. M. Bierman, P. J. Van Beek, O. A. Van Keeken, P. W. Wessels, and R. P. Dekeling. 2012. Common Sole Larvae Survive High Levels of Pile-Driving Sound in Controlled Exposure Experiments. *PLoS One* 7(3):e33052.
- Bottom, D. L., G. Anderson, A. Baptista, J. Burke, M. Burla, M. Bhuthimethee, L. Campbell, E. Casillas, S. Hunton, K. Jacobson, D. Jay, R. McNatt, P. Moran, G. G. Roegner, C. A. Simenstad, V. Stamatiou, D. Teel, and J. E. Zamon. 2008. *Salmon Life Histories, Habitat, and Food Webs in the Columbia River Estuary: An Overview of Research Results, 2002–2006*. Report of the National Marine Fisheries Service to the U.S. Army Corps of Engineers and Bonneville Power Administration, Portland, OR.
- Brooks, K. M. 1995. Literature Review, Computer Model, and Assessment of the Environmental Risks Associated with Creosote Treated Wood Products Used in Aquatic Environments. August 30, 1994. *Aquatic Environmental Sciences*, Port Townsend, Washington (reissued in 1997).
- Buklis, L. S. and L. H. Barton. 1984. *Yukon River Fall Chum Biology and Stock Status*. Alaska Department of Fish and Game, Division of Commercial Fisheries. Anchorage, Alaska. Available: <http://www.sf.adfg.state.ak.us/FedAidPDFs/afrbil.239.pdf>. Accessed: September 2014.
- Carlson, T., M. Hastings, and A. N. Popper. 2007. *Update on Recommendations for Revised Interim Sound Exposure Criteria for Fish during Pile Driving Activities*. Memorandum to Suzanne Theiss at California Department of Transportation and Paul Wagner at Washington Department of Transportation.

- Carlson TJ, Ploskey G, Johnson RL, Mueller RP, Weiland MA, Johnson PN. 2001. Observations of the behavior and distribution of fish in relation to the Columbia River navigation channel and channel maintenance activities. Pacific Northwest National Laboratory, Richland, p 35.
- Carrasquero, J. 2001. *Over-Water Structures: Freshwater Issues*. Herrera Environmental Consultants. White Paper submitted to Washington Department of Fish and Wildlife, Washington Department of Ecology, Washington Department of Transportation. April 12, 2001.
- Carter, J. A., G. A. McMichael, I. D. Welch, R. A. Harnish, and B. J. Bellgraph. 2009. *Seasonal Juvenile Salmonid Presence and Migratory Behavior in the Lower Columbia River*. PNNL-18246, Pacific Northwest National Laboratory, Richland, WA.
- Central Dredging Association. 2011. *Underwater Sound in Relation to Dredging*. Central Dredging Association (CEDA), CEDA position paper, November 7. Available: http://www.dredging.org/media/ceda/org/documents/resources/cedaonline/2011-11_ceda_positionpaper_underwatersound_v2.pdf.
- Clemens, B. J., S. van de Wetering, S. A. Sower, and C. B. Schreck. 2013. Maturation Characteristics and Life-History Strategies of the Pacific Lamprey, *Entosphenus tridentatus*. *Canadian Journal of Zoology* 91:775–788.
- Columbia River Research. 2013. *DART Smolt Index 10 Year Historical Run Timing*. Columbia Basin Research, University of Washington (juvenile fish passage). Available: http://www.cbr.washington.edu/dart/query/smolt_hrt. Queried: September 2013.
- Columbia River Research. 2014. *DART Adult Passage 10 Year Historical Run Timing*. Columbia Basin Research, University of Washington. Available: http://www.cbr.washington.edu/dart/query/adult_hrt. Queried: September 2014.
- David Evans and Associates, Inc. 2011. *Columbia River Crossing Test Pile Project Hydroacoustic Monitoring Final Report*. August 2011. Prepared by James Coleman, David Evans and Associates, Inc.
- Dawley, E. M., R. D. Ledgerwood, T. H. Blahm, R. A. Kirn, and A. E. Rankis. 1984. *Migrational Characteristics and Survival of Juvenile Salmonids Entering the Columbia River Estuary during 1983*. Annual Report of Research Financed by Bonneville Power Administration, Agreement DE-A179-83BP39652 and Coastal Zone and Estuarine Studies Division of Northwest and Alaska Fisheries Center, National Oceanic and Atmospheric Administration. Seattle, WA.
- DeVore, J. D., B. W. James, C. A. Tracy, and D. H. Hale. 1995. Dynamics and Potential Production of White Sturgeon in the Unimpounded Lower Columbia River. *Transactions of the American Fisheries Society* 124:845–856.
- Dickerson, C., K. J. Reine, and D. G. Clark. 2001. *Characterization of Underwater Sounds Produced by Bucket Dredging Operations*. DOER Technical Notes Collection (ERDC TN-DOER-E14), U.S. Army Engineer Research and Development Center, Vicksburg, MS.
- ECORP Consulting, Inc. 2009. Literature review (for studies conducted prior to 2008): Fish behavior in response to dredging and dredged material placement activities (Contract No. W912P7-07-P-0079). Prepared for the U.S. Army Corps of Engineers, San Francisco District. 69pp.

- Eisler, R. 1987. *Polycyclic Aromatic Hydrocarbon Hazards to Fish, Wildlife, and Invertebrates: A Synoptic Review*. U.S. Fish and Wildlife Service, Biological Report 85.
- English, K. K., D. Robichaud, C. Sliwinski, R. F. Alexander, W. R. Koski, T. C. Nelson, B. L. Nass, S. A. Bickford, S. Hammond, and T. R. Mosey. 2006. Comparison of Adult Steelhead Migrations in the Mid-Columbia Hydrosystem and in Large Naturally Flowing British Columbia Rivers. *Transactions of the American Fisheries Society* 135:739–754.
- ENTRIX. 2008. *Spatial Analysis of Beach Susceptibility for Stranding of Juvenile Salmon by Ship Wakes*. Final Report. Prepared for: The Port of Vancouver. Vancouver, WA 98660.
- Fish Passage Center. 2014. Query of Adult Passage at Bonneville Dam: Graph with Current Year, Last Year, and 10-Year Average. Available: http://www.fpc.org/adultsalmon/adultqueries/Adult_Table_Species_Graph.html.
- Fisheries Hydroacoustic Working Group. 2008. Agreement in Principle for Interim Criteria for Injury to Fish from Pile Driving Activities.
- Fisheries and Oceans Canada. 2014. Recovery Strategy for White Sturgeon (*Acipenser transmontanus*) in Canada [Final]. In *Species at Risk Act Recovery Strategy Series*. Ottawa: Fisheries and Oceans Canada.
- Fresh, K. L., E. Casillas, L. L. Johnson, and D. L. Bottom. 2005. *Role of the Estuary in the Recovery of Columbia River Basin Salmon and Steelhead: An Evaluation of the Effects of Selected Factors on Salmonid Population Viability*. U.S. Dept. Commerce, Seattle, WA. NOAA Tech. Memo. NMFS-NWFSC-69.
- Graves, J. K., J. A. Christy, P. J. Clinton, and P. L. Britz. 1995. *Historic Habitats of the Lower Columbia River*. Report by the Columbia River Estuary Study Taskforce, Astoria, Oregon. In Johnson et al. 2003.
- Grette Associates, LLC. 2014a. *Millennium Coal Export Terminal Longview, Washington: Affected Environment Biological Resources. Technical Report*. January 2014, revised March 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals – Longview, LLC. Longview, WA.
- Grette Associates, LLC. 2014b. *Millennium Coal Export Terminal Longview, Washington: Docks 2 and 3 and Associated Trestle Direct Effects of Construction*. September 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals – Longview, LLC. Longview, WA.
- Grette Associates, LLC. 2014c. *Millennium Coal Export Terminal Longview, Washington: Off-Site Alternative – Barlow Point Pile Driving and Underwater Sound*. September 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals – Longview, LLC. Longview, WA.
- Grette Associates, LLC. 2014d. *Millennium Coal Export Terminal Longview, Washington: Docks 2 and 3 and Associated Trestle: Proposed Mitigation Measures to Minimize Construction and Long-Term Effects*. September 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals – Longview, LLC. Longview, WA.
- Grette Associates, LLC. 2014e. *Millennium Coal Export Terminal Longview, Washington: Off-Site Alternative – Barlow Point Permanent Impacts to Aquatic Habitat*. September 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals – Longview, LLC. Longview, WA.

- Grette Associates, LLC. 2014f. *Millennium Coal Export Terminal Longview, Washington: Permanent Impacts to Aquatic Habitat*. September 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals – Longview, LLC. Longview, WA.
- Gustafson, R. G., M. J. Ford, D. Teel, and J. S. Drake. 2010. *Status Review of Eulachon (Thaleichthys pacificus) in Washington, Oregon, and California*. U.S. Department of Commerce, NOAA Technical Memorandum. NMFS-NWFSC-105. Available: http://www.westcoast.fisheries.noaa.gov/publications/status_reviews/other_species/eulachon/7092_06162010_142619_eulachontm105webfinal.pdf. Accessed: September 2014.
- Hastings, M. C. and A. Popper. 2005. *Effects of Sound on Fish*. Final Report #CA05-0537. Project P476 Noise Thresholds for Endangered Fish. California Department of Transportation. Sacramento, CA 95811
- Hemmera Environchem Inc., SMRU Canada Ltd., and JASCO Applied Sciences (Canada) Ltd. 2014. Roberts Bank Terminal 2 Technical Data Report: Underwater Noise Ship Sound Signature Analysis Study. Prepared for Port Metro Vancouver. December 2014.
- Hinton, S. A. and R. L. Emmett. 1994. *Juvenile Salmonid Stranding in the Lower Columbia River, 1992 and 1993*. NOAA Technical Memorandum NMFS-NWFSC-20. Prepared by the National Marine Fisheries Service, Northwest Fisheries Science Center, Coast Zone and Estuaries Studies Division, Seattle, WA.
- Howell, M. D., M. D. Romano, and T. A. Rien. 2001. *Draft Outmigration Timing and Distribution of Larval Eulachon, Thaleichthys pacificus, in the Lower Columbia River, Spring 2001*. Washington Department of Fish and Wildlife and Oregon Department of Fish and Wildlife, Olympia, Washington.
- ICF Jones & Stokes and Illingworth and Rodkin. 2009. *Final Technical Guidance for Assessment and Mitigation of the Hydroacoustic Effects of Pile Driving on Fish*. February 2009. Prepared for California Department of Transportation. ICF Jones & Stokes and Illingworth and Rodkin, Inc., Sacramento, CA. *Appendix I: Compendium of Pile Driving Sound Data*, updated October 2012.
- ICF International. 2016a. *Millennium Bulk Terminals— Longview, NEPA Environmental Impact Statement, NEPA Groundwater Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016b. *Millennium Bulk Terminals— Longview, NEPA Environmental Impact Statement, NEPA Vegetation Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016c. *Millennium Bulk Terminals— Longview, NEPA Environmental Impact Statement, NEPA Water Quality Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016d. *Millennium Bulk Terminals— Longview, NEPA Environmental Impact Statement, NEPA Hazardous Materials Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.

- ICF International. 2016e. *Millennium Bulk Terminals— Longview, NEPA Environmental Impact Statement, NEPA Air Quality Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016f. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statements, NEPA Vessel Transportation Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016g. *Millennium Bulk Terminals— Longview, SEPA Environmental Impact Statements, SEPA Coal Technical Report; Coal Dust Exposure, Coal Spill Analysis and Sulfur Dioxide and Mercury Analysis*. April. Seattle, WA. Prepared for Cowlitz County, Kelso, WA, in cooperation with Washington State Department of Ecology, Southwest Region.
- ICF International and Wilson Ihrig Associates. 2016. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Noise and Vibration Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- Independent Scientific Review Panel. 2013. *Review of the Draft Columbia Basin White Sturgeon Planning Framework*.
- Jefferies, S. J., P. J. Gearin, H. R. Huber, D. L. Saul, and D. A. Pruett. 2000. *Atlas of Seal and Sea Lion Haulout Sites in Washington*. Washington Department of Fish and Wildlife, Wildlife Science Division, 600 Capitol Way North, Olympia, WA.
- Johnson, G. E., B. D. Ebberts, R. M. Thom, N. M. Ricci, A. H. Whiting, J. A. Southard, G. B. Sutherland, J. D. Wilcox, T. Berquam. 2003. *An Ecosystem-Based Approach to Habitat Restoration Projects with Emphasis on Salmonids in the Columbia River Estuary*. Final Report. November 2003. Prepared for the U.S. Department of Energy under Contract DE-AC06-76RL01830. PNNL-14412
- Jolley, J. C., G. S. Silver, and T. A. Whitesel. 2012. *Occurrence, Detection, and Habitat Use of Larval Lamprey in Columbia River Mainstem Environments: Bonneville Tailwater and Tributary Mouths*. 2011 Annual Report. U.S. Fish and Wildlife Service, Columbia River Fisheries Program Office, Vancouver, WA. Available: http://www.fws.gov/columbiariver/publications/2011AR_Bonneville_lamprey.pdf.
- Jones, T., C. Kern, C. Mallette, and T. Rien. 2011. Lower Columbia River and Oregon Coast White Sturgeon Conservation Plan. Oregon Department of Fish and Wildlife, Ocean Salmon and Columbia River Program. 192pp.
- Keefer, M. L., C. A. Perry, M. A. Jepson, and L. C. Struhrenberg. 2004. Upstream Migration Rates of Radio-Tagged Adult Chinook Salmon in Riverine Habitats of the Columbia River Basin. *Journal of Fish Biology*. 64:1126–1141.
- Kelly, J. T., and A. P. Klimley. 2012. Relating the Swimming Movements of Green Sturgeon to the Movement of Water Currents. *Environmental Biology of Fishes* 96(2):151–167.
- Kulisch, E. 2013. Expanding the Pie for Containerized Exports. *American Shipper* 55(3):8–9.
- Lindley, S. T., M. L. Moser, D. L. Erickson, M. Belchik, D. W. Welch, E. L. Rechisky, J. T. Kelly, J. Heublein, and P. Klimley. 2008. Marine Migration of North American Green Sturgeon. *Transactions of the American Fisheries Society* 137:182–194.

- Lindley, S. T., D. L. Erickson, M. L. Moser, G. Williams, O. P. Langness, B. W. McCovey, M. Belchik, D. Vogel, W. Pinnix, J. T. Kelly, J. C. Heublein, and A. P. Klimley. 2011. Electronic Tagging of Green Sturgeon Reveals Population Structure and Movement among Estuaries. *Transactions of the American Fisheries Society* 140:108–122.
- Lord, J. 2011. Interstate 5 Columbia River Crossing—Pacific lamprey and the Columbia River Crossing Project: A white paper. 304pp.
- Mallette, C. 2014. Studies of Eulachon Smelt in Oregon and Washington. Project Completion Report Prepared by Oregon Department of Fish and Wildlife and Washington Department of Fish and Wildlife. C. Mallette (editor).
- McCabe, G. T., and C. A. Tracy. 1994. Spawning and Early Life History of White Sturgeon, *Acipenser transmontanus*, in the Lower Columbia River. Seattle, Washington. *Fisheries Bulletin* 92:760–772.
- McCabe, G.T., S.A. Hinton, R.L. Emmett. 1996. Benthic invertebrates and sediment characteristics in Wahkiakum County Ferry Channel, Washington, before and after dredging. Final Report to U.S. Army Corps of Engineers and NMFS, Seattle, WA. 32pp.
- McCabe, G.T., S.A. Hinton, R.L. Emmett, and B.P. Sanford. 1997. Benthic Invertebrates and Sediment Characteristics in Main Channel Habitats in the Lower Columbia River. Northwest Science, Volume 71, Number 1, 1997. 11pp.
- Meyers, J. R. and J. T. Corwin. 2008. Morphological Correlates of Regeneration and Repair in the Inner Ear. Pages 39–75 in R. J. Salvi, A. N. Popper, and R. R. Fay (eds.), *Springer Handbook of Auditory Research, Vol. 33: Hair Cell Regeneration, Repair, and Protection*.
- Moser, M. L. and S. T. Lindley. 2007. Use of Washington Estuaries by Subadult and Adult Green Sturgeon. *Environmental Biology of Fishes* 79:243–253.
- Moyle, P. B. 2002. Lampreys, Petromyzontidae – River Lamprey, (*Lampetra ayresii*). Pages 101–103 in *Inland Fishes of California*. Los Angeles, California: University of California Press.
- National Marine Fisheries Service. 2010. *Status Review of Eulachon (Thaleichthys pacificus) in Washington, Oregon, and California*. NOAA Technical Memorandum NMFS-NWFSC-105
- National Marine Fisheries Service. 2011. *Columbia River Estuary ESA Recovery Plan Module for Salmon and Steelhead*. NMFS Northwest Region. Portland, OR. January. Prepared for NMFS by the Lower Columbia River Estuary Partnership (contractor) and PC Trask & Associates, Inc., subcontractor. January.
- National Marine Fisheries Service. 2013. *ESA Recovery Plan for Lower Columbia River Coho Salmon, Lower Columbia River Chinook Salmon, Columbia River Chum Salmon, and Lower Columbia River Steelhead*. NMFS Northwest Region. June 2013.
- National Marine Fisheries Service. 2015. *Status of ESA Listings & Critical Habitat Designations for West Coast Salmon & Steelhead*. Updated October 31, 2012. Available: http://www.westcoast.fisheries.noaa.gov/publications/protected_species/salmon_steelhead/status_of_esa_salmon_listings_and_ch_designations_map.pdf. Accessed: March 19, 2015.
- National Oceanic and Atmospheric Administration. 2013. Datums for 9440422, Longview WA. Elevations on station datum for NOAA tide gage 9440422. Available: <http://tidesandcurrents.noaa.gov/datums.html?id=9440422>. Last revised: October 15, 2013.

- National Oceanic and Atmospheric Administration. 2014a. *West Coast Region*. Available: <http://www.westcoast.fisheries.noaa.gov/>. Accessed on April 17, 2014.
- National Oceanic and Atmospheric Administration. 2014b. *West Coast Region, Chinook Salmon*. Available: http://www.westcoast.fisheries.noaa.gov/protected_species/salmon_steelhead/salmon_and_steelhead_listings/chinook/chinook_salmon.html. Accessed on April 14, 2014.
- Parsley, M. J., L. G. Beckman, and G. T. McCabe, Jr. 1993. Spawning and Rearing Habitat Use by White Sturgeons in the Columbia River Downstream from McNary Dam. *Transactions of the American Fisheries Society* 122:217–227.
- Parsley, M. J., Popoff, N. D., & Romine, J. G. (2011). Short-term response of subadult white sturgeon to hopper dredge disposal operations. *North American Journal of Fisheries Management*, 31(1), 1–11.
- Parsley, M. J., N. D. Popoff, C. D. Wright, C. D., and B. K. van der Leeuw. 2008. Seasonal and Diel Movements of White Sturgeon in the Lower Columbia River. *Transactions of the American Fisheries Society* 137(4):1007–1017.
- Pearson, W. H., and J. R. Skalski. 2006. *Assessing Loss of Juvenile Salmon to Stranding by Ship Wakes at Three Sites along the Lower Columbia River*. Draft Report.
- Pearson, W. H., J. R. Skalski, K. L. Sobocinski, M. C. Miller, G. E. Johnson, G. D. Williams, J. A. Southard, and R. A. Buchanan. 2006. *A Study of Stranding of Juvenile Salmon by Ship Wakes along the Lower Columbia River Using a Before-and-After Design: Before-Phase Results*. Pacific Northwest National Laboratory.
- Popper, A. N. and M. C. Hastings. 2009. Review Paper: The Effects of Anthropogenic Sources of Sound on Fishes. *Journal of Fish Biology* 75:455–489.
- Popper, A. N., M. E. Smith, P. A. Cott, B. W. Hanna, A. O. MacGillivray, M. E. Austin, and D. A. Mann. 2005. Effects of Exposure to Seismic Airgun Use on Hearing of Three Fish Species. *Journal of the Acoustical Society of America* 117:3958–3971.
- Port of Longview. 2010. *Port of Longview 2010 Annual Report*.
- Pribyl, A. L., J. S. Vile, and T. A. Friesen. 2004. Population Structure, Movement, Habitat Use, and Diet of Resident Piscivorous Fishes in the Lower Willamette River. Paper #3 in T.A. Friesen (ed.), *Biology, Behavior, and Resources of Resident and Anadromous Fish in the Lower Willamette River - Final Report of Research, 2000–2004*. Prepared for the City of Portland Bureau of Environmental Services by the Oregon Department of Fish and Wildlife. March 2005.
- Redding, J. M., C. B. Schreck, and F. H. Everest. 1987. Physiological Effects on Coho Salmon and Steelhead of Exposure to Suspended Solids. *Transactions of the American Fisheries Society* 116:737–744.
- Roegner, G. C., and K. Sobocinski. 2008. Ecology of Juvenile Salmonids in Tidal Fresh and Estuarine Waters. *Proceedings to the Columbia River Estuary Conference on Ecosystem Restoration*. Astoria, OR. August.
- Roegner, G. C., R. McNatt, D. J. Teel, and D. L. Bottom. 2012. Distribution, Size, and Origin of Juvenile Chinook Salmon in Shallow-Water Habitats of the Lower Columbia River and Estuary, 2002–

2007. *Marine and Coastal Fisheries: Dynamics, Management, and Ecosystem Science* 4(1):450–472. DOI: 10.1080/19425120.2012.675982.
- Roegner, G. C., E. A. Daly, and R. D. Brodeur. 2013. Surface Distribution of Brachyuran Megalopae and Ichthyoplankton in the Columbia River Plume during Transition from Downwelling to Upwelling Conditions. *Continental Shelf Research* 60:70–86.
- Romano, M. D., M. D. Howell, and T. A. Rien. 2002. *Use of an Artificial Substrate to Capture Eulachon Eggs in the Lower Columbia River*. Draft Report by the Oregon Department of Fish and Wildlife to the U. S. Army Corps of Engineers, Portland, OR.
- Sandercock, F.K. 1991. Life history of Coho Salmon (*Oncorhynchus kisutch*). Pages 395–446 in C. Groot and L. Margolis (eds.), *Pacific Salmon Life Histories*. Vancouver, Canada: UBC Press. (Reprinted 1998.)
- Servizi, J. A., and D. W. Martens. 1992. Sublethal Responses of Coho Salmon (*Oncorhynchus kisutch*) to Suspended Sediments. *Canadian Journal of Aquatic Sciences* 49:1389–1395.
- Shreffler, D. K. and R. A. Moursund. 1999. *Impacts of Ferry Terminals on Juvenile Salmon Migrating along Puget Sound Shorelines. Phase II: Field Studies at Port Townsend Ferry Terminals*. Washington State Transportation Center, University of Washington, Seattle, WA. WA-RD 480.1.
- Silver, G. S., C. W. Luzier, and T. A. Whitesel. 2007. *Investigation of Larval Pacific Lamprey Occupancy of the Mainstem Columbia River and Willamette River*. 2007 Annual Report. U.S. Fish and Wildlife Service, Columbia River Fisheries Program Office, Vancouver, WA. Available: http://www.fws.gov/columbiariver/publications/2007_Mainstem_Lamprey_AR.pdf.
- Simenstad, C. A., B. J. Nightingale, R. M. Thom, and D. K. Shreffler, D. K. 1999. *Impacts of Ferry Terminals on Juvenile Salmon Migration along Puget Sound Shorelines, Phase I; Synthesis of State of Knowledge*. Prepared for the Washington State Transportation Commission, Research Project, 9903.
- Stadler, J. H., and D. P. Woodbury. 2009 *Assessing the Effects to Fishes from Pile Driving: Application of New Hydracoustic Criteria*. Inter-noise 2009, Ottawa, Ontario, Canada.
- Stober, Q. J., B. D. Ross, C. L. Melby, P. A. Dinnel, T. H. Jagielo, and E. O. Salo. 1981. *Effects of Suspended Sediment on Coho and Chinook Salmon in the Toutle and Cowlitz Rivers*. FRI-UW-8124, Fisheries Research Institute, University of Washington, Seattle, WA.
- Todd, V. L. G., I. B. Todd, J. C. Gardiner, E. C. N. Morrin, N. A. MacPherson, N. A. DiMarzio, and F. Thomsen. 2014. A Review of Impacts of Marine Dredging Activities on Marine Mammals. *ICES Journal of Marine Science* 72:328–340.
- Trotter, P. 1989. Coastal Cutthroat Trout: A Life History Compendium. *Transactions of the American Fisheries Society* 118:463–473.
- URS Corporation. 2014. *Millennium Coal Export Terminal Longview, Washington; Water Resource Report*. September.
- U.S. Army Corps of Engineers. 2004a. *Portland-Vancouver Harbor Information Package*. Second Edition. Portland District, Reservoir Regulation and Water Quality Section. November.

- U.S. Army Corps of Engineers. 2004b. *Biological Assessment, Columbia River Channel Operations and Maintenance, Mouth of the Columbia to Bonneville Dam*. Prepared by the U.S. Army Corps of Engineers, Portland District. September.
- U.S. Army Corps of Engineers, Dredged Material Management Office. 2010. *Memorandum for Record: Determination Regarding the Suitability of Proposed Dredged Material from Berth 1 of the Chinook Ventures Facility, Longview, Washington for Flowlane Disposal in the Columbia River*. November.
- U.S. Fish and Wildlife Service. 2002. Lower Columbia Recovery Unit, Washington. Chapter 20 in U.S. Fish and Wildlife Service, *Bull Trout (Salvelinus confluentus) Draft Recovery Plan*. Portland, OR.
- U.S. Fish and Wildlife Service. 2014. *IPaC-Information, Planning, and Conservation System*. Environmental Conservation Online System. Available: <http://ecos.fws.gov/ipac/>. Accessed: April 15, 2014.
- U.S. Geological Survey. 2007. *Coal Quality and Major, Minor, and Trace Elements in the Powder River, Green River, and Williston Basins, Wyoming and North Dakota*. Open-File Report 2007-1116. U.S. Department of the Interior, U.S. Geological Survey.
- U.S. Geological Survey. 2014. *USGS 14246900 Columbia River at Beaver Army Terminal near Quincy, OR*. Available: <http://wdr.water.usgs.gov/wy2013/pdfs/14246900.2013.pdf?1423677243767>.
- Washington Department of Fish and Wildlife. 2015a. *Priority Habitats and Species (PHS) – PHS Statewide List and Distribution by County*. Available: <http://wdfw.wa.gov/conservation/phs/list/> Accessed: January 29, 2015.
- Washington Department of Fish and Wildlife. 2015b. *Salmonscape*. Available: <http://apps.wdfw.wa.gov/salmonscape/map.html>. Accessed: January 29, 2015.
- Washington Department of Fish and Wildlife and Oregon Department of Fish and Wildlife. 2001. *Washington and Oregon Eulachon Management Plan*. November.
- Washington State Department of Ecology. 2015. Vessel Entries and Transits for Washington Waters: VEAT 2014. Ecology Publication 15-08-012. Olympia, WA.
- Washington State Department of Ecology. 2014. Washington State Proposed Draft Assessment Database – Review Tool. 303(d) /305(b) Integrated Report Viewer. Available: <http://apps.ecy.wa.gov/wats/Default.aspx>, on-line mapper: <https://fortress.wa.gov/ecy/wqamapviewer/default.aspx>. Queried December 2014
- Washington State Department of Transportation (WSDOT). 2010. Underwater Sound Levels Associated with Driving Steel Piles at the Wahkiakum County Ferry Terminal. Prepared by Jim Laughlin, Office of Air Quality and Noise, Seattle, Washington. Available at: <http://www.wsdot.wa.gov/environment/air/piledrivingreports.htm>. Accessed: September 2014.
- Washington State Department of Transportation. 2015. *Biological Assessment Preparation for Transportation Projects – Advanced Training Manual – Version 2015*. Available at: <http://www.wsdot.wa.gov/Environment/Biology/BA/BAGuidance.htm#manual>. Accessed: March 20, 2015.
- WorleyParsons. 2012. *Hydrodynamic Modeling and Sediment Transport Analysis*. Prepared for Millennium Bulk Terminals Longview, LLC.

MILLENNIUM BULK TERMINALS—LONGVIEW NEPA ENVIRONMENTAL IMPACT STATEMENT

NEPA WILDLIFE TECHNICAL REPORT

PREPARED FOR:

U.S. Army Corps of Engineers, Seattle District
4735 East Marginal Way South
Seattle, WA 98134

PREPARED BY:

ICF International
710 Second Avenue, Suite 550
Seattle, WA 98104

September 2016



ICF International. 2016. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statements, NEPA Wildlife Technical Report*. September. (ICF 00264.13.) Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.

Contents

List of Tables	iii
List of Figures.....	iii
List of Acronyms and Abbreviations.....	iv
Chapter 1 Introduction	1-1
1.1 Project Description	1-1
1.1.1 On-Site Alternative	1-1
1.1.2 Off-Site Alternative	1-4
1.1.3 No-Action Alternative	1-6
1.2 Regulatory Setting.....	1-7
1.3 Study Area.....	1-8
1.3.1 On-Site Alternative	1-8
1.3.2 Off-Site Alternative	1-10
Chapter 2 Affected Environment.....	2-1
2.1 Methods.....	2-1
2.1.1 Data Sources	2-1
2.1.2 Impact Analysis	2-2
2.2 Affected Environment.....	2-6
2.2.1 On-Site Alternative	2-6
2.2.2 Off-Site Alternative	2-19
Chapter 3 Impacts	3-1
3.1 On-Site Alternative	3-1
3.1.1 Construction: Direct Impacts	3-1
3.1.2 Construction: Indirect Impacts	3-16
3.1.3 Operations: Direct Impacts	3-16
3.1.4 Operations: Indirect Impacts	3-18
3.2 Off-Site Alternative	3-24
3.2.1 Construction: Direct Impacts	3-24
3.2.2 Construction: Indirect Impacts	3-29
3.2.3 Operations: Direct Impacts	3-29
3.2.4 Operations: Indirect Impacts	3-29
3.3 No-Action Alternative	3-29
Chapter 4 Required Permits.....	4-1
4.1 On-Site Alternative	4-1
4.2 Off-Site Alternative	4-4

Chapter 5	References	5-1
5.1	Written References.....	5-1
Appendix A	Special-Status Wildlife Species in Cowlitz County	

Tables

Table 1	Regulations, Statutes, and Guidelines for Wildlife	1-7
Table 2	Harassment Distances for Federally Listed Species in Washington State	2-5
Table 3	NMFS Underwater Sound Level Effect Thresholds for Marine Mammals.....	2-5
Table 4	Bird Species Observed at Project Area during 2013–2014 Surveys.....	2-11
Table 5	Special-Status Wildlife Species that Could Occur in the Study Area—On-Site Alternative	2-12
Table 6	Permanent Direct Impacts by Terrestrial Habitat Type in the Project Area—On-Site Alternative.....	3-3
Table 7	Underwater Sound Level Effects Thresholds and Distances to Threshold	3-8
Table 8	Permanent Direct Impacts by Terrestrial Habitat Type within the Project Area—Off-Site Alternative	3-25

Figures

Figure 1	Project Vicinity	1-2
Figure 2	On-Site Alternative	1-3
Figure 3	Off-Site Alternative	1-5
Figure 4	Direct Impact Study Area Boundaries for the On-Site Alternative	1-9
Figure 5	Indirect Impact Study Area Boundaries for the On-Site and Off-Site Alternatives	1-11
Figure 6	Study Area Boundaries for the Off-Site Alternative	1-11
Figure 7	Aquatic Habitats for the On-Site Alternative.....	2-9
Figure 8	Terrestrial Habitats in the On-Site and Off-Site Alternative Project Areas	2-21
Figure 9	Aquatic Habitats for the Off-Site Alternative.....	2-23
Figure 10	Existing Land and Vegetation Cover Types Affected during Construction	3-2
Figure 11	Level A Harassment Area for Impact Pile Driving for the On-Site Alternative.....	3-14
Figure 12	Level B Harassment Area for Impact Pile Driving for the On-Site Alternative.....	3-15
Figure 13	Existing Land and Vegetation Cover Types Affected during Construction Off-Site Alternative	3-26

Acronyms and Abbreviations

ACM	active channel margin
ADD	auditory deterrence device
Applicant	Millennium Bulk Terminals—Longview, LLC
BA	biological assessment
BMP	best management practice
BNSF	BNSF Railway Company
CDID #1	Consolidated Diking Improvement District # 1
CEQ	Council on Environmental Quality
CFR	Code of Federal Regulations
Corps	U.S. Army Corps of Engineers
CRC	Columbia River Crossing
CRD	Columbia River Datum
dB	decibel
dB _{RMS}	decibel root mean square
dB _{SEL}	decibel sound exposure level
DNR	Washington Department of Natural Resources
Ecology	Washington State Department of Ecology
ESA	Endangered Species Act
g/m ² /year	grams per square meter per year
GIS	geographic information system
Hz	Hertz
IHA	Incidental Harassment Authorization
IPaC	Information, Planning, and Conservation
kHz	kilohertz
LOA	Letter of Authorization
LVSF	Longview Switching Company
MMPA	Marine Mammal Protection Act
NEPA	National Environmental Policy Act
NMFS	National Marine Fisheries Service
PAH	polycyclic aromatic hydrocarbon
PHS	Priority Habitat and Species
RCW	Revised Code of Washington
Reynolds facility	Reynolds Metals Company facility
SEL	sound exposure level
SEPA	Washington State Environmental Policy Act
SPLs	Sound pressure levels
UP	Union Pacific
USC	United States Code
USFWS	U.S. Fish and Wildlife Service
WAC	Washington Administrative Code
WDFW	Washington Department of Fish and Wildlife
WSDOT	Washington State Department of Transportation

This technical report assesses the potential wildlife impacts of the proposed Millennium Bulk Terminals—Longview project (On-Site Alternative), Off-Site Alternative, and No-Action Alternative. For the purposes of this assessment, wildlife refers to terrestrial and aquatic wildlife species other than fish. This report describes the regulatory setting, establishes the method for assessing potential wildlife impacts, presents the historical and current wildlife conditions in the study area, and assesses potential impacts. Fish and their habitat are discussed in the NEPA Fish Technical Report (ICF International 2016a).

1.1 Project Description

Millennium Bulk Terminals—Longview, LLC (Applicant) proposes to construct and operate an export terminal in Cowlitz County, Washington, along the Columbia River (Figure 1). The export terminal would receive coal from the Powder River Basin in Montana and Wyoming and the Uinta Basin in Utah and Colorado via rail shipment, then load and transport the coal by ocean-going ships via the Columbia River and Pacific Ocean to overseas markets in Asia. The export terminal would be capable of receiving, stockpiling, blending, and loading coal by conveyor onto ships for export. Construction of the export terminal would begin in 2018. For the purpose of this analysis, it is assumed the export terminal would operate at full capacity by 2028. The following subsections present a summary of the On-Site Alternative, Off-Site Alternative, and No-Action Alternative.

1.1.1 On-Site Alternative

Under the On-Site Alternative, the Applicant would develop an export terminal on 190 acres (project area). The project area is located within an existing 540-acre area currently leased by the Applicant at the former Reynolds Metals Company facility (Reynolds facility), and land currently owned by Bonneville Power Administration. The project area is adjacent to the Columbia River in unincorporated Cowlitz County, Washington near Longview city limits (Figure 2).

The Applicant currently and separately operates at the Reynolds facility, and would continue to separately operate a bulk product terminal on land leased by the Applicant. Industrial Way (State Route 432) provides vehicular access to the Applicant's leased land. The Reynolds Lead and the BNSF Spur rail lines, both operated by Longview Switching Company (LVSW),¹ provide rail access to the Applicant's leased area from the BNSF Railway Company (BNSF) main line (Longview Junction) located to the east in Kelso, Washington. Ships access the Applicant's leased area including the bulk product terminal via the Columbia River and berth at an existing dock (Dock 1) operated by the Applicant in the Columbia River.

¹ LVSW is jointly owned by BNSF Railway Company (BNSF) and Union Pacific Railroad (UP).



Figure 1. Project Vicinity

Figure 2. On-Site Alternative

Under the On-Site Alternative, BNSF or Union Pacific Railroad (UP) trains would transport coal in rail cars from the BNSF main line at Longview Junction to the project area via the BNSF Spur and Reynolds Lead. Coal would be unloaded from rail cars, stockpiled and blended, and loaded by conveyor onto ocean-going ships at two new docks (Docks 2 and 3) on the Columbia River for export to Asia.

Once construction is complete, the export terminal would have an annual throughput capacity of up to 44 million metric tons of coal.² The export terminal would consist of one operating rail track, eight rail tracks for the storage of rail cars, rail car unloading facilities, stockpile areas for coal storage, conveyor and reclaiming facilities, two new docks in the Columbia River (Docks 2 and 3), and ship-loading facilities on the two docks. Dredging of the Columbia River would be required to provide access to and from the Columbia River navigation channel and for berthing at the two new docks.

Vehicles would access the project area from Industrial Way (State Route 432). Ships would access the project area via the Columbia River and berth at one of the two new docks. Trains would access the export terminal via the BNSF Spur and the Reynolds Lead. Terminal operations would occur 24 hours per day, 7 days per week. The export terminal would be designed for a minimum 30-year period of operation.


1.1.2 Off-Site Alternative

Under the Off-Site Alternative, the export terminal would be developed on an approximately 220-acre site adjacent to the Columbia River, located in both Longview, Washington, and unincorporated Cowlitz County, Washington, in an area commonly referred to as Barlow Point (Figure 3). The project area for the Off-Site Alternative is west and downstream of the project area for the On-Site Alternative. Most of the project area for the Off-Site Alternative is located within Longview city limits and owned by the Port of Longview. The remainder of the project area is within unincorporated Cowlitz County and privately owned.

Under the Off-Site Alternative, BNSF or UP trains would transport coal from the BNSF main line at Longview Junction over the BNSF Spur and the Reynolds Lead, which would be extended approximately 2,500 feet to the west. Coal would be unloaded from rail cars, stockpiled and blended, and loaded by conveyor onto ocean-going ships at two new docks (Docks A and B) on the Columbia River. The Off-Site Alternative would serve the same purpose as the On-Site Alternative.

Once construction is complete, the Off-Site Alternative would have an annual throughput capacity of up to 44 million metric tons of coal. The export terminal would consist of the same elements as the On-Site Alternative: one operating rail track, eight rail tracks for the storage of rail cars, rail car unloading facilities, stockpile areas for coal storage, conveyor and reclaiming facilities, two new docks in the Columbia River (Docks A and B), and ship-loading facilities on the two docks. Dredging of the Columbia River would be required to provide access to and from the Columbia River navigation channel and for berthing at the two new docks.

² A metric ton is the U.S. equivalent to a tonne per the International System of Units, or 1,000 kilograms or approximately 2,204.6 pounds.

Figure 3. Off-Site Alternative

Vehicles would access the project area via a new access road extending from Mount Solo Road (State Route 432) to the project area. Trains would access the terminal via the BNSF Spur and the extended Reynolds Lead. Ships would access the project area via the Columbia River and berth at one of the two new docks. Terminal operations would occur 24 hours per day, 7 days per week. The export terminal would be designed for a minimum 30-year period of operation.

1.1.3 No-Action Alternative

Under the No-Action Alternative, the Corps would not issue the requested Department of the Army permit under the Clean Water Act Section 404 and the Rivers and Harbors Act Section 10. This permit is necessary to allow the Applicant to construct and operate the proposed export terminal. The No-Action Alternative also includes the Applicant's expected future development of the On-Site Alternative project area, described below. This action is analyzed as part of the No-Action Alternative because it is a foreseeable consequence of a Department of the Army permit denial.

The Applicant plans to continue operating its existing bulk product terminal located adjacent to the On-Site Alternative project area, as well as expand this business. Ongoing operations would include storing and transporting alumina and small quantities of coal, and continued use of Dock 1. Maintenance of the existing bulk product terminal would continue, including maintenance dredging at Dock 1 every 2 to 3 years. Under the terms of an existing lease, expanded operations could include increased storage and upland transfer of bulk products utilizing new and existing buildings. The Applicant would likely undertake demolition, construction, and other related activities to develop expanded bulk product terminal facilities adjacent to the proposed export terminal.

In addition to the current and planned activities, if the requested permit is not issued, the Applicant would intend to expand its bulk product terminal business onto areas that would have been subject to construction and operation of the proposed export terminal. The Applicant has described a future expansion scenario that would involve handling bulk materials already permitted for off-loading at Dock 1. Additional bulk product transfer activities could involve products such as a calcine pet coke, coal tar pitch, cement, fly ash, and sand or gravel. While future expansion of the Applicant's bulk product terminal business might not be limited to this scenario, it was analyzed to help provide context to a No-Action Alternative evaluation.

1.2 Regulatory Setting

The jurisdictional authorities and corresponding regulations, statutes, and guidance for determining potential impacts on wildlife are summarized in Table 1.

Table 1. Regulations, Statutes, and Guidelines for Wildlife

Regulation, Statute, Guideline	Description
Federal	
National Environmental Policy Act (42 USC 4321 et seq.)	Requires the consideration of potential environmental effects. NEPA implementation procedures are set forth in the President's Council on Environmental Quality's Regulations for Implementing NEPA (49 CFR 1105).
U.S. Army Corps of Engineers NEPA Environmental Regulations (33 CFR 230)	Provides guidance for implementing the procedural provisions of NEPA for the Corps. It supplements CEQ regulations 40 CFR 1500–1508.
Endangered Species Act Section 7	The federal ESA provides for the conservation of threatened and endangered species and the habitat upon which they depend. ESA Section 7 requires that federal agencies initiate consultation with the USFWS and/or NMFS to ensure federal actions are not likely to jeopardize the continued existence of threatened or endangered species or result in the destruction or adverse modification of designated critical habitat.
Migratory Bird Treaty Act of 1918, as amended (16 USC 703–713)	Makes it illegal for anyone to take, possess, import, export, transport, sell, purchase, barter, or offer for sale, purchase, or barter, any migratory bird, or the parts, nests, or eggs of such a bird except under the terms of a valid permit issued pursuant to federal regulations. Under the regulatory authority of USFWS.
Bald and Golden Eagle Protection Act of 1940, as amended (16 USC 668–668c)	Prohibits the taking of bald eagles, including their parts, nests, or eggs without a permit issued by the USFWS, and provides criminal penalties for persons who "take, possess, sell, purchase, barter, offer to sell, purchase or barter, transport, export or import, at any time or any manner, any bald eagle... [or any golden eagle], alive or dead, or any part, nest, or egg thereof."
Marine Mammal Protection Act of 1972, as amended (50 CFR 216)	Protects marine mammals from "take" without appropriate authorization, which is only granted under certain circumstances. NMFS and the USFWS enforce the MMPA. Animals under the jurisdiction of NMFS could be present within the study area. An Incidental Harassment Authorization or Letter of Authorization (specific authorization to be determined) could be required pursuant to the MMPA.


Regulation, Statute, Guideline	Description
State	
Washington State Environmental Policy Act (WAC 197-11, RCW 43.21C)	Requires state and local agencies in Washington to identify potential environmental impacts that could result from governmental decisions.
Washington State Growth Management Act (RCW 36.70A)	Defines a variety of critical areas, which are designated and regulated at the local level under city and county critical areas ordinances.
Washington State Shoreline Management Act (90.58 RCW)	Requires cities and counties (through their Shoreline Master Programs) to protect shoreline natural resources.
Washington State Hydraulic Code (RCW 77.55)	Designed to protect fish life. The hydraulic project approval is administered by WDFW under the state hydraulic code.
Marinas and Terminals in Freshwater Areas (WAC 220-660-160)	Applies to constructing, maintaining, and repairing marinas and terminals in freshwater areas and provides provisions intended to address fish life concerns.
Local	
Cowlitz County SEPA Regulations (CCC Code 19.11)	Provide for the implementation of SEPA in Cowlitz County.
Cowlitz County Critical Areas Protection Ordinance (19.15)	Regulates activities within and adjacent to critical areas including fish and wildlife habitat conservation areas.
Cowlitz County Shoreline Master Program	Regulates development in the shoreline zone, including the shoreline of the Columbia River, a Shoreline of Statewide Significance.
City of Longview Shoreline Master Program (17.60) (Off-Site Alternative only)	Adopts Cowlitz County Shoreline Master Program by reference.
City of Longview Critical Areas Ordinance(17.10.140) (Off-Site Alternative only)	Regulates activities within and adjacent to critical areas and in so doing regulates fish and wildlife habitat conservation areas.
Notes: USC = United States Code; NEPA = National Environmental Policy Act; CFR = Code of Federal Regulations; Corps = U.S. Army Corps of Engineers; CEQ = Council on Environmental Quality; USFWS = U.S. Fish and Wildlife Service; NMFS = National Marine Fisheries Service; ESA = Endangered Species Act; MMPA = Marine Mammal Protection Act; WAC = Washington Administrative Code; RCW = Revised Code of Washington; WDFW = Washington Department of Fish and Wildlife; Ecology = Washington State Department of Ecology	

1.3 Study Area

The study areas for the On-Site Alternative and Off-Site Alternative are described below.

1.3.1 On-Site Alternative

The study area for the On-Site Alternative includes both terrestrial and aquatic habitats that could be affected by construction and operations (Figure 4). The study area is the same for both direct and indirect impacts.

Figure 4. Direct Impact Study Area Boundaries for the On-Site Alternative

1.3.1.1 Terrestrial Species and Habitats Study Area for Direct Impacts

The On-Site Alternative terrestrial study area for direct impacts on terrestrial species and habitats consists of the project area plus the area extending up to 0.5 mile beyond the project area (Figure 4), based on the sensitivity to visual disturbance of some wildlife species. This distance accommodates noise and visual disturbance thresholds set by the U.S. Fish and Wildlife Service (USFWS) for some sensitive species (2006).

1.3.1.2 Aquatic Species and Habitats Study Area for Direct Impacts

The aquatic study area for direct impacts on aquatic wildlife species and habitats includes the main channel of the Columbia River and extends approximately 5.1 miles upstream and 2.1 miles downstream in the Columbia River, measured respectively, from the upstream and downstream extents of the proposed docks (Docks 2 and 3) at the project area (Figure 4). The aquatic study area is based on the distances where underwater noise generated by construction or operation of the proposed terminal is estimated to reach harassment levels (Section 3.1, *Impacts*). These distances represent the in-water “line of site” distances from the ends of the dock that underwater noise could extend to.

1.3.1.3 Terrestrial and Aquatic Species and Habitats Study Area for Indirect Impacts

The study area for indirect impacts includes the project area and lands in the vicinity where project-related disturbance to wildlife and habitat could occur. The indirect study area also extends to the shipping corridor to the mouth of the Columbia River from the project area (Figure 5). This study area captures the potential impacts of increased vessel traffic on aquatic species and habitat that could occur because of increased vessel traffic in the lower Columbia River.

1.3.2 Off-Site Alternative

The study area for the Off-Site Alternative includes both terrestrial and aquatic habitats in and around the project area for the Off-Site Alternative that could be affected by construction and operations (Figure 6). The study area is the same for both direct and indirect impacts.

1.3.2.1 Terrestrial Species and Habitats Study Area for Direct Impacts

The Off-Site Alternative study area for terrestrial species includes terrestrial and aquatic habitats in and around the project area for the Off-Site Alternative that could be affected by construction and operations. The study area extends 0.5 mile beyond the project area to account for impacts related to construction noise and visual changes, as described for the On-Site Alternative.



Figure 5. Indirect Impact Study Area Boundaries for the On-Site and Off-Site Alternatives

Figure 6. Study Area Boundaries for the Off-Site Alternative

1.3.2.2 Aquatic Species and Habitat Study Area for Direct Impacts

The Off-Site Alternative study area for aquatic species includes the main channel of the Columbia River and a small section of the Fisher Island Slough side channel (between Fisher Island and Washington State mainland) in which construction noise could disturb pinnipeds. The main channel study area extends 7.1 miles upstream and 6.8 miles downstream from the extents of the proposed docks in the project area, and is defined by the following approximate boundaries (Grette Associates 2014b) (Figure 6).

- **Downstream:** near Bunker Hill (river mile 54.4) on the Washington side and near Crims Island (river mile 57.9) on the Oregon side.
- **Upstream:** near the Lewis and Clark Bridge (river mile 66.0) on the Washington side and upstream from the City of Rainier (river mile 68.7) on the Oregon side.

The aquatic study area is based on the same criteria of harassment levels mentioned above for the On-Site Alternative. The distance is greater for the Off-Site Alternative, compared to the On-Site Alternative due to the location of the docks for the Off-Site Alternative.

1.3.2.3 Terrestrial and Aquatic Species and Habitats Study Area for Indirect Impacts

The study area for indirect impacts associated with the Off-Site Alternative is the same as identified above for the On-Site Alternative.

Chapter 2

Affected Environment

This chapter describes the methods for assessing the affected environment and determining impacts, and the affected environment in the study areas for the On-Site and Off-Site Alternatives as it pertains to wildlife.

2.1 Methods

This section describes the sources of information that were used to characterize the affected environment and assess potential impacts of the proposed export terminal on wildlife and wildlife habitat.

2.1.1 Data Sources

The following data sources were used to define the affected environment relevant to wildlife and wildlife habitat and to evaluate potential impacts in the terrestrial and aquatic study areas.

- Site visits to the project area for the On-Site Alternative conducted by ICF International biologists on April 8, 2014, and December 12, 2014.
- A site visit to the Mount Solo Landfill was conducted by ICF International biologists on December 12, 2014, to view the project area for the Off-Site Alternative³ with binoculars from an elevated position. The site was also viewed with binoculars from the project area for the On-Site Alternative and from publicly accessible roads.
- Reports prepared by Grette Associates for the Applicant as part of the permit application materials.
 - *Docks 2 and 3 and Associated Trestle: Direct Effects of Construction Pile Driving and Marine Mammals* (Grette Associates 2014a).
 - *Off-Site Alternative – Barlow Point Pile Driving and Underwater Sound, Marine Mammals* (Grette Associates 2014b).
 - *Wetland and Stormwater Ditch Delineation Report – Parcel 619530400* (Grette Associates 2014c).
 - *Bulk Product Terminal Shoreline Wetland Delineation Report – Parcel 61950* (Grette Associates 2014d).
 - *Wetland and Stormwater Ditch Delineation Report – Parcel 61953* (Grette Associates 2014e).
 - *Off-Site Alternative – Barlow Point Shoreline Habitat Inventory* (Grette Associates 2014f).
 - *Bulk Product Terminal Wetland Stormwater Reconnaissance Report – Parcel 10213* (Grette Associates 2014g).
 - *Wetland Impact Report – Parcel 619530400* (Grette Associates 2014h).

³ Permission was not granted to visit the project site for the Off-Site Alternative directly.

- *Permanent Impacts to Aquatic Habitat* (Grette Associates 2014i).
- *Affected Environment Biological Resources. Technical Report* and associated appendices (Grette Associates 2014j).
- *Affected Environment Biological Resources. Addendum: Technical Memorandum: Streaked Horned Lark Surveys at Millennium Bulk Terminals* (Grette Associates 2014k).
- *Off-Site Alternative – Barlow Point Wetland Reconnaissance Report* (Grette Associates 2014l).
- *Docks 2 and 3 and Associated Trestle: Proposed Mitigation Measures to Minimize Construction and Long-Term Effects* (Grette Associates 2014m).
- *Docks 2 and 3 and Associated Trestle Direct Effects of Construction* (Grette Associates 2014n).
- *Off-Site Alternative – Barlow Point Permanent Impacts to Aquatic Habitat* (Grette Associates 2014o).
- *Affected Environment Biological Resources. Addendum: Technical Memorandum: Docks 2 and 3 and Associated Trestle Effects of Construction and Terminal Operations on Streaked Horned Larks and Columbian White-Tailed Deer* (Grette Associates 2014p).
- NMFS West Coast Region species list.
- U.S. Fish and Wildlife Service (USFWS) Information, Planning, and Conservation (IPaC) system online database (2015).
- Washington Department of Fish and Wildlife (WDFW) Priority Habitat and Species (PHS) Statewide List and Distribution for Cowlitz County.
- WDFW interactive mapping for PHS spatial data provided by WDFW on May 5, 2014, for a 5-mile radius surrounding the project areas.
- Washington Department of Natural Resources (DNR) online Herpetological Atlas spatial database (2015).
- Literature relative to threatened and endangered species.
- Comments received from interested parties during the project scoping period relative to wildlife, as summarized in the Scoping Report (February 10, 2014).

2.1.2 Impact Analysis

The impact analysis involved conducting a quantitative analysis of vegetated habitats at the project areas and a qualitative analysis of wildlife species in the study areas. For the purpose of this analysis, construction impacts are based on peak construction period and operations impacts are based on maximum throughput capacity (up to 44 million metric tons per year). For direct impacts, the analysis assumes best management practices were incorporated into the design, construction, and operations of the export terminal. More information about best management practices can be found in the Draft Environmental Impact Statement (Volume I), Chapter 8, *Minimization and Mitigation* and Appendix H, *Export Terminal Design Features*.

The following methods were used to evaluate the potential impacts of the On-Site Alternative, Off-Site Alternative, and No-Action Alternative.

2.1.2.1 Vegetated Habitats

Direct impacts on habitat are based on the method outlined in the NEPA Vegetation Technical Report (ICF International 2016c). Vegetation communities were identified, characterized, and mapped for both project areas using recent and historic aerial photographs and the information gathered from the references cited in Section 2.1.1, *Impact Analysis*, of the NEPA Vegetation Technical Report. Mapped plant communities in the majority of the project area for the On-Site Alternative were ground-truthed by ICF biologists during the December 12, 2014 site visit. The vegetation types present in the project area for the Off-Site Alternative were also verified for the On-Site Alternative by observing the project area, Mount Solo Landfill, and public roads through binoculars. Visual observations of the vegetation in the study area on adjacent, off-site areas and along Industrial Way, Mt. Solo Road, and Memorial Park Drive were also documented during this site visit.

Once verified, vegetation communities were mapped on a recent aerial photograph using geographic information system (GIS) and overlain with the on- and off-site wetland boundaries delineated by Grette Associates (2014c, d, e, f, g). Direct impacts on vegetation from the clearing of land to construct the buildings and infrastructure of the On-Site Alternative and Off-Site Alternative were determined by overlaying the export terminal footprints on the vegetation maps using GIS. All vegetated areas that fell within the footprint were considered direct impacts.

2.1.2.2 Wildlife Species

Potential impacts on wildlife species were determined by considering species that are likely to occur in the study area based on field surveys, site visits, the presence of suitable habitat and geographic range, and documented species occurrences. For documented occurrences, the focus was on wildlife species identified in the WDFW Priority Habitat Species (PHS) database. The PHS program provides comprehensive information on important fish, wildlife, and habitat resources in Washington. It is the principal means by which WDFW provides wildlife and habitat information to public and private entities for planning purposes. In addition, the USFWS list of federally listed species in Cowlitz County and the NMFS West Coast Region species list of marine mammals (most of which are also included in the PHS database) were also considered.

WDFW maintains a PHS geospatial database that maps locations of priority species occurrences and priority habitats. Priority species in the PHS program include wildlife species classified under state law (Washington Administrative Code [WAC] 232-12-297) as threatened, endangered, or sensitive, as well as species that are candidates for such classification. Other PHS species include vulnerable aggregations of species or groups of animals that are susceptible to significant population declines due to their inclination to aggregate, and species of recreational, commercial, or tribal importance. The PHS database also includes state-monitored species, which are not considered special-status, but are monitored for status and distribution trends. Geospatial PHS data containing mapped locations of priority species occurrences and priority habitats were obtained from WDFW (Washington Department of Fish and Wildlife 2014).

These data were overlaid with the study area to determine presence of documented priority species and habitat occurrences.

- A list of special-status wildlife species was compiled for the study area, consisting of those species federally listed as threatened, endangered, proposed, or candidate species; wildlife species listed in the WDFW PHS database; and marine mammals.

- A list of federally listed wildlife species for Cowlitz County was generated from the USFWS iPAC online planning tool (U.S. Fish and Wildlife Service 2015).
- A list of state priority species that occur in Cowlitz County was obtained from the WDFW PHS program website (Washington Department of Fish and Wildlife 2013).
- A list of federally protected marine mammals that could occur in the study area was compiled from the NMFS (2015) West Coast Region website.

The impact analysis for wildlife habitat is quantitative; however, the impact analysis for wildlife species is qualitative because wildlife species are generally mobile and their presence in the study area cannot be predicted at any one location or time. In addition, a species' reaction to an impact mechanism, such as construction-generated noise, can be different for each species given the variability in species' hearing frequencies, mobility, vision, and overall sensitivity (e.g., juveniles could be more sensitive and susceptible to potential impacts than older animals). Therefore, impact mechanisms are identified and a qualitative impact discussion describes the potential effect an impact mechanism could have on species that could be in the study area during construction and operations.

2.1.2.3 Assessing Noise Impacts

An animal's response to sound depends on various factors, including noise level and frequency, distance and event duration, equipment type and conditions, frequency of noisy events over time, slope, topography, weather conditions, previous exposure to similar noises, hearing sensitivity, reproductive status, time of day, behavior during the noise event, and an animal's location relative to the noise source (Delaney and Grubb 2003 in Washington State Department of Transportation 2015). However, USFWS has established noise and visual distance thresholds for some sensitive species in Washington, including the bald eagle (*Haliaeetus leucocephalus*), marbled murrelet (*Brachyramphus marmoratus*), northern spotted owl (*Strix occidentalis caurina*), and Columbia white-tailed deer (*Odocoileus virginianus leucurus*) (U.S. Fish and Wildlife Service 2006).

USFWS has determined the distances presented in Table 2 as the point at which these species would likely experience harassment⁴ from specific construction activities. Of these four sensitive species, the bald eagle can experience harassment from visual impacts at 0.5 mile from a construction site, the greatest distance of potential harassment of the four species. The remaining three species can experience harassment through either visual or noise disturbance at lesser distances (including distances for impact pile driving) than the 0.5-mile bald eagle harassment distance (Table 2). Therefore, the terrestrial study area for the On-Site Alternative extends 0.5 mile beyond the project area. Even though this distance is based on the bald eagle's sensitivities to noise and visual impacts, it is a reasonable proxy to use for terrestrial wildlife species in the absence of similar information for other wildlife species.

⁴ *Harassment* under the Endangered Species Act is defined as actions that create the likelihood of injury to such an extent as to significantly disrupt normal behavior patterns, which include but are not limited to, breeding, feeding, or sheltering [50 CFR 17.3].

Table 2. Harassment Distances for Federally Listed Species in Washington State

Species	Scientific Name	Activity and Harassment Distance
Bald eagle	<i>Haliaeetus leucocephalus</i>	Noise: 0.25 mile ^a Visual: 0.5 mile ^b
Marbled murrelet	<i>Brachyramphus marmoratus</i>	Pile driving: 180 feet ^c Visual: 300 feet
Northern spotted owl	<i>Strix occidentalis caurina</i>	Pile driving: 180 feet
Columbia white tailed deer	<i>Odocoileus virginianus leucurus</i>	Noise: 0.25 mile

Notes:

^a Noise level disturbance varies for bald eagles. It has been found that visual disturbance is more likely to provoke escape behavior than noise disturbance (U.S. Department of Transportation 2004).

^b Visual disturbance can be caused by close visual proximity of human activities at sensitive locations (i.e., nest trees), and could result in significant disruption of normal behavior patterns.

^c Injury would occur at 202 decibels at this distance (Washington State Department of Transportation 2015). Source: U.S. Fish and Wildlife Service 2006.

NMFS has established standard underwater noise thresholds under the Marine Mammals Protection Act. NMFS has established Levels A and B harassment thresholds for pinnipeds (i.e., seals and sea lions) from impact and vibratory pile driving (Grette Associates 2014a) (Table 3).

Table 3. NMFS Underwater Sound Level Effect Thresholds for Marine Mammals

Effect Type	Effect Threshold (dB _{RMS})
Impulse Sound (Impact Driver Operation)	
Level A harassment	190
Level B harassment	160
Continuous Sound (Vibratory Driver Operation)	
Level B harassment	120

Notes:

Source: Grette Associates 2014a

dB_{RMS} = decibel root mean square

Pinniped harassment can occur between approximately 178 feet and the extent of the aquatic study area for direct impacts, from the noise source without attenuation, depending on the method of pile driving. Use of a bubble curtain during impact pile driving decreases the distance at which pinniped harassment can occur to between 45 feet and 4,459 feet. Harassment can include hearing-related injuries and behavior changes. These criteria were used to establish pinniped impact thresholds in the aquatic wildlife study area.

For diving birds, USFWS has established impact thresholds for the federally listed marbled murrelet (Table 2), which can provide some guidance on underwater noise thresholds for other diving birds in the aquatic study area. The USFWS recognizes a behavioral guideline of 150 decibels root mean square (dB_{RMS}), an injurious auditory threshold of 202 sound exposure level (dB_{SEL}) (i.e., permanent threshold shift in hearing due to permanent loss of cochlear hair cells), and a non-auditory injury (i.e., barotrauma) threshold of 208 dB_{SEL}; underwater noise below 150 dB_{SEL} does not cause injury (Washington State Department of Transportation 2015). These criteria were used to establish impact thresholds for diving birds in the aquatic study area.

2.2 Affected Environment

The affected environment related to wildlife in the study area is described below.

2.2.1 On-Site Alternative

The project area for the On-Site Alternative is located along the north side of the Columbia River at river mile 63, within unincorporated Cowlitz County and adjacent to the City of Longview.

2.2.1.1 Terrestrial Habitat

Terrestrial habitats in the study area are characterized by their main land cover classification and dominant form of vegetation and are described in detail in the NEPA Vegetation Technical Report (ICF International 2016c). Habitat types present in the study area include developed (disturbed), upland (forested, scrub-shrub, herbaceous, and managed herbaceous), wetland (forested, scrub-shrub, herbaceous, managed herbaceous, and disturbed), and riparian (forested, scrub-shrub, and herbaceous).

Developed land includes areas where the majority of vegetation has been removed and replaced with pavement, buildings, or infrastructure associated with existing and historical industrial, agricultural, and recreational uses. Occasionally, scattered vegetation is present and typically consists of nonnative grasses, forbs, and shrubs. There is one vegetation type, disturbed, categorized in the developed areas.

Uplands include areas landward of the Columbia River levee with undeveloped vegetated areas that do not exhibit wetland characteristics. Vegetation within the uplands is categorized as forested, scrub-shrub, herbaceous, and managed herbaceous.

Wetlands include areas that exhibit the diagnostic wetland characteristics required by state and federal wetland delineation manuals (hydrophytic vegetation, hydric soils, and wetland hydrology). Wetland mapping and classifications were taken directly from the wetland delineation and determination work completed for the project areas by Grette Associates (2014c, d, e, f, g). Vegetation in the wetlands is categorized as forested, scrub-shrub, herbaceous, managed herbaceous, and disturbed.

Riparian lands include the areas along the shoreline of the Columbia River between the ordinary high water mark and the top of the Columbia River levee. Vegetation is categorized as forested, scrub-shrub, and herbaceous.

Project Area

The project area for the On-Site Alternative is located on a disturbed industrial site developed with roads and industrial buildings. Many of the surrounding areas are also highly disturbed. Of the undeveloped areas on the project area, many are small and fragmented from other similar habitat patches. The largest, contiguous areas of habitat are located on the west side of the project area and include an herbaceous wetland dominated by reed canarygrass and a forested wetland dominated by deciduous trees with an understory of shrubs and reed canarygrass. The highest quality habitat on the project area is a small forested area surrounding parallel drainage ditches, located in the southwest portion of the site. The habitat is characterized by deciduous trees along the banks of the ditches and abundant understory vegetation. In general, suitable wildlife habitat on the project area

is degraded because of past industrial uses on the property. The patches of suitable habitat support foraging and cover for small to large mammals, foraging and nesting for birds, including waterfowl, raptors, and passerine birds, and foraging, breeding, and nesting for amphibians (Grette Associates 2014c, d, e, h). However, these areas are limited in their habitat value due to their relatively small size and fragmented condition.

Study Area

The terrestrial study area for the On-Site Alternative includes land both up- and down-stream of the project area, land north of Industrial Way, a strip of land between the project area and Columbia River, and a small portion of Lord Island (Figure 4). Upstream land is predominantly disturbed with heavy industrial development and wildlife is not present due to the lack of suitable habitat.

The downstream portion of the terrestrial study area overlaps with the terrestrial study area for the Off-Site Alternative. Predominant habitat types include disturbed areas, herbaceous and managed herbaceous upland habitats, herbaceous and managed herbaceous wetland habitats, and scrub-shrub or forested riparian habitat. Habitat support for wildlife is similar to that described for the project area and includes foraging and cover for small to large mammals, foraging and nesting for waterfowl, raptors, and passerine birds, and foraging, breeding, and nesting for amphibians.

North of Industrial Way, the landscape can be generally separated into three similar habitat areas that are separated by Consolidated Diking Improvement District #1 (CDID #1) drainage ditches (Figure 4). To the northwest is Mount Solo, a forested ridge that is covered with a large area of contiguous native forest intermixed with rural residential areas and some light industrial uses. Smaller areas of scrub-shrub and managed herbaceous habitats are interspersed with the developed areas. Mount Solo is the largest contiguous forested upland habitat within 2 miles of the project area, and as such, is likely to support a greater diversity of wildlife—including small to large mammals, bird species (passerine, raptor, and owl), lizards, and snakes—than habitats on the project area.

Adjacent to the project area is a triangular area bounded by Industrial Way to the south and CDID drainage ditches to the east and west. This area primarily contains herbaceous wetland habitat dominated by reed canarygrass. Other habitats, including forested and scrub-shrub wetlands and uplands (forested, scrub-shrub, and herbaceous) are small and isolated from other similar habitat types. A small portion of the site is disturbed. The habitat likely supports foraging and cover for small to large mammals; foraging and nesting for waterfowl, raptors, and passerine birds; and foraging, breeding, and refuge for amphibians and reptiles. Land to the east is largely disturbed by the Mint Farm Industrial Park, with few small areas of herbaceous or scrub-shrub habitat.

South of the project area, the terrestrial study area consists of a levee with managed herbaceous vegetation and riparian shoreline bordering the Columbia River. The riparian area is primarily forested and scrub-shrub habitat and likely provides foraging and cover for small and large mammals, foraging and nesting for passerine, waterfowl and raptor bird species, and foraging, breeding, and refuge for amphibians (Grette Associates 2014d).

A small portion of Lord Island is located in the terrestrial study area and is approximately 0.5 mile south of the project area. The island is located within the Columbia River and was previously used for dredged material disposal. Lord Island is primarily forested and connects to Walker Island downstream, by a narrow band of sand. An embayment between the two islands contains a tidal marsh and shallows. This area provides foraging and resting habitat for waterfowl and has been

previously documented as supporting significant numbers of wintering ducks and geese (Pacific Coast Joint Venture 1994). With the exception of several transmission towers, the island is undeveloped and contains wildlife habitat. Lord Island could support Columbian white tailed deer; however, no occurrences have been documented on the island (Washington Department of Fish and Wildlife 2014). Additional wildlife species supported by Lord Island include small mammals, birds (raptors and passerine), amphibians, and reptiles.

2.2.1.2 Aquatic Habitat

Aquatic habitats in the aquatic study area include wetlands (refer to Section 5.3, *Wetlands*, in the Draft EIS for more information), the Columbia River, and smaller areas of open water within the study area, including various ditches and a pond created on the project area by the excavation of dredged materials in 2006. Ditches in the aquatic study area include those maintained by CDID and privately owned stormwater ditches.

Habitat types in the Columbia River include the deepwater zone (deeper than -20 feet Columbia River Datum [CRD]), shallow water zone (0 to -20 feet CRD), and the active channel margin (ACM) (0 to +11.1 feet CRD) (Grette Associates 2014i).

The ACM includes the shoreline and nearshore edge habitat extending waterward from the ordinary high water mark out to a depth of 11.1 feet, based on an Ordinary High Water (OHW) of +11.1 feet Columbia River Datum (CRD).⁵ In general, the shoreline adjacent to the aquatic study area is sparsely vegetated and consists of sandy substrate with little organic matter (Grette Associates 2014j). The shoreline is highly modified by extensive dikes and riprap armoring with scattered large woody debris, bordered by the riparian zone.

The bottom structure of the shallow water zone consists primarily (90%) of flat or shallow sloping substrate, with some moderate slopes out to depths of about 20 feet where the habitat becomes markedly steeper. There are two pile dikes and one overwater dock that extend into the shallow water zone (Figure 7). The substrates in the study area consist primarily of silty river sand with little organic matter. Little to no aquatic vegetation is expected in the shallow water zone, however, sparse vegetation could exist in the upper elevations where light could penetrate, and flow is reduced. Conditions in the shallow-water portion of the in-water footprint are narrow and more steeply sloped and are, therefore, unlikely to support aquatic vegetation (Grette Associates 2014j).

Benthic habitats in the deepwater portion of the aquatic study area are subjected to strong currents and reduced light penetration due to depth. Aquatic vegetation is not expected to occur in deepwater habitats and these areas are generally associated with low productivity.

Aquatic habitats of the Columbia River support pinnipeds, fish, birds, and a variety of invertebrates, many of which serve as forage for fish and bird species. Fish are discussed in the NEPA Fish Technical Report (ICF International 2016a). Smaller freshwater areas in the aquatic study area, such as ponds and ditches, could support common species of invertebrates and amphibians and could be used by small mammals and birds.

⁵ Columbia River Datum (CRD) is a vertical datum that is the adopted fixed low water reference plane for the lower Columbia River. It is the plane of reference from which river stage is measured on the Columbia River from the lower Columbia River up to Bonneville Dam, and on the Willamette River up to Willamette Falls.

Figure 7. Aquatic Habitats for the On-Site Alternative

2.2.1.3 Wildlife

Wildlife includes terrestrial and marine mammals, birds, reptiles, amphibians, and invertebrates, including species that are currently protected or proposed for protection under the federal Endangered Species Act (ESA) or other federal and state regulations. Fish are discussed in the NEPA Fish Technical Report (ICF International 2016a).

Based on the data sources described in Section 2.1.1, *Impact Analysis*, wildlife likely to be found in both the terrestrial and aquatic study areas include common species of birds (waterfowl, raptors, shorebirds, marine birds, and passerine birds), rodents, frogs, salamanders, snakes, lizards, and invertebrates. Larger and highly mobile species of mammals that are habituated to disturbed environments could also be present in the study area, including coyote (*Canis latrans*), raccoon (*Procyon lotor*), striped skunk (*Mephitis mephitis*) and deer (*Odocoileus* sp.).

During the December site visit, two Columbian black-tailed deer (*Odocoileus hemionus columbianus*) were observed in the forested wetland area (Wetland A) at the northwest portion of project area, and two nutrias (*Myocastor coypus*) were observed on the sloped bank of the CDID Ditch 10, on the north side of Industrial Way. Other signs of mammal presence were observed during both site visits, including several unidentified small mammal scats, a coyote scat along the dike road, a beaver (*Castor canadensis*)-chewed tree in the riparian habitat along the Columbia River, and an unidentified species of sea lion heard barking from the Columbia River.

Several common bird species were recorded in the terrestrial study area during the site visits, including red-winged blackbird (*Agelaius phoeniceus*), sparrows (*sp.*), robins (*Turdus migratorius*) and other songbirds, American coot (*Fulica Americana*), bufflehead (*Bucephala albeola*), mallards (*Anas platyrhynchos*) and other unidentified ducks, Canada geese (*Branta Canadensis*), cormorants (*sp.*), scaup (*sp.*), gulls (*sp.*), and great blue heron (*Ardea herodias*). A turkey vulture (*Cathartes aura*), red-tailed hawk, kestrel (*Falco sparverius*), and bald eagle (*Haliaeetus leucocephalus*) were observed flying overhead. A small flock of Canada geese were also observed grazing on wetland grasses at the project area, and several unoccupied raptor nests were also observed in the forested habitat adjacent to the stormwater ditches on the southwest side of the project area and on an electrical tower near the west side of the dike road.

Grette Associates biologists conducted surveys for the federally threatened and state endangered streaked horned lark in the project area during the 2013 (July 12, 2013) and 2014 breeding season (May 15, June 11, and July 10, 2014). The focus of these surveys was to detect the presence of streaked horned lark; however, other bird species were recorded during the surveys (Table 4). A few of the bird species recorded during these surveys are also special-status species, which are addressed in more detail in Section 2.2.1.4, *Special-Status Wildlife Species*. Surveys were conducted in all areas of suitable streaked horned lark breeding habitat on the west side of the project area and immediately adjacent land (Grette Associates 2014k). Streaked horned lark are discussed further in Section 2.2.1.1, *Terrestrial Habitat*.

Table 4. Bird Species Observed at Project Area during 2013–2014 Surveys

Common Name	Scientific Name
Osprey	<i>Pandion haliaetus</i>
Red-tailed hawk	<i>Buteo jamaicensis</i>
Bald eagle	<i>Haliaeetus leucocephalus</i>
Northern harrier	<i>Circus cyaneus</i>
Great blue heron	<i>Ardea Herodias</i>
Canada goose	<i>Branta Canadensis</i>
Mallard	<i>Anas platyrhynchos</i>
Turkey vulture	<i>Cathartes aura</i>
Killdeer	<i>Charadrius vociferous</i>
Sandpiper	Scolopacidae
Common raven	<i>Corvus corax</i>
American crow	<i>Corvus brachyrhynchos</i>
Brewer's blackbird	<i>Euphagus cyanocephalus</i>
Red-winged blackbird	<i>Agelaius phoeniceus</i>
American robin	<i>Turdus migratorius</i>
European starling	<i>Sturnus vulgaris</i>
Lesser goldfinch	<i>Carduelis psaltria</i>
American goldfinch	<i>Spinus tristis</i>
Common yellowthroat	<i>Geothlypis trichas</i>
White-crowned sparrow	<i>Zonotrichia leucocephalus</i>
Savannah sparrow	<i>Passerculus sandwichensis</i>
Vesper sparrow	<i>Poocetes gramineus</i>
Song sparrow	<i>Melospiza melodia</i>
Mourning dove	<i>Zenaida macroura</i>
Rock dove	<i>Columba livia</i>
Barn swallow	<i>Hirundo rustica</i>
Violet-green swallow	<i>Tachycineta thalassina</i>
Tree swallow	<i>Tachycineta bicolor</i>
Cliff swallow	<i>Petrochelidon pyrrhonota</i>
Western bluebird	<i>Sialia Mexicana</i>
Swainson's thrush	<i>Catharus ustulatus</i>
Purple martin	<i>Progne subis</i>
Black phoebe	<i>Sayornis nigricans</i>
Notes:	
Source: Grette Associates 2014j, k	

Wildlife likely to be found only in aquatic habitats include three species of pinnipeds, which could be present in the aquatic study area within the Columbia River: harbor seal (*Phoca vitulina*), California sea lion (*Zalophus californianus*), and Steller sea lion (*Eumetopias jubatus*) (Jeffries et al. 2000). Because these marine mammals are all protected under the Marine Mammal Protection Act, they are described in more detail in Section 2.2.1.4, *Special-Status Wildlife Species*. Various bird species, including waterfowl, raptors, and shorebirds are supported by the Columbia River's aquatic habitats

in the aquatic study area, as well as numerous fish species. Freshwater insects and other invertebrate species (e.g., mollusks, crayfish) inhabit the upper layers of the benthos and provide forage for many species of fish and birds. Fish and their habitats, are discussed in the NEPA Fish Technical Report (ICF International 2016a).

2.2.1.4 Special-Status Wildlife Species

Special-status wildlife species are those listed as threatened, endangered, proposed for listing, or candidate species under the ESA or listed as a WDFW priority species.

Table 5 provides a list of special-status wildlife species that are likely to occur in the terrestrial or aquatic study areas. Some of the PHS listings are not for individuals of a species (PHS Criteria 1) but for vulnerable aggregations (PHS Criteria 2) of individuals, such as Western Washington nonbreeding concentrations. The likelihood of each species or vulnerable aggregation occurring in the terrestrial or aquatic study areas is listed as either *Yes* (known to occur), *Possibly* (likely to occur due to presence of suitable habitat but not documented), or *Unlikely* (individuals could occur in the study area but vulnerable aggregations are not documented in the PHS database) (Washington Department of Fish and Wildlife 2014). A complete list of all special status species that could occur in Cowlitz County is located in Appendix A, *Special-Status Wildlife Species in Cowlitz County*, including species that do not occur or are unlikely to occur in the terrestrial or aquatic study areas.

Table 5. Special-Status Wildlife Species that Could Occur in the Study Area—On-Site Alternative

Wildlife Species	Potential for Occurrence ^a	Potential Habitat	State Priority Species Criteria ^b	Federal Status ^c	State Status ^d
Mammals					
Columbian black-tailed deer (<i>Odocoileus hemionus columbianus</i>)	Yes	Species documented on project area. Limited habitat on project area. May use forested portions of terrestrial study area.	3	N/A	N/A
Columbian white-tailed deer (<i>Odocoileus virginianus leucurus</i>)	Yes	Species documented on project area. ^e Limited forage and cover on project area. Suitable habitat available on Lord Island.	1	E	E
Harbor seal (<i>Phoca vitulina</i>)	Yes	Present in Columbia River	2	N/A	N/A
California sea lion (<i>Zalophus californianus</i>)	Yes	Present in Columbia River	2	N/A	N/A
Stellar Sea lion (<i>Eumetopias jubatus</i>)	Yes	Present in Columbia River	1, 2	SC	T

Wildlife Species	Potential for Occurrence ^a	Potential Habitat	State Priority Species Criteria ^b	Federal Status ^c	State Status ^d
Birds					
Streaked horned lark (<i>Eremophila alpestris strigata</i>)	Possibly	Not documented during surveys on project area. Potential suitable habitat on Lord Island.	1	T	E
Bald eagle (<i>Haliaeetus leucocephalus</i>)	Yes	Forested wetlands could provide roosting habitat. Suitable habitat on Lord Island.	1	SC	S
Peregrine falcon (<i>Falco peregrinus</i>)	Possibly	Potential foraging habitat	1	SC	S
Barrows Goldeneye (<i>Bucephala islandica</i>)	Possibly (Nonbreeding Concentrations Unlikely)	Open water	2, 3	N/A	N/A
Common Goldeneye (<i>Bucephala clangula</i>)	Possibly (Nonbreeding concentrations Unlikely ^f)	Open water	2, 3	N/A	N/A
Bufflehead (<i>Bucephala albeola</i>)	Yes (Nonbreeding Concentrations Unlikely ^f)	Open water	2, 3	N/A	N/A
Waterfowl concentrations	Yes	Suitable habitat documented in terrestrial and aquatic study areas.	2, 3	N/A	N/A
Vaux's swift (<i>Chaetura vauxi</i>)	Possibly	No large snags for nesting or roosting identified on project area but possible in terrestrial study area.	1	N/A	C
Pileated woodpecker (<i>Dryocopus pileatus</i>)	Possibly	Possible in forested habitat.	1	N/A	C
Purple martin (<i>Progne subis</i>)	Yes	Species documented in terrestrial study area, possible foraging habitat.	1	N/A	C

Notes:

^a The likelihood of each species or vulnerable aggregations occurring in the terrestrial and aquatic study areas is listed as follows (Washington Department of Fish and Wildlife 2013).

- Yes (known to occur)
- Possibly (likely to occur due to presence of suitable habitat, but not documented)
- Unlikely (individuals may occur in the terrestrial or aquatic study areas but vulnerable aggregations are not documented in the PHS database).

^b State PHS Species Criteria: 1 – State-listed or candidate species; 2 – Vulnerable aggregation; 3 – commercial, recreational, or tribal importance

^c Federal Status under the U.S. Endangered Species Act: E = Endangered; T = Threatened; SC = Species of Concern

^d State Status: E = Endangered; T = Threatened; C = Candidate; S = Sensitive

^e Grette Associates 2014j

^f Western Washington Nonbreeding Concentrations

^g Willapa Hills Audubon Society 2014

Terrestrial Mammals

Columbian White-tailed Deer (*Odocoileus virginianus leucurus*)

The Columbia River population of the Columbian white-tailed deer is a federal and state listed endangered species. The Columbia River population is one of only two extant populations in the United States (i.e., the lower Columbia River population and the Douglas County population). The lower Columbia River population occurs in Wahkiakum and Cowlitz Counties, Washington, and Clatsop and Columbia Counties, Oregon. The other, in Douglas County Oregon, was delisted by USFWS in 2003, when population recovery goals were attained. The Columbia River population inhabits the Lower Columbia River floodplain and islands within the river channel. The current range of the Columbian white-tailed deer overlaps with the study area, including Barlow Point and Fisher, Walker, and Lord Islands (Washington Department of Fish and Wildlife 2013). The current population is estimated at 582 deer (Washington Department of Fish and Wildlife 2013).

WDFW has identified specific locations along the Columbia River for recovery (Washington Department of Fish and Wildlife 2013) based on the availability of secure habitat. The nearest recovery location to the study area is the upper estuary islands downstream of Longview (Figure 4), which includes Fisher, Hump, Lord, and Walker Islands (Washington Department of Fish and Wildlife 2013). Lord Island is approximately 0.5 mile from the project area and is visible from and directly across the Columbia River channel. Although 66 individuals have been translocated to these islands to date, WDFW estimates the population on these four islands totals only 10 deer (Washington Department of Fish and Wildlife 2013).

Historically, the Columbia River population has inhabited the river bottomlands, where riparian habitat dominated by Sitka spruce, alder, cottonwood, and willow provided a desirable mix of cover and forage (U.S. Fish and Wildlife Service 1983). The Columbia River floodplain has been drastically altered from historic times, with diking, road building, and conversion of forestlands to pasturelands among the most prominent changes. Although deer will forage in maintained pastures (U.S. Fish and Wildlife Service 1983), studies on the Julia Butler Hanson National Wildlife Refuge in the 1970s show that deer preferred to forage where vegetation was over 70 centimeters high and rarely foraged greater than 250 meters from woodland cover (U.S. Fish and Wildlife Service 1983).

Because of its proximity to the upper estuary islands and Barlow Point, portions of the study area could be occupied by the upper estuary islands subpopulation of Columbia River Columbian white-tailed deer. On the project area, cover habitat is limited to the forested wetland in the northwest portion of the site. Industrial Way separates this forested patch from other cover habitat within the study area located further north. Most of the “forage” habitat on the project area and within the study area consists of managed herbaceous habitat, where mowed grasses are less than 70 centimeters high. In spite of this, Columbia white-tailed deer have been observed on the project area (Grette Associates 2014j). While the project area does not provide optimal habitat conditions, the presence of white-tailed deer on the site has been documented. Occurrences within the study area have been documented in the PHS database (Washington Department of Fish and Wildlife 2014).

Columbian Black-tailed Deer (*Odocoileus hemionus columbianus*)

Unlike the endangered Columbian white-tailed deer that inhabit the river bottoms, black-tailed deer use upland slopes and closed-canopy coniferous forests. They require a mix of forest and openings for cover and forage, and browse on common shrubs and trees such as vine maple, red alder, and serviceberry (Washington Department of Fish and Wildlife 2014). Columbian black-tailed deer have

been observed on the project area. The high level of human activity on the site, lack of well-distributed cover and forage areas, and general lack of preferred habitat (coniferous forest with brushy openings), indicate that the site could be used for travel, migration, and resting, but is not suitable for supporting a black-tailed deer population. The nearest black-tailed deer population documented by WDFW (as cited in Grette Associates 2014j) is 10 miles from the project area.

Birds

Streaked Horned Lark (*Eremophila alpestris strigata*)

The streaked horned lark is a federally threatened and state endangered species. The Pacific Northwest subspecies was once widespread throughout western Washington, Oregon, and British Columbia. Due primarily to habitat loss, this subspecies now breeds and winters over a fraction of its former range. USFWS estimated the overall population of streaked horned larks between 1,170 and 1,610 individuals, and listed the species as threatened on October 3, 2013 (U.S. Fish and Wildlife Service 2012, 2013).

The breeding range for this species historically ranged from southern British Columbia south through the Puget lowlands; Washington Coast; Lower Columbia River, Willamette, Rogue and Umpqua River valleys; and the Oregon Coast (U.S. Fish and Wildlife Service 2012). It has been eliminated as a breeding species from at least half of that range and is no longer found in southern British Columbia, the San Juan Islands, the northern Puget Trough, the Washington coast north of Grays Harbor, the Oregon coast, and the Rogue and Umpqua River valleys in Oregon (Pearson and Altman 2005; U.S. Fish and Wildlife Service 2012).

Historic breeding range consisted primarily of prairie and open coastal habitats (Pearson and Altman 2005). Over the past 150 years, prairie lands in Washington and Oregon have declined by 90% to 95% (U.S. Fish and Wildlife Service 2012). Streaked horned larks are now found nesting in both traditional and some nontraditional habitats, including agricultural fields, wetland mudflats, Christmas tree farms, gravel roads, airports, and dredge deposition sites in the Lower Columbia River (U.S. Fish and Wildlife Service 2012; Pearson and Altman 2005). Active establishment of territories and breeding occurs from late March until early August. During this time, streaked horned larks are susceptible to human activities that can jeopardize successful nesting. Human activities can disturb larks by causing them to become alert, fly, or directly destroy their nests. These activities include moving vehicles, gatherings of people and/or vehicles, fireworks, dog walking, flying model airplanes, construction activities, and mowing. Disruptive activities that keep larks away from their nests for more than one hour could result in nest abandonment. In general, activities occurring within approximately 100 feet (30 meters) are more likely to cause larks to flush than activities located farther away (Pearson and Altman 2005).

Streaked horned larks prefer wide-open spaces characterized by flat, treeless landscapes of 300 acres or more, sparse grass/forb vegetation, and few or no shrubs. They will use smaller habitat patches if there is an adjacent open landscape, such as agricultural fields or water (U.S. Fish and Wildlife Service 2012). In the Lower Columbia River, they were historically known to nest on sandy beaches and spits. Now, they can be found nesting on dredge spoil depositions, which provide the open expanses of bare ground preferred by this species. At the project area and in the study area, a few small areas containing potentially suitable habitat (low vegetative cover and no woody vegetation) are adjacent to the Columbia River: near the closed Reynolds landfill and along the edges

of roadbeds. These areas are regularly disturbed by maintenance (mowing) and operations (Grette Associates 2014j, k).

Adult streaked horned larks feed mainly on grass and weed seeds, but could feed insects to their young (U.S. Fish and Wildlife Service 2012). They typically establish nests in areas of extensive bare ground next to a clump of bunchgrass (U.S. Fish and Wildlife Service 2012). Habitat within the study area contains extensive areas of short (mowed) grass and forb vegetation, but relatively little bare ground and even less undisturbed vegetation as most of the grass/forb areas are maintained by mowing.

Critical habitat has been designated for the streaked horn lark, but none of these designated areas are in the terrestrial study area. All critical habitat areas within the Lower Columbia River are located downstream from the study area, with the exception of one area. The closest designated critical habitat is on Crims Island, approximately 5 miles downstream of the direct impact terrestrial study area for the On-Site Alternative. The only critical habitat upstream of the study area is on Sandy Island, Columbia County, Oregon at river mile 76, approximately 13 miles upriver of the direct impact terrestrial study area for the On-Site Alternative (U.S. Fish and Wildlife Service 2012).

Grette Associates biologists conducted surveys for streaked horned larks in the project area during the breeding season in 2013 (July 12, 2013) and 2014 (May 15, June 11, and July 10, 2014). The surveys were conducted within the open, grassy areas that most closely resemble streaked horned lark habitat onsite. No streaked horned larks were observed during the surveys (Grette Associates 2014j, k). Standardized monitoring protocols were developed by WDFW for streaked horned larks, which require surveys on 3 separate days during the breeding season (Washington Department of Fish and Wildlife 2013).

Bald Eagle (*Haliaeetus leucocephalus*)

Bald eagles nest and forage for fish along the Lower Columbia River. They build their nests in the tops of large trees, typically using the nests year after year. Nests could weigh up to 0.5 ton and span 10 feet in diameter (U.S. Fish and Wildlife Service 2007). There are no documented bald eagle nests in the study area and no suitable nesting habitat in the project area. The nearest documented nest sites are located approximately 2 miles downstream and 4 miles upstream of the study area (Washington Department of Fish and Wildlife 2014). The study area provides foraging habitat for this species. Bald eagles could perch in riparian vegetation or manmade structures over the water to forage for fish. Salmon and other fish within the Columbia River provide an important source of food for this species. Lord Island also provides suitable habitat for bald eagles (Pacific Coast Joint Venture 1994).

Bald eagles were observed soaring over the study area during the April 8, 2014 site visit. Bald eagles were also observed in the study area during the July 12, 2013 streaked horned lark surveys (Grette Associates 2014j).

Peregrine Falcon (*Falco peregrinus*)

Peregrine falcons nest on cliff ledges but also use tall manmade structures such as bridges, overpasses, buildings, and power plants (Oregon Department of Transportation undated). They prey primarily on other birds, including songbirds, shorebirds, ducks, pigeons, and starlings (Washington Department of Fish and Wildlife 2013). The nearest documented nest location is approximately 3 miles south of the study area (Washington Department of Fish and Wildlife 2014). A study of

peregrines nesting in quarries in Ireland found that peregrines will use industrial areas if nesting requirements are met and sufficient prey is available (Moore et al. 1997). Peregrine falcons nesting within a few miles of the study area could potentially use the study area for foraging.

Waterfowl

Nonbreeding concentrations of Barrows goldeneye (*Bucephala islandica*), common goldeneye (*B. clangula*), and bufflehead (*B. albeola*) are considered priority species (vulnerable aggregation) by WDFW. A few individual bufflehead were observed resting on open water (both in wetlands and on the Columbia River) in the study area during the April 8, 2013 site visit. However, within the study area there are no vulnerable concentrations of waterfowl documented by WDFW in the PHS database (Washington Department of Fish and Wildlife 2014). The nearest documented vulnerable concentration is located approximately 0.25 mile north of the study area, east of Willow Grove. Lord Island and adjoining Walker Island support waterfowl and suitable habitat is located just outside of the study area in the tidal marsh area between the islands south of the sand spit (Pacific Coast Joint Venture 1994). This area provides foraging and resting habitat for waterfowl and has been previously documented as supporting significant numbers of wintering ducks and geese (Pacific Coast Joint Venture 1994). Within the study area (Figure 4), Lord Island is documented in the PHS database as supporting nesting Canada goose (Washington Department of Fish and Wildlife 2014).

Purple Martin (*Progne subis*)

The purple martin is a state-listed species of concern. Purple martins were observed on the project area during the streaked horned lark surveys in July 2013 (Grette Associates 2014j). Several nest sites are documented in the Coal Creek Slough, approximately 3 to 4 miles downstream of the study area (Washington Department of Fish and Wildlife 2014). Purple martin nest in natural cavities found in tree snags and crevices, as well as in artificial nest boxes and gourds provided by humans for this purpose (Washington Department of Fish and Wildlife 2014). Nesting habitat is unlikely on the project area; however, other forested areas in the study area could contain this habitat. Purple martins forage for insects while in flight and individuals could occasionally use the study area for this purpose. However, they are more likely to use areas such as Coal Creek Slough, where insect concentrations would be more abundant in herbaceous wetlands, forests, or marshes (Grette Associates 2014j).

Vaux's Swift (*Chaetura vauxi*)

The Vaux's swift is a state candidate species. They are summer (June to mid-August) residents in Washington, migrating north to Washington during the spring (April to late May) and south during the fall (mid-August to late September). They spend winters in central Mexico, Central America, and Venezuela. The species has a strong association with old-growth coniferous forests, using large hollowed-out trees and snags for nesting and roosting. They spend the majority of their day foraging in the air for flying insects over forests, grasslands, and aquatic habitats (Washington Department of Fish and Wildlife 2013). There is no suitable nesting or roosting habitat on the project area; however, other forested areas in the study area could contain suitable habitat. Vaux's swifts may fly through the study area during migrations or while foraging. They are commonly observed at the Mint Farm (Willapa Hills Audubon Society 2014) east of the study area (Figure 4).

Pileated Woodpecker (*Dryocopus pileatus*)

Pileated woodpeckers inhabit mature deciduous or mixed deciduous-coniferous forests. They are also found in younger forests containing scattered, large, dead trees or decaying, downed wood, and in suburban areas containing large trees and woodland patches. Dead wood is an important component of their habitat, including snags, stumps, and downed logs. They forage for insects in the bark and use snags or dead branches of live trees for nesting (Cornell Lab of Ornithology 2015). There is no suitable nesting habitat in the project area. Limited foraging habitat could be available in the forested areas onsite. Forested portions of the study area could contain suitable habitat for nesting and foraging.

Marine Mammals

Pinnipeds

Three species of pinniped are found in the Lower Columbia River in the study area: California sea lions (*Zalophus californianus*), Steller sea lions (*Eumetopias jubatus*), and harbor seals (*Phoca vitulina*). Sea lions use the Lower Columbia River for foraging on fish and resting at haulout sites. Breeding areas (both mating rookeries and pupping sites) for California sea lions are located in California and Mexico. Only males are present in the Columbia River and primarily during the nonbreeding season, fall through spring (Jeffries et al. 2000). Steller sea lions in Washington come from rookeries in Oregon and British Columbia, but pupping sites have increased along the outer Washington Coast in recent years (Washington Department of Fish and Wildlife 2013). Breeding does not occur in the Columbia River, thus, Steller sea lions are primarily present during the nonbreeding season.

Since 2002, California and Steller sea lions have greatly increased in abundance below the Bonneville Dam, which is approximately 80 miles upstream of the study area. Migrating salmon and steelhead collect in a bottleneck below the dam, providing an abundant source of food for the sea lions (Washington Department of Fish and Wildlife 2013).

Sea lions use jetties, shoals, concrete slabs, rock rubble, marina floats, log booms, and other manmade structures as haulout sites along the Columbia River. Surveys conducted in the 1990s identified four haulout sites used by sea lions between the mouth of the Columbia River and its confluence with the Cowlitz River (Jeffries et al. 2000), which is approximately 4.5 miles upstream of the project area. There are no documented sea lion haulout sites in the study area, but individuals likely swim through the study area as they migrate up and down the Columbia River. The nearest California sea lion haulout site to the project area is near the mouth of the Cowlitz River (Washington Department of Fish and Wildlife 2014), approximately 1 mile upstream of the study area. The nearest Steller sea lion haulout site to the project area is approximately 48 miles downstream in the east mooring basin in Astoria, Oregon (Jeffries et al. 2000).

Harbor seals are the most numerous of the pinnipeds found in Washington waters. Like sea lions, they forage and rest along the Lower Columbia River, with dozens of haulout sites identified between the mouth of the river and the study area. Harbor seals use shoals, beaches, sandbars on islands, and the main shoreline as haulouts (Jeffries et al. 2000). There are no documented seal haulout sites in the study area, but individuals swim through the study area as they migrate up and down the Columbia River. The nearest haulout site to the study area is approximately 1 mile upstream from the study area at Carroll Slough, near the confluence of the Columbia and Cowlitz Rivers (Washington Department of Fish and Wildlife 2014). Harbor seal breeding and pupping takes

place in the Columbia River estuary and nursery areas are present downstream from the study area in Cathlamet Bay. Haulouts located further upriver are used primarily in the winter and spring (Jeffries et al. 2000).

Pinniped use and abundance in the study area is expected to vary seasonally as they transit between areas of known use at the mouth of the Columbia River, haulout sites upstream of the study area, and foraging areas farther upstream at the Bonneville Dam. For California sea lions, seasonal use is largely informed by the annual U.S. Army Corps of Engineers pinniped observation program at the Bonneville Dam during salmonid fish passage season (typically January through May, with some observations as early as August). This Corps program began in 2002 and is scheduled to end in 2016. California sea lions typically are not observed at the dam prior to January; they have been observed foraging below Bonneville Dam in very low numbers as early as August. Harbor seals are relatively rare at Bonneville Dam, but are known to haul out at a number of other locations upstream of the study area.

4.8.1.1 Vessel Corridor in the Lower Columbia River

The indirect study area includes wildlife habitats along the vessel corridor in the lower Columbia River.

Vessel Corridor

Forest and shrublands are the most prevalent terrestrial wildlife habitats in the Lower Columbia River, along the route vessels transiting to/from the project areas will navigate. Other habitats common along the Lower Columbia River include intertidal wetlands, coastal dunes, and mudflats. These habitats also support a diverse variety of wildlife species, including terrestrial wildlife species listed as either threatened or endangered under the federal ESA.

2.2.2 Off-Site Alternative

The project area for the Off-Site Alternative is located at approximately river mile 61 on the Columbia River in Cowlitz County, downstream and adjacent to the project area for the On-Site Alternative. The project area is located mostly within Longview city limits and encompasses approximately 277 acres. Historically, the project area contained a combination of meadow, wetland, floodplain, and riparian forest associated with the Columbia River. As Longview began to develop, the habitat was modified. A system of levees and dikes was developed in the 1920s by CDID #1 for flood protection.

2.2.2.1 Wildlife Habitat

Terrestrial and aquatic habitats in the study area are described below.

Terrestrial Habitat

Terrestrial habitat types found in the study area are characterized by their main land cover classification and dominant form of vegetation as described in Section 2.2.1, *Project Area for the On-Site Alternative*, and described in detail in the NEPA Vegetation Technical Report (ICF International 2016c). Habitat types present in the study area include developed (disturbed), upland (forested, scrub-shrub, herbaceous, and managed herbaceous), wetland (forested, scrub-shrub, herbaceous,

managed herbaceous, and disturbed), and riparian (forested and scrub-shrub). Terrestrial habitats characterized on the project area are displayed in Figure 8.

Project Area


The project area for the Off-Site Alternative is located on previously disturbed lands adjacent to upstream industrial developments. Prior to 2000, the project area was used primarily for agriculture and grazing and a small portion of the site continues to be used for agricultural activities. In the northwest portion of the site, there is a small developed area containing an agricultural building (likely a pole barn) surrounded by areas where the vegetation has been disturbed. In approximately 2003, less than one-fifth of the site was developed into a motocross track consisting of several winding dirt tracks, dirt roads, a drag strip, and buildings. This area is currently undeveloped; buildings associated with the motocross trails are no longer present and vegetation on the property is mostly overgrown, consisting of dense shrub vegetation and grassy areas that extend to the shoreline. The majority of the site consists of herbaceous habitat.

At the northern end of the project area, the habitat is predominantly herbaceous uplands with smaller herbaceous seasonal wetlands. This habitat supports waterfowl and has been documented in the PHS database as supporting regular concentrations of wintering waterfowl, including Canada Geese (Washington Department of Fish and Wildlife 2014). Other wildlife that could be supported by herbaceous habitats at the site includes foraging and cover for small to large mammals and foraging by raptors.

The majority of wetland habitats on the project area is in the southern part of the site and includes both forested and herbaceous wetland areas. The forested wetlands are dominated by deciduous trees, particularly black cottonwood (*Populus balsamifera*), and the herbaceous wetlands are dominated by reed canarygrass (*Phalaris arundinacea*). Wetlands on the project area likely support foraging and cover for small to large mammals, foraging and nesting for raptors, waterfowl, and passerine birds, and foraging, breeding, and nesting for amphibians (Grette Associates 2014i, l).

Study Area

The study area includes lands both up- and downstream from the project area, areas landward from the site (north/northeast), a strip of land between the project area and the Columbia River, and Walker Island. Approximately one-half of the peripheral lands in the study area for the Off-Site Alternative overlap with the study area for the On-Site Alternative (Section 2.2.1, *Project Area for the On-Site Alternative*). A large portion of the landward study area habitats overlap with the study area for the On-Site Alternative (Section 2.2.1, *On-Site Alternative*). In addition to these previously described landward habitats is the Mount Solo Landfill, located adjacent to the project area. The landfill habitat is classified as disturbed and likely to provide some wildlife habitat, including foraging and cover for small to large mammals, and foraging for bird species, including raptors and waterfowl.

Figure 8. Terrestrial Habitats in the On-Site and Off-Site Alternative Project Areas

Upstream habitats are described in Section 2.2.1.1, *Terrestrial Habitat*. Downstream habitats are similar to those described at the downstream end of the project area, consisting of herbaceous agricultural fields that support regular concentrations of wintering waterfowl (Washington Department of Fish and Wildlife 2014), foraging and cover for small to large mammals, and foraging for raptors. There is a small disturbed area close to the Columbia River containing houses and other small buildings associated with the residences and agricultural fields. A levee with managed herbaceous vegetation spans the length of the study area.

The riparian area in the downstream portion of the study area is dominated by densely forested trees and shrubs and likely provides high-quality habitat for wildlife. Moving upstream, the riparian area transitions to scrub-shrub habitat and is more sparsely vegetated. Support for wildlife in the riparian area includes foraging and cover for small and large mammals, foraging and nesting for waterfowl, raptors, and passerine birds, and foraging, breeding and nesting for amphibians.

Walker Island is located offshore from the project area in the Columbia River (Figure 6). The island was previously used for dredged-material disposal; however, it contains high-quality habitat for wildlife. Walker Island is predominantly forested and connects upstream to Lord Island by a narrow sand bar. An embayment between the two islands contains a tidal marsh and shallows. This area provides foraging and resting habitat for waterfowl and has been previously documented as supporting significant numbers of wintering ducks and geese (Pacific Coast Joint Venture 1994). Walker Island has been documented by WDFW as supporting nesting Canada Geese (Washington Department of Fish and Wildlife 2014). Columbian white-tailed deer have not been documented on this island; however, suitable habitat is present for this species. Additional wildlife species supported by Walker Island include mammals, birds (raptors and passerine), amphibians, and reptiles.

Aquatic Habitat


Aquatic habitats include wetlands (refer to Section 5.3, *Wetlands*, in the Draft EIS for more information), the Columbia River, and smaller open-water areas, such as ponds and drainage ditches, throughout the study area.

The majority of wetland habitats in the project area are in the southern portion of the project area, and include both forested and herbaceous wetland areas. Wetlands in the project area likely support foraging and cover for small to large mammals, foraging and nesting for a variety of birds, and foraging, breeding, and nesting for amphibians (Grette Associates 2014f, and 2014l).

Habitat types in the Columbia River are described in Section 2.2.1.1, *Terrestrial Habitat*, and include the deep-water zone, shallow-water zone, and the ACM (Figure 9).

Much of the ACM adjacent to the project area is modified with shoreline armoring and the dike that extends the length of the shoreline (Grette Associates 2014f).

The bottom structure of the shallow-water zone varies from steep at the downstream end to flat at the upstream end. Substrates in this area consist of silty river sand. Similar to the project area for the On-Site Alternative, little to no aquatic vegetation is expected; however, sparse vegetation could exist in the upper elevations where light could penetrate and flow is reduced (Grette Associates 2014f).

Figure 9. Aquatic Habitats for the Off-Site Alternative

Benthic habitats in the deep-water portion of the study area for the Off-Site Alternative are similar to those in the study area for the On-Site Alternative. They are subjected to strong currents and reduced-light penetration due to depth. Aquatic vegetation is not expected to occur in deep-water habitats and these areas are generally associated with low productivity.

Aquatic habitats of the Columbia River support pinnipeds, fish, birds, and a variety of invertebrates, many of which serve as forage for fish and bird species. Fish are discussed in the NEPA Fish Technical Report (ICF International 2016a).

Smaller open-water areas, such as ponds and drainage ditches, could support common species of invertebrates and amphibians and could be used by small mammals and birds.

2.2.2.2 Wildlife

The project area for the Off-Site Alternative is adjacent to the project area for the On-Site Alternative and the two study areas overlap. Due to its proximity and similar habitat types and characteristics, wildlife species that could occur in the study area for the Off-Site Alternative are expected to be similar to those described for the On-Site Alternative (Section 2.2.1, *On-Site Alternative*).

The following species were documented on the project area. During the December 12, 2014 site visit to adjacent Mount Solo Landfill, a few bird species were observed through binoculars at the project area: a red-tailed hawk was seen flying over the site; a great blue heron was observed in the herbaceous habitat at the south end of the site; and mallards were observed in the drainage ditch that meanders through the site. An unoccupied raptor nest was observed within the forested wetland habitat.

Columbian white-tailed deer have been documented on the project area (Washington Department of Fish and Wildlife 2014).

2.2.2.3 Special-Status Wildlife Species

Special-status wildlife species described in this section are those listed as threatened, endangered, proposed, or candidate species under the ESA or listed as a WDFW priority species. Descriptions of special-status wildlife species that could occur in the study area for the Off-Site Alternative are the same as those described for the On-Site Alternative (Section 2.2.1.3, *Wildlife*).

Table 5 contains a list of special-status wildlife species that are likely to occur in the study area. Some of the PHS listings are not for individuals of a species (PHS Criteria 1) but for vulnerable aggregations (PHS Criteria 2) of individuals, such as Western Washington nonbreeding concentrations. The likelihood of each species or vulnerable aggregation occurring in the study area is listed as either *Yes* (known to occur), *Possibly* (likely to occur due to presence of suitable habitat but not documented), or *Unlikely* (individuals are known to occur or possibly occur in the study area but vulnerable concentrations are not documented in the PHS database [Washington Department of Fish and Wildlife 2014]). A listing of *No* does not mean individuals of that species could not occur in the study area; it only signifies there are no documented vulnerable concentrations.

This chapter describes the impacts on wildlife that would result from construction and operations of the proposed export terminal.

3.1 On-Site Alternative

This section describes the impacts on wildlife and their habitat that could result from the proposed export terminal at the On-Site Alternative location.

The following construction activities could affect wildlife.

- Permanent removal of habitat and wildlife displacement or mortality in terrestrial and aquatic habitats associated with clearing and construction of the export terminal.
- Noise impacts and visual disturbance on terrestrial and aquatic wildlife associated with operation of construction equipment, general construction related noise and pile driving.
- Spills and leaks associated with the use of construction equipment and materials.

The following operation activities could affect wildlife.

- Noise impacts on wildlife associated with operations such as train movements, managing the coal stockpile, transfer of coal to vessels, and general industrial operations.
- Spills and leaks from trains, vehicles, or equipment.
- Vessel strikes of marine mammals.
- Underwater vessel noise impacts on pinnipeds and diving birds.
- Removal of benthic habitat during maintenance dredging impacting wildlife and habitat.
- Coal dust deposition affecting terrestrial, wetland, and aquatic habitats and wildlife.

3.1.1 Construction: Direct Impacts


Construction of the On-Site Alternative would result in the following direct impacts.

3.1.1.1 Permanent Impacts on Terrestrial Habitat and Wildlife

Permanently Remove Habitat and Cause Associated Wildlife Mortality

Construction of the On-Site Alternative would result in the permanent removal of wildlife habitat within the limits of the project area.

A total of 201.5 terrestrial acres would be permanently removed during construction grading and clearing activities (Figure 10). The majority (151.14 acres) of these impacts would occur in previously developed lands in which industrial buildings, pavement, and infrastructure currently exist with scattered areas of vegetation surrounding the developed areas, or sparsely

Figure 10. Existing Land and Vegetation Cover Types Affected during Construction

vegetated areas that previously served as material storage or disposal sites associated with past industrial uses of the property. In general, these developed lands provide degraded wildlife habitat conditions that do not provide suitable habitat for many species of wildlife, but may support bats, birds, rodents, and insects.

Construction of the On-Site Alternative would result in the permanent loss of 26.26 acres of upland and 24.10 acres of wetland habitats containing forested, herbaceous, managed herbaceous, and scrub-shrub vegetation and a small area (0.05 acre) of forested riparian habitat (Table 6). Animals inhabiting these areas could be displaced to other habitats outside of the project area and mortality of some less mobile individual species could occur. Highly mobile wildlife species, such as larger mammals and birds, would likely leave the terrestrial study area for the On-Site Alternative during construction activities. Some mortality of less mobile species could occur, such as burrowing mammals, reptiles, amphibians and insects. Typically, these species reproduce rapidly and any losses due to mortality would not be expected to affect the viability or fitness of the species at the population scale.

Table 6. Permanent Direct Impacts by Terrestrial Habitat Type in the Project Area—On-Site Alternative

Habitat Type	Direct Impact Area (acres)
Disturbed	151.14
<i>Developed</i>	<i>151.14</i>
Riparian	0.05
<i>Forested</i>	<i>0.05</i>
Upland	26.26
<i>Forested</i>	<i>8.90</i>
<i>Herbaceous</i>	<i>10.88</i>
<i>Managed Herbaceous</i>	<i>4.37</i>
<i>Scrub-Shrub</i>	<i>2.11</i>
Wetland	24.10
Total	201.5

3.1.1.2 Temporary Impacts on Wildlife Habitat

Construction activities could temporarily affect wildlife habitat adjacent to the project area, including riparian vegetation along the shoreline of the Columbia River. Temporary disturbance could occur through soil disturbance, stockpiling, and erosion. These disturbances could temporarily increase total suspended sediments in the Columbia River and freshwater ditches on and adjacent to the project area. The potential for these types of impacts would be avoided or greatly reduced given protective measures to guard against these risks, including construction best management practices, avoidance and minimization measures, and regulatory requirements, such as those associated with 401 Water Quality Certification and hydraulic project approval that would be required for the On-Site Alternative. The NEPA Water Quality Technical Report (ICF International 2016d) includes a detailed discussion on the potential impacts on water quality associated with the On-Site Alternative.

Displace Wildlife

Construction of the On-Site Alternative would be limited to the project area, including the aquatic portions of the project area. Aquatic and terrestrial wildlife species present in the project area could be at risk of displacement during construction activities. Wildlife present at the project area during construction could be displaced from increased human activity, elevated underwater and terrestrial noise levels, and/or ground-disturbing activities.

Approximately 71% or 151 acres of the project area is currently developed and many species of wildlife would likely not be present in these areas due to the lack of suitable habitat. The areas of the project area that are vegetated and could provide suitable habitat (approximately 50 acres) are generally degraded because of past industrial uses of the property. Although construction could affect a relatively small area of potentially suitable but degraded habitat, most wildlife species are mobile; construction activities could result in the displacement. The On-Site Alternative would be consistent with the general character and land uses of surrounding areas, particularly the shoreline within the study area. Other heavy industrial sites are located along the shoreline to the east of the project area. Overall, the potential displacement of wildlife during construction would not be expected to have a measurable affect to wildlife species at the population scale or in terms of overall population fitness.

Result in Construction Noise and Visual Impacts on Wildlife

Construction-related noise and human presence at the project area could affect wildlife in the aquatic and terrestrial study areas during construction activities (Tables 4 and 5). While wildlife in and around the terrestrial and aquatic study area are likely habituated to human activity and noise levels associated with industrial and developed areas, noise levels at the project area would increase above ambient levels for the duration of construction, especially during impact pile-driving activities associated with dock and trestle construction. Wildlife species exhibit different hearing ranges and all wildlife do not respond the same way to similar sound sources or levels. Even within a species, individuals do not necessarily respond the same way. Wildlife response to sounds depends on numerous complicated factors, including noise level, frequency, distance and event duration, equipment type and conditions, frequency of noise events over time, slope, topography, weather conditions, previous exposure to similar noises, hearing sensitivity, reproductive status, time of day, behavior during the noise event, and the animal's location relative to the noise source (Delaney and Grubb 2003 in Washington State Department of Transportation 2015). Therefore, an animal's reaction to elevated noise levels could range from mild disturbance with little or no reaction to escape behavior, which would displace individuals by forcing them to abandon the area of elevated noise levels, potentially resulting in significant impairment or disruption of normal behavioral patterns. Such displacement and disruption of behavior could reduce productivity and survival of individuals as the individual would likely expend more energy relocating to new suitable habitat, and would be less familiar with new habitat areas and at an increased risk of predation, potentially limiting survival of individual adults or offspring (e.g., abandoning young). These impacts would be exacerbated where there is no adjacent or nearby suitable habitat that is easily accessible. In addition, visible construction equipment, materials, and an increase in infrastructure could cause displacement because some species would avoid areas within the line-of-sight of construction equipment operations.

Dredging and the associated noise could affect birds, including streaked horned larks, during the nesting season. There are no studies that specifically identify noise level sensitivities of the streaked horned lark. Noise sensitivity studies have been conducted for the marbled murrelet. These studies found that marbled murrelets are very sensitive to underwater noise such as pile driving and prolonged terrestrial noise that lasts longer than 10 to 15 minutes (Mountain Loop Conservancy 2010). Little information is available on the impacts of noise on birds. Shorebird sensitivities are more closely related to those of sea lions because they spend most of their time above water and generally stay in the shallow water while hunting (Science Applications International Corporation 2011). Dredging related activities have been shown to generate in-air noise levels of 72 decibels in commercial or industrial areas (Epsilon Associates 2006). Terrestrial noise levels in this range could disturb birds but would not be expected to result in injury.

Additionally, construction-related noise impacts and the presence of construction equipment and materials would be temporary, lasting the estimated 6 years required for project construction. In addition, there is a lower density of development to the northwest of the study area where connectivity to other potentially suitable wildlife habitat exists, and where wildlife could relocate during and after construction. Given that the wildlife present in the study area are likely habituated to noise levels associated with industrial areas and are generally mobile, it is anticipated that construction-related noise would affect individuals of a species, but would not affect a species' whole population or the overall fitness of a population.

3.1.1.3 Aquatic Habitat and Wildlife Impacts

The following section describes potential impacts on aquatic habitat and wildlife.

Remove and Alter Aquatic Habitat and Impacts on Aquatic Wildlife

Project construction would result in the alteration and removal of aquatic habitat in the Columbia River and open freshwater areas (e.g., ditches) located in the project area.

Construction of the On-Site Alternative would result in the permanent loss of approximately 10.78 acres of aquatic habitat (ditches and ponds) and 24 acres of wetlands, which would reduce suitable habitat available to wildlife species throughout the the project area. These open areas of freshwater habitats and wetlands support common species of amphibians and could be used by small mammals and birds. Mammals and birds are highly mobile species and are expected to leave the vicinity during construction activities.

Habitat in the Columbia River would be permanently altered and removed by the placement of piles. A total of 603 of the 622 36-inch-diameter steel piles required for the trestle and docks would be placed below the ordinary high water mark, permanently removing an area equivalent to 0.10 acre (4,263 square feet) of benthic habitat. The majority of this habitat is located in deep water (Grette Associates 2014i). The placement of piles would displace benthic habitat and the areas within each pile footprint would cease to contribute toward primary or secondary productivity. Individual pile footprints would be relatively small (7.07 square feet) and would be spaced throughout the dock and trestle footprint. Benthic organisms (i.e., benthic, epibenthic, and infaunal organisms) within the pile footprint at the time of pile driving would likely perish.

Creosote-treated piles would be removed from the deepest portions of two existing timber pile dikes. The piles would be removed using vibratory extraction as feasible, or cut, pull and cap

methods, depending on the condition of the piles (Grette Associates 2014n). In total, approximately 225 linear feet of the pile dikes would be removed from the waterward end of the pile dikes. Approximately 125 linear feet would be removed from the western, or downstream, pile dike and approximately 100 linear feet would be removed from the eastern, or upstream, pile dike. Pile dikes were installed throughout the Lower Columbia River between 1889 and 1969. The specific year the pile dikes to be partially removed as part of the proposed project were installed is unknown, but their degraded condition indicates that they've been in the river for considerable time. Overall, removing creosote-treated piles from the Columbia River would result in an improvement in water quality, as most remaining creosote in those piles would be removed from the aquatic environment. However, removing the piles could result in temporary increases in suspended sediments, short-term water contamination, and long-term sediment contamination from creosote released during extraction. Those portions of the creosote treated piles that have been exposed to water and air have little creosote remaining. Those portions of the treated piles below the mud line likely have more creosote remaining, which would become exposed during extraction. Backfilling the holes left after extracting the piles with clean-sand would avoid and minimize exposure to the water column of the creosote that may be present in the surrounding soils. Creosote contains a mixture 200 to 250 compounds, with primary components composed of polycyclic aromatic hydrocarbons (PAHs) (Brookes 1995; National Marine Fisheries Service 2009). PAHs are known to be toxic to aquatic organisms including invertebrates and fish and can cause sublethal and lethal effects (Eisler 1987; Brooks 1997).

Creosote and associated chemicals, particularly those that are water-soluble and that persist in the water column are known to bioconcentrate in many aquatic invertebrates (Eisler 1987; Brooks 1997). This could expose higher trophic level species such as fish, birds, and pinnipeds to creosote/PAH compounds through the food chain. Many vertebrates, including fish, however, metabolize PAHs and excrete them, reducing the potential risk to higher trophic-level species (Varanasi et al. 1989 in National Marine Fisheries Service 2009; Strauss 2006 in National Marine Fisheries Service 2009).

Most of the components of creosote are heavier than water and sink in the water column. PAHs from creosote accumulate in sediments and are likely to persist at the site of pile removal or wherever they settle after suspension until they degrade (National Marine Fisheries Service 2009). However, PAHs from sediment are less bioavailable to aquatic species and thus these organisms are not likely to bioaccumulate PAHs from sediments (Brooks 1997).

Over the long term, the source of creosote would be removed or capped by the sediment falling into the hole left by the extracted pile. Water quality would improve, the concentration of creosote in the sediment would be expected to decrease, and the potential pathway of exposure for wildlife through contamination of prey would be reduced.

Dredging would permanently alter a 48-acre area of deepwater habitat (below -20 feet CRD) by removing approximately 500,000 cubic yards of benthic sediment to achieve a depth of -43 feet CRD, with a 2-foot overdredge allowance. Within the proposed dredged area (Figure 2), the amount of deepening would depend on existing depths, varying from no removal up to a depth of approximately 16 feet of removal. Most benthic organisms are stationary or slow moving and would likely perish during dredging. Benthic organisms typically recolonize disturbed areas within 30 to 45 days. The majority of the area of the proposed dredge prism is at or below a depth of -31 feet CRD. It is anticipated that sediment within the dredge prism for Docks 2 and 3 would be deemed suitable for flow-lane disposal or beneficial use in the Columbia River based

on past sediment sampling near the project area. However, prior to obtaining permits for the On-Site Alternative, including dredging permits, the Applicant would conduct site-specific sediment sampling to characterize the proposed dredge prism and ensure compliance with the Dredged Materials Management Plan (Grette Associates 2014i, m). This flow lane disposal area would likely be located within an area of approximately 80 to 110 acres between approximately river miles 60 and 66 (Figure 6).

The majority of benthic, epibenthic, and infaunal organisms are nonmotile or slow moving and become entrained during dredging. Benthic, epibenthic, and infaunal organisms in the proposed dredge prism above -43 feet CRD would be removed during dredging, likely resulting in mortality. These organisms often serve as prey for larger animal species. Most of the habitat in the proposed dredge prism is in deep water where benthic productivity is expected to be low relative to shallower habitat. Deep-water channels are subjected to higher water velocities, which periodically scour bottom sediments, limiting the standing crop of invertebrates and the buildup of detritus and fine materials that support these invertebrates (McCabe et al. 1997). Dredging activities are not typically associated with long-term reductions in the availability of prey resources and impacts on benthic productivity are expected to be temporary. Benthic organisms typically recolonize disturbed areas within 30 to 45 days. Disturbed habitats are expected to return to reference conditions with rapid recolonization by benthic organisms (McCabe et al. 1996).

Dredging activities could affect pinnipeds. In *A Review of Impacts of Marine Dredging Activities on Marine Mammals*, Todd et al. (2014) states that potential direct impacts on marine mammals include collisions, turbidity, and noise. Collisions between dredging vessels and pinnipeds are possible but unlikely to occur given the slow speeds of dredging vessels. Information on turbidity is limited; however, existing research indicates that dredge-related turbidity is not likely to cause substantial impacts on pinnipeds since they often inhabit naturally turbid or dark environments and are likely to use senses in addition to their vision (Todd et al. 2014). Noise could cause masking and behavioral changes but is unlikely to cause auditory damage to pinnipeds (Todd et al. 2014). Dredging would be conducted using a clamshell dredger; however, a hydraulic dredger could also be used (Grette Associates 2014n). Sound pressure levels (SPLs) can vary widely, based on dredger type, operations stage, or environmental conditions (Todd et al. 2014). The operations stage is an important component of noise levels produced by a clamshell (grab) dredger. Dickerson et al. (2001) measured the entire clamshell dredge process at increasing distances from the dredge operation. The loudest measurement, 124 dB_{RMS}, was recorded at a distance of 518 feet from the dredge operation. This measurement is consistent with SPLs that could result in behavioral changes in pinnipeds, but likely would not cause auditory damage. Hydraulic dredges typically produce higher SPLs than clamshell dredges but these SPLs would be unlikely to reach levels that could cause auditory damage (Central Dredging Association 2011; Todd et al. 2014).

Dredging and Underwater Construction Noise Impacts on Pinnipeds

Dredging activities could affect pinnipeds through collisions with vessels and dredge-related increases in turbidity. Collisions with vessels and dredging equipment are possible but unlikely given the slow speeds of dredging vessels. Information on turbidity is limited; however, existing research indicates that dredge-related turbidity is not likely to cause substantial impacts on pinnipeds since they often inhabit naturally turbid or dark environments and are likely to use senses in addition to their vision (Todd et al. 2014). Noise generated during dredging activities

could cause masking and behavioral changes but is unlikely to cause auditory damage to pinnipeds (Todd et al. 2014). Increases in turbidity and underwater noise associated with dredging would be short-term and localized. Dredging would not likely cause long-term or negative impacts on pinnipeds.

Potential underwater noise impacts on pinnipeds could also occur during in-water installation of the trestle and dock piles. NMFS has established standard underwater noise thresholds for marine mammals for purposes of determining take (through harassment) under the Marine Mammal Protection Act. Table 7 summarizes NMFS' marine mammal noise thresholds and the distances from the pile-driving activity at which these thresholds would extend (Grette Associates 2014a).

Table 7. Underwater Sound Level Effects Thresholds and Distances to Threshold

Effect Type	NMFS Threshold	Distance to Threshold	
		No Attenuation ^a	With Bubble Curtain ^a
Impulsive Sound (Impact Pile Driver)			
Level A Harassment: Hearing-related injury	190 dB _{RMS}	178 feet	45 feet
Level B Harassment: Behavioral disruption	160 dB _{RMS}	3.36 miles	4,459 feet
Continuous Sound (Vibratory Pile Driver)			
Level B Harassment: Behavioral disruption	120 dB _{RMS}	5.4 miles based on landmass	N/A
Notes:			
^a Grette Associates 2014a			

Level A harassment and Level B harassment are defined in more detail under Impact Pile Driving below. Construction of the trestle and dock could include both vibratory pile driving for installation and impact pile driving for proofing. For purposes of this analysis, it is assumed that pile-driving activities would occur during approved in-water work windows. Based on in-water work windows established by NMFS, USFWS, and WDFW for the protection of other aquatic species, in-water pile installation could occur from September 1 to February 28 for vibratory pile driving and September 1 through December 31 for impact pile driving. Actual dates of pile-driving activities would be outlined in permits issued for the project from both the Corps and WDFW. Pile installation and the applicable work window(s) would be provisioned in the hydraulic project approval. Pile installation would occur over two in-water work window construction periods, due to the number of in-water piles required for the dock and trestle. To reduce underwater sound pressure levels from impact pile-driving operations, a confined bubble curtain system or similar noise attenuation technology would be used. Whether or not in-water pile driving would affect pinnipeds depends on timing of pile driving and whether pinnipeds are in the aquatic study area during this time. Impact pile driving is proposed from September 1 through December 31, which would be prior to the beginning of seasonal use of the study area by California sea lions and harbor seals; it is unlikely that individuals would be present during impact pile driving. Steller sea lions have been observed at the Bonneville Dam from September through December, but in low numbers. Eleven individuals were observed from October through December 2011 (Stansell et al. 2012); no regular observations were reported

in October through December 2012. Therefore, individual Steller sea lions could be transiting through the aquatic study area during pile-driving activities.

Grette Associates (2014a) assessed the direct effects of in-water pile driving on marine mammals at the project area in its *Millennium Coal Export Terminal Docks 2 and 3 and Associated Trestle: Direct Effects of Construction, Pile Driving and Marine Mammals* report. Multiple sources were reviewed for comparable reference of underwater sounds levels during vibratory and impact installation of the 36-inch-diameter steel piles, including sound level data on pile installations compiled by the Washington State Department of Transportation (WSDOT), Caltrans, Port of Seattle, Port of Kalama, and the Columbia River Crossing (CRC) Test Pile Project. After reviewing all applicable information, sound levels from the CRC 48-inch-diameter test pile were selected as reference levels for the 36-inch-diameter steel pile proposed for the project area. While these piles are larger than those proposed, the proximity of the CRC site to the project area (less than 50 miles apart) and similar conditions are expected to be more comparable than more distance locations elsewhere in Washington and California. Using these reference levels provides for a liberal assessment of sound (i.e., estimating at the high end for impact area), and therefore, presents a conservative evaluation that is protective of marine mammals because it considers relatively louder sounds, and therefore, larger potential impact areas than other reference values.

Impact Pile Driving

Level A Harassment

Level A harassment could occur up to a radius distance of 178 feet from active impact pile driving without any sound attenuation in place. With implementation of a bubble curtain to attenuate noise levels during impact pile driving, there would be a reduction of at least 9 decibels (dB) at the source, which would decrease the Level A harassment area to a 45-foot radius around each pile as it is driven. This estimate is based on a review of the Columbia River Crossing Test Pile Project (CRC), which was conducted in the Columbia River at river mile 106.5, approximately 43 miles upstream of the project area. The CRC found bubble curtains around 48-inch-diameter steel piles attenuated sound by 10 dB, and for 24-inch-diameter steel piles between 6 and 11 decibels. In addition, at a WSDOT project downstream of Puget Island, bubble curtains attenuated sound levels by 13 decibels. Therefore, assuming sound values would be attenuated by 9 decibels during use of a confined bubble curtain is considered realistic and achievable, and likely conservative. Because the Columbia River is approximately 3,000 feet wide at the point where pile driving would occur, there would be a wide area of the river that pinnipeds could utilize and avoid exposure to the small area where underwater noise reaching Level A harassment would be generated.

Based on the seasonal use patterns for California sea lion, Steller sea lion, and harbor seals in the study area and based on the proposed work window for in-water impact pile installation (i.e., September 1 through December 31), presence of individual pinnipeds during impact pile driving would be unlikely. In addition, given the small potential noise impact area around each pile for Level A harassment, the adherence to in-water work windows, and the use of bubble curtains to reduce noise and the potential impact distance, the three pinniped species are not expected to experience underwater noise in excess of the Level A harassment threshold.

Level B Harassment

It is estimated that Level B harassment could occur up to a radius distance of 3.36 miles from active impact pile driving without any sound attenuation in place. With implementation of a bubble curtain to attenuate sounds, it is estimated that there would be a reduction of at least 9 decibels at the source, which would decrease the Level B harassment area to a 0.84 mile radius (4,459 feet) around each pile as it is driven. The Columbia River is approximately 3,000 feet wide at the point where pile driving would occur, so in either case sound would extend across the river's entire width, although not to the side channel on the Oregon side of Lord Island.

Based on the seasonal use patterns for California sea lions and harbor seals in the study area, presence of individuals of these species during impact pile driving would be unlikely. Steller sea lions are known to occur in the study area during the period when impact pile driving would occur, (September through December), but in very low numbers. In the event these pinnipeds pass through the study area during impact pile driving, they would be exposed to sound in excess of the Level B harassment threshold. However, it is so unlikely that California sea lions or harbor seals would be transiting through the area on their way to upstream locations such as haulouts or the Bonneville Dam that few, if any, individuals would be expected to experience sound in excess of the Level B harassment threshold. A relatively small number of Steller sea lions (less than 20) could experience sound in excess of the Level B harassment threshold.

The NMFS 160- dB_{RMS} effect threshold for Level B harassment is for all marine mammals (cetaceans and pinnipeds). According to Southall et al. (2007), there is limited potential for pinnipeds exposed to multiple pulses between approximately 150 and 180 dB_{RMS} to respond with avoidance. The majority of individual documented behavioral responses at these levels are related to alert or orientation response, which could result in changes or interruption in feeding or diving, to cessation of vocalizations, to temporary displacement from habitat.

The relatively small number of Steller sea lions that would potentially experience pulsed sound above the Level B harassment threshold are not expected to significantly alter their behavior. Based on an average swim speed of approximately 3 meters per second (Stelle et al. 2000), a Steller sea lion would traverse the study area in approximately 20 minutes (assuming pile driving at any/all locations). Based on observations of swimming speeds in the Columbia River determined through telemetry, this speed could be somewhat high, particularly during upstream migration (Brown et al. 2011). However even for speeds at the low end of those reported by Brown et al. (2011) (more than 1 meter per second), it is expected that the study area would be traversed in less than one hour. The lower-end estimates from Brown et al. (2011) are applicable to California sea lions and have been applied to harbor seals as well. For all three species, additional alert or orientation responses over the duration of the construction period would not be expected to impede transit through the area or otherwise significantly disrupt behavioral patterns. In the unlikely event a significant disruption of behavior were to occur to an individual during pile driving, effects could range from startle responses to changes or interruption in feeding or diving, to cessation of vocalizations, to temporary displacement from habitat.

The estimated distance to the 180 dB_{RMS} level, above which the likeliness of avoidance behavior as opposed to an alert or orientation response increases (Southall et al. 2007), is estimated to be approximately 200 feet from impact pile-driving activities. Should an individual pinniped be present to experience this sound, avoidance of the area within 200 feet of impact pile driving (which represents less than 15% of the Columbia River's width where pile driving would occur)

would not impede transit through the study area and would not otherwise adversely affect individuals or significantly disrupt behavioral patterns.

Vibratory Pile Driving

Vibratory pile driving could occur during much or all of each working day during the proposed September 1 through February 28 in-water work window. Vibratory pile driving would be used to drive the pile to the greatest extent possible. Final driving and/or proofing would require an impact pile driver to achieve bearing strength, depending upon the level of embedment achieved during vibratory installation. The contractor would determine sequencing and the need for multiple pile-driving rigs. It is possible that vibratory pile driving could occur at any time during the proposed in-water work window (September 1 through February 28), and it could be continuous during working days (Monday through Friday), particularly if multiple pile-driving rigs are operating. However, given the likely use of multiple pile-driving rigs, variable subsurface conditions, vibratory pile driving might not occur throughout the working day. Therefore, it is possible that some or all of the pinnipeds transiting through the study area would not experience Level B harassment from vibratory pile driving.

Aside from the vibratory pile-driving schedule and sequence of events during the in-water work window, individual California sea lions, Steller sea lions, and harbor seals are considered unlikely to be present during much of the vibratory pile-driving period, based on their seasonal occurrence and the in-water pile-driving construction timing. This would minimize the likelihood that individual pinnipeds would experience sound in excess of the 120 dB_{RMS} Level B harassment threshold for continuous pile-driving sound. However, some California sea lions and harbor seals are expected to pass through the study area during the latter part of the vibratory driving period (mid-January through February) on their way to upstream haulouts and the Bonneville Dam. Steller sea lions could pass through the study area throughout the vibratory pile-driving period, but in relatively small numbers (less than 20) prior to January 1, with increasing numbers possible thereafter.

NMFS applies the 120 dB_{RMS} effect Level B harassment threshold for continuous sound to all marine mammals. As noted in Southall et al. (2007), the 120 dB_{RMS} value is primarily based on data from two field studies observing the response of baleen whales (gray and bowhead whales) to continuous industrial sound (e.g., drilling or icebreaking). Southall et al. (2007) also states the effects of continuous sound exposures on pinnipeds are poorly understood, and existing data do not indicate strong behavioral responses to sounds between 90 and 140 dB_{RMS}. As such, the application of the 120 dB_{RMS} threshold for pinnipeds is considered a conservative analysis that is protective of the species.

The assertion that the 120 dB_{RMS} is considered conservative could be further supported by observed responses of sea lions, including Steller sea lions, to auditory deterrence devices (ADDs) employed at the Bonneville Dam (Stansell et al. 2010). The ADDs were installed in 2008 at most of the fishway entrances to deter pinniped foraging in these areas. Each ADD consisted of an Airmar decibel Plus II acoustic deterrent system emitting a 205-decibel sound in the 15-kilohertz (kHz) frequency range, placed within the tailrace of the dam (Stansell et al. 2010). The ADDs are marketed as pinniped deterrents and are set to a frequency within the range of greatest hearing sensitivity for pinnipeds. Steller sea lion hearing sensitivity peaks between 1 and 16 kHz for males and between 16 and 25 kHz for females (Kastelein et al. 2005). California sea lion hearing sensitivity peaks between 1 and 28 kHz with a peak at 16 kHz (Schusterman et

al. 1972). Harbor seal hearing sensitivity peaks between approximately 10 and 40 kHz (Mohl 1968 in Richardson et al. 1995).

The ADDs were left on continuously for the entirety of the 2008 observation season (January through May), turned on or off randomly in 2009, and on or off for random two-day periods in 2010 to mitigate against habituation (Stansell et al. 2010). According to observations, the ADDs had no detectable effect on sea lions when they were on continuously in 2008 or when they were randomly on or off in 2009 and 2010. Pinnipeds have been observed each year since 2008 swimming and foraging within 20 feet of the active ADDs, and many of the same individuals present in 2008 returned the following 2 years. Due to the ineffectiveness of the ADDs as deterrents at the Bonneville Dam, the investigators recommended discontinuing their use (Stansell et al. 2010).

The pinnipeds' reactions to the ADDs employed at Bonneville Dam illustrates that the environmental context plays a significant role on whether or not pinnipeds react to continuous noise. The noise from ADDs was well above both the documented pinniped hearing thresholds and the established threshold of potentially disturbing continuous sound. While the ADDs have been effectively used as a pinniped deterrent elsewhere, the acoustic deterrent was not enough to dissuade the animals from the abundant foraging opportunity at Bonneville Dam.

The results of the ADDs employed at Bonneville Dam strongly suggest that sea lions can habituate to high levels of continuous sound. Sound from vibratory pile driving is conservatively estimated to be 181 dB_{RMS} (170 dB_{RMS} could be more typical). The ADDs used at Bonneville Dam emitted sound at 205 decibels at the source (not specified as dB_{RMS}, decibels sound exposure level (dB_{SEL}) or decibels peak. However, since the ADDs emit continuous sound, dB_{RMS} should be a comparable metric). A modeled comparison of these sound levels determined that sound from vibratory pile driving is expected to be of comparable loudness to that emitted by the ADDs at Bonneville Dam. Other characteristics including frequencies could be different, but the ADDs targeted the most sensitive frequencies for pinnipeds and were still not effective deterrents at the Bonneville Dam.

California sea lions, Steller sea lions, and harbor seals would pass through the study area during the period proposed for vibratory pile driving with increasing numbers toward the end of the vibratory pile in-water work window. Individuals that occur within 5.4 miles (28,512 feet) of vibratory pile driving would experience elevated sound levels. As discussed above, based on Southall et al. (2007), pinnipeds do not typically elicit strong behavioral responses to continuous sound between 90 and 140 dB_{RMS}. While not included in the detailed behavioral analysis, Southall et al. (2007) also discuss a number of studies that suggest a high tolerance of and/or limited behavioral changes by pinnipeds to sounds from underwater drilling, ADDs, and other continuous sources in the field. Stansell et al. (2012) observed that Steller sea lions did not avoid areas ensonified by ADDs and were observed foraging within 20 feet of the ADDs. Those ADDs emitted sound at levels comparable to what is expected during vibratory pile driving, and were frequency-specific to target peak sensitivity for pinniped hearing. Taken together, these findings suggest that a strong behavioral response such as absolute avoidance of the entire area of elevated sound is unlikely during vibratory pile driving, even with the relatively long time-period (September 1 through February 28) and daily duration proposed over the two in-water construction seasons. Even if an individual were to initially avoid the area of elevated sound it would be expected to eventually move through the study area, either once acclimated to the sound or once pile driving has ceased. Vibratory pile driving is not expected to affect the ability

of, or the likelihood for, individual California sea lions, Steller sea lions, or harbor seals to transit through the study area or to eventually reach other upstream areas and the Bonneville Dam.

Underwater Noise Impacts on Diving Birds

Potential underwater noise impacts on diving birds in the Columbia River could occur during in-water installation of the trestle and dock piles, specifically impact pile driving, which would generate the loudest and most intense underwater noise during construction. Although hearing range and sensitivity has been measured in many terrestrial birds, little is known of diving bird hearing; most published literature on bird hearing focuses on terrestrial birds and their ability to hear in air (U.S. Navy 2014). There is little published literature on hearing abilities of birds underwater, and the manner in which birds could use sound underwater is unclear (Dooling and Therrien 2012 in U.S. Navy 2014). In fact, there are no measurements of underwater hearing ability in any diving birds (Therrien et al. 2011 in U.S. Navy 2014). Diving birds may not hear as well underwater, compared to other (nonavian) terrestrial species, based on adaptations to protect their ears from pressure changes (Dooling and Therrien 2012 in U.S. Navy 2014).

USFWS has provided information on underwater noise impact thresholds for impact pile driving for the federally listed marbled murrelet. While marbled murrelets would not be found in the study area, the underwater noise thresholds provide some guidance on potential underwater noise impacts that could be useful for other diving birds that could be in the study area. USFWS recognizes a behavioral threshold of 150 dB_{RMS}, an injury auditory threshold of 202 dB_{SEL}, and a nonauditory injury (i.e., barotrauma) threshold of 208 dB_{SEL}; underwater noise below 150 dB_{SEL} does not cause injury (Washington State Department of Transportation 2015). WSDOT has summarized underwater sound levels from impact pile driving (single strike) in Washington State for various types and sizes of piles. For a single strike of a 36-inch-diameter steel pile (similar to what is proposed for the project area), sound levels are estimated to be 201 dB_{RMS} and 186 dB_{SEL} 10 meters from the pile (Washington State Department of Transportation 2015). For all pile types and sizes that WSDOT summarizes, the sound equivalent level is always less than the root mean square.

Knowing that the use of bubble curtains for pile driving at the project area would reduce underwater noise levels to 190 dB_{RMS} at a 45-foot radius from each pile during a strike (Figure 11) and based on WSDOT's summary of underwater noise levels for impact pile driving, a marbled murrelet would need to be within 45 feet of the pile during an impact strike to experience the injury thresholds of 202 dB_{SEL} or 208 dB_{SEL}. Given the small area where these noise levels would be reached and the presence of construction equipment, vessels, and human activities during pile driving, it is likely a diving bird would avoid the area and not be close enough to a pile to be exposed to the injury thresholds established for the marbled murrelet. However, it is possible that diving birds could experience the behavioral threshold of 150 dB_{RMS}. The level B harassment (160 dB_{RMS}) distance for impact pile driving with use of a bubble curtain is 4,459 feet (Figure 12), and the distance to 150 dB_{RMS} would be slightly beyond this distance.



Figure 11. Level A Harassment Area for Impact Pile Driving for the On-Site Alternative

Figure 12. Level B Harassment Area for Impact Pile Driving for the On-Site Alternative

The reaction of a diving bird exposed to underwater noise levels above 150 dB_{RMS} (but below 202 dB_{SEL}) could range from mild disturbance to escape behavior, which would displace individuals. Displacement and disruption of behavior could interrupt feeding and diving, and reduce productivity and survival of individuals, as the individual would likely expend more energy relocating to a new area. However, impact pile-driving noise impacts would be temporary, occurring over 2 in-water work windows. It is not anticipated that underwater impact pile-driving noise would affect the overall fitness of diving bird populations.

Result in Spills and Leaks

During all construction related activities there is the potential risk of temporary water quality impacts resulting from the release of hazardous materials such as fuels, lubricants, hydraulic fluids, or other construction-related chemicals. These materials could enter surface waters of the Columbia River or drainage ditches located near the project area. Such spills could affect aquatic habitat or wildlife, including pinnipeds, waterfowl, or terrestrial wildlife, resulting in toxic acute or subacute impacts that could affect the respiration, growth, and reproduction of these species. Over-water and in-water work increases this risk as well as the potential for construction debris or materials to enter the Columbia River. The potential for these types of impacts would be avoided or greatly reduced given protective measures to guard against these risks, including: construction best management practices, avoidance and minimization measures, adherence to the in-water work windows (to be identified in permits that may be issued), and regulatory requirements. The NEPA Water Quality Technical Report (ICF International 2016d) includes a detailed discussion on the potential impacts on water quality associated with the On-Site Alternative.

3.1.2 Construction: Indirect Impacts

Construction of the On-Site Alternative would not result in indirect impacts on wildlife or wildlife habitat because construction of the export terminal would be limited to the project area.

3.1.3 Operations: Direct Impacts

Operation of the proposed export terminal at the On-Site Alternative location would result in the following direct impacts.

Affect Wildlife as a Result of Noise

Operations of the On-Site Alternative could result in increased noise from movement of trains, transfer of coal from train to stockpile areas to vessels, and general industrial operations, which could affect wildlife in a manner similar to that described for construction noise. Increased operations noises could affect wildlife by causing disturbance or avoidance behaviors. Wildlife present in the area are likely habituated to noise levels associated with industrial and developed areas, and operations noises associated with the On-Site Alternative are anticipated to be comparable to existing noises associated with the ongoing industrial operations in the study area. Given that the species present in the study area are likely habituated to elevated noise levels associated with industrial areas and are generally mobile and avoid disturbing noise levels and human activities that are beyond those they are habituated to, it is anticipated that

operations noise associated with the On-Site Alternative would not have a measurable impact on wildlife within the terrestrial study area.

Result in Spills and Leaks

Routine operations could result in spills or leaks at the project area from vehicles, trains, or equipment that could affect water quality and the condition of aquatic habitat in the Columbia River and drainage ditches located in the project area. Potential impacts on wildlife and wildlife habitat are similar to those described for construction leaks and spills. Personnel training, oil discharge prevention briefings, and implementation of prevention and control measures, as required under the Spill Prevention, Control and Countermeasure Regulation (40 CFR 112) would guard against these risks, greatly reducing the likelihood of accidental spills. Further information is contained in the NEPA Water Quality Technical Report (ICF International 2016d) and NEPA Hazardous Materials Technical Report (ICF International 2016e).

Affect Wildlife from a Spill of Coal

Direct impacts on the natural environment from a coal spill during operation of the On-Site Alternative could occur. Direct impacts resulting from a spill during coal handling at the proposed terminal would likely be minor because the amount of coal that could be spilled would be relatively small. Also, there would be no impacts to wildlife or wildlife habitat in the project area due to the absence of terrestrial and aquatic environments in the project area and the contained nature and features of the proposed terminal (e.g., fully enclosed belt conveyors, transfer towers, and shiploaders). Potential physical and chemical effects of a coal release on the aquatic and terrestrial environments adjacent to the export terminal are described below.

Coal spilled into the Columbia River could have physical effects on aquatic wildlife and their habitats, including abrasion, smothering, diminished photosynthesis, altered sediment texture and stability, reduced availability of light, temporary loss of habitat, and diminished respiration and feeding for aquatic organisms. The magnitude of these potential impacts would depend on the amount and size of coal particles suspended in the water, duration of coal exposure, and existing water clarity (Ahrens and Morrissey 2005). Therefore, the circumstances of a coal spill, the conditions of a particular aquatic environment (e.g., pond, stream, wetland), and the physical effects on aquatic organisms and habitat from a coal spill would vary. Similarly, cleanup of coal released into the aquatic environment could result in temporary impacts on habitat, such as smothering, altering sediment composition, temporary loss of habitat, and diminished respiration and feeding for aquatic organisms.

The recovery time required for aquatic resources would depend on the amount of coal spill and the extent and duration of cleanup efforts, as well as the environment in which the incident occurred. It is unlikely that coal handling in the upland portions of the coal export terminal would result in a spill of coal that would affect the Columbia River because the rail loop and stockpile areas would be contained. Other areas adjacent to the export terminal are separated from the Columbia River by an existing levee. Coal could be spilled during shiploading operations because of human error or equipment malfunction. However, such a spill would likely result in a limited release of coal into the environment due to safeguards to prevent such operational errors. These measures include start-up alarms and dock containment measures (containment gutters placed beneath the docks to capture water and other materials that could fall onto and through the dock surface).

The chemical effects on aquatic organisms and habitats would depend on the circumstances of a coal spill and the conditions of a particular aquatic environment (e.g., stream, lake, wetland). Some research suggests that physical effects are likely to be more harmful than the chemical effects (Ahrens and Morrissey 2005).

A recent coal train derailment and coal spill in Burnaby, British Columbia, in 2014, and subsequent cleanup and monitoring efforts provide some insight into the potential impacts of coal spilled in the aquatic environment. Findings from spill response and cleanup found there were potentially minor impacts in the coal spill study area, and that these impacts were restricted to a localized area (Borealis Environmental Consulting 2015).

3.1.4 Operations: Indirect Impacts

Impacts indirectly associated with proposed operations of the proposed export terminal at the On-Site Alternative location could occur as a result of project related vessel traffic in the Columbia River within the indirect study area. These impacts include vessel strikes and underwater vessel noise impacts on pinnipeds. Periodic maintenance dredging could result in removal of habitat and associated impacts on pinnipeds and aquatic invertebrates as well as noise impacts on birds. Coal dust could indirectly affect terrestrial and aquatic wildlife. The potential risk of a vessel related spill is discussed in the NEPA Vessel Transportation Technical Report (ICF International 2016g). Operations of the On-Site Alternative would result in the following indirect impacts.

Potential Vessel Strike Impacts on Pinnipeds

Increased vessel traffic related to operations of the proposed export terminal would increase the risk of vessel collisions with pinnipeds in the indirect study area. Most available research and literature on marine mammal vessel strikes is associated with vessel-whale collisions at sea. Compared to pinnipeds, whales are typically much larger, slower-moving, and therefore, are assumed more vulnerable to vessel strikes. Vessel strikes on marine mammals are usually described as massive blunt force trauma (Geraci and Lounsbury 1993 in Horning and Mellish 2009), but are considered extremely rare for pinnipeds (Andersen et al. 2007 in Horning and Mellish 2009). The blunt force trauma that results from a marine mammal collision with a vessel can result in death or injury. Blunt force trauma to marine mammals can include, but are not limited to, bone fractures, organ damage, and internal hemorrhages (National Oceanic Atmospheric Administration 2008). There are cases in which small marine mammals survive strikes but sustain injuries and disfigurement to dorsal fins and other body parts (National Oceanic and Atmospheric Administration 2008); in Sarasota Bay, Wells and Scott (1997) (in National Oceanic Atmospheric Administration 2008) documented four cases of vessel strikes on bottlenose dolphins in which all four animals survived the strike.

Laist et al. (2001) examined collisions between vessels and whales by examining historical records and computerized stranding databases for evidence of vessel strikes, and concluded that larger vessels and higher vessel speeds can increase the risk of collisions. Even though pinnipeds are generally smaller and more agile than whales, it is reasonable to assume that vessel size and speed would also be a factor in the risk of collisions with pinnipeds. Laist et al. (2001) found that the most lethal and serious injuries to whales are caused by vessels 262 feet or longer, and by vessels traveling above 14 knots (16 miles per hour). Vessels accessing the project area would likely be larger than 262 feet, but typical transit speeds would be much less than 14 knots in the study area. Vessel speeds in the Columbia River are typically 12 knots,

slowing to about 8 knots when passing moored vessels (ICF International 2016g). In the indirect study area around the project area, the speed would likely be even slower as there would likely be a “no wake zone” around the vessel mooring area.

In summary, the potential for a pinniped strike with a vessel in the indirect study area would depend on many factors, including time of year, vessel type, vessel size, pinniped species, vessel location, vessel speed, and location of animal relative to vessel. The behavior of a pinniped in the path of an approaching vessel in the study area is uncertain, but it is likely that an individual would have the ability to swim away from an approaching vessel. In addition, pinnipeds in the lower Columbia River are likely habituated to existing Columbia River vessel traffic (estimated to be 3,185 vessels per year between 2021 and 2023), and vessel speed would be less than 14 knots. Therefore, the potential risk for a vessel collision with a pinniped would be low.

Potential Underwater Vessel Noise Impacts on Pinnipeds

Increased vessel traffic related to operation of the On-Site Alternative contributes to underwater noise generated by existing ship traffic in the Columbia River. Ships generate noise primarily by propeller cavitation, propulsion machinery, hydraulic flow over the hull, and flexing of the hull (Marine Mammal Commission 2007). Studies in the Salish Sea have shown that the greater the ship size, the greater the underwater source level due to propeller cavitation⁶; however, tug vessels exhibit greater source noise levels underwater while performing activities such as berthing or accelerating a ship (Hemmera Envirochem Inc., SMRU Canada Ltd., and JASCO Applied Sciences (Canada) Ltd., 2014). While this information is from studies in the Salish Sea, noise levels from vessels would be similar in the Columbia River. Depending on the type of noise and ambient noise conditions, underwater noise generated by vessels could affect marine mammals because they rely on sound as a means of communication, for finding food and mates, and for detecting predators. Increasing background noise levels could decrease communication ranges and modify behavior as well as induce stress responses (Wright 2008).


Operations of the project area at full build-out would result in approximately 840 additional vessels per year within the lower Columbia River compared to approximately 3,099 vessels that are estimated would transit the Lower Columbia River annually in 2028 (approximate timeframe for full build-out). With the project, total vessels per year would be approximately 3,939 (3,099 + 840). The 840 On-Site Alternative-related vessels represents approximately 21% of the expected total vessel traffic volume in the Lower Columbia River per year. See the NEPA Vessel Transportation Technical Report for additional information on vessel traffic resulting from the On-Site Alternative (ICF International 2016g).

Underwater noise frequencies associated with shipping vessels typically range between 10 Hertz (Hz) and 1kHz (Wright 2008) (Chart 1), but most ships produce noise primarily in the low frequency range (up to 100 Hz) (Marine Mammal Commission 2007). Additionally, tugboats, the vessels that would be used to assist vessels in docking and departing the project area, typically produce less near-surface sounds than other vessels. This is not because they are quieter but because the propellers of a typical tugboat are recessed to protect the propeller from damage in

⁶ As propellers move through water, low-pressure areas are formed as the water accelerates around and moved past the propellers. The faster the propeller moves, the lower the pressure around it can become. As it reaches vapor pressure, the water vaporizes and forms small bubbles. This is cavitation. When the bubbles collapse, they typically cause very strong local shock waves in the water, which may be audible and may even damage the propellers.

case of grounding. With the propeller in this position, the sound rays from the propellers are blocked by the hull. Thus, the propeller noise cannot be heard ahead of the tug (University of Rhode Island 2015).

Chart 1. Frequency Relationship between Marine Animals Sounds and Sounds from Shipping



Source: Wright 2008.

As shown in Chart 1, several groups of marine animals hear sound within and outside of the primary shipping noise frequency range. Sea lions have been shown to be sensitive to a fairly wide range of mid frequencies (approximately 1 to 30 kHz) while seals are generally capable of hearing across a wider range of low to mid sound frequencies (approximately 0.2 to 50 kHz) (National Oceanic and Atmospheric Administration 2005). Steller sea lion hearing sensitivity peaks between 1 kHz and 16 kHz for males and 16 kHz and 25 kHz for females (Kastelein et al. 2005 in Grette Associates 2014a); California sea lion hearing sensitivity peaks between 1 kHz and 28 kHz with a peak at 16 kHz (Schusterman et al. 1972 in Grette Associates 2014a); harbor seal hearing sensitivity peaks between approximately 10 kHz and 40 kHz (Mohl 1968 in Richardson et al. 1995 in Grette Associates 2014a). Comparing these pinnipeds' hearing frequency ranges with the shipping noise frequency range, underwater noise generated by ships in the study area would generally be outside of the peak sensitive hearing frequencies for Steller sea lion, California sea lion, and harbor seal; and potentially outside the full range of their sensitive hearing frequencies given that most ships produce noise primarily in the low frequency range (up to 100 Hz). In addition, pinnipeds that migrate through the study area would likely be habituated to ship noise because ship traffic on the Lower Columbia River is relatively frequent; between 2021 and 2023, it is estimated that a total of 3,185 vessels (this includes the estimated 840 vessels accessing the project area annually) would transit the Lower Columbia River annually (ICF International 2016g). Marine mammals have adapted to varying levels of natural sound, and the adaptive mechanisms could allow them to function normally in the presence of many anthropogenic sounds. The unknown variable is when introduced sounds

could exceed the adaptive capacity of marine mammals and thus pose a threat to individual animals or their populations (Marine Mammal Commission 2007).

In the event a pinniped were in the study area during the transit of a ship to or from the project area and if the underwater noise frequency of a particular ship were within the frequency range in which the pinniped is sensitive, there could be potential effects to the individual. Research has suggested that the primary auditory effect of vessel noise on marine animals is the masking of biologically significant sounds (National Oceanic and Atmospheric Administration 2005), which can affect communications between individuals. Complex behavioral responses to the same noise source can range from mild to severe and can vary among species and individuals, making it challenging to broadly characterize impacts of shipping noise on marine mammal species (Ellison et al. 2012 in Joint Working Group on Vessel Strikes and Acoustic Impacts 2012). The effects of underwater noise exposure on marine organisms have been generally characterized by the following range of physical and behavioral responses (Richardson et al. 1995 in Bureau of Ocean Energy Management 2012), although it would not be anticipated that ship noise would cause all of these responses given the low frequency of underwater ship noise and the higher frequencies that Steller sea lion, California sea lion, and harbor seal are most sensitive. Additionally, it would be difficult to measure the effect that could be caused by the increase in vessel traffic associated with the project, as compared to the overall vessel traffic that would occur in the Columbia River.

- **Behavioral reactions.** Range from brief startle responses to changes or interruptions in feeding, diving, or respiratory patterns, to cessation of vocalizations, to temporary or permanent displacement from habitat.
- **Masking.** Reduction in ability to detect communication or other relevant sound signals due to elevated levels of background noise.
- **Temporary threshold shift.** Temporary, recoverable reduction in hearing sensitivity caused by exposure to sound.
- **Permanent threshold shift.** Permanent, irreversible reduction in hearing sensitivity due to damage or injury to ear structures caused by prolonged exposure to sound or temporary exposure to very intense sound.
- **Nonauditory physiological effects.** Effects of sound exposure on tissues in nonauditory systems either through direct exposure or because of changes in behavior (e.g., resonance of respiratory cavities or growth of gas bubbles in body fluids).

The effects of increased vessel noise associated with project related vessels on pinnipeds in the study area would depend on many factors, including vessel size and type, existing vessel traffic in Columbia River, ambient underwater noise, time of year, species of pinniped, vessel location, and location of animal relative to vessel and the intervening environment. Given that the peak hearing sensitivity frequencies of Steller sea lion, California sea lion, and harbor seal are generally outside of the noise frequencies generated by vessels and because these species would likely be habituated to existing Columbia River vessel generated noise levels, it is likely that any response to project related vessel noise would be relatively minimal, and could in fact be indistinguishable from the response of pinnipeds to Columbia River vessel traffic in general.

Remove Habitat during Maintenance Dredging

Maintenance dredging would likely be required on a multiyear basis or following extreme flow conditions; however it could be needed as frequently as every year to maintain required depths at Docks 2 and 3 and to access the navigation channel, especially in the years following the initial dredging work (WorleyParsons 2012). Other neighboring berths typically do maintenance dredging on an annual basis.

Sediment accretion in the proposed dredge prism would most likely occur because of bedload transport due to river currents, and local scour and sediment redistribution resulting from propeller wash. Hydrodynamic modeling and sediment transport analysis was conducted for the proposed Docks 2 and 3 berthing/navigation basin. Sedimentation is complex in a newly dredged basin. Specific morphologic data is unavailable for the proposed new dredging basin; therefore the rate of accretion can only be estimated roughly. Based on current accretion estimates, rough estimates for annual accretion height is approximately 0.16 feet (0.07 to 0.26 feet range) and annual accretion volume is approximately 11,675 yd³ (4,670 to 23,350 y³ range). Maintenance dredging would likely be required on a multiyear basis or following occasions with extreme flow events. Small scale maintenance dredging could be needed more frequently, especially in the early years following the initial dredging work when higher than normal accretion is more likely (WorleyParsons 2012).

Impacts on pinnipeds and benthic organisms would be similar to those described for initial dredging associated with construction activities (Section 3.1.1.1, *Construction: Direct Impacts*) but maintenance dredging would likely remove a smaller amount of material, resulting in some mortality of invertebrate organisms and temporary disruption of benthic productivity. Habitat within the proposed dredge prism is in deep water where benthic productivity is expected to be low compared to shallow water habitats (McCabe et al. 1997). As mentioned in Section 3.1.1.1, *Construction: Direct Impacts*, benthic organisms typically recolonize disturbed areas in 30 to 45 days following disturbance. Thus, should dredging occur annually, it would not prevent recolonization of the benthic habitat.

Maintenance related dredging activities could affect pinnipeds in a similar manner as was described for initial dredging associated with construction activities in Section 3.1.1.1, *Construction: Direct Impacts*. Pinnipeds could be affected by colliding with dredging vessels, increased turbidity, and noise associated with dredging activities (Todd et al. 2014). Collisions between dredging vessels and pinnipeds are possible but unlikely to occur given the slow speeds of dredging vessels (Todd et al. 2014). Turbidity is unlikely to cause substantial impacts on pinnipeds since they often inhabit naturally turbid or dark environments and are likely to use other senses in addition to their vision to locate potential hazards and prey (Todd et al. 2014). Noise could cause masking and behavioral changes in pinnipeds but is unlikely to cause auditory damage (Central Dredging Association 2011; Dickerson et al. 2001; Todd et al. 2014).

Noise Impacts from Maintenance Dredging

Potential noise impacts from maintenance dredging would be similar to those described for dredging in Section 3.1.1.1, *Construction: Direct Impacts*.

Produce Coal Dust

Coal particles would be generated during operation of the proposed export terminal as coal is unloaded from trains, stored in large stockpiles, and then loaded onto vessels.

The potential extent and deposition rate of coal dust particles less than 75 microns was modeled as part of the air quality analysis. See the NEPA Air Quality Technical Report for additional details (ICF International 2016f). Based on the models, the highest rate of coal dust deposition would be expected in the immediate area surrounding the export terminal, but smaller particles would also be expected to deposit in a zone extending around and downwind of the export terminal. Deposition rates could range from 1.45 grams per square meter per year ($\text{g}/\text{m}^2/\text{year}$) adjacent to the export terminal, gradually declining to less than $0.01 \text{ g}/\text{m}^2/\text{year}$ approximately 2.41 miles from the export terminal. Refer to the SEPA Coal Technical Report (ICF International 2016h). Thresholds for possible effects of coal dust on wildlife have not been established. However, as described in Section 6.7, *Coal Dust*, the benchmark used for the analysis of potential negative impacts to people was $2.0 \text{ g}/\text{m}^2/\text{month}$. Coal dust deposition in the indirect study area from the proposed terminal would be below this benchmark. See Section 6.7, *Coal Dust*, for more information.

Based on the models, the zone of deposition would extend primarily northwest of the project area for the On-Site Alternative and over the Columbia River, encompassing the project area for the Off-Site Alternative and forested hills at the northern extent of the project area for the Off-Site Alternative, riparian habitat along the shoreline, and extending across the Columbia River to Lord and Walker islands. Deposition rates of less than $0.1 \text{ g}/\text{m}^2/\text{year}$ are projected to occur over the forested habitats of Lord Island in the study area (Figure 4), with declining concentrations across the island and to the south and west toward Walker Island.

Although concerns regarding coal dust are commonly expressed relative to air quality and human health concerns, there is a paucity of peer-reviewed scientific literature examining the potential effects of coal dust on wildlife, in particular, on terrestrial wildlife. More research has been conducted on potential effects of coal dust on aquatic organisms. Potential physical effects of coal dust have been well documented; however, documentation on potential toxic effects on aquatic organisms is lacking.

Ahrens and Morrissey (2005) conducted a literature review on the biological effects of unburnt coal in the marine environment. The following discussion is distilled from that review. Coal particles could affect aquatic wildlife in a manner comparable to any form of suspended particulates. Impacts could include tissue abrasion, smothering, obstruction or damage to feeding or respiratory organs, and effects resulting from reduced light. Another manner in which coal could affect aquatic wildlife is through coal leachates. Unburnt coal can be a source of acidity, salinity, trace metals, hydrocarbons, chemical oxygen demand, and potentially macronutrients if they leach from the coal matrix into aquatic habitats. Toxic constituents of coal include PAHs and trace metals, which are present in coal in variable amounts and combinations dependent on the type of coal. The coal type, along with mineral impurities in the coal and environmental conditions determine whether these compounds can be leached from the coal. Some PAHs are known to be toxic to aquatic animals and humans.

Metals and PAHs could also leach from coal to the pore water of sediments and be ingested by benthic-feeding organisms, providing a mechanism for subsequent ingestion by other organisms throughout the food chain. However, the low aqueous extractability and bioavailability of the

contaminants minimizes the potentially toxic effects. The coal anticipated to be exported from the export terminal is alkaline and low in sulfur and trace metals. The conditions to produce concentrations in pore waters are not present in a dynamic riverine environment. This would further support the view of Ahrens and Morrissey (2005) that the bioavailability of such toxins would likely be low.

In summary, fugitive coal dust from operation of the On-Site Alternative is not expected to increase suspended solids in the Columbia River to the point that there would be a demonstrable effect on aquatic wildlife and fish distribution, abundance, or survival. Additionally, the potential risk for exposure to toxic chemicals contained in coal (e.g., PAHs and trace metals) would be relatively low as these chemicals tend to be bound in the matrix structure and not quickly or easily leached. Particles would likely be transported downstream and either carried out to sea or distributed over a sufficiently broad area as not to be problematic. Coal dust accumulation within the area is expected to be below the trigger level for sensitive areas, as indicated in the SEPA Coal Technical Report (ICF International 2016h). Sensitive areas, as defined by New Zealand Trigger Levels referenced in the NEPA Coal Technical Report typically include areas with significant residential development. Over the long term, coal dust could accumulate in the terrestrial study area; however, predicting the extent to which wind and rain would further disperse coal dust and to what extent coal dust could affect wildlife species and their habitats over the life of the On-Site Alternative is unknown. Refer to the NEPA Vegetation Technical Report for information related to coal dust impacts on vegetation (ICF International 2016c).

3.2 Off-Site Alternative

Potential impacts on wildlife from the proposed export terminal at the Off-Site Alternative location are described below.

3.2.1 Construction: Direct Impacts

Construction of the terminal would affect both terrestrial habitats as well as aquatic habitats in the Columbia River. The types of construction impacts would be similar to those described for the On-Site Alternative. Potential impacts in terrestrial habitat due to construction include removal of habitat, wildlife disturbance and possibly mortality, and construction related noise and visual impacts. Potential impacts in aquatic habitat from construction would include removal or alteration of habitat, animal disturbance and possibly mortality, underwater noise, and potential leaks or spills.

Construction of the Off-Site Alternative would result in the following direct impacts.

3.2.1.1 Terrestrial Habitat and Wildlife Impacts

Permanently Remove Habitat and Cause Associated Wildlife Mortality

Construction of the Off-Site Alternative would destroy all wildlife habitat within the limits of construction.

A total of 216.36 acres of terrestrial habitat (aquatic habitat is discussed in the *Aquatic Habitat and Wildlife Impacts* section, below) would be permanently removed during construction by grading and clearing (Table 8 and Figure 13). The majority of impacts at the project area would occur in upland (155.46 acres) and wetland (51.28 acres) habitats, which would affect nearly six times as much upland habitat (compared to 26.26 acres for the project area for the On-Site Alternative) and twice as much wetland habitat (compared to 24.10 acres for the project area for the On-Site Alternative). Less than 5% of impacts at the project area (9.62 acres) would occur on developed lands, compared to more than 75% at the project area for the On-Site Alternative (151.14 acres) which is predominantly developed.


Although the majority of the habitats at the project area are vegetated, habitats at the site have been degraded by past disturbances related to agriculture and recreational activities, including a motocross track that consisted of several winding dirt tracks, dirt roads, and a drag strip. Wildlife currently inhabiting and using the project area would be displaced to habitats outside of the site and mortality of some individuals could occur. Highly mobile wildlife species, such as larger mammals and birds, would be expected to leave the vicinity of the project area for the On-Site Alternative during construction activities. Some mortality of individuals could occur in less mobile species, such as burrowing mammals, reptiles, and amphibians that could occur in suitable habitats on the project area. Typically, these species reproduce rapidly and any losses due to mortality of individuals would not be expected to affect the viability or fitness of the species' population overall.

Table 8. Permanent Direct Impacts by Terrestrial Habitat Type within the Project Area—Off-Site Alternative

Habitat Type	Direct Impact Area (acres)
Developed	9.62
Upland	155.46
Wetland	51.28
Open Water	8.61
Total	224.97

Affect Wildlife Habitat

Potential temporary impacts on wildlife habitat resulting from construction activities would be the same or similar to those described for the On-Site Alternative in Section 3.1.1.1, *Construction: Direct Impacts*.

Figure 13. Existing Land and Vegetation Cover Types Affected during Construction Off-Site Alternative

Displace and Cause Mortality of Wildlife

Construction of the Off-Site Alternative would be limited to the project area. If wildlife species were present on the project area during construction activities, there could be an increased risk of disturbance or direct mortality. Wildlife present at the project area during construction could be directly injured or killed during a collision with construction vehicles or equipment, or by placement of construction materials on the ground. This impact is unlikely because wildlife species in the study area are already habituated to the nearby industrial noise and individual animals are generally mobile and would be able to flee the construction area in advance of construction equipment operating at the project area. Suitable, similar habitats exist north and east of the site and wildlife are likely to relocate to these other adjacent areas. In addition, some of the project area is currently developed (approximately 10 acres) with an agricultural building (likely a pole barn) and some areas of dirt road and thus does not provide suitable habitat for most wildlife species. It would be anticipated that wildlife would not be present in those areas that do not provide suitable habitat; and most areas of the project area that are vegetated are of lower habitat quality due to the overall historic disturbance. Further, the risk of this impact would be temporary and would last only the duration of construction (i.e., up to 6 years). Given the general lack of high quality suitable habitat, the ability of wildlife to relocate away from construction areas, and the short-term use of construction equipment; the potential risk of construction equipment collisions with wildlife would be minimal and would not be expected to adversely affect species populations or fitness.

Result in Noise and Visual Impacts on Wildlife

Potential impacts on wildlife resulting from construction noise and visual inputs associated with construction equipment, materials and infrastructure would be the same or similar to those described for the On-Site Alternative.

Result in Spills and Leaks

Potential impacts on wildlife and habitat resulting from construction spills and leaks would be similar to those described for the On-Site Alternative.

3.2.1.2 Aquatic Habitat and Wildlife Impacts

Remove or Alter Habitat and Cause Animal Disturbance and Mortality

A total of 597 36-inch-diameter steel piles would be installed in the river for the trestle and docks, removing an area equivalent to 0.10 acre of benthic habitat. Approximately 94% of this habitat (3,980 square feet) is located in deep water (Grette Associates 2014o). Benthic, epibenthic, and infaunal organisms within the pile footprint at the time of pile driving would likely perish.

Dredging would permanently alter a 15-acre area of deepwater habitat (below -20 feet CRD) by removing approximately 50,000 cubic yards of benthic sediment to achieve a depth of -43 feet CRD, with a two-foot overdredge allowance (Grette Associates 2014o). The amount of deepening required to reach target depth would be 3 feet or less, as the proposed dredge prism (Figure 3) is at or below -42 feet CRD (Grette Associates 2014o). Required sediment removal at the project area would be ten times less than would be needed at the project area for the On-Site

Alternative, which would involve the removal of approximately 500,000 cubic yards of sediment over an area more than three times larger (48 acres at the project area for the On-Site Alternative). As with the On-Site Alternative, dredged materials would be expected to be disposed of within the flow lane, adjacent to the navigation channel, to support the downstream sediment transport system (Grette Associates 2014i, m, o). This area would be located within an area of approximately 80 to 110 acres between approximately RMs 60-66 (Figure 2).

Potential impacts on wildlife and habitat from dredging activities would be similar in nature to those described for the On-Site Alternative, although the magnitude would be much less for the Off-Site Alternative. The On-Site Alternative would dredge an area approximately 48 acres in size and remove and dispose of approximately 500,000 cubic yards of material. The Off-Site Alternative would dredge an area approximately 15 acres in size (approximately 1/3 the area) and remove and dispose of approximately 50,000 cubic yards of material (approximately 1/10 the volume). The majority of benthic, epibenthic, and infaunal organisms are nonmotile or slow-moving and occur relatively close to the substrate surface and would become entrained during dredging. Because the benthic organisms generally occur near the interface between the water and substrate, the area of impact best represents the magnitude of the potential impact to benthic organisms, which for the Off-Site Alternative would be approximately 1/3 less than the potential magnitude of impact associated with the On-Site Alternative. Benthic organisms often serve as prey for larger animal species. All of the habitat within the proposed dredge prism is in deep water where benthic productivity is expected to be low relative to shallower habitat. Deepwater channels are subjected to higher water velocities which periodically scour bottom sediments, limiting the standing crop of invertebrates and the buildup of detritus and fine materials which support these invertebrates (McCabe et al. 1997). Dredging activities are not typically associated with long-term reductions in the availability of prey resources and impacts on benthic productivity are expected to be temporary. Disturbed habitats are expected to return to reference conditions with rapid recolonization by benthic organisms (McCabe et al. 1996).

Dredging activities could affect pinnipeds. In *A review of Impacts of Marine Dredging Activities on Marine Mammals*, Todd et al. (2014) states that potential direct impacts on marine mammals include collisions, turbidity, and noise. Collisions between dredging vessels and pinnipeds are possible but unlikely to occur given the slow speeds of dredging vessels. Information on turbidity is limited, however existing research indicates that dredge related turbidity is not likely to cause substantial impacts on pinnipeds since they often inhabit naturally turbid or dark environments and are likely to use senses in addition to their vision (Todd et al. 2014). Noise could cause masking and behavioral changes but is unlikely to cause auditory damage to pinnipeds (Todd et al. 2014). Dredging would be conducted using a clamshell or hydraulic dredger (Grette Associates 2014o). Sound pressure levels (SPLs) can vary widely, based on dredger type, operations stage, or environmental conditions (Todd et al. 2014). Operations stage is an important component of noise levels produced by a clamshell (grab) dredger. Dickerson et al. (2001) measured the entire dredge process at increasing distances from the dredge operation. The loudest measurement, 124 dB_{RMS} was recorded at a distance of 518 feet from the dredge operation. This measurement is consistent with SPLs that could result in behavioral changes in pinnipeds but would not be likely to cause auditory damage. Hydraulic dredges typically produce higher SPLs than clamshell dredges but these SPLs are unlikely to reach levels that could cause auditory damage (Central Dredging Association 2011; Todd et al. 2014). Further discussion on underwater noise follows (*Underwater Construction Noise Impacts on Pinnipeds*).

Construction would result in the loss of approximately 8.61 acres of aquatic habitat (i.e., ditches) that meander through the project area. These open water areas support amphibians and are used by small mammals and birds. Mammals and birds are highly mobile species and would be expected to leave the vicinity during construction. Some mortality of amphibians and less mobile species would likely occur.

Result in Underwater Noise Impacts on Pinnipeds and Diving Birds

Potential impacts on pinnipeds and diving birds resulting from underwater construction noise would be the same or similar to those described for the On-Site Alternative (Section 3.1.1.1, *Construction: Direct Impacts*).

Result in Spills and Leaks

Potential impacts on habitat and wildlife resulting from construction related spills and leaks would be the same or similar to those described for the On-Site Alternative (Section 3.1.1.1, *Construction: Direct Impacts*).

3.2.2 Construction: Indirect Impacts

Construction of the Off-Site Alternative would not result in indirect impacts on wildlife or wildlife habitat because construction of the export terminal would be limited to the project area.

3.2.3 Operations: Direct Impacts

Operation of the Off-Site Alternative would result in similar types of direct impacts as those described for the On-Site Alternative (Section 3.1.1.2, *Operations: Direct Impacts*).

3.2.4 Operations: Indirect Impacts

Operation of the Off-Site Alternative would result in similar types of indirect impacts as those described for the On-site Alternative (Section 3.1.1.3, *Operations: Indirect Impacts*).

However, deposition rates could range from 1.83 grams per square meter per year (g/m²/year) adjacent to the project area, gradually declining to 0.01 g/m²/year approximately 2.98 miles from the project area. Based on the models, the zone of deposition would extend primarily northwest of the project area and over the Columbia River. Deposition rates of less than 0.1 g/m²/year are projected to occur over the forested habitats of Lord Island within the study area, with declining concentrations across the island and to the south and west toward Walker Island.

3.3 No-Action Alternative

Under the No- Action Alternative, the Applicant would not construct the proposed export terminal. Current operations would continue, and the existing bulk product terminal site could be expanded. However, any expansion would only include activities that would not require a permit from the U.S. Army Corps of Engineers or a shoreline permit; thus, no impacts on aquatic habitats would occur as a result of an expansion occurred under the No Action Alternative. New construction, demolition, or related activities to expand the bulk terminal could occur on previously developed upland portions

of the On-Site Alternative. This could affect upland areas and terrestrial habitats that provide suitable wildlife habitat. The specific extent cannot be determined, as the specific build-out is undefined for the No-Action Alternative.

It is assumed that growth in the region would likely continue, which would allow continued operation of the export terminal and the adjacent bulk terminal site within the 20-year analysis period (2018–2038). Cleanup activities, relative to past industrial uses, would continue to occur. This could affect developed areas and associated disturbed upland habitats. Vessel traffic volumes are expected to continue and any aquatic wildlife disturbance or injury associated with vessel movements would continue at levels similar to current conditions; however, no additional measurable impact on aquatic wildlife or their habitat would be expected to occur under the No-Action Alternative because no in-water work would occur.

The following permits would be required in relation to wildlife.

4.1 On-Site Alternative

The On-Site Alternative would require the following permits related to wildlife.

- **Endangered Species Act Consultation—U.S. Fish and Wildlife Service and National Marine Fisheries Service.** Constructing and operating the proposed export terminal at the On-Site Alternative location would result in impacts on wildlife species listed (or eligible for listing) under the ESA or designated critical habitat. In accordance with Section 7(a)(2) of the ESA, as amended, any action that requires federal authorization or funding, or is carried out by a federal agency must undergo consultation with the USFWS and/or NMFS to ensure the action is not likely to jeopardize the continued existence of any listed threatened or endangered animal species or result in the destruction or adverse modification of designated critical habitat. Since the proposed project could affect listed species, a Section 7 consultation with NMFS and USFWS is required under the ESA. A biological assessment (BA) would be prepared and submitted to the federal lead for consultation with NMFS and USFWS. NMFS and USFWS would issue biological opinions containing their conclusions on the effects of the On-Site Alternative on ESA-listed species and critical habitats.
- **Clean Water Act Authorization, Section 404—U.S. Army Corps of Engineers.** Construction and operation of the terminal would result in discharges of dredged and fill material into waters of the United States, including wetlands. Department of the Army authorization from the U.S. Army Corps of Engineers would be required.
- **Marine Mammal Protection Act—National Marine Fisheries Service.** The On-Site Alternative would involve pile-driving, which could result in harassment, or “take,” of marine mammals protected under the Marine Mammal Protection Act (MMPA) of 1972, as amended. Under the MMPA, the NMFS would have to issue authorization for incidental “take” of marine mammals. Take is defined under the MMPA as “to harass, hunt, capture, or kill, or attempt to harass, hunt, capture, or kill any marine mammal.”
- **Local Critical Areas and Construction Permits—Cowlitz County.** The On-Site Alternative would also require local permits for clearing and grading of the site and for impacts on regulated critical areas. Chapter 19.15 of the Cowlitz County Code regulates activities within and adjacent to critical areas and in so doing regulates vegetation occurring in wetlands and their buffers, fish and wildlife habitat conservation areas (including streams and their buffers), frequently flooded areas, and geological hazard areas. Cowlitz County would require an application for Planning Clearance, a Fill and Grade Permit, and would review the proposed project for consistency with the County’s critical areas ordinance.
- **Shoreline Substantial Development and Conditional Use Permits—Cowlitz County.** Cowlitz County administers the Shoreline Management Act through its Shoreline Management Master Program. The project area would have elements and impacts within jurisdiction of the Act

(Washington Administrative Code (CCC 19.20) and would, thus, require a Shoreline Substantial Development and Conditional Use permit from Cowlitz County and Ecology

- **Hydraulic Project Approval—Washington Department of Fish and Wildlife.** The On-Site Alternative would require a hydraulic project approval from WDFW because it will change the natural flow or bed of the Columbia River.
- **Clean Water Act, Section 401 Water Quality Certification—Washington State Department of Ecology.** Because the export terminal would require authorization under Section 404 of the Clean Water Act, the regulated discharges would require a Clean Water Act, Section 401 water quality certification. This certification is administered by Ecology. The dredged materials management plan requires site-specific sediment sampling to characterize sediments and determination of suitability of dredged material for disposal.

The following measures were identified by the Applicant as measures that would be implemented during construction and/or operations. These measures are assumed conditions or requirements of permits that would be issued for the On-Site Alternative or Off-Site Alternative. These measures were considered when evaluated the potential impacts.

- The Applicant will use flow-lane disposal (initial and maintenance dredging) to keep dredged materials in aquatic areas, thus maintaining sediment transport processes and aquatic habitats in the Lower Columbia River.
- While the Applicant will plan construction for an 8- to 10-hour day, 5 days per week. On occasion, dredging could occur 7 days per week to complete work within specific fish windows.
- The Applicant will limit the impact of turbidity to a defined mixing zone and would otherwise comply with WAC 173-201A.
- The Applicant will not stockpile dredged material on the river bottom surface.
- The Applicant will contain all dredged material in a barge prior to flow-lane disposal; dredged material would not be stockpiled on the riverbed.
- During hydraulic dredging, the Applicant will not operate the hydraulic pumps unless the dredge intake is within 3 feet of the bottom.
- The Applicant will remove any floating oil, sheen, or debris within the work area as necessary to prevent loss of materials from the site. The contractor will be responsible for retrieval of any floating oil, sheen, or debris from the work area and any damages resulting from the loss.
- For material being transported to flow-lane disposal sites, the Applicant will remove all debris (larger than 2 feet in any dimension) from the dredged sediment prior to disposal. Similar-sized debris floating in the dredging or disposal area will also be removed.
- The Applicant will use mixing zones established in the water quality certification for flow-lane disposal associated with the Corps' Channel Deepening Project (150 feet radially and 900 feet downstream from the point of disposal location).
- The Applicant will comply with BMPs and operations requirements for flow-lane disposal, as determined by the Corps.
- The Applicant will dispose materials to the flow lane using a bottom-dump barge or hopper dredge. These systems release material below the surface, minimizing surface turbidity.

- The Applicant will limit all construction activities to daylight hours to ensure that construction noise levels would be controlled and within local and state noise limits.
- The Applicant will install and maintain a noise monitoring station at an appropriate location on or near the site boundary to create 24-hour per day noise record during construction. The measurements would be recorded and monitored on a real time basis, and the contractor would take actions to halt or alter construction activities that exceed noise levels.
- To reduce the sound along the rail line, the Applicant will work with the Longview Switching Company to convert both the Oregon Way and Industrial Way crossings to quiet crossings and would fund such improvements to the rail line as necessary to achieve this mitigation.
- The Applicant will plan construction for an 8- to 10-hour day, 5 days per week. On occasion, it could be necessary to work 6 or 7 days per week depending on the nature of the task. For example, dredging could occur 7 days per week to complete work within specific fish windows.
- The Applicant will use activity-specific work windows designed to minimize specific impact mechanisms that could affect individual species (or populations within those species) of concern. These proposed work windows would protect species of concern while providing feasible construction periods for the in-water portion of construction over a 2-year schedule.
- The Applicant will comply with timing restrictions specifying that in-water construction must occur when species of concern (i.e., salmonids, eulachon, and green sturgeon) are absent or present in very low numbers in the adjacent waterbody. All timing restrictions established by WDFW, the Corps, NMFS, or USFWS would be strictly observed.
- The Applicant will conduct impact pile driving using a confined bubble curtain or similar sound attenuation system capable of achieving approximately 9 decibels of sound attenuation.
- Where possible, the Applicant will keep extraction equipment out of the water to avoid “pinching” pile below the water line in order to minimize creosote release during extraction.
- During pile removal and pile driving, the Applicant will place a containment boom around the perimeter of the work area to capture wood debris and other materials released into the waters because of construction activities. The Applicant will collect all accumulated debris and dispose of it upland at an approved disposal site. The contractor will deploy absorbent pads should any sheen be observed.
- The Applicant will provide a containment basin on the work surface on the barge deck or pier for piles and any sediment removed during pulling. The Applicant will dispose of any sediment collected in the containment basin at an appropriate upland facility, as with all components of the basin (e.g., straw bales, geotextile fabric) and all pile removed.
- Upon removal from substrate, the Applicant will move the pile expeditiously from the water into the containment basin. The contractor will not shake, hose, strip, or scrape the pile, nor leave it hanging to drip or any other action intended to clean or remove adhering material from the pile.
- The Applicant will dispose of all piles removed at an appropriate upland facility.
- The Applicant will prepare a mitigation plan in coordination with the Corps, Ecology, and Cowlitz County to address impacts on wetlands and aquatic habitats. Mitigation actions could be implemented at one or several locations to ensure that a wide range of ecological functions is provided to offset identified, unavoidable impacts of the On-Site Alternative. The mitigation

actions could include Applicant-sponsored mitigation actions or use of credits from existing or proposed mitigation banks

4.2 Off-Site Alternative

The Off -Site Alternative would require the same permits related to wildlife as described for the On-Site Alternative.

- Endangered Species Act Consultation
- Clean Water Act Authorization, Section 404
- Marine Mammal Protection Act
- Hydraulic Project Approval
- Clean Water Act, Section 401 Water Quality Certification
- **Local Critical Areas and Construction Permits—City of Longview.** In addition to the Cowlitz County permits, the Off-Site Alternative would require permits from the City of Longview. Chapter 17.10 of the City of Longview Municipal Code regulates activities within and adjacent to critical areas such as wetlands and their buffers, fish and wildlife habitat conservation areas (including streams and their buffers), frequently flooded areas, and geological hazard areas. The City of Longview would require Critical Areas and Floodplain permits, as well as a Building Permit for clearing, grading, and construction.
- **Shoreline Substantial Development—City of Longview.** A Shoreline Substantial Development permit from the City of Longview would also be required. The City of Longview administers the Shoreline Management Act through its Shoreline Management Master Program. The project area would have elements and impacts within jurisdiction of the act and would thus require a Shoreline Substantial Development permit from the City of Longview. The Off-Site Alternative would not require a Shoreline Substantial Development Permit or Conditional Use Permit from Cowlitz County.

5.1 Written References

- Ahrens M.J. and D.J. Morrissey. 2005. Biological effects of unburnt coal in the marine environment. *Oceanography and Marine Biology: An Annual Review* 43(69–122).
- Anderson et al. 2007. See Horning and Mellish 2009.
- Borealis Environmental Consulting. 2015. *Aquatic Impact Assessment, Burnaby Lake Coal Derailment, Yale Subdivision Mile 122.7*. Prepared for CN Environment.
- Brooks, K.M. 1997. Literature Review, Computer Model and Assessment of the Potential Environmental Risks associated with Creosote Treated Wood Products Used in Aquatic Environments. Prepared by: Aquatic Environmental Sciences, Port Townsend, WA. Prepared for: Western Wood Preservers, Vancouver, WA.
- Brown, R., S. Jeffries, D. Hatch, B. Wright, and S. Jonker. 2011. *Field Report: 2011 Pinniped Research and Management Activities at and Below Bonneville Dam*. Oregon Department of Fish and Wildlife, Salem, Oregon, and Washington Department of Fish and Wildlife, Olympia, Washington.
- Bureau of Ocean Energy Management (BOEM), Office of Renewable Energy Programs. 2012. *Commercial Wind Lease Issuance and Site Assessment Activities on the Atlantic Outer Continental Shelf Offshore New Jersey, Delaware, Maryland, and Virginia, Final Environmental Assessment*. 2012. Office of Renewable Energy Programs, Herndon, VA.
- Central Dredging Association. 2011. Underwater Sound in Relation to Dredging. CEDA Position Paper. 7 November 2011.
- Cornell Lab of Ornithology. 2015. *All About Birds - Bird Guide - Pileated Woodpecker*. Available: http://www.allaboutbirds.org/guide/pileated_woodpecker/lifehistory#top. Accessed: February 7, 2015.
- Delany and Grubb. 2003. See Washington State Department of Transportation. 2015.
- Dickerson, C., K.J. Reine, and D.G. Clarke. 2001. *Characterization of Underwater Sounds Produced by Bucket Dredging Operations*. DOER Technical Notes Collection (ERDC TN-DOER-E14), U.S. Army Engineer Research and Development Center, Vicksburg, MS.
- Doolin and Therrien. 2012. See U.S. Navy 2014.
- Dorsey, Benjamin Paul. 2011. *Factors Affecting Bear and Ungulate Mortalities along the Canadian Pacific Railroad through Banff and Yoho National Parks*. A thesis submitted in partial fulfillment of the requirements for the degree of Master of Science in Land Resources and Environmental Sciences. Montana State University.
- Eisler, R. 1987. *Polycyclic Aromatic Hydrocarbon Hazards to Fish, Wildlife, and Invertebrates: a Synoptic Review*. Contaminant Hazard Reviews Report 11. U.S. Fish and Wildlife Service, Laurel, MD.

- Ellison et al. 2012. See Joint Working Group on Vessel Strikes and Acoustic Impacts 2012.
- Epsilon Associates, Inc. 2006. *Hudson River PCBs Superfund Site Phase 1 Final Design Report Attachment J - Noise Impact Assessment*" Maynard.
- Geraci and Lounsbury. 1993. See Horning and Mellish 2009.
- Grette Associates, LLC. 2014a. *Millennium Coal Export Terminal Longview, Washington: Docks 2 and 3 and Associated Trestle: Direct Effects of Construction. Pile Driving and Marine Mammals*. September 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals—Longview, LLC. Longview, WA.
- Grette Associates, LLC. 2014b. *Millennium Coal Export Terminal Longview, Washington: Off-Site Alternative – Barlow Point Pile Driving and Underwater Sound, Marine Mammals*. September 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals—Longview, LLC. Longview, WA.
- Grette Associates, LLC. 2014c. *Millennium Coal Export Terminal Longview, Washington: Coal Export Terminal Wetland and Stormwater Ditch Delineation Report – Parcel 619530400*. September 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals—Longview, LLC. Longview, WA.
- Grette Associates, LLC. 2014d. *Millennium Coal Export Terminal Longview, Washington: Bulk Product Terminal Shoreline Wetland Delineation Report – Parcel 61950*. September 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals—Longview, LLC. Longview, WA.
- Grette Associates, LLC. 2014e. *Millennium Coal Export Terminal Longview, Washington: Bulk Product Terminal Wetland and Stormwater Ditch Delineation Report – Parcel 61953*. September 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals—Longview, LLC. Longview, WA.
- Grette Associates, LLC. 2014f. *Millennium Coal Export Terminal Longview, Washington: Off-Site Alternative – Barlow Point Shoreline Habitat Inventory*. August 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals—Longview, LLC. Longview, WA.
- Grette Associates, LLC. 2014g. *Millennium Coal Export Terminal Longview, Washington: Bulk Product Terminal Wetland and Stormwater Reconnaissance Report – Parcel 10213*. September 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals—Longview, LLC. Longview, WA.
- Grette Associates, LLC. 2014h. *Millennium Coal Export Terminal Longview, Washington: Coal Export Terminal Wetland Impact Report – Parcel 619530400*. September 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals—Longview, LLC. Longview, WA.
- Grette Associates, LLC. 2014i. *Millennium Coal Export Terminal Longview, Washington: Permanent Impacts to Aquatic Habitat*. September 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals—Longview, LLC. Longview, WA.
- Grette Associates, LLC. 2014j. *Millennium Coal Export Terminal Longview, Washington: Affected Environment Biological Resources. Technical Report*. January 2014, revised March 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals—Longview, LLC. Longview, WA.
- Grette Associates, LLC. 2014k. *Millennium Coal Export Terminal Longview, Washington: Affected Environment Biological Resources. Addendum: Technical Memorandum: Streaked Horned Lark Surveys at Millennium Bulk Terminals—Longview*. September 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals—Longview, LLC. Longview, WA.

- Grette Associates, LLC. 2014l. *Millennium Coal Export Terminal Longview, Washington: Off-Site Alternative – Barlow Point Wetland Reconnaissance Report*. September 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals—Longview, LLC. Longview, WA.
- Grette Associates, LLC. 2014m. *Millennium Coal Export Terminal Longview, Washington: Docks 2 and 3 and Associated Trestle: Proposed Mitigation Measures to Minimize Construction and Long-Term Effects*. September 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals—Longview, LLC. Longview, WA.
- Grette Associates, LLC. 2014n. *Millennium Coal Export Terminal Longview, Washington: Docks 2 and 3 and Associated Trestle Direct Effects of Construction*. September 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals—Longview, LLC. Longview, WA.
- Grette Associates, LLC. 2014o. *Millennium Coal Export Terminal Longview, Washington: Off-Site Alternative – Barlow Point Permanent Impacts to Aquatic Habitat*. September 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals—Longview, LLC. Longview, WA.
- Grette Associates, LLC. 2014p. *Millennium Coal Export Terminal Longview, Washington: Affected Environment Biological Resources. Addendum: Technical Memorandum: Docks 2 and 3 and Associated Trestle Effects of Construction and Terminal Operations on Streaked Horned Larks and Columbian White-Tailed Deer*. September 2014. Wenatchee, WA. Prepared for Millennium Bulk Terminals—Longview, LLC. Longview, WA.
- Hemmera Environchem Inc., SMRU Canada Ltd., and JASCO Applied Sciences (Canada) Ltd. 2014. *Roberts Bank Terminal 2 Technical Data Report: Underwater Noise Ship Sound Signature Analysis Study*. Prepared for Port Metro Vancouver. December 2014.
- Horning, M. and J.E. Mellish. 2009. Spatially explicit detection of predation on individual pinnipeds from implanted post-mortem satellite data transmitters. *Endangered Species Research* 10:135–143.
- ICF International. 2016a. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Fish Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016b. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Land Use Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016c. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Vegetation Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016d. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Water Quality Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016e. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Hazardous Materials Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.

- ICF International. 2016f. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Air Quality Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016g. *Millennium Bulk Terminals—Longview, NEPA Environmental Impact Statement, NEPA Vessel Transportation Technical Report*. September. Seattle, WA. Prepared for U.S. Army Corps of Engineers, Seattle District.
- ICF International. 2016h. *Millennium Bulk Terminals—Longview, SEPA Environmental Impact Statement, SEPA Coal Technical Report*. June. Prepared for Cowlitz County in cooperation with Washington State Department of Ecology, Southwest Region.
- Joint Working Group on Vessel Strikes and Acoustic Impacts. 2012. *Vessel Strikes and Acoustic Impacts. Report of a Joint Working Group of Gulf of the Farallones and Cordell Bank National Marine Sanctuaries Advisory Councils*. San Francisco, CA.
- Jeffries, S.J., P.J. Gearin, H.R. Huber, D.L. Saul, and D.A. Pruett. 2000. *Atlas of Seal and Sea Lion Haulout Sites in Washington*. Washington Department of Fish and Wildlife, Wildlife Science Division, Olympia, WA.
- Kastelein et al. 2005. See Grette Associates 2014.
- Kusta, T., M. Hola, Z. Kekken, M. Jezek, T. Zika, and V. Hart. 2014. Deer on the railway line: spatiotemporal trends in mortality patterns of roe deer. *Turkish Journal of Zoology*. 38: 479.
- Laist, D.W., A.R. Knowlton, J.G. Mead, A.S. Collet, and M. Podesta. 2001. Collisions between ships and whales. *Marine Mammal Science* 17(1):35–75.
- Marine Mammal Commission. 2007. *Marine Mammals and Noise: A Sound Approach to Research and Management*. A Report to Congress.
- McCabe, G. T., S. A. Hinton, and R. L. Emmett. 1996. *Benthic invertebrates and sediment characteristics in Wahkiakum County Ferry Channel, Washington, before and after dredging*. Coastal Zone and Estuarine Studies Division, Northwest Fisheries Science Center, National Marine Fisheries Service. Seattle, WA.
- McCabe, G.T., Jr., S.A. Hinton, R.L. Emmett, and B.J. Sandford. 1997. Benthic invertebrates and sediment characteristics in main channel habitats in the lower Columbia River: *Northwest Science* 71:45–55.
- Mohl 1968. See Grette Associates 2014a.
- Moore, N.P., P.F. Kelly, F. A. Lang, J. M. Lynch, and S. D. Langston. 1997. The Peregrine Falco peregrinus in quarries: Current status and factors influencing occupancy in the Republic of Ireland. *Bird Study*, 44, 176-181.
- Mountain Loop Conservancy. 2010. *Marbled Murrelet Brachyramphus marmoratus*. June. <http://mtloopconservancy.org/Mt.Loop/MLCFactSheetMarbledMurrelet.pdf>.
- National Marine Fisheries Service (NMFS) Southwest Region. 2009. *The Use of Treated Wood Products in Aquatic Environments: Guidelines to West Coast NOAA Fisheries Staff for Endangered Species Act and Essential Fish Habitat Consultations in the Alaska, Northwest and Southwest Regions*.

- National Marine Fisheries Service (NMFS) West Coast Region. 2015. *Protected Species – Pinnipeds*. Available: http://www.westcoast.fisheries.noaa.gov/protected_species/marine_mammals/pinnipeds/index.html Accessed: January 30, 2015.
- National Oceanic and Atmospheric Administration. 2005. Final Report of the National Oceanic and Atmospheric Administration (NOAA) International Symposium: “Shipping Noise and Marine Mammals: A Forum for Science, Management, and Technology” 18-19 May 2004 Arlington, Virginia, U.S.A. NOAA Fisheries Acoustics Program. Prepared by Southall B.L.
- National Oceanic and Atmospheric Administration. 2008. Differentiating Serious and Non-Serious Injury of Marine Mammals: Report of the Serious Injury Technical Workshop, 10-13 September 2007, Seattle, WA. NOAA Tech. Memo. NMFS-OPR-39. U.S. Department of Commerce. Prepared by Andersen, M. S., K. A. Forney, T. V. N. Cole, T. Eagle, R. Angliss, K. Long, L. Barre, L. Van Atta, D. Borggaard, T. Rowles, B. Norberg, J. Whaley, and L. Engleby.
- Oregon Department of Transportation (ODOT). Undated. *Peregrine Falcon Management Plan 2002-2007*. Prepared by Mason, Bruce and Girard, Inc., Portland, OR. Revised by ODOT Environmental Services, Salem, OR.
- Pacific Coast Joint Venture. 1994. Joint Venture Implementation Plans Lower Columbia River 1994. Prepared by Oregon Wetlands Joint Venture, West Linn, OR.
- Pearson, S.F. and B. Altman. 2005. Range-wide Streaked Horned Lark (*Eremophila alpestris strigata*) Assessment and Preliminary Conservation Strategy. WDFW, Olympia, WA.
- Richardson et al. 1995. See Bureau of Ocean Management (BOEM) 2012.
- Schusterman et al. 1972. See Grette Associates 2014a.
- Science Applications International Corporation. 2011. Environmental Science Panel for Marbled Murrelet Underwater Noise Injury Threshold. Final Summary Report, Bothell.
- Southall, Brandon L., Bowles, A. E., Ellison, W. T., Finneran, J. J., Gentry, R. L., Greene Jr, C. R., Kastak, D., et al. 2007. Marine mammal noise exposure criteria: Initial scientific recommendations. *Aquatic Mammals*, 33(4), 411-521.
- Stansell, R., K.M. Gibbons, and W.T. Nagy. 2010. *Evaluation of pinniped predation on adult salmonids and other fish in the Bonneville Dam tailrace, 2008–2010*. U.S. Army Corps of Engineers, Fisheries Field Unit, Bonneville Lock and Dam, Cascade Locks, OR.
- Stansell, R., K.M. Gibbons, W.T. Nagy, and B.K. van der Leeuw. 2012. *Evaluation of pinniped predation on adult salmonids and other fish in the Bonneville Dam tailrace, 2012*. U.S. Army Corps of Engineers, Fisheries Field Unit, Bonneville Lock and Dam, Cascade Locks, OR.
- Stelle L. L., Blake R. W., Trites A. W. (2000). Hydrodynamic drag in Steller sea lions (*Eumetopias jubatus*). *Journal of Experimental Biology*. 203: 1915–1923.
- Strauss 2006. See National Marine Fisheries Service 2009.
- Therrien et al. 2011. See U.S. Navy 2014.
- Todd, V.L.G., I.B. Todd, J.C. Gardiner, E.C.N. Morrin, N.A. MacPherson, N.A. DiMarzio, and F. Thomsen. 2014. A review of impacts of marine dredging activities on marine mammals. *ICES Journal of Marine Science* 72: 328–340.

- University of Rhode Island. 2015. *Discovery of Sound in the Sea*. Available: <http://www.dosits.org/audio/anthropogenicsounds/ship/>. Accessed: January 8, 2015.
- U.S. Fish and Wildlife Service. 1983. *Revised Columbian White-Tailed Deer Recovery Plan*. USFWS. Portland, OR.
- U.S. Fish and Wildlife Service. 2006. *Oregon Fish and Wildlife Office, USFWS Harassment Analysis and Distance Thresholds Notes*. Provided by David Lear, USFWS.
- U.S. Fish and Wildlife Service. 2007. Bald Eagle *Haliaeetus leucocephalus* Species Fact Sheet. U. S. Fish and Wildlife Service Endangered Species Program, Arlington, VA. Available: [http://www.fws.gov/migratorybirds/NewReportsPublications/FactSheets/bald_eagle_fact_sheet\[1\].pdf](http://www.fws.gov/migratorybirds/NewReportsPublications/FactSheets/bald_eagle_fact_sheet[1].pdf).
- U.S. Fish and Wildlife Service. 2012. Endangered and Threatened Wildlife and Plants: Listing Taylor's Checkerspot Butterfly and Streaked Horned Lark and Designation of Critical Habitat; Proposed Rule. October 11, 2012. *Federal Register* 77(197):61938–62058.
- U.S. Fish and Wildlife Service. 2015. *Information, Planning, and Conservation (IPaC) system database*. Trust Resources List - Cowlitz County. Available: <http://ecos.fws.gov/ipac/>. Accessed: January 30, 2015.
- U.S. Navy. 2014. *Northwest Training and Testing. Environmental Impact Statement/Overseas Environmental Impact Statement*. January 2014. Available: <http://nwtteis.com/Portals/NWTT/DraftEIS2014/EIS/3.6%20Birds.pdf>. Accessed: February 25, 2015.
- Varanasi et al. 1989. See National Marine Fisheries Service 2009.
- Washington Department of Fish and Wildlife. 2013. *Threatened and Endangered Wildlife in Washington: 2012 Annual Report*. Listing and Recovery Section, Wildlife Program, Olympia, WA.
- Washington Department of Fish and Wildlife. 2014. *PHS Statewide List and Distribution by County 2013*. Priority Habitats and Species (PHS) Program. Available: <http://wdfw.wa.gov/conservation/phs/list/>. Accessed: January 29, 2015.
- Washington Department of Natural Resources. 2015. *Herpetological Atlas spatial database*. Available: <http://www1.dnr.wa.gov/nhp/refdesk/herp/herpmain.html>. Accessed: February 2, 2015.
- Washington State Department of Transportation. 2015. *Biological Assessment Preparation: Advanced Training Manual Version 02-2015: Chapter 7.0 Construction Noise Impact Assessment*. 2015. Available: <http://www.wsdot.wa.gov/Environment/Biology/BA/BAGuidance.htm>.
- Willapa Hills Audubon Society. 2014. *Cowlitz County Willapa Hills Audubon Society Annual Bird List 2014*. Available: http://willapahillsaudubon.org/WHAS_files/Birdlists/2014cowlitz_birdlist.pdf. Accessed: November 21, 2014.
- WorleyParsons. 2012. *Millennium Bulk Terminals—Longview, LLC. Hydrodynamic Modeling and Sediment Transport Analysis (draft)*. December 2012. Bellevue, WA.

Wright, A.J. (ed.) 2008. International Workshop on Shipping Noise and Marine Mammals, Hamburg, Germany, 21st-24th April 2008. Okeanos-Foundation for the Sea, Auf der Marienhöhe 15, D-64297 Darmstadt. Available: http://www.sound-in-the-sea.org/download/ship2008_en.pdf.

Appendix A

Special-Status Wildlife Species in Cowlitz County

Appendix A

Special-Status Wildlife Species in Cowlitz County

Table A-1. Special-Status Wildlife Species that Could Occur in Cowlitz County, Washington

Common Name	Scientific Name	Element of Concern	Potential for Occurrence in the study area	Potential for Habitat in the study area
Mammals				
Columbian black-tailed deer	<i>Odocoileus hemionus columbianus</i>	Individuals	Yes	Documented on the project site for the On-Site Alternative
Columbian white-tailed deer	<i>Odocoileus virginianus leucurus</i>	Individuals	Yes	Documented on the project site for the On-Site Alternative ^a
Harbor seal (<i>Phoca vitulina</i>)	<i>Phoca vitulina</i>	Individuals	Yes	Present in Columbia River
California sea lion	<i>Zalophus californianus</i>	Individuals	Yes	Present in Columbia River
Stellar Sea lion	<i>Eumetopias jubatus</i>	Individuals	Yes	Present in Columbia River
Big brown bat	<i>Eptesicus fuscus</i>	Roosting concentrations	Unlikely	No suitable habitat identified
Myotis bats	<i>Myotis spp.</i>	Roosting concentrations	Unlikely	No suitable habitat identified
Pallid bat	<i>Antrozous pallidus</i>	Roosting concentrations	Unlikely	No suitable habitat identified
Townsend's big-eared bat	<i>Corynorhinus townsendii</i>	Individuals	Unlikely	No suitable habitat identified
Fisher	<i>Martes pennant</i>	Individuals	No	No suitable habitat identified
Marten	<i>Martes Americana</i>	Individuals	No	No suitable habitat identified
Wolverine	<i>Gulo gulo</i>	Individuals	No	No suitable habitat identified
Elk	<i>Cervus elaphus</i>	Individuals	Unlikely	No suitable habitat identified
Birds				
Western grebe	<i>Aechmophorus occidentalis</i>	Individuals	Unlikely	Open water
Marbled murrelet	<i>Brachyramphus marmoratus</i>	Individuals	No	No suitable habitat identified
Yellow-billed cuckoo	<i>Coccyzus americanus</i>	Individuals	Unlikely, extremely rare	Very limited habitat

Common Name	Scientific Name	Element of Concern	Potential for Occurrence in the study area	Potential for Habitat in the study area
Streaked horned lark	<i>Eremophila alpestris strigata</i>	Individuals	Possibly	Not documented on project site for the On-Site Alternative; Other areas of potential habitat in study area not surveyed
Great-blue heron	<i>Ardea herodias</i>	Breeding Colony	No (Individuals documented on project site for the On-Site Alternative)	No breeding habitat documented in study area
Cavity nesting ducks	N/A	Breeding Areas	No	No breeding habitat documented in study area
Barrows Goldeneye	<i>Bucephala islandica</i>	Western Washington non-breeding concentrations	Unlikely	Open water
Common Goldeneye	<i>Bucephala clangula</i>	Western Washington non-breeding concentrations	Unlikely	Open water
Bufflehead	<i>Bucephala albeola</i>	Western Washington non-breeding concentrations	Unlikely	Open water
Harlequin duck	<i>Histrionicus histrionicus</i>	breeding areas and regular concentrations in salt water	No	No open salt water; no suitable breeding habitat identified
Tundra swan	<i>Cygnus columbianus</i>	regular concentrations	No	No suitable habitat identified
Trumpeter swan	<i>Cygnus buccinators</i>	Individuals	No	No suitable habitat identified
Waterfowl concentrations	N/A	significant breeding areas, regular winter concentrations	Unlikely	Suitable habitat not likely to support large concentrations
Bald eagle	<i>Haliaeetus leucocephalus</i>	breeding areas, communal roosts, regular concentrations	Possibly (Individuals documented flying over the project	No breeding habitat identified; forested wetland could provide roosting habitat.

Common Name	Scientific Name	Element of Concern	Potential for Occurrence in the study area site for the On-Site Alternative)	Potential for Habitat in the study area
Golden eagle	<i>Aquila chrysaetos</i>	breeding and foraging areas	Unlikely	Not found in lowland industrial areas
Northern goshawk	<i>Accipiter gentilis</i>	breeding areas	No	No suitable habitat identified
Peregrine falcon	<i>Falco peregrinus</i>	breeding areas; regular occurrences	Possibly	Potential foraging habitat
Sooty grouse	<i>Dendragapus fuliginosus</i>	breeding areas; regular concentrations	No	No suitable habitat identified
Wild turkey	<i>Meleagris galiopavo</i>	Individuals	Unlikely	No suitable habitat identified
Sandhill Crane	<i>Grus Canadensis</i>	breeding areas, regular concentrations, migration staging areas	Unlikely	No suitable habitat for breeding or congregating.
Plovers	Charadriidae	Western Washington non-breeding concentrations	Unlikely	Suitable habitat is limited
Waders/Sandpipers	Scolopacidae	Western Washington non-breeding concentrations	Unlikely	Suitable habitat is limited
Phalaropes	Phalaropodidae	Western Washington non-breeding concentrations	Unlikely	Suitable habitat is limited
Band-tailed pigeon	<i>Columba fasciata</i>	regular concentrations, occupied mineral sites	No	No known habitat on the project site for the On-Site Alternative
Spotted owl	<i>Strix occidentalis</i>	Individuals	No	No suitable habitat on the project site for the On-Site Alternative
Vaux's swift	<i>Chaetura vauxi</i>	breeding areas, communal roosts	Possibly	No large snags for breeding or roosting on the project site for the On-Site Alternative ; known

Common Name	Scientific Name	Element of Concern	Potential for Occurrence in the study area	Potential for Habitat in the study area
				sightings at Mint Farm Industrial Park ^b
Pileated woodpecker	<i>Dryocopus pileatus</i>	breeding areas	Unlikely (individuals possibly)	Breeding habitat component unlikely at the project site for the On-Site Alternative
Purple martin	<i>Progne subis</i>	breeding and feeding areas	Yes	Species presence documented on the project site for the On-Site Alternative ^a
Slender-billed white-breasted nuthatch	<i>Sitta carolinensis</i>	Individuals	Unlikely	Lack of mature deciduous forest on the project site for the On-Site Alternative
Amphibians				
Western toad	<i>Bufo boreas</i>	Individuals	Unlikely, recently extirpated from local range	Species is uncommon; No large natural ponds for breeding on the project site for the On-Site Alternative and unlikely in study area
Dunn's salamander	<i>Plethodon dunii</i>	Individuals	No	No suitable habitat on the project site for the On-Site Alternative and unlikely in study area
Van Dyke's salamander	<i>Plethodon vandykii</i>	Individuals	No	No suitable habitat on the project site for the On-Site Alternative and unlikely in study area
Cascade torrent salamander	<i>Rhyacotriton cascadae</i>	Individuals	No	No suitable habitat on the project site for the On-Site Alternative and unlikely in study area
Larch mountain salamander	<i>Plethodon larselli</i>	Individuals	No	No suitable habitat on the project site for the On-Site Alternative and unlikely in study area

Common Name	Scientific Name	Element of Concern	Potential for Occurrence in the study area	Potential for Habitat in the study area
Reptiles				
Western pond turtle	<i>Actinemys marmorata</i>	Individuals	No	No suitable habitat on the project site for the On-Site Alternative and unlikely in study area

^a Grette Associates 2014

^b Willapa Hills Audubon Society 2014

Grette Associates, LLC. 2014. Appendix F, Noxious weeds and sensitive plants, in Millennium Coal Export Terminal, Wetland and Stormwater Ditch Delineation Report – Parcel 619530400; prepared for Millennium Bulk Terminals—Longview, LLC. September 1, 2014. Pages 1 and 2.

Willapa Hills Audubon Society. 2014. *Cowlitz County Willapa Hills Audubon Society Annual Bird List 2014*. Available: http://willapahillsaudubon.org/WHAS_files/Birdlists/2014cowlitz_birdlist.pdf Accessed: November 21, 2014.